

Notice to Contractors -- Letting May 17, 2024

Sealed proposals for furnishing all labor, material, equipment and other things necessary for the work described herein will be received by the undersigned at the General Office of the Department of Highway until 11:00 AM on May 17, 2024 and publically opened.

Soil borings are generally available on all grading or bridge projects. They are free. They may be ordered at (999) 999-9999. There will be no refunds for plans or proposals. Please put the invoice number on all checks when paying for plans, proposals and specifications.

Quantities shown herein are for information only and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

Contract ID	Federal Project Number / State Project Number	Description
240517-A01		
FAF 69-1(36)	J1P3373	
J1P3373 - ROUTE 69 - DEKALB COUNTY		
FAF 69-1(36)	J1P3373	
Add turn lane		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-A01

Contract ID: 240517-A01

Letting Date: May 17, 2024 11:00 AM

Projects: J1P3373

FAF 69-1(36)

Counties: DEKALB

District: Northwest

DBE Goal Percent: 6.00

Description: ****(1): Job J1P3373 Route 69 DEKALB County. Add turn lane at Route EE north of Cameron, the total length of improvement being 0.403 miles.

Contract Time: DT - 11/1/2024

Item No.	Description	Quantity	Units
2013000	CLEARING AND GRUBBING	2.000	ACRE
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2031000	CLASS A EXCAVATION	3,718.000	CUYD
2036000	COMPACTING EMBANKMENT	1,228.000	CUYD
2037075	COMPACTING IN CUT	23.600	STA
2063000	CLASS 3 EXCAVATION	158.000	CUYD
2063300	CLASS 4 EXCAVATION	7.000	CUYD
3040506	TYPE 5 AGGREGATE FOR BASE (6 IN. THICK)	4,251.000	SQYD
3105002	GRAVEL (A) OR CRUSHED STONE (B)	95.000	TONS
4011231	BITUMINOUS PAVEMENT MIXTURE PG58-28H, (BP-1)	363.600	TONS
4013000	BITUMINOUS PAVEMENT MIXTURE PG64-22 (BASE)	1,286.900	TONS
4071005	TACK COAT	330.000	GAL
6096020	FURNISHING TYPE 2 ROCK DITCH LINER	93.000	CUYD
6096042	PLACING TYPE 2 ROCK DITCH LINER	93.000	CUYD
6097000	ROCK LINING	4.000	CUYD
6122012	IMPACT ATTENUATOR 55 MPH (SAND BARREL ARRAY)	2.000	EA
6122020	REPLACEMENT SAND BARREL	4.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-A01

Item No.	Description	Quantity	Units
6122030	IMPACT ATTENUATOR (RELOCATION)	2.000	EA
6161005	CONSTRUCTION SIGNS	608.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	4.000	EA
6161025	CHANNELIZER (TRIM LINE)	64.000	EA
6161030	TYPE III MOVEABLE BARRICADE	10.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	3.000	EA
6162002	TEMPORARY LONG-TERM RUMBLE STRIPS	3.000	EA
6169901	MISC. WORK ZONE TRAFFIC SIGNAL SYSTEM	1.000	LS
6173600D	TEMPORARY TRAFFIC BARRIER, CONTRACTOR FURNISHED / RETAINED	255.000	LF
6175010A	RELOCATING TEMPORARY TRAFFIC BARRIER	255.000	LF
6181000	MOBILIZATION	1.000	LS
6181020	ADDITIONAL MOBILIZATION FOR SEEDING	3.000	EA
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	35.000	LF
6200018	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. YELLOW	303.000	LF
6200021	PREFORMED THERMOPLASTIC PAVEMENT MARKING, LEFT/RIGHT ARROW	3.000	EA
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	8,455.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	9,389.000	LF
6207001	PAVEMENT MARKING REMOVAL	22,470.000	LF
6208076	4 IN TEMPORARY PAVEMENT MARKING PAINT	15,210.000	LF
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	358.000	SQYD
6261000A	BITUMINOUS SHOULDER RUMBLE STRIP	11.800	STA
6274000	CONTRACTOR FURNISHED SURVEYING AND	1.000	LS



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-A01

Item No.	Description	Quantity	Units
	STAKING		
7034041	CLASS B-1 CONCRETE (CULVERTS)	14.200	CUYD
7061030	REINFORCING STEEL (CULVERTS)	2,730.000	LB
7250318A	18 IN. PIPE GROUP B	56.000	LF
7250418	18 IN. PIPE GROUP C	64.000	LF
7250424	24 IN. PIPE GROUP C	42.000	LF
7250436	36 IN. PIPE GROUP C	48.000	LF
7261048	48 IN. PIPE GROUP A	76.000	LF
7320648A	48 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	2.000	EA
7320818A	18 IN. OR ALLOWED SUBSTITUTE GROUP C FLARED END SECTION	4.000	EA
7321014A	18 IN. OR ALLOWED SUBSTITUTE SAFETY SLOPE END SECTION	2.000	EA
7321016A	24 IN. OR ALLOWED SUBSTITUTE SAFETY SLOPE END SECTION	2.000	EA
7321018A	36 IN. OR ALLOWED SUBSTITUTE SAFETY SLOPE END SECTION	2.000	EA
8025006	MULCHING	2.500	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	2.500	ACRE
8061004	SEDIMENT TRAP ROCK	57.900	CUYD
8061005	ROCK DITCH CHECK	124.000	LF
8061006	ALTERNATE DITCH CHECK	391.000	LF
8061016	SEDIMENT REMOVAL	45.000	CUYD
8061019	SILT FENCE	140.000	LF
9031010	CONCRETE FOOTINGS, EMBEDDED	0.800	CUYD
9031220	PIPE POSTS	90.000	LB
9031241	BREAKAWAY ASSEMBLY (PERFORATED SQUARE STEEL TUBE)	2.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-A01

Item No.	Description	Quantity	Units
9031272A	2.25 IN. PSST POST INSERT (6 FT.) - 12 GA.	2.000	EA
9031280	2.5 IN. PSST POST - 12 GA.	101.000	LF
9031285	CONCRETE POST ANCHOR FOR 2.5 IN. PSST. - 7 GA.	9.000	EA
9035004A	SH-FLAT SHEET	137.000	SQFT

() Item will be bid as lump sum.



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-B01

Contract ID	Federal Project Number / State Project Number	Description
240517-B01		
FAF 47-1(83)	J2P3043	
J2P3043 - ROUTE 47 - LINCOLN COUNTY		
FAF 47-1(83)	J2P3043	
Bridge replacement, interchange and ADA improvements		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-B01

Contract ID: 240517-B01

Letting Date: May 17, 2024 11:00 AM

Projects: J2P3043

FAF 47-1(83)

Counties: LINCOLN

District: Northeast

DBE Goal Percent: 8.00

Description: ****(1): Job J2P3043 Route 47 LINCOLN County. Bridge replacement, interchange and ADA improvements at Route 61 in Troy, the total length of improvement being 1.385 miles.

Contract Time: DT - 10/31/2025

Item No.	Description	Quantity	Units
2010000	MOWING	9.800	ACRE
2013000	CLEARING AND GRUBBING	5.000	ACRE
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2031000	CLASS A EXCAVATION	21,111.000	CUYD
2035000	UNCLASSIFIED EXCAVATION	14,322.000	CUYD
2035500	EMBANKMENT IN PLACE	35,554.000	CUYD
2036000	COMPACTING EMBANKMENT	30,118.000	CUYD
2063000	CLASS 3 EXCAVATION	1,898.000	CUYD
2063300	CLASS 4 EXCAVATION	145.000	CUYD
2065500	TEMPORARY SHORING	1.000	LS
2071000	LINEAR GRADING CLASS 1	14.300	STA
2142000	FURNISHING ROCK FILL	4,454.000	CUYD
2143000	PLACING ROCK FILL	4,454.000	CUYD
2163500	PARTIAL REMOVAL OF CULVERT CONCRETE	1.000	LS
3030600	FURNISHING ROCK BASE MATERIAL	33,552.000	SQYD
3030610A	PLACING ROCK BASE	33,552.000	SQYD
3040506	TYPE 5 AGGREGATE FOR BASE (6 IN. THICK)	9,930.000	SQYD
4019905	MISC. TEMPORARY ASPHALT SURFACE	1,110.000	SQYD



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-B01

Item No.	Description	Quantity	Units
	MODIFICATION		
4019905	MISC. TEMPORARY OPTIONAL PAVEMENT AND BASE	4,636.000	SQYD
4030116	ASPHALTIC CONCRETE MIXTURE PG 76-22 (SP125B MIX)	2,092.700	TONS
5021310	CONCRETE PAVEMENT (10 IN. NON-REINFORCED 15 FT. JOINTS)	15,718.500	SQYD
5021340	TYPE A2 SHOULDER	422.300	SQYD
5041000	CONCRETE APPROACH PAVEMENT	466.500	SQYD
6044011	PIPE COLLAR, TYPE A	4.000	EA
6071012A	CHAIN-LINK FENCE (60 IN.)	505.000	LF
6081010	CONCRETE CURB RAMP	188.800	SQYD
6081012	TRUNCATED DOMES	483.000	SQFT
6083008	8 IN. CONCRETE MEDIAN STRIP	2,220.200	SQYD
6085008	PAVED APPROACH, 8 IN.	661.700	SQYD
6086004	CONCRETE SIDEWALK, 4 IN.	3,140.700	SQYD
6091052	CURB AND GUTTER TYPE B	8,009.000	LF
6096010A	FURNISHING TYPE 1 ROCK DITCH LINER	194.000	CUYD
6096020	FURNISHING TYPE 2 ROCK DITCH LINER	168.000	CUYD
6096030A	FURNISHING TYPE 3 ROCK DITCH LINER	22.000	CUYD
6096041	PLACING TYPE 1 ROCK DITCH LINER	194.000	CUYD
6096042	PLACING TYPE 2 ROCK DITCH LINER	168.000	CUYD
6096043	PLACING TYPE 3 ROCK DITCH LINER	22.000	CUYD
6096050	BEDDING MATERIAL FOR ROCK DITCH LINER	8.000	CUYD
6097000	ROCK LINING	341.000	CUYD
6113020	FURNISHING TYPE 2 ROCK BLANKET	2,941.000	CUYD
6113040	PLACING TYPE 2 ROCK BLANKET	2,941.000	CUYD
6122009	IMPACT ATTENUATOR 45 MPH (SAND BARREL	2.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-B01

Item No.	Description	Quantity	Units
6122014	ARRAY IMPACT ATTENUATOR 60 MPH (SAND BARREL ARRAY)	4.000	EA
6122020	REPLACEMENT SAND BARREL	16.000	EA
6122030	IMPACT ATTENUATOR (RELOCATION)	10.000	EA
6122040	WORK ZONE CRASH CUSHION (NARROW)	8.000	EA
6122041	WORK ZONE CRASH CUSHION (NARROW) (RELOCATION)	24.000	EA
6123001	TRUCK MOUNTED ATTENUATOR (TMA)	1.000	LS
6141023	GRATE AND BEARING PLATE (5 FT. X 2 FT. OR 1524 MM X 610 MM)	2.000	EA
6143011	MANHOLE FRAME AND COVER, TYPE 1-B	2.000	EA
6143012	MANHOLE FRAME AND COVER, TYPE 2	7.000	EA
6143013	MANHOLE FRAME AND COVER, TYPE 3	35.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	6.000	EA
6162002	TEMPORARY LONG-TERM RUMBLE STRIPS	38.000	EA
6169901	MISC. LUMP SUM TEMPORARY TRAFFIC CONTROL	1.000	LS
6169902	MISC. ADA COMPLIANT BARRICADE	12.000	EA
6173100	CONCRETE TRAFFIC BARRIER, TYPE D	896.000	LF
6173600D	TEMPORARY TRAFFIC BARRIER, CONTRACTOR FURNISHED / RETAINED	4,475.000	LF
6173700B	TEMPORARY TRAFFIC BARRIER ANCHORED, CONTRACTOR FURNISHED / RETAINED	4,788.000	LF
6173706	TEMPORARY TRAFFIC BARRIER STIFFNESS TRANSITION SECTION, CONTRACTOR FURNISHED / RETAINED	850.000	LF
6175010A	RELOCATING TEMPORARY TRAFFIC BARRIER	950.000	LF
6175011B	RELOCATING TEMPORARY TRAFFIC BARRIER ANCHORED	1,175.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-B01

Item No.	Description	Quantity	Units
6181000	MOBILIZATION	1.000	LS
6191000	PAVEMENT EDGE TREATMENT	11,842.000	LF
6200012	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 12 IN WHITE	873.000	LF
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	446.000	LF
6200018	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. YELLOW	161.000	LF
6200021	PREFORMED THERMOPLASTIC PAVEMENT MARKING, LEFT/RIGHT ARROW	36.000	EA
6200024	PREFORMED THERMOPLASTIC PAVEMENT MARKING, STRAIGHT ARROW	27.000	EA
6200027	PREFORMED THERMOPLASTIC PAVEMENT MARKING, COMBINATION STR/LT/RT	4.000	EA
6200042	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 12 IN WHITE, YIELD LINE TRIANGLES	94.000	EA
6205901A	4 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	14,288.000	LF
6205902A	6 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	21,554.000	LF
6205903A	6 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	4,906.000	LF
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	758.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	7,336.000	LF
6207001	PAVEMENT MARKING REMOVAL	133,681.000	LF
6207002	PAVEMENT MARKING REMOVAL (SYMBOLS)	54.000	EA
6208063	TEMPORARY PAVEMENT MARKING	54.000	EA
6208076	4 IN TEMPORARY PAVEMENT MARKING PAINT	124,994.000	LF
6209902	MISC. PREFORMED THERMOPLASTIC PAVEMENT MARKING, LANE REDUCTION ARROW	2.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-B01

Item No.	Description	Quantity	Units
6221001	COLDMILLING BITUMINOUS PAVEMENT FOR REMOVAL OF SURFACING (3 IN. THICK OR LESS)	10,224.000	SQYD
6240101A	SUBSURFACE DRAINAGE GEOTEXTILE	1,739.000	SQYD
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	4,412.000	SQYD
6240104A	SEPARATION GEOTEXTILE	7,718.000	SQYD
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7034041	CLASS B-1 CONCRETE (CULVERTS)	274.400	CUYD
7061030	REINFORCING STEEL (CULVERTS)	34,170.000	LB
7201000	MECHANICALLY STABILIZED EARTH WALL SYSTEMS	1,316.000	SQFT
7250312A	12 IN. PIPE GROUP B	351.000	LF
7250318A	18 IN. PIPE GROUP B	411.000	LF
7250324A	24 IN. PIPE GROUP B	106.000	LF
7261012	12 IN. PIPE GROUP A	633.000	LF
7261018	18 IN. PIPE GROUP A	2,358.000	LF
7261030	30 IN. PIPE GROUP A	22.000	LF
7261048	48 IN. PIPE GROUP A	71.000	LF
7310048	PRECAST CONCRETE MANHOLE - 48 IN.	67.000	FT
7310060	PRECAST CONCRETE MANHOLE - 60 IN.	18.000	FT
7311030	PRECAST CONCRETE DROP INLET 3 FT X 2 FT-6 IN.	35.000	FT
7311033	PRECAST CONCRETE DROP INLET 3 FT X 3 FT	4.000	FT
7311052	PRECAST CONCRETE DROP INLET 5 FT X 2 FT	11.000	FT
7311053	PRECAST CONCRETE DROP INLET 5 FT X 3 FT	173.000	FT
7320012A	12 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION	1.000	EA
7320018A	18 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION	1.000	EA
7320024A	24 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION	2.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-B01

Item No.	Description	Quantity	Units
7320612A	12 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	10.000	EA
7320618A	18 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	3.000	EA
7320630A	30 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	2.000	EA
7320648A	48 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	2.000	EA
8025006	MULCHING	15.600	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	9.800	ACRE
8061004	SEDIMENT TRAP ROCK	17.000	CUYD
8061005	ROCK DITCH CHECK	192.000	LF
8061007A	CURB INLET CHECK	33.000	EA
8061016	SEDIMENT REMOVAL	113.000	CUYD
8061017	TEMPORARY SEEDING	9.800	ACRE
8061019	SILT FENCE	9,617.000	LF
8061020	TEMPORARY PIPE	110.000	LF
8064137	TYPE 2C EROSION CONTROL BLANKET	19,219.000	SQYD
4039905	MISC. 12.5 IN. THICK ASPHALTIC CONCRETE PAVEMENT, SP125B	14,366.500	SQYD
5021310	CONCRETE PAVEMENT (10 IN. NON-REINFORCED 15 FT. JOINTS)	14,366.500	SQYD
4019905	MISC. 9 IN. THICK BITUMINOUS PAVEMENT	7,273.100	SQYD
5021308	CONCRETE PAVEMENT (8 IN. NON-REINFORCED, 15 FT. JOINTS)	7,273.100	SQYD
4010150	TYPE A2 SHOULDER	2,250.000	SQYD
5021340	TYPE A2 SHOULDER	2,250.000	SQYD
6061040	GUARDRAIL TYPE D	125.000	LF
6061060	MGS GUARDRAIL	1,638.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-B01

Item No.	Description	Quantity	Units
6061067	MGS DOUBLE FACED GUARDRAIL	50.000	LF
6061070	MGS VERTICAL CONCRETE BARRIER TRANSITION	4.000	EA
6061080	MGS END ANCHOR	8.000	EA
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	8.000	EA
6063016	TYPE B CRASHWORTHY END TERMINAL	2.000	EA
9014003	CONDUIT, 3 IN. RIGID, PUSHED	500.000	LF
9015020	TRENCHING TYPE II	3,130.000	LF
9016110	PULL BOX, PREFORMED CLASS 1	14.000	EA
9017006	CABLE, 6 AWG 1 CONDUCTOR	3,090.000	LF
9017110	CABLE, 10 AWG 1 CONDUCTOR, POLE AND BRACKET	2,200.000	LF
9017206	WIRE, 6 AWG, BARE NEUTRAL	1,550.000	LF
9017404	CABLE-CONDUIT, 1 IN., 2 CONDUCTORS AND 1 BARE NEUTRAL, 6 AWG	3,270.000	LF
9018245	POLE FOUNDATION (45 FT. OR 13.5 M MOUNTING HEIGHT)	17.000	EA
9019902	MISC. 45' TOP MOUNT POLE	22.000	EA
9019902	MISC. COMBINATION PAD MOUNTED POWER SUPPLY AND LIGHTING CONTROL,240V LIGHTING ONLY	1.000	EA
9019902	MISC. LED B TOP MOUNTED LUMINAIRE	22.000	EA
9020113	SIGNAL HEAD, TYPE 3T	4.000	EA
9020213	SIGNAL HEAD, TYPE 3S	2.000	EA
9020513	SIGNAL HEAD, TYPE 3B	20.000	EA
9020514	SIGNAL HEAD, TYPE 4B	4.000	EA
9020833	SH-FLAT SHEET - SIGNAL SIGN	202.000	SQFT
9020834	SIGNAL SIGN, MOUNTING HARDWARE	24.000	EA
9022651	LUMINAIRE LED-A, 120 VOLT COMPATIBLE	8.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-B01

Item No.	Description	Quantity	Units
9022708	POST, SIGNAL 8 FT.	11.000	EA
9022715	POST, SIGNAL 15 FT.	2.000	EA
9023135	POST, TYPE CL, 35 FT. ARM OR 10.7 M ARM	3.000	EA
9023140	POST, TYPE CL, 40 FT. ARM OR 12.2 M ARM	1.000	EA
9023145	POST, TYPE CL, 45 FT. ARM OR 13.7 M ARM	1.000	EA
9023150	POST, TYPE CL, 50 FT. ARM OR 15.2 M ARM	1.000	EA
9023155	POST, TYPE CL, 55 FT. ARM	2.000	EA
9023235	POST, TYPE C, 35 FT. ARM OR 10.7 M ARM	1.000	EA
9023240	POST, TYPE C, 40 FT. ARM OR 12.2 M ARM	1.000	EA
9024283	CONTROLLER ASSEMBLY HOUSING, NEMA TS2 CONTROLLER ATC TRAFFIC SIGNAL CONTROLLER	3.000	EA
9024330	DIAL-UP MODEM	2.000	EA
9024340	SPREAD SPECTRUM TELEMETRY RADIO	2.000	EA
9024349	900 MHZ OMNIDIRECTIONAL ANTENNA, 9DB GAIN	2.000	EA
9024975	VIDEO DETECTION SYSTEM VIDEO DETECTION SYSTEM	2.000	EA
9025200	CONDUIT, 2 IN., TRENCH WITH TRACER WIRE	660.000	LF
9025300	CONDUIT, 3 IN., TRENCH WITH TRACER WIRE	540.000	LF
9027300	CONDUIT, 3 IN., PUSHED WITH TRACER WIRE	890.000	LF
9028100	CABLE, 10 AWG 1 CONDUCTOR, POLE AND BRACKET	1,020.000	LF
9028208	CABLE, 8 AWG 1 CONDUCTOR, POWER	700.000	LF
9028302	CABLE, 12 AWG 2 CONDUCTOR	3,100.000	LF
9028308	CABLE, 16 AWG 2 CONDUCTOR	4,900.000	LF
9028310	CABLE, 16 AWG 5 CONDUCTOR	4,990.000	LF
9028311	CABLE, 16 AWG 7 CONDUCTOR	11,370.000	LF
9028810	PULL BOX, PREFORMED CLASS 1	11.000	EA
9028821	PULL BOX, CONCRETE, DOUBLE, TYPE A	2.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-B01

Item No.	Description	Quantity	Units
9029100	BASE, CONCRETE	41.300	CUYD
9029901	MISC. TEMPORARY SIGNALS AND LIGHTING - CHERRY STAGE 2A-B	1.000	LS
9029901	MISC. TEMPORARY SIGNALS AND LIGHTING - CHERRY STAGE 2C-3B	1.000	LS
9029901	MISC. TEMPORARY SIGNALS AND LIGHTING - NB RAMP STAGE 2A-C	1.000	LS
9029901	MISC. TEMPORARY SIGNALS AND LIGHTING - NB RAMP STAGE 3A	1.000	LS
9029901	MISC. TEMPORARY SIGNALS AND LIGHTING - NB RAMP STAGE 3B	1.000	LS
9029901	MISC. TEMPORARY SIGNALS AND LIGHTING - OLD CAP	1.000	LS
9029901	MISC. TEMPORARY SIGNALS AND LIGHTING - SB RAMP STAGE 2A-B	1.000	LS
9029901	MISC. TEMPORARY SIGNALS AND LIGHTING - SB RAMP STAGE 3A-B	1.000	LS
9029901	MISC. TRAFFIC SIGNAL MAINTENANCE AND PROGRAMMING	1.000	LS
9029902	MISC. AUDIBLE PEDESTRIAN PUSHBUTTON AND SIGNING WITH VERBAL WALK MESSAGE	16.000	EA
9029902	MISC. COMBINATION PAD MOUNTED 120V/240V POWER SUPPLY AND LIGHTING CONTROLLER WITH UPS	2.000	EA
9029902	MISC. NETWORK CONNECTED SIGNAL MONITOR	3.000	EA
9031010	CONCRETE FOOTINGS, EMBEDDED	2.800	CUYD
9031020	CONCRETE FOOTINGS, BOLT DOWN	37.300	CUYD
9031210	STRUCTURAL STEEL POSTS	1,860.000	LB
9031220	PIPE POSTS	150.000	LB
9031250A	U-CHANNEL POST, 3 LB	56.000	LF
9031270A	2 IN. PSST POST - 12 GA.	600.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-B01

Item No.	Description	Quantity	Units
9031271A	DRIVEN POST ANCHOR FOR 2 IN. PSST - 12 GA.	39.000	EA
9031274	CONCRETE POST ANCHOR FOR 2 IN. PSST. - 7 GA.	4.000	EA
9031280	2.5 IN. PSST POST - 12 GA.	331.000	LF
9031281A	DRIVEN POST ANCHOR FOR 2.5 IN. PSST - 7 GA.	19.000	EA
9031285	CONCRETE POST ANCHOR FOR 2.5 IN. PSST. - 7 GA.	4.000	EA
9035004A	SH-FLAT SHEET	718.000	SQFT
9035011A	ST-STRUCTURAL	899.000	SQFT
9035069A	SHF-FLAT SHEET FLUORESCENT	294.000	SQFT
9039901	MISC. TUBULAR SUPPORT, TYPE S-2318-55	1.000	LS
9039901	MISC. TUBULAR SUPPORT, TYPE S-27718-62	1.000	LS
9039901	MISC. TUBULAR SUPPORT, TYPE S-27718-70	1.000	LS
9039901	MISC. TUBULAR SUPPORT, TYPE S-27718-72	1.000	LS
2024043	REMOVAL OF MISCELLANEOUS ACM (NON-FRIABLE)	23.000	SQFT
2061000	CLASS 1 EXCAVATION	274.000	CUYD
2160500	REMOVAL OF BRIDGES	1.000	LS
5031010A	BRIDGE APPROACH SLAB (MAJOR)	424.000	SQYD
7021212	GALVANIZED STRUCTURAL STEEL PILES (12 IN)	2,531.000	LF
7025002	PILE WAVE ANALYSIS	3.000	EA
7027000	PILE POINT REINFORCEMENT	50.000	EA
7032003	CLASS B CONCRETE (SUBSTRUCTURE)	246.100	CUYD
7034219A	TYPE D BARRIER	1,122.000	LF
7034221	SLAB ON CONCRETE NU-GIRDER	2,494.000	SQYD
7056023	NU 53, PRESTRESSED CONCRETE NU-GIRDER	2,145.000	LF
7061060	REINFORCING STEEL (BRIDGES)	40,780.000	LB
7061070	MECHANICAL BAR SPLICE	1,111.000	EA
7071000	CONDUIT SYSTEM ON STRUCTURE	1.000	LS



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-B01

Item No.	Description	Quantity	Units
7123301	STEEL INTERMEDIATE DIAPHRAGM FOR P/S CONCRETE GIRDERS	32.000	EA
7123610	SLAB DRAIN	22.000	EA
7151001	VERTICAL DRAIN AT END BENTS	2.000	EA
7161000	PLAIN NEOPRENE BEARING PAD	18.000	EA
7161003	LAMINATED NEOPRENE BEARING PAD (TAPERED)	18.000	EA

() Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
240517-B02		
FAF 6-3(15)	JNE0183	
JNE0183 - ROUTE 6 - MARION COUNTY		
FAF 6-3(15)	JNE0183	
Bridge superstructure replacement		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-B02

Contract ID: 240517-B02

Letting Date: May 17, 2024 11:00 AM

Projects: JNE0183

FAF 6-3(15)

Counties: MARION

District: Northeast

DBE Goal Percent: 6.00

Description: ****(1): Job JNE0183 Route 6 MARION County. Bridge superstructure replacement over Route 24/61 near Taylor, the total length of improvement being 0.087 miles.

Contract Time: DT - 6/30/2025

Item No.	Description	Quantity	Units
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2153000	SHAPING SLOPES, CLASS III	6.000	100F
3040143	TYPE 1 AGGREGATE FOR BASE (4 IN. THICK)	324.000	SQYD
5021108	CONCRETE PAVEMENT (8 IN. NON-REINF)	323.300	SQYD
5041000	CONCRETE APPROACH PAVEMENT	133.400	SQYD
6113020	FURNISHING TYPE 2 ROCK BLANKET	280.000	CUYD
6113040	PLACING TYPE 2 ROCK BLANKET	280.000	CUYD
6122017	IMPACT ATTENUATOR 65 MPH (SAND BARREL ARRAY)	2.000	EA
6122020	REPLACEMENT SAND BARREL	2.000	EA
6122030	IMPACT ATTENUATOR (RELOCATION)	2.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	8.000	EA
6169901	MISC. TEMPORARY TRAFFIC CONTROL LUMP SUM	1.000	LS
6173600D	TEMPORARY TRAFFIC BARRIER, CONTRACTOR FURNISHED / RETAINED	364.000	LF
6175010A	RELOCATING TEMPORARY TRAFFIC BARRIER	284.000	LF
6181000	MOBILIZATION	1.000	LS



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-B02

Item No.	Description	Quantity	Units
6205901A	4 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS 6 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	770.000	LF
6205902A	6 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	770.000	LF
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	475.000	SQYD
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
8025006	MULCHING	0.200	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	0.200	ACRE
8061016	SEDIMENT REMOVAL	10.000	CUYD
8061019	SILT FENCE	946.000	LF
6061060	MGS GUARDRAIL	375.000	LF
6061069	MGS BRIDGE APPROACH TRANSITION SECTION (REGULAR/NO CURB)	4.000	EA
6061080	MGS END ANCHOR	2.000	EA
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	2.000	EA
2024043	REMOVAL OF MISCELLANEOUS ACM (NON-FRIABLE)	24.000	SQFT
2169901	MISC. REMOVAL OF EXISTING SUPERSTRUCTURE	1.000	LS
5031010A	BRIDGE APPROACH SLAB (MAJOR)	182.000	SQYD
7032003	CLASS B CONCRETE (SUBSTRUCTURE)	27.900	CUYD
7034212	SLAB ON STEEL	1,164.000	SQYD
7034219A	TYPE D BARRIER	539.000	LF
7040101	SUBSTRUCTURE REPAIR (FORMED)	25.000	SQFT
7040102	SUBSTRUCTURE REPAIR (UNFORMED)	19.000	SQFT
7101000	REINFORCING STEEL (EPOXY COATED)	5,680.000	LB
7110200	PROTECTIVE COATING - CONCRETE BENTS AND PIERS (EPOXY)	1.000	LS



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-B02

Item No.	Description	Quantity	Units
7121121	FABRICATED STRUCTURAL LOW ALLOY STEEL (PLATE GIRDER) A709, GRADE 50	254,380.000	LB
7125365A	INTERMEDIATE FIELD COAT (SYSTEM G)	10,200.000	SQFT
7125370A	FINISH FIELD COAT (SYSTEM G)	2,400.000	SQFT
7161002	LAMINATED NEOPRENE BEARING PAD	30.000	EA
7162000	LAMINATED NEOPRENE BEARING PAD ASSEMBLY	5.000	EA

() Item will be bid as lump sum.



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-B03

Contract ID	Federal Project Number / State Project Number	Description
240517-B03		
FAF 54-4(68)	JNE0205	
JNE0205 - ROUTE 54 - AUDRAIN COUNTY		
FAF 54-4(68)	JNE0205	
Centerline rumble strip		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-B03

Contract ID: 240517-B03

Letting Date: May 17, 2024 11:00 AM

Projects: JNE0205

FAF 54-4(68)

Counties: AUDRAIN

District: Northeast

DBE Goal Percent:

Description: ****(1): Job JNE0205 Route 54 AUDRAIN County. Centerline rumble strip from 0.3 mile south of BU 54 to 0.6 mile north of Route 15 in Mexico, the total length of improvement being 3.353 miles.

Contract Time: DT - 11/1/2024

Item No.	Description	Quantity	Units
6169901	MISC. LUMP SUM TEMPORARY TRAFFIC CONTROL	1.000	LS
6181000	MOBILIZATION	1.000	LS
6205901A	4 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	18,212.000	LF
6262001	PORTLAND CEMENT CONCRETE CENTERLINE RUMBLE STRIP	177.100	STA

() Item will be bid as lump sum.



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-B04

Contract ID	Federal Project Number / State Project Number	Description
240517-B04		
FAS S203(34)	JNE0226	
JNE0226 - ROUTE A - ADAIR COUNTY		
FAS S203(34)	JNE0226	
Bridge removal		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-B04

Contract ID: 240517-B04

Letting Date: May 17, 2024 11:00 AM

Projects: JNE0226

FAS S203(34)

Counties: ADAIR

District: Northeast

DBE Goal Percent:

Description: ****(1): Job JNE0226 Route A ADAIR County. Bridge removal over North Fork South Fabius River, the total length of improvement being 0.047 miles.

Contract Time: DT - 7/14/2024

Item No.	Description	Quantity	Units
6181000	MOBILIZATION	1.000	LS
8059901	MISC. SEEDING AND MULCHING	1.000	LS
2160500	REMOVAL OF BRIDGES	1.000	LS

() Item will be bid as lump sum.



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-C02

Contract ID	Federal Project Number / State Project Number	Description
240517-C02		
FAF 7-1(48)	J4P3268C	
J4P3268C - ROUTE 7, VV - CASS COUNTY		
FAF 7-1(48)	J4P3268C	
ADA improvements		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-C02

Contract ID: 240517-C02

Letting Date: May 17, 2024 11:00 AM

Projects: J4P3268C

FAF 7-1(48)

Counties: CASS

District: Kansas City

DBE Goal Percent: 6.00

Description: ****(1): Job J4P3268C Route 7, VV CASS County. ADA improvements from 163rd Street to Richland Parkway and from Route 7 to Lexington Road, the total length of improvement being 2.701 miles.

Contract Time: DT - 11/1/2025

Item No.	Description	Quantity	Units
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2071000	LINEAR GRADING CLASS 1	233.600	STA
3040504	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK)	6,380.000	SQYD
6081010	CONCRETE CURB RAMP	2,061.200	SQYD
6081012	TRUNCATED DOMES	677.000	SQFT
6085007	PAVED APPROACH, 7 IN.	1,035.900	SQYD
6085008	PAVED APPROACH, 8 IN.	5,341.800	SQYD
6086004	CONCRETE SIDEWALK, 4 IN.	10,431.200	SQYD
6091052	CURB AND GUTTER TYPE B	37.000	LF
6092011	INTEGRAL CURB (6 IN. HEIGHT AND UNDER) TYPE A	154.000	LF
6099903	MISC. APWA CURB AND GUTTER TYPE CG-1	485.000	LF
6161005	CONSTRUCTION SIGNS	630.000	SQFT
6161025	CHANNELIZER (TRIM LINE)	200.000	EA
6169902	MISC. ADA COMPLIANT MOVEABLE BARRICADE	6.000	EA
6181000	MOBILIZATION	1.000	LS
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-C02

Item No.	Description	Quantity	Units
8025006	MULCHING	1.200	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	1.200	ACRE
8061005	ROCK DITCH CHECK	540.000	LF
8061007A	CURB INLET CHECK	87.000	EA
8061016	SEDIMENT REMOVAL	168.000	CUYD
8061019	SILT FENCE	5,996.000	LF
9020811	SIGNAL HEAD, TYPE 1S, PEDESTRIAN	24.000	EA
9020833	SH-FLAT SHEET - SIGNAL SIGN	24.000	SQFT
9020834	SIGNAL SIGN, MOUNTING HARDWARE	24.000	EA
9022708	POST, SIGNAL 8 FT.	7.000	EA
9024920	DETECTOR, PUSHBUTTON	24.000	EA
9025300	CONDUIT, 3 IN., TRENCH WITH TRACER WIRE	112.000	LF
9027300	CONDUIT, 3 IN., PUSHED WITH TRACER WIRE	82.000	LF
9028308	CABLE, 16 AWG 2 CONDUCTOR	1,890.000	LF
9028310	CABLE, 16 AWG 5 CONDUCTOR	920.000	LF
9029100	BASE, CONCRETE	3.100	CUYD

() Item will be bid as lump sum.



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-C03

Contract ID
Federal Project Number / State Project Number
Description

240517-C03	
FAF 58-1(41)	J4P3268D
J4P3268D - Route 58, 2, 7, A, O, OUTER ROAD 71 - CASS COUNTY	
FAF 58-1(41)	J4P3268D
ADA improvements	



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-C03

Contract ID: 240517-C03

Letting Date: May 17, 2024 11:00 AM

Projects: J4P3268D

FAF 58-1(41)

Counties: CASS

District: Kansas City

DBE Goal Percent: 6.00

Description: ****(1): Job J4P3268D Route 58, 2, 7, 71, A, O CASS County. ADA improvements at various locations in Cass County, the total length of improvement being 2.907 miles.

Contract Time: DT - 12/31/2025

Item No.	Description	Quantity	Units
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2029903	MISC. SIDEWALK MANICURING	211.000	LF
2035500	EMBANKMENT IN PLACE	85.000	CUYD
2063000	CLASS 3 EXCAVATION	101.000	CUYD
2063300	CLASS 4 EXCAVATION	25.000	CUYD
2071000	LINEAR GRADING CLASS 1	6.400	STA
2079909	MISC. LINEAR GRADING FOR SIDEWALKS	86.500	STA
2163500	PARTIAL REMOVAL OF CULVERT CONCRETE	1.000	LS
3040504	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK)	1,795.000	SQYD
3105003	GRAVEL (A) OR CRUSHED STONE (B)	8.000	SQYD
6044011	PIPE COLLAR, TYPE A	2.000	EA
6081010	CONCRETE CURB RAMP	1,473.900	SQYD
6081012	TRUNCATED DOMES	1,017.000	SQFT
6083003	3 IN. CONCRETE MEDIAN STRIP	20.200	SQYD
6083006	6 IN. CONCRETE MEDIAN STRIP	212.400	SQYD
6084023	SIDEWALK HAND-RAILING WITHOUT BALUSTERS	251.000	LF
6085007	PAVED APPROACH, 7 IN.	799.500	SQYD
6085008	PAVED APPROACH, 8 IN.	301.200	SQYD



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-C03

Item No.	Description	Quantity	Units
6086004	CONCRETE SIDEWALK, 4 IN.	3,411.800	SQYD
6091010	CONCRETE CURB (6 IN. HEIGHT AND UNDER) TYPE S	600.000	LF
6091052	CURB AND GUTTER TYPE B	1,435.000	LF
6096020	FURNISHING TYPE 2 ROCK DITCH LINER	10.000	CUYD
6096042	PLACING TYPE 2 ROCK DITCH LINER	10.000	CUYD
6099903	MISC. MODIFIED TYPE A GUTTER WITH STEEL PLATE	14.000	LF
6099903	MISC. MODIFIED TYPE A MOUNTABLE CURB AND GUTTER	148.000	LF
6099903	MISC. MODIFIED TYPE S CURB	10.000	LF
6123001	TRUCK MOUNTED ATTENUATOR (TMA)	1.000	LS
6161005	CONSTRUCTION SIGNS	268.500	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	2.000	EA
6161025	CHANNELIZER (TRIM LINE)	75.000	EA
6161030	TYPE III MOVEABLE BARRICADE	6.000	EA
6161040	FLASHING ARROW PANEL	1.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	2.000	EA
6181000	MOBILIZATION	1.000	LS
6200003	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 4 IN., WHITE	52.000	LF
6200006	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 4 IN YELLOW	91.000	LF
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	227.000	LF
6200021	PREFORMED THERMOPLASTIC PAVEMENT MARKING, LEFT/RIGHT ARROW	1.000	EA
6200036	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 30 IN WHITE MIDBLOCK	269.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-C03

Item No.	Description	Quantity	Units
6200042	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 12 IN WHITE, YIELD LINE TRIANGLES	9.000	EA
6207001	PAVEMENT MARKING REMOVAL	584.000	LF
6207002	PAVEMENT MARKING REMOVAL (SYMBOLS)	105.000	EA
6209902	MISC. PREFORMED THERMOPLASTIC PAVEMENT MARKING, WORD (STOP)	1.000	EA
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7034041	CLASS B-1 CONCRETE (CULVERTS)	17.100	CUYD
7061030	REINFORCING STEEL (CULVERTS)	2,860.000	LB
7250412	12 IN. PIPE GROUP C	41.000	LF
7250415	15 IN. PIPE GROUP C	496.000	LF
7250418	18 IN. PIPE GROUP C	53.000	LF
7250424	24 IN. PIPE GROUP C	46.000	LF
7261018	18 IN. PIPE GROUP A	26.000	LF
7320618A	18 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	2.000	EA
7320818A	18 IN. OR ALLOWED SUBSTITUTE GROUP C FLARED END SECTION	2.000	EA
7320824A	24 IN. OR ALLOWED SUBSTITUTE GROUP C FLARED END SECTION	2.000	EA
8025006	MULCHING	1.300	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	1.300	ACRE
8061006	ALTERNATE DITCH CHECK	165.000	LF
8061007A	CURB INLET CHECK	29.000	EA
8061016	SEDIMENT REMOVAL	83.000	CUYD
9011010	RELOCATED POLE	1.000	EA
9017407	CABLE-CONDUIT, 1 IN., 2 CONDUCTORS AND 1 BARE NEUTRAL, 8 AWG	20.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-C03

Item No.	Description	Quantity	Units
9018245	POLE FOUNDATION (45 FT. OR 13.5 M MOUNTING HEIGHT)	1.000	EA
9020833	SH-FLAT SHEET - SIGNAL SIGN	6.000	SQFT
9020834	SIGNAL SIGN, MOUNTING HARDWARE	6.000	EA
9021211	SIGNAL HEAD, OPTICALLY LIMITED, TYPE 1S	5.000	EA
9022708	POST, SIGNAL 8 FT.	13.000	EA
9025020	CONDUIT, 1 IN., LOOP DETECTOR WITH TRACER WIRE	22.000	LF
9025300	CONDUIT, 3 IN., TRENCH WITH TRACER WIRE	326.000	LF
9027300	CONDUIT, 3 IN., PUSHED WITH TRACER WIRE	48.000	LF
9028308	CABLE, 16 AWG 2 CONDUCTOR	3,770.000	LF
9028310	CABLE, 16 AWG 5 CONDUCTOR	3,790.000	LF
9028500	CABLE, LOOP DETECTOR, IN DUCT	1,290.000	LF
9028811	PULL BOX, PREFORMED CLASS 2	1.000	EA
9029100	BASE, CONCRETE	8.800	CUYD
9029902	MISC. ADJUST PUSH BUTTON, RAISE/LOWER	3.000	EA
9029902	MISC. ADJUST SIGNAL PULL BOX	2.000	EA
9029902	MISC. ADJUST VEHICLE DETECTION ZONE	13.000	EA
9029902	MISC. DETECTOR, PUSH BUTTON (APS)	7.000	EA
9029902	MISC. RELOCATE COUNTDOWN PEDESTRIAN SIGNAL HEAD	8.000	EA
9029902	MISC. RELOCATE PEDESTRIAN SIGNAL POST	7.000	EA
9029902	MISC. RELOCATE PUSH BUTTON TO NEW POST	11.000	EA
9031280	2.5 IN. PSST POST - 12 GA.	384.000	LF
9031281A	DRIVEN POST ANCHOR FOR 2.5 IN. PSST - 7 GA.	21.000	EA
9031285	CONCRETE POST ANCHOR FOR 2.5 IN. PSST. - 7 GA.	3.000	EA
9035004A	SH-FLAT SHEET	8.000	SQFT
9035069A	SHF-FLAT SHEET FLUORESCENT	148.000	SQFT



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-C03

Item No.	Description	Quantity	Units
9039902	MISC. INSTALL BUTTON FOR RRFB ON SIGN POST	4.000	EA
9039902	MISC. INSTALL RECTANGULAR RAPID FLASHING BEACON	4.000	EA
9039902	MISC. RELOCATE RECTANGULAR RAPID FLASHING BEACON ASSEMBLY	2.000	EA

() Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
240517-C04		
FAS S303(79)	J4S3454	
J4S3454 - ROUTE Z - PLATTE COUNTY		
FAS S303(79)	J4S3454	
Bridge replacement		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-C04

Contract ID: 240517-C04

Letting Date: May 17, 2024 11:00 AM

Projects: J4S3454

FAS S303(79)

Counties: PLATTE

District: Kansas City

DBE Goal Percent: 4.00

Description: ****(1): Job J4S3454 Route Z PLATTE County. Bridge replacement over the Platte River in Edgerton, the total length of improvement being 0.33 miles.

Contract Time: DT - 7/8/2025 Days

Item No.	Description	Quantity	Units
2013000	CLEARING AND GRUBBING	1.000	ACRE
2019901	MISC. TREE AND LIMB TRIMING (LUMP SUM)	1.000	LS
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2031000	CLASS A EXCAVATION	1,671.000	CUYD
2035500	EMBANKMENT IN PLACE	2,983.000	CUYD
2036000	COMPACTING EMBANKMENT	844.000	CUYD
2063000	CLASS 3 EXCAVATION	210.000	CUYD
2072000	LINEAR GRADING CLASS 2	1.000	STA
2101006A	SUBGRADE COMPACTION (6-INCH DEPTH)	9.000	100F
3040143	TYPE 1 AGGREGATE FOR BASE (4 IN. THICK)	2,611.000	SQYD
3107003	GRAVEL (A) OR CRUSHED STONE (B) OR CHAT (C)	237.000	SQYD
4019905	MISC. OPTIONAL PAVEMENT {ROUTE Z}	2,486.400	SQYD
6096010A	FURNISHING TYPE 1 ROCK DITCH LINER	38.000	CUYD
6096041	PLACING TYPE 1 ROCK DITCH LINER	38.000	CUYD
6097000	ROCK LINING	4.000	CUYD
6113020	FURNISHING TYPE 2 ROCK BLANKET	513.000	CUYD
6113040	PLACING TYPE 2 ROCK BLANKET	513.000	CUYD
6161005	CONSTRUCTION SIGNS	1,039.000	SQFT



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-C04

Item No.	Description	Quantity	Units
6161008	ADVANCED WARNING RAIL SYSTEM	4.000	EA
6161012	BUOYS (BOATS KEEP OUT)	8.000	EA
6161013	BUOYS (NO WAKE)	6.000	EA
6161014	SPECIAL SIGN ASSEMBLY (BOATS KEEP OUT)	4.000	EA
6161025	CHANNELIZER (TRIM LINE)	26.000	EA
6161030	TYPE III MOVEABLE BARRICADE	12.000	EA
6161099	CHANGEABLE MESSAGE SIGN WITH COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	4.000	EA
6181000	MOBILIZATION	1.000	LS
6181020	ADDITIONAL MOBILIZATION FOR SEEDING	2.000	EA
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	3,526.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	3,254.000	LF
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	820.000	SQYD
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7250415	15 IN. PIPE GROUP C	27.000	LF
7250424	24 IN. PIPE GROUP C	20.000	LF
7261030	30 IN. PIPE GROUP A	75.000	LF
7320630A	30 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	2.000	EA
7320815A	15 IN. OR ALLOWED SUBSTITUTE GROUP C FLARED END SECTION	2.000	EA
7320824A	24 IN. OR ALLOWED SUBSTITUTE GROUP C FLARED END SECTION	2.000	EA
8025006	MULCHING	3.100	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	3.100	ACRE
8061003	SEDIMENT TRAP EXCAVATION	14.000	CUYD



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-C04

Item No.	Description	Quantity	Units
8061004	SEDIMENT TRAP ROCK	14.000	CUYD
8061005	ROCK DITCH CHECK	280.000	LF
8061016	SEDIMENT REMOVAL	66.000	CUYD
8061017	TEMPORARY SEEDING	0.700	ACRE
8061019	SILT FENCE	3,370.000	LF
8061050	TYPE C BERM	295.000	LF
8064129	TYPE 2 TURF REINFORCEMENT MAT	2,124.000	SQYD
6061060	MGS GUARDRAIL	188.000	LF
6061069	MGS BRIDGE APPROACH TRANSITION SECTION (REGULAR/NO CURB)	4.000	EA
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	4.000	EA
2024043	REMOVAL OF MISCELLANEOUS ACM (NON-FRIABLE)	74.000	SQFT
2061000	CLASS 1 EXCAVATION	115.000	CUYD
2160500	REMOVAL OF BRIDGES	1.000	LS
5031011A	BRIDGE APPROACH SLAB (MINOR ROAD)	117.000	SQYD
7011111	DRILLED SHAFTS (6 FT. 6 IN. DIA.)	147.000	LF
7011210	ROCK SOCKETS (6 FT 0 IN. DIA.)	64.000	LF
7011300	VIDEO CAMERA INSPECTION	4.000	EA
7011400	FOUNDATION INSPECTION HOLES	116.000	LF
7011600	SONIC LOGGING TESTING	4.000	EA
7021214	GALVANIZED STRUCTURAL STEEL PILES (14 IN)	468.000	LF
7021324	GALVANIZED CAST-IN-PLACE CONCRETE PILES (24 IN)	1,452.000	LF
7025001	DYNAMIC PILE TESTING	4.000	EA
7029902	MISC. PILE POINT REINFORCEMENT (CIP-PILE)	24.000	EA
7029902	MISC. PILE POINT REINFORCEMENT (H-PIPE)	12.000	EA
7032003	CLASS B CONCRETE (SUBSTRUCTURE)	255.400	CUYD



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-C04

Item No.	Description	Quantity	Units
7034219A	TYPE D BARRIER	1,759.000	LF
7034221	SLAB ON CONCRETE NU-GIRDER	2,697.000	SQYD
7056023	NU 53, PRESTRESSED CONCRETE NU-GIRDER	1,369.000	LF
7056025	NU 70, PRESTRESSED CONCRETE NU-GIRDER	1,155.000	LF
7061060	REINFORCING STEEL (BRIDGES)	79,700.000	LB
7109911	MISC. REINFORCING STEEL (GALVANIZED)	3,750.000	LB
7110200	PROTECTIVE COATING - CONCRETE BENTS AND PIERS (EPOXY)	1.000	LS
7120900	EXPANSION DEVICE (FINGER PLATE)	27.000	LF
7123301	STEEL INTERMEDIATE DIAPHRAGM FOR P/S CONCRETE GIRDERS	28.000	EA
7123610	SLAB DRAIN	78.000	EA
7151001	VERTICAL DRAIN AT END BENTS	2.000	EA
7161002	LAMINATED NEOPRENE BEARING PAD	6.000	EA
7161003	LAMINATED NEOPRENE BEARING PAD (TAPERED)	30.000	EA
7163000	TYPE N PTFE BEARING	6.000	EA

() Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
-------------	-----------------------------------------------	-------------

240517-C05		
FAS S304(37)	JKU0033	
JKU0033 - LITTLE BLUE PARKWAY - JACKSON COUNTY		
FAS S304(37)	JKU0033	
ADA improvements, bridge rehabilitation, interchange and signal improvements		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-C05

Contract ID: 240517-C05

Letting Date: May 17, 2024 11:00 AM

Projects: JKU0033

FAS S304(37)

Counties: JACKSON

District: Kansas City

DBE Goal Percent: 8.00

Description: ****(1): Job JKU0033 Route Little Blue Pkwy JACKSON County. ADA improvements, bridge rehabilitation, interchange and signal improvements at I-70 near Independence, the total length of improvement being 0.261 miles.

Contract Time: DT - 12/17/2024

Item No.	Description	Quantity	Units
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2031000	CLASS A EXCAVATION	2,407.000	CUYD
2035500	EMBANKMENT IN PLACE	3,893.000	CUYD
2036000	COMPACTING EMBANKMENT	2,407.000	CUYD
2037075	COMPACTING IN CUT	34.700	STA
2063000	CLASS 3 EXCAVATION	4.000	CUYD
3040504	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK)	7,231.000	SQYD
5021312	CONCRETE PAVEMENT (12 IN. NON-REINFORCED 15 FT. JOINTS)	3,927.300	SQYD
5021333	CONCRETE PAVEMENT (9 1/2 IN. NON- REINFORCED, 15 FT. JOINTS)	1,912.400	SQYD
6044011	PIPE COLLAR, TYPE A	1.000	EA
6049902	MISC. ADJUST VALVE BOX	1.000	EA
6081010	CONCRETE CURB RAMP	84.900	SQYD
6081012	TRUNCATED DOMES	190.000	SQFT
6083004	4 IN. CONCRETE MEDIAN STRIP	508.900	SQYD
6083006	6 IN. CONCRETE MEDIAN STRIP	143.900	SQYD
6086004	CONCRETE SIDEWALK, 4 IN.	699.400	SQYD



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-C05

Item No.	Description	Quantity	Units
6091052	CURB AND GUTTER TYPE B	1,709.000	LF
6122008	IMPACT ATTENUATOR 40 MPH (SAND BARREL ARRAY)	1.000	EA
6161005	CONSTRUCTION SIGNS	932.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	10.000	EA
6161010	RELOCATED SIGNS	170.000	SQFT
6161025	CHANNELIZER (TRIM LINE)	252.000	EA
6161030	TYPE III MOVEABLE BARRICADE	7.000	EA
6161040	FLASHING ARROW PANEL	6.000	EA
6161055	SEQUENTIAL FLASHING WARNING LIGHT	60.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	2.000	EA
6173600D	TEMPORARY TRAFFIC BARRIER, CONTRACTOR FURNISHED / RETAINED	716.000	LF
6181000	MOBILIZATION	1.000	LS
6181020	ADDITIONAL MOBILIZATION FOR SEEDING	3.000	EA
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	249.000	LF
6200019	COLD APPLIED TAPE PAVEMENT MARKING, LEFT/RIGHT ARROW	48.000	EA
6200021	PREFORMED THERMOPLASTIC PAVEMENT MARKING, LEFT/RIGHT ARROW	35.000	EA
6200036	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 30 IN WHITE MIDBLOCK	39.000	EA
6205301B	TEMPORARY REMOVABLE MARKING TAPE 4 IN., WHITE	2,853.000	LF
6205303B	TEMPORARY REMOVABLE MARKING TAPE 4 IN., YELLOW	72.000	LF
6205309	TEMPORARY REMOVABLE MARKING TAPE, 24 IN., WHITE	36.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-C05

Item No.	Description	Quantity	Units
6205901A	4 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	542.000	LF
6205902A	6 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	9,635.000	LF
6205903A	6 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	3,564.000	LF
6207001	PAVEMENT MARKING REMOVAL	15,070.000	LF
6207002	PAVEMENT MARKING REMOVAL (SYMBOLS)	64.000	EA
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7261018	18 IN. PIPE GROUP A	6.000	LF
7320618A	18 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	1.000	EA
8025006	MULCHING	1.900	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	1.900	ACRE
8061005	ROCK DITCH CHECK	511.000	LF
8061007A	CURB INLET CHECK	5.000	EA
8061016	SEDIMENT REMOVAL	59.000	CUYD
8061017	TEMPORARY SEEDING	1.900	ACRE
8061019	SILT FENCE	3,517.000	LF
6062303	ASYMMETRICAL TRANSITION SECTION, 6.5 FT. POSTS	1.000	EA
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	1.000	EA
6063022	TYPE E CRASHWORTHY END TERMINAL (MASH)	1.000	EA
9011010	RELOCATED POLE	6.000	EA
9013502	CONDUIT, 2 IN. RIGID, MEDIAN	314.000	LF
9014003	CONDUIT, 3 IN. RIGID, PUSHED	211.000	LF
9014004	CONDUIT, 4 IN. RIGID, PUSHED	59.000	LF
9015010	TRENCHING TYPE I	3,000.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-C05

Item No.	Description	Quantity	Units
9016110	PULL BOX, PREFORMED CLASS 1	11.000	EA
9016111	PULL BOX, PREFORMED CLASS 2	2.000	EA
9017401	CABLE-CONDUIT, 1 IN., 2 CONDUCTORS AND 1 BARE NEUTRAL, 2 AWG	1,160.000	LF
9017402	CABLE-CONDUIT, 1 IN., 2 CONDUCTORS AND 1 BARE NEUTRAL, 4 AWG	2,380.000	LF
9018245	POLE FOUNDATION (45 FT. OR 13.5 M MOUNTING HEIGHT)	6.000	EA
9020513	SIGNAL HEAD, TYPE 3B	20.000	EA
9020833	SH-FLAT SHEET - SIGNAL SIGN	94.000	SQFT
9020834	SIGNAL SIGN, MOUNTING HARDWARE	11.000	EA
9021213	SIGNAL HEAD, OPTICALLY LIMITED, TYPE 3S	1.000	EA
9021413	SIGNAL HEAD, OPTICALLY LIMITED, TYPE 3B	2.000	EA
9022651	LUMINAIRE LED-A, 120 VOLT COMPATIBLE	7.000	EA
9022708	POST, SIGNAL 8 FT.	5.000	EA
9023115	POST, TYPE CL, 15 FT. ARM OR 4.6 M ARM	1.000	EA
9023130	POST, TYPE CL, 30 FT. ARM OR 9.1 M ARM	1.000	EA
9023135	POST, TYPE CL, 35 FT. ARM OR 10.7 M ARM	1.000	EA
9023155	POST, TYPE CL, 55 FT. ARM	3.000	EA
9023315	POST, TYPE B, LONGEST ARM 15 FT. OR 4.6 M	2.000	EA
9024283	CONTROLLER ASSEMBLY HOUSING, NEMA TS2 CONTROLLER	1.000	EA
9024921	ACCESSIBLE PEDESTRIAN SIGNAL	8.000	EA
9025300	CONDUIT, 3 IN., TRENCH WITH TRACER WIRE	1,024.000	LF
9027300	CONDUIT, 3 IN., PUSHED WITH TRACER WIRE	886.000	LF
9028100	CABLE, 10 AWG 1 CONDUCTOR, POLE AND BRACKET	620.000	LF
9028202	CABLE, 2 AWG 1 CONDUCTOR, POWER	110.000	LF
9028206	CABLE, 6 AWG 1 CONDUCTOR, POWER	60.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-C05

Item No.	Description	Quantity	Units
9028219	CABLE, 10 AWG 1 CONDUCTOR, POWER	9,780.000	LF
9028308	CABLE, 16 AWG 2 CONDUCTOR	5,450.000	LF
9028310	CABLE, 16 AWG 5 CONDUCTOR	5,460.000	LF
9028311	CABLE, 16 AWG 7 CONDUCTOR	11,230.000	LF
9028315	CABLE, 16 AWG 3-PAIR CONDUCTOR, INTERCONNECT	540.000	LF
9028810	PULL BOX, PREFORMED CLASS 1	4.000	EA
9028811	PULL BOX, PREFORMED CLASS 2	2.000	EA
9028812	PULL BOX, PREFORMED CLASS 3	8.000	EA
9029100	BASE, CONCRETE	24.100	CUYD
9029902	MISC. COUNTDOWN PEDESTRIAN SIGNAL HEAD, TYPE 1S	8.000	EA
9029902	MISC. KC DISTRICT VIDEO DETECTION SYSTEM	2.000	EA
9029901	MISC. OGL CCTV CAMERA SYSTEM	1.000	LS
9031010	CONCRETE FOOTINGS, EMBEDDED	2.900	CUYD
9031220	PIPE POSTS	980.000	LB
9031270A	2 IN. PSST POST - 12 GA.	265.000	LF
9031271A	DRIVEN POST ANCHOR FOR 2 IN. PSST - 12 GA.	25.000	EA
9035004A	SH-FLAT SHEET	55.000	SQFT
9039902	MISC. SIGNAGE REPLACEMENT / REMOVE & RESET	34.000	EA
9109902	MISC. REMOVING EXISTING SCOUT ITS PULL BOX	2.000	EA
9109903	MISC. LOWERING SCOUT ITS CONDUITS	40.000	LF
2163000	PARTIAL REMOVAL OF EXISTING BRIDGE DECK PARTIAL REMOVAL OF EXISTING BRIDGE DECK	1,095.000	SQFT
2169904	MISC. REMOVAL OF RAISED BRIDGE MEDIAN	1,595.000	SQFT
7034214	CLASS B-2 CONCRETE	31.100	CUYD
7049902	MISC. STEEL DIAPHRAGM & CROSSFRAME AT END & INTERMEDIATE BENTS	3.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-C05

Page 46 of 203

Item No.	Description	Quantity	Units
7101000	REINFORCING STEEL (EPOXY COATED)	8,740.000	LB

() Item will be bid as lump sum.



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-C06

Contract ID	Federal Project Number / State Project Number	Description
240517-C06		
FAS S304(42)	JKU0161	
JKU0161-VARIOUS ROUTES-VARIOUS COUNTIES		
FAS S304(42)	JKU0161	
Job Order Contract for guard cable and guardrail repair		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-C06

Contract ID: 240517-C06

Letting Date: May 17, 2024 11:00 AM

Projects: JKU0161

FAS S304(42)

Counties: CASS, CLAY, JACKSON, PLATTE

District: Kansas City

DBE Goal Percent:

Description: ****(1): Job JKU0161 Route Various CASS, CLAY, JACKSON, PLATTE County. Job Order Contract for guard cable and guardrail repair at various locations in the urban Kansas City District, the total length of improvement being 0 miles.

Contract Time: DT - 6/30/2025

Item No.	Description	Quantity	Units
6189916	MISC. Adjustment Factor	3,200,000.000	DLR

() Item will be bid as lump sum.



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-C07

Page 49 of 203

Contract ID

Federal Project Number / State Project Number

Description

240517-C07

JKUP0003

JKUP0003 - WESTON BENDSTATE PARK ROAD - PLATTE COUNTY

JKUP0003

Resurface



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-C07

Contract ID: 240517-C07

Letting Date: May 17, 2024 11:00 AM

Projects: JKUP0003

JKUP0003

Counties: PLATTE

District: Kansas City

DBE Goal Percent:

Description: ****(1): Job JKUP0003 Route WESTON BEND ST PARK PLATTE County. Resurface in Weston Bend State Park, the total length of improvement being 3.1405 miles.

Contract Time: DT - 6/1/2025

Item No.	Description	Quantity	Units
3049910	MISC. PERMANENT AGGREGATE EDGE TREATMENT	40.600	TONS
4020520	BITUMINOUS PAVEMENT MIXTURE PG64-22 (SURFACE LEVELING)	2,723.600	TONS
4071005	TACK COAT	3,163.000	GAL
6161005	CONSTRUCTION SIGNS	352.000	SQFT
6161025	CHANNELIZER (TRIM LINE)	20.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	2.000	EA
6181000	MOBILIZATION	1.000	LS
6200024	PREFORMED THERMOPLASTIC PAVEMENT MARKING, STRAIGHT ARROW	14.000	EA
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	193.000	LF
6224010	MODIFIED COLDMILLING (DEPTH TRANSITIONS)	1,057.000	SQYD

() Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
240517-C08		
FAS-S303(034)	J4I3176	
		J4I3176-VARIOUS ROUTES-CLAY, CASS, JACKSON, PLATTE COUNTIES
FAS-S303(034)	J4I3176	
		Job Order Contract for bridge repair



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-C08

Contract ID: 240517-C08

Letting Date: May 17, 2024 11:00 AM

Projects: J4I3176

FAS-S303(034)

Counties: CASS, CLAY, JACKSON, PLATTE

District: Kansas City

DBE Goal Percent:

Description: ****(1): Job J4I3176 Route Various CASS, CLAY, JACKSON, PLATTE County. Job Order Contract for bridge repair on major and interstate routes in the urban Kansas City District, the total length of improvement being 0 miles.

Contract Time: DT - 6/30/2025

Item No.	Description	Quantity	Units
6189916	MISC. BRIDGE REPAIR	2,000,000.000	DLR

() Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
240517-D01		
FAF 19-1(18)	J5P3420	
J5P3420 - ROUTE 19 - DENT COUNTY		
FAF 19-1(18)	J5P3420	
Bridge replacement		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D01

Contract ID: 240517-D01

Letting Date: May 17, 2024 11:00 AM

Projects: J5P3420

FAF 19-1(18)

Counties: DENT

District: Central

DBE Goal Percent: 4.00

Description: ****(1): Job J5P3420 Route 19 DENT County. Bridge replacement on Route 19 over Standing Rock Creek, south of Salem, the total length of improvement being 0.206 miles.

Contract Time: DT - 5/1/2025 Days

Item No.	Description	Quantity	Units
2013000	CLEARING AND GRUBBING	1.000	ACRE
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2031000	CLASS A EXCAVATION	962.000	CUYD
2035500	EMBANKMENT IN PLACE	4,354.000	CUYD
2036000	COMPACTING EMBANKMENT	818.000	CUYD
2063000	CLASS 3 EXCAVATION	44.000	CUYD
3040143	TYPE 1 AGGREGATE FOR BASE (4 IN. THICK)	3,106.000	SQYD
3105002	GRAVEL (A) OR CRUSHED STONE (B)	307.000	TONS
4011209	BITUMINOUS PAVEMENT MIXTURE PG64-22, (BP-1) MISC. OPTIONAL PAVEMENT	95.000	TONS
4019905	MISC. MISC. OPTIONAL PAVEMENT	2,283.200	SQYD
4019905	MISC. OPTIONAL SHOULDER	415.100	SQYD
4019905	MISC. TEMPORARY PAVEMENT AND BASE	130.000	SQYD
6113020	FURNISHING TYPE 2 ROCK BLANKET	1,806.000	CUYD
6113040	PLACING TYPE 2 ROCK BLANKET	1,806.000	CUYD
6123001	TRUCK MOUNTED ATTENUATOR (TMA)	1.000	LS
6161005	CONSTRUCTION SIGNS	220.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	2.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D01

Item No.	Description	Quantity	Units
6161010	RELOCATED SIGNS	32.000	SQFT
6161025	CHANNELIZER (TRIM LINE)	35.000	EA
6161040	FLASHING ARROW PANEL	2.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	2.000	EA
6162000A	WORK ZONE TRAFFIC SIGNAL SYSTEM	1.000	EA
6162002	TEMPORARY LONG-TERM RUMBLE STRIPS	2.000	EA
6181000	MOBILIZATION	1.000	LS
6205309	TEMPORARY REMOVABLE MARKING TAPE, 24 IN., WHITE	28.000	LF
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	2,173.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	2,173.000	LF
6208076	4 IN TEMPORARY PAVEMENT MARKING PAINT	2,725.000	LF
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	2,710.000	SQYD
6261000A	BITUMINOUS SHOULDER RUMBLE STRIP	10.600	STA
6261001	BITUMINOUS CENTERLINE RUMBLE STRIP	9.300	STA
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7250415	15 IN. PIPE GROUP C	98.000	LF
7320815A	15 IN. OR ALLOWED SUBSTITUTE GROUP C FLARED END SECTION	4.000	EA
8025006	MULCHING	1.000	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	1.000	ACRE
8061003	SEDIMENT TRAP EXCAVATION	33.000	CUYD
8061004	SEDIMENT TRAP ROCK	33.000	CUYD
8061005	ROCK DITCH CHECK	30.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D01

Item No.	Description	Quantity	Units
8061016	SEDIMENT REMOVAL	73.000	CUYD
8061019	SILT FENCE	2,200.000	LF
6061060	MGS GUARDRAIL	150.000	LF
6061069	MGS BRIDGE APPROACH TRANSITION SECTION (REGULAR/NO CURB)	4.000	EA
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	4.000	EA
9031250A	U-CHANNEL POST, 3 LB	83.000	LF
9031280	2.5 IN. PSST POST - 12 GA.	15.000	LF
9031281A	DRIVEN POST ANCHOR FOR 2.5 IN. PSST - 7 GA.	1.000	EA
9035069A	SHF-FLAT SHEET FLUORESCENT	40.000	SQFT
2061000	CLASS 1 EXCAVATION	80.000	CUYD
2160500	REMOVAL OF BRIDGES	1.000	LS
5031011A	BRIDGE APPROACH SLAB (MINOR ROAD)	118.000	SQYD
7021314	GALVANIZED CAST-IN-PLACE CONCRETE PILES (14 IN)	440.000	LF
7025001	DYNAMIC PILE TESTING	10.000	EA
7027000	PILE POINT REINFORCEMENT	10.000	EA
7032003	CLASS B CONCRETE (SUBSTRUCTURE)	25.800	CUYD
7034219A	TYPE D BARRIER	267.000	LF
7034221	SLAB ON CONCRETE NU-GIRDER	358.000	SQYD
7056023	NU 53, PRESTRESSED CONCRETE NU-GIRDER	332.000	LF
7123301	STEEL INTERMEDIATE DIAPHRAGM FOR P/S CONCRETE GIRDERS	4.000	EA
7123610	SLAB DRAIN	22.000	EA
7151001	VERTICAL DRAIN AT END BENTS	2.000	EA
7161000	PLAIN NEOPRENE BEARING PAD	6.000	EA

() Item will be bid as lump sum.



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D04

Contract ID	Federal Project Number / State Project Number	Description
240517-D04		
FAF 50-3(112)	J5P3574	
J5P3574 - ROUTE 50, CC - OSAGE COUNTY		
FAF 50-3(112)	J5P3574	
Pavement widening, signals, ADA improvements and watermain relocation		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D04

Contract ID: 240517-D04

Letting Date: May 17, 2024 11:00 AM

Projects: J5P3574

FAF 50-3(112)

Counties: OSAGE

District: Central

DBE Goal Percent: 5.00

Description: ****(1): Job J5P3574 Route 50, CC OSAGE County. Pavement widening, signals, ADA improvements and watermain relocation at Route CC in Linn, the total length of improvement being 0.08 miles.

Contract Time: DT - 12/26/2024

Item No.	Description	Quantity	Units
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2031000	CLASS A EXCAVATION	6,690.000	CUYD
2036000	COMPACTING EMBANKMENT	1,618.000	CUYD
2063000	CLASS 3 EXCAVATION	778.000	CUYD
3040504	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK)	5,714.000	SQYD
3040506	TYPE 5 AGGREGATE FOR BASE (6 IN. THICK)	9,314.000	SQYD
4010106	6 INCHES, BITUMINOUS PAVEMENT	289.100	SQYD
4010150	TYPE A2 SHOULDER	998.600	SQYD
4030101	ASPHALTIC CONCRETE MIXTURE PG 64-22 (SP125C MIX)	2,053.900	TONS
4030306	ASPHALTIC CONCRETE MIXTURE PG 64-22 (SP250C MIX)	3,307.600	TONS
4039905	MISC. OPTIONAL PAVEMENT	2,688.400	SQYD
4071005	TACK COAT	752.000	GAL
5021331	CONCRETE PAVEMENT (7 1/2 IN. NON-REINFORCED, 15 FT. JOINTS)	1,099.000	SQYD
5029905	MISC. CONCRETE TRUCK APRON, 8"	314.600	SQYD
6044013	PIPE COLLAR, TYPE C	2.000	EA



Item No.	Description	Quantity	Units
6081000	CONCRETE MEDIAN	86.400	SQYD
6081010	CONCRETE CURB RAMP	52.000	SQYD
6081012	TRUNCATED DOMES	110.000	SQFT
6083006	6 IN. CONCRETE MEDIAN STRIP	64.200	SQYD
6085008	PAVED APPROACH, 8 IN.	1,004.800	SQYD
6091011	CONCRETE CURB (OVER 6 IN. HEIGHT) TYPE S	944.000	LF
6091052	CURB AND GUTTER TYPE B	1,167.000	LF
6092011	INTEGRAL CURB (6 IN. HEIGHT AND UNDER) TYPE A	157.000	LF
6092031	CONCRETE CURB LOW PROFILE TYPE E	210.900	LF
6096010A	FURNISHING TYPE 1 ROCK DITCH LINER	87.000	CUYD
6096020	FURNISHING TYPE 2 ROCK DITCH LINER	39.000	CUYD
6096030A	FURNISHING TYPE 3 ROCK DITCH LINER	57.000	CUYD
6096041	PLACING TYPE 1 ROCK DITCH LINER	87.000	CUYD
6096042	PLACING TYPE 2 ROCK DITCH LINER	39.000	CUYD
6096043	PLACING TYPE 3 ROCK DITCH LINER	57.000	CUYD
6097000	ROCK LINING	37.000	CUYD
6099903	MISC. CURB AND GUTTER, SPECIAL	1,519.000	LF
6141120	CURVED VANE GRATE AND FRAME (2 FT. X 2 FT. OR 600MM X 600MM)	3.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	6.000	EA
6162002	TEMPORARY LONG-TERM RUMBLE STRIPS	4.000	EA
6169901	MISC. LUMP SUM TEMPORARY TRAFFIC CONTROL	1.000	LS
6181000	MOBILIZATION	1.000	LS
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	621.000	LF
6200018	PREFORMED THERMOPLASTIC PAVEMENT	436.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D04

Item No.	Description	Quantity	Units
6200021	MARKING, 24 IN. YELLOW PERFORMED THERMOPLASTIC PAVEMENT MARKING, LEFT/RIGHT ARROW	29.000	EA
6200030	PERFORMED THERMOPLASTIC PAVEMENT MARKING, WORD (ONLY) PERFORMED THERMOPLASTIC PAVEMENT MARKING, "ONLY" SYMBOL	4.000	EA
6205301B	TEMPORARY REMOVABLE MARKING TAPE 4 IN., WHITE	8,130.000	LF
6205303B	TEMPORARY REMOVABLE MARKING TAPE 4 IN., YELLOW	9,000.000	LF
6205901A	4 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	11,750.000	LF
6205902A	6 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	11,060.000	LF
6207001	PAVEMENT MARKING REMOVAL	13,189.000	LF
6209901	MISC. TEMPORARY PAVEMENT MARKING PAINT	1.000	LS
6221001	COLDMILLING BITUMINOUS PAVEMENT FOR REMOVAL OF SURFACING (3 IN. THICK OR LESS)	15,027.000	SQYD
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7250315A	15 IN. PIPE GROUP B	22.000	LF
7261015	15 IN. PIPE GROUP A	513.000	LF
7261018	18 IN. PIPE GROUP A	198.000	LF
7261021	21 IN. PIPE GROUP A	188.000	LF
7261024	24 IN. PIPE GROUP A	442.000	LF
7261036	36 IN. PIPE GROUP A	40.000	LF
7269921	SEWER MISC. CULVERT EXTENSION	1.000	LS
7311022	PRECAST CONCRETE DROP INLET 2 FT X 2 FT	11.000	FT
7311030	PRECAST CONCRETE DROP INLET 3 FT X 2 FT-6 IN.	4.000	FT
7311053	PRECAST CONCRETE DROP INLET 5 FT X 3 FT	41.000	FT



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D04

Item No.	Description	Quantity	Units
7320015A	15 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION	2.000	EA
7320615A	15 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	4.000	EA
8031000A	TURF TYPE TALL FESCUE SODDING	3,792.000	SQYD
8052000A	SEEDING - WARM SEASON GRASSES	1.000	ACRE
8061004	SEDIMENT TRAP ROCK	30.000	CUYD
8061005	ROCK DITCH CHECK	1,663.000	LF
8061007A	CURB INLET CHECK	16.000	EA
8061016	SEDIMENT REMOVAL	61.000	CUYD
8061017	TEMPORARY SEEDING	1.000	ACRE
8061019	SILT FENCE	2,664.000	LF
8064141	TYPE 4 EROSION CONTROL BLANKET	4,876.000	SQYD
9011030	LIGHTING POLE, 30 FT. OR 9.0 M, TYPE AT	1.000	EA
9011115	BRACKET ARM, 15 FT. OR 4.6 M	8.000	EA
9011311	LUMINAIRE, LED-A	1.000	EA
9016110	PULL BOX, PREFORMED CLASS 1	2.000	EA
9018230	POLE FOUNDATION (30 FT. OR 9.0 M MOUNTING HEIGHT)	1.000	EA
9020111	SIGNAL HEAD, TYPE 1T	1.000	EA
9020211	SIGNAL HEAD, TYPE 1S	1.000	EA
9020213	SIGNAL HEAD, TYPE 3S	4.000	EA
9020513	SIGNAL HEAD, TYPE 3B	13.000	EA
9020514	SIGNAL HEAD, TYPE 4B	4.000	EA
9020811	SIGNAL HEAD, TYPE 1S, PEDESTRIAN	8.000	EA
9020833	SH-FLAT SHEET - SIGNAL SIGN	130.000	SQFT
9020834	SIGNAL SIGN, MOUNTING HARDWARE	21.000	EA
9022651	LUMINAIRE LED-A, 120 VOLT COMPATIBLE	7.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D04

Item No.	Description	Quantity	Units
9022708	POST, SIGNAL 8 FT.	2.000	EA
9022715	POST, SIGNAL 15 FT.	3.000	EA
9023130	POST, TYPE CL, 30 FT. ARM OR 9.1 M ARM	1.000	EA
9023140	POST, TYPE CL, 40 FT. ARM OR 12.2 M ARM	1.000	EA
9023145	POST, TYPE CL, 45 FT. ARM OR 13.7 M ARM	2.000	EA
9023155	POST, TYPE CL, 55 FT. ARM	1.000	EA
9023255	POST, TYPE C, 55 FT. ARM	1.000	EA
9023455	POST, TYPE BL, LONGEST ARM 55 FT.	1.000	EA
9024283	CONTROLLER ASSEMBLY HOUSING, NEMA TS2 CONTROLLER	2.000	EA
9024965	DETECTOR, MICROWAVE	2.000	EA
9025200	CONDUIT, 2 IN., TRENCH WITH TRACER WIRE	955.000	LF
9025300	CONDUIT, 3 IN., TRENCH WITH TRACER WIRE	360.000	LF
9027200	CONDUIT, 2 IN., PUSHED WITH TRACER WIRE	280.000	LF
9027300	CONDUIT, 3 IN., PUSHED WITH TRACER WIRE	620.000	LF
9028100	CABLE, 10 AWG 1 CONDUCTOR, POLE AND BRACKET	770.000	LF
9028208	CABLE, 8 AWG 1 CONDUCTOR, POWER	570.000	LF
9028302	CABLE, 12 AWG 2 CONDUCTOR	1,790.000	LF
9028308	CABLE, 16 AWG 2 CONDUCTOR	1,790.000	LF
9028310	CABLE, 16 AWG 5 CONDUCTOR	1,800.000	LF
9028311	CABLE, 16 AWG 7 CONDUCTOR	5,660.000	LF
9028811	PULL BOX, PREFORMED CLASS 2	6.000	EA
9028812	PULL BOX, PREFORMED CLASS 3	2.000	EA
9029100	BASE, CONCRETE	26.000	CUYD
9029902	MISC. AUDIBLE ACCESSIBLE PENDERSTRIAN PUSHBUTTON AND SIGN	8.000	EA
9029902	MISC. COMBINATION PAD MOUNTED 120/240 VOLT	2.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D04

Item No.	Description	Quantity	Units
	POWER SUPPLY & LIGHTING CONTROLLER W/UNINTERRUPTIBLE POWER SUPPLY		
9031250A	U-CHANNEL POST, 3 LB	69.000	LF
9031270A	2 IN. PSST POST - 12 GA.	130.000	LF
9031271A	DRIVEN POST ANCHOR FOR 2 IN. PSST - 12 GA.	12.000	EA
9035004A	SH-FLAT SHEET	166.000	SQFT
9035069A	SHF-FLAT SHEET FLUORESCENT	18.000	SQFT
9105200	CONDUIT, 2 IN., RIGID, IN TRENCH	1,300.000	LF
9108354	FIBER OPTIC CABLE, 48-STRAND, SINGLE MODE	2,130.000	LF
9108811	PULL BOX, PREFORMED CLASS 2	6.000	EA
9108816	PULL BOX, PREFORMED CLASS 5	2.000	EA
9109902	MISC. FIBER OPTIC JUMPER, SINGLE MODE	12.000	EA
9109902	MISC. FIBER OPTIC PIGTAIL, SINGLE MODE	12.000	EA
9109902	MISC. FUSION SPLICE, SINGLE MODE	12.000	EA
9109902	MISC. HARDENED ETHERNET SWITCH - LAYER 2 - INSTALL ONLY	2.000	EA
9109902	MISC. RACK-MOUNTED INTERCONNECT CENTER	1.000	EA
9109902	MISC. WALL-MOUNTED INTERCONNECT CENTER	2.000	EA
6039901	WATER BONDING & MOBILIZATION	1.000	LS
6039901	WATER POTABLE WATER SYSTEM IMPROVEMENTS, AS-BUILT SURVEYING, CAD, AND PLANS	1.000	LS
6039901	WATER REINF. CONC. SERVICE VAULT (8 X 14)	1.000	LS
6039901	WATER STAKING	1.000	LS
6039901	WATER TRAFFIC CONTROL	1.000	LS
6039902	WATER 1 1/2" DIA. METER SERVICE AND APPURTENANCES	3.000	EA
6039902	WATER 1 1/2" DIA. SERVICE LATERAL CONNECTION	5.000	EA
6039902	WATER 2" DIA. METER SERVICE AND APPURTENANCES	2.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D04

Item No.	Description	Quantity	Units
6039902	WATER 2" DIA. PVC, SDR-9, CTS SERVICE LATERAL	40.000	EA
6039902	WATER 2" DIA. SERVICE LATERAL CONNECTION	2.000	EA
6039902	WATER 3/4" DIA. RUPERLE ELICPSE NO. 88-55 WATER SAMPLING STATIONS	2.000	EA
6039902	WATER 4" DIA. GATE VALVE	2.000	EA
6039902	WATER 6" DIA. DIP (22.5 DEG. ELBOW)	9.000	EA
6039902	WATER 6" DIA. DIP (45 DEG. ELBOW)	8.000	EA
6039902	WATER 6" DIA. GATE VALVE AND APPURTENANCES	6.000	EA
6039902	WATER 6" DIA. GUARD POST AROUND NEW HYDRANT	2.000	EA
6039902	WATER 6" DIP TEE	9.000	EA
6039902	WATER AIR/VACUUM RELEASE VALVES	3.000	EA
6039902	WATER CONNECTION (TIE) INTO EXISTING 6" DIA PVC MAIN	7.000	EA
6039902	WATER FIRE HYDRANTS	6.000	EA
6039902	WATER MECHANICAL JOINT CAP & THRUST BLOCK	7.000	EA
6039902	WATER REMOVALS	10.000	EA
6039903	WATER 1 1/2" DIA. PVC, SDR-9, CTS, SERVICE LATERAL	30.000	LF
6039903	WATER 2" DIA. RJPVC, SDR-17 PIPE IN 6" DIA. CASING	45.000	LF
6039903	WATER 6" DIA. RJPVC, SDR-21 PIPE IN 12" DIA. CASING	50.000	LF
6039903	WATER 6" DIA. SDR-21 PVC WATER MAIN PIPING	2,100.000	LF
6039903	WATER 6" DIA. SDR-21, PVC, (GREATER THAN 42" DEPTH)	270.000	LF
6039903	WATER ABANDONED EXISTING 6" DIA. AND 2" DIA. WATER LINES	385.000	LF
6039903	WATER ABANDONED EXISTING 6" DIA. WATER MAIN	160.000	LF
6039903	WATER CLEARING AND GRUBBING	200.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D04

Item No.	Description	Quantity	Units
6039903	WATER FINISH GRADING, TOP SOIL, SEEDING, LIMING, FERTILIZAING & MULCHING OF NEW WATER MAIN TRENCHING, CONNECTIONS & RESTORE ALL DISTURBED AREAS TO ORIGINAL CONDITIONS OR BETTER, COMPLETE.	1,359.000	LF
6039903	WATER OPEN-CUT #1	20.000	LF
6039903	WATER OPEN-CUT #2	90.000	LF
6039903	WATER OPEN-CUT #3	30.000	LF
6039903	WATER ROADWAY BORE #1	40.000	LF
6039903	WATER ROADWAY BORE #2	40.000	LF
6039903	WATER ROADWAY BORE #3	80.000	LF

() Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
240517-D05		
FAF 52-3(26)	J5P3575	
J5P3575 - ROUTES 52, 5 - MORGAN COUNTY		
FAF 52-3(26)	J5P3575	
Roundabout		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D05

Contract ID: 240517-D05

Letting Date: May 17, 2024 11:00 AM

Projects: J5P3575

FAF 52-3(26)

Counties: MORGAN

District: Central

DBE Goal Percent: 6.00

Description: ****(1): Job J5P3575 Route 52 MORGAN County. Roundabout at Route 5 in Versailles, the total length of improvement being 0.736 miles.

Contract Time: DT - 11/1/2025

Item No.	Description	Quantity	Units
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2031000	CLASS A EXCAVATION	4,206.000	CUYD
2035500	EMBANKMENT IN PLACE	1,788.000	CUYD
2036000	COMPACTING EMBANKMENT	5,681.000	CUYD
2063000	CLASS 3 EXCAVATION	3,003.000	CUYD
2063300	CLASS 4 EXCAVATION	1,231.000	CUYD
3040504	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK)	2,693.000	SQYD
3040506	TYPE 5 AGGREGATE FOR BASE (6 IN. THICK)	7,334.000	SQYD
3105002	GRAVEL (A) OR CRUSHED STONE (B)	72.000	TONS
4011209	BITUMINOUS PAVEMENT MIXTURE PG64-22, (BP-1)	26.600	TONS
4019905	MISC. OPTIONAL PAVEMENT - 7 IN. HMA VS. 7 IN. NRPCCP	1,265.600	SQYD
4030101	ASPHALTIC CONCRETE MIXTURE PG 64-22 (SP125C MIX)	2,488.800	TONS
4030403	10 INCHES, ASPHALTIC CONCRETE PAVEMENT SP125C	3,536.900	SQYD
4039905	MISC. OPTIONAL PAVEMENT - 10 IN. HMA VS. 8.5 IN. NRPCCP	282.900	SQYD
4071005	TACK COAT	1,493.000	GAL



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D05

Item No.	Description	Quantity	Units
5021308	CONCRETE PAVEMENT (8 IN. NON-REINFORCED, 15 FT. JOINTS)	18.100	SQYD
5021333	CONCRETE PAVEMENT (9 1/2 IN. NON-REINFORCED, 15 FT. JOINTS)	783.500	SQYD
5029905	MISC. CONCRETE PAVEMENT (8 IN. NON-REINFORCED, 15 FT. JOINTS) - TINTED	251.100	SQYD
5029905	MISC. CONCRETE PAVEMENT (9 1/2 IN. NON-REINFORCED, 15 FT. JOINTS)-TINTED/STAMPED	131.900	SQYD
5062030A	FURNISHING UNBONDED CONCRETE OVERLAY	424.700	CUYD
5069905	MISC. UNBONDED CONCRETE OVERLAY, PLACING 7 IN.	1,905.900	SQYD
5069905	MISC. UNBONDED CONCRETE OVERLAY, PLACING 7 IN. - STAMPED	278.800	SQYD
6046015A	15 IN. SLOTTED DRAIN	20.000	LF
6081012	TRUNCATED DOMES	32.000	SQFT
6083003	3 IN. CONCRETE MEDIAN STRIP	295.400	SQYD
6083006	6 IN. CONCRETE MEDIAN STRIP	1,355.100	SQYD
6085008	PAVED APPROACH, 8 IN.	1,319.400	SQYD
6086004	CONCRETE SIDEWALK, 4 IN.	57.300	SQYD
6091010	CONCRETE CURB (6 IN. HEIGHT AND UNDER) TYPE S	197.900	LF
6091041	CONCRETE GUTTER TYPE A	6.000	LF
6091051	CURB AND GUTTER TYPE A	4,622.000	LF
6091052	CURB AND GUTTER TYPE B	10.000	LF
6092012	INTEGRAL CURB (6 IN. HEIGHT AND UNDER) TYPE B	74.000	LF
6096010A	FURNISHING TYPE 1 ROCK DITCH LINER	50.000	CUYD
6096020	FURNISHING TYPE 2 ROCK DITCH LINER	89.000	CUYD
6096030A	FURNISHING TYPE 3 ROCK DITCH LINER	207.000	CUYD
6096041	PLACING TYPE 1 ROCK DITCH LINER	50.000	CUYD



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D05

Item No.	Description	Quantity	Units
6096042	PLACING TYPE 2 ROCK DITCH LINER	89.000	CUYD
6096043	PLACING TYPE 3 ROCK DITCH LINER	207.000	CUYD
6096050	BEDDING MATERIAL FOR ROCK DITCH LINER	73.000	CUYD
6097000	ROCK LINING	6.000	CUYD
6099903	MISC. MODIFIED 6" TYPE A CURB AND GUTTER	53.000	LF
6122008	IMPACT ATTENUATOR 40 MPH (SAND BARREL ARRAY)	2.000	EA
6122009	IMPACT ATTENUATOR 45 MPH (SAND BARREL ARRAY)	1.000	EA
6122020	REPLACEMENT SAND BARREL	4.000	EA
6122030	IMPACT ATTENUATOR (RELOCATION)	1.000	EA
6141022	GRATE AND BEARING PLATE (3 FT. X 3 FT. OR 914 MM X 914 MM)	16.000	EA
6141024	GRATE AND BEARING PLATE (5 FT. X 3 FT. OR 1524 MM X 914 MM)	1.000	EA
6141120	CURVED VANE GRATE AND FRAME (2 FT. X 2 FT. OR 600MM X 600MM)	30.000	EA
6143012	MANHOLE FRAME AND COVER, TYPE 2	2.000	EA
6143013	MANHOLE FRAME AND COVER, TYPE 3	2.000	EA
6143014	MANHOLE FRAME AND COVER, TYPE 4	7.000	EA
6161005	CONSTRUCTION SIGNS	1,254.000	SQFT
6161025	CHANNELIZER (TRIM LINE)	150.000	EA
6161030	TYPE III MOVEABLE BARRICADE	17.000	EA
6161040	FLASHING ARROW PANEL	3.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	4.000	EA
6173600D	TEMPORARY TRAFFIC BARRIER, CONTRACTOR FURNISHED / RETAINED	63.000	LF
6173700B	TEMPORARY TRAFFIC BARRIER ANCHORED,	438.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D05

Item No.	Description	Quantity	Units
6175011B	CONTRACTOR FURNISHED / RETAINED RELOCATING TEMPORARY TRAFFIC BARRIER ANCHORED	650.000	LF
6181000	MOBILIZATION	1.000	LS
6181020	ADDITIONAL MOBILIZATION FOR SEEDING	4.000	EA
6191000	PAVEMENT EDGE TREATMENT	2,929.000	LF
6200018	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. YELLOW	125.000	LF
6200021	PREFORMED THERMOPLASTIC PAVEMENT MARKING, LEFT/RIGHT ARROW	13.000	EA
6200027	PREFORMED THERMOPLASTIC PAVEMENT MARKING, COMBINATION STR/LT/RT	4.000	EA
6200036	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 30 IN WHITE MIDBLOCK	7.000	EA
6200042	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 12 IN WHITE, YIELD LINE TRIANGLES	36.000	EA
6205301B	TEMPORARY REMOVABLE MARKING TAPE 4 IN., WHITE	1,372.000	LF
6205303B	TEMPORARY REMOVABLE MARKING TAPE 4 IN., YELLOW	1,175.000	LF
6205320	TEMPORARY REMOVABLE MARKING TAPE, 12 IN., WHITE	187.000	LF
6205902A	6 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	1,652.000	LF
6205903A	6 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	2,311.000	LF
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	3,051.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	11,096.000	LF
6207001	PAVEMENT MARKING REMOVAL	5,343.000	LF
6208076	4 IN TEMPORARY PAVEMENT MARKING PAINT	6,860.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D05

Item No.	Description	Quantity	Units
6221001	COLDMILLING BITUMINOUS PAVEMENT FOR REMOVAL OF SURFACING (3 IN. THICK OR LESS)	6,879.000	SQYD
6221003	COLDMILLING BITUMINOUS PAVEMENT FOR REMOVAL OF SURFACING (GREATER THAN 3 IN. THICK)	10,236.000	SQYD
6240104A	SEPARATION GEOTEXTILE	1,017.000	SQYD
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7034041	CLASS B-1 CONCRETE (CULVERTS)	197.700	CUYD
7061030	REINFORCING STEEL (CULVERTS)	26,790.000	LB
7201200	SELECT GRANULAR BACKFILL FOR STRUCTURAL SYSTEMS	125.000	CUYD
7250312A	12 IN. PIPE GROUP B	41.000	LF
7250315A	15 IN. PIPE GROUP B	253.000	LF
7250318A	18 IN. PIPE GROUP B	1,173.000	LF
7250324A	24 IN. PIPE GROUP B	972.000	LF
7250330A	30 IN. PIPE GROUP B	415.000	LF
7250336A	36 IN. PIPE GROUP B	487.000	LF
7250348A	48 IN. PIPE GROUP B	90.000	LF
7252005	CORRUGATED METALLIC-COATED STEEL PIPE- ARCH TYPE B-5	178.000	LF
7261018	18 IN. PIPE GROUP A	47.000	LF
7310048	PRECAST CONCRETE MANHOLE - 48 IN.	22.000	FT
7310060	PRECAST CONCRETE MANHOLE - 60 IN.	19.000	FT
7310072	PRECAST CONCRETE MANHOLE - 72 IN.	14.000	FT
7311022	PRECAST CONCRETE DROP INLET 2 FT X 2 FT	3.000	FT
7311033	PRECAST CONCRETE DROP INLET 3 FT X 3 FT	60.000	FT
7311053	PRECAST CONCRETE DROP INLET 5 FT X 3 FT	6.000	FT
7319913	MISC. CAST-IN-PLACE DROP INLET, 2.5 FT L	106.000	FT



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D05

Item No.	Description	Quantity	Units
7319913	MISC. CAST-IN-PLACE DROP INLET, 5.0 FT L	15.000	FT
7319913	MISC. PRECAST DROP INLET, TYPE T, 2'-6" CURB INLET	5.000	FT
7319913	MISC. PRECAST DROP INLET, TYPE T, 5'-0" CURB INLET	5.000	FT
7320012A	12 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION	2.000	EA
7320015A	15 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION	5.000	EA
7320048A	48 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION	1.000	EA
7320618A	18 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	2.000	EA
7321005	B5 FLARED END SECTION	2.000	EA
8025006	MULCHING	3.100	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	2.200	ACRE
8052000A	SEEDING - WARM SEASON GRASSES	0.300	ACRE
8061005	ROCK DITCH CHECK	330.000	LF
8061006	ALTERNATE DITCH CHECK	1,112.000	LF
8061007A	CURB INLET CHECK	46.000	EA
8061016	SEDIMENT REMOVAL	40.000	CUYD
8061017	TEMPORARY SEEDING	0.600	ACRE
8061019	SILT FENCE	612.000	LF
9011030	LIGHTING POLE, 30 FT. OR 9.0 M, TYPE AT	8.000	EA
9011104	BRACKET ARM, 4 FT. OR 1.2 M	1.000	EA
9011108	BRACKET ARM, 8 FT. OR 2.4 M	1.000	EA
9011110	BRACKET ARM, 10 FT. OR 3.0 M	2.000	EA
9011112	BRACKET ARM, 12 FT. OR 3.6 M	2.000	EA
9011115	BRACKET ARM, 15 FT. OR 4.6 M	2.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D05

Item No.	Description	Quantity	Units
9011311	LUMINAIRE, LED-A	8.000	EA
9012230	BASE MOUNTED CONTROL STATION 240 VOLT - 4 CIRCUIT	1.000	EA
9013002	CONDUIT, 2 IN. RIGID, IN TRENCH	80.000	LF
9013003	CONDUIT, 3 IN. RIGID, IN TRENCH	195.000	LF
9014003	CONDUIT, 3 IN. RIGID, PUSHED	124.000	LF
9015010	TRENCHING TYPE I	1,092.000	LF
9015020	TRENCHING TYPE II	75.000	LF
9016110	PULL BOX, PREFORMED CLASS 1	6.000	EA
9017002	CABLE, 2 AWG 1 CONDUCTOR	260.000	LF
9017110	CABLE, 10 AWG 1 CONDUCTOR, POLE AND BRACKET	650.000	LF
9017407	CABLE-CONDUIT, 1 IN., 2 CONDUCTORS AND 1 BARE NEUTRAL, 8 AWG	2,090.000	LF
9018230	POLE FOUNDATION (30 FT. OR 9.0 M MOUNTING HEIGHT)	8.000	EA
9018612	POWER SUPPLY ASSEMBLY, TYPE 2, 240/120 VOLT SERVICE, LIGHTING ONLY	1.000	EA
7032002	CLASS B CONCRETE (MISC)	2.000	CUYD
7061000	REINFORCING STEEL	200.000	LB
9025200	CONDUIT, 2 IN., TRENCH WITH TRACER WIRE	22.000	LF
9025300	CONDUIT, 3 IN., TRENCH WITH TRACER WIRE	15.000	LF
9027504	CONDUIT, 3 IN., EXTERNAL ON STRUCTURE	9.000	LF
9028202	CABLE, 2 AWG 1 CONDUCTOR, POWER	60.000	LF
9028208	CABLE, 8 AWG 1 CONDUCTOR, POWER	50.000	LF
9029901	MISC. Traffic Signal/Lighting Modifications	1.000	LS
9029902	MISC. RELOCATE CONTROLLER ASSEMBLY AND AUXILIARY EQUIPMENT	1.000	EA
9029902	MISC. RELOCATE POWER SUPPLY	1.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D05

Item No.	Description	Quantity	Units
9029902	MISC. RELOCATE SIGNAL HEAD	3.000	EA
9031010	CONCRETE FOOTINGS, EMBEDDED	1.800	CUYD
9031220	PIPE POSTS	1,800.000	LB
9031241	BREAKAWAY ASSEMBLY (PERFORATED SQUARE STEEL TUBE)	42.000	EA
9031242	36 IN. SURFACE-MOUNT DELINEATOR POST	43.000	EA
9031250A	U-CHANNEL POST, 3 LB	64.000	LF
9031280	2.5 IN. PSST POST - 12 GA.	947.000	LF
9031281A	DRIVEN POST ANCHOR FOR 2.5 IN. PSST - 7 GA.	17.000	EA
9031285	CONCRETE POST ANCHOR FOR 2.5 IN. PSST. - 7 GA.	42.000	EA
9035004A	SH-FLAT SHEET	346.000	SQFT
9035011A	ST-STRUCTURAL	104.000	SQFT
9035069A	SHF-FLAT SHEET FLUORESCENT	78.000	SQFT
2063300	CLASS 4 EXCAVATION	460.000	CUYD
2065500	TEMPORARY SHORING	1.000	LS
2069901	MISC. Dewatering	1.000	LS
7034040	CLASS B-1 CONCRETE (CULVERTS-BRIDGE)	244.900	CUYD
7061020	REINFORCING STEEL (CULVERTS-BRIDGE)	45,080.000	LB
7061070	MECHANICAL BAR SPLICE	95.000	EA

() Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
240517-D07		
FAF-22-1 (11)	JCD0030	
JCD0030-ROUTE 22-BOONE COUNTY		
FAF-22-1 (11)	JCD0030	
Roundabout		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D07

Contract ID: 240517-D07

Letting Date: May 17, 2024 11:00 AM

Projects: JCD0030

FAF-22-1 (11)

Counties: BOONE

District: Central

DBE Goal Percent: 6.00

Description: ****(1): Job JCD0030 Route 22 BOONE County. Roundabout at Route 124 and Route 151, the total length of improvement being 0.2 miles.

Contract Time: DT - 8/1/2025

Item No.	Description	Quantity	Units
1049910	MISC. TEMPORARY SURFACING Gravel (A), Crushed Stone (B)	100.000	TONS
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2031000	CLASS A EXCAVATION	1,759.000	CUYD
2035500	EMBANKMENT IN PLACE	516.000	CUYD
2036000	COMPACTING EMBANKMENT	1,301.000	CUYD
3040504	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK)	2,153.000	SQYD
3040506	TYPE 5 AGGREGATE FOR BASE (6 IN. THICK)	5,285.000	SQYD
3105002	GRAVEL (A) OR CRUSHED STONE (B)	92.000	TONS
4019905	MISC. Optional Pavement	2,153.000	SQYD
5021108	CONCRETE PAVEMENT (8 IN. NON-REINF)	1,010.000	SQYD
5021333	CONCRETE PAVEMENT (9 1/2 IN. NON-REINFORCED, 15 FT. JOINTS)	4,710.000	SQYD
6091011	CONCRETE CURB (OVER 6 IN. HEIGHT) TYPE S	249.000	LF
6161005	CONSTRUCTION SIGNS	688.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	4.000	EA
6161010	RELOCATED SIGNS	266.000	SQFT
6161025	CHANNELIZER (TRIM LINE)	165.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D07

Item No.	Description	Quantity	Units
6161030	TYPE III MOVEABLE BARRICADE	5.000	EA
6161099	CHANGEABLE MESSAGE SIGN WITH COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	5.000	EA
6181000	MOBILIZATION	1.000	LS
6181020	ADDITIONAL MOBILIZATION FOR SEEDING	4.000	EA
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	129.000	LF
6200018	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. YELLOW	88.000	LF
6200042	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 12 IN WHITE, YIELD LINE TRIANGLES	36.000	EA
6205301B	TEMPORARY REMOVABLE MARKING TAPE 4 IN., WHITE	4,794.000	LF
6205303B	TEMPORARY REMOVABLE MARKING TAPE 4 IN., YELLOW	5,068.000	LF
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	1,743.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	1,985.000	LF
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
8059901	MISC. Seeding Cool Season Mixtures	1.000	LS
8061005	ROCK DITCH CHECK	104.000	LF
8061016	SEDIMENT REMOVAL	130.000	CUYD
9011030	LIGHTING POLE, 30 FT. OR 9.0 M, TYPE AT	8.000	EA
9011115	BRACKET ARM, 15 FT. OR 4.6 M	8.000	EA
9011311	LUMINAIRE, LED-A	8.000	EA
9012230	BASE MOUNTED CONTROL STATION 240 VOLT - 4 CIRCUIT	1.000	EA
9013002	CONDUIT, 2 IN. RIGID, IN TRENCH	89.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D07

Item No.	Description	Quantity	Units
9013003	CONDUIT, 3 IN. RIGID, IN TRENCH	135.000	LF
9016110	PULL BOX, PREFORMED CLASS 1	6.000	EA
9017110	CABLE, 10 AWG 1 CONDUCTOR, POLE AND BRACKET	720.000	LF
9017401	CABLE-CONDUIT, 1 IN., 2 CONDUCTORS AND 1 BARE NEUTRAL, 2 AWG	110.000	LF
9017407	CABLE-CONDUIT, 1 IN., 2 CONDUCTORS AND 1 BARE NEUTRAL, 8 AWG	1,100.000	LF
9018230	POLE FOUNDATION (30 FT. OR 9.0 M MOUNTING HEIGHT)	8.000	EA
9018610	POWER SUPPLY ASSEMBLY, TYPE 1, 240/120 VOLT SERVICE, LIGHTING ONLY	1.000	EA
9031210	STRUCTURAL STEEL POSTS	300.000	LB
9031241	BREAKAWAY ASSEMBLY (PERFORATED SQUARE STEEL TUBE)	20.000	EA
9031280	2.5 IN. PSST POST - 12 GA.	704.000	LF
9031281A	DRIVEN POST ANCHOR FOR 2.5 IN. PSST - 7 GA.	24.000	EA
9035004A	SH-FLAT SHEET	343.000	SQFT
9035011A	ST-STRUCTURAL	81.000	SQFT
9035069A	SHF-FLAT SHEET FLUORESCENT	151.000	SQFT

() Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
240517-D08		
FAF S403(82)	JCD0041	
JCD0041-ROUTES BB. MM, FF-CALLAWAY COUNTY		
FAF S403(82)	JCD0041	
Seal coat		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D08

Contract ID: 240517-D08

Letting Date: May 17, 2024 11:00 AM

Projects: JCD0041

FAF S403(82)

Counties: CALLAWAY

District: Central

DBE Goal Percent:

Description: ****(1): Job JCD0041 Route BB, MM, FF CALLAWAY County. Seal coat on Route BB from Route 54 to Route AA, on Route MM from CR397 to Route J, and on Route FF from CR225 to Route 54, the total length of improvement being 19.407 miles.

Contract Time: DT - 9/1/2025

Item No.	Description	Quantity	Units
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	6.000	EA
6169901	MISC. Temporary Traffic Control	1.000	LS
6181000	MOBILIZATION	1.000	LS
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	82.000	LF
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	205,687.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	205,885.000	LF
6206108A	8 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	110.000	LF
4091048	EMULSIFIED ASPHALT, SEAL COAT	43,696.000	GAL
4094012	SEAL COAT AGGREGATE, GRADE B2	156,057.000	SQYD
4091048	EMULSIFIED ASPHALT, SEAL COAT	19,898.000	GAL
4094012	SEAL COAT AGGREGATE, GRADE B2	71,064.000	SQYD
4091048	EMULSIFIED ASPHALT, SEAL COAT	4,936.000	GAL
4094012	SEAL COAT AGGREGATE, GRADE B2	17,628.000	SQYD



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D08

Page 81 of 203

() Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
240517-D09		
FAS S403(83)	JCD0043	
JCD0043-ROUTES H, CC, BB-COLE COUNTY		
FAS S403(83)	JCD0043	
Resurface		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D09

Contract ID: 240517-D09

Letting Date: May 17, 2024 11:00 AM

Projects: JCD0043

FAS S403(83)

Counties: COLE

District: Central

DBE Goal Percent: 4.00

Description: ****(1): Job JCD0043 Route BB, H, CC COLE County. Resurface on Route BB from Route 17 to Route H, on Route CC from Route C to Route 54 WB, and on Route H from Route E to SME, the total length of improvement being 12.991 miles.

Contract Time: DT - 11/1/2025

Item No.	Description	Quantity	Units
3105002	GRAVEL (A) OR CRUSHED STONE (B)	955.000	TONS
4071005	TACK COAT	13,719.000	GAL
6161005	CONSTRUCTION SIGNS	2,080.000	SQFT
6161025	CHANNELIZER (TRIM LINE)	100.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	6.000	EA
6181000	MOBILIZATION	1.000	LS
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	137,539.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	131,381.000	LF
6206108A	8 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	72.000	LF
6206124A	24 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	12.000	LF
6224010	MODIFIED COLDMILLING (DEPTH TRANSITIONS)	1,113.000	SQYD
4020520	BITUMINOUS PAVEMENT MIXTURE PG64-22 (SURFACE LEVELING)	3,409.400	TONS
4020520	BITUMINOUS PAVEMENT MIXTURE PG64-22	1,572.200	TONS



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D09

Item No.	Description	Quantity	Units
4020520	(SURFACE LEVELING) BITUMINOUS PAVEMENT MIXTURE PG64-22 (SURFACE LEVELING)	5,416.000	TONS

() Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
240517-D10		
FAF 49-1(22)	JCD0084	
JCD0084- ROUTE 49-CRAWFORD, IRON COUNTIES		
FAF 49-1(22)	JCD0084	
Seal coat		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D10

Contract ID: 240517-D10

Letting Date: May 17, 2024 11:00 AM

Projects: JCD0084

FAF 49-1(22)

Counties: CRAWFORD, IRON

District: Central

DBE Goal Percent:

Description: ****(1): Job JCD0084 Route 49 CRAWFORD, IRON County. Seal coat from Route 19 to Route 32 near Viburnum, the total length of improvement being 19.959 miles.

Contract Time: DT - 10/1/2025

Item No.	Description	Quantity	Units
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2153000	SHAPING SLOPES, CLASS III	4.000	100F
4091048	EMULSIFIED ASPHALT, SEAL COAT	74,418.000	GAL
4094012	SEAL COAT AGGREGATE, GRADE B2	265,778.000	SQYD
6161005	CONSTRUCTION SIGNS	1,757.000	SQFT
6161025	CHANNELIZER (TRIM LINE)	100.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	2.000	EA
6181000	MOBILIZATION	1.000	LS
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	212,193.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	188,740.000	LF
6061060	MGS GUARDRAIL	275.000	LF
6061080	MGS END ANCHOR	1.000	EA
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	1.000	EA

() Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
240517-D11		
FAS S403(84)	JCD0087	
JCD0087 - ROUTE AB, Z - PULASKI, PHELPS COUNTIES		
FAS S403(84)	JCD0087	
Seal coat		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D11

Contract ID: 240517-D11

Letting Date: May 17, 2024 11:00 AM

Projects: JCD0087

FAS S403(84)

Counties: PHELPS, PULASKI

District: Central

DBE Goal Percent:

Description: ****(1): Job JCD0087 Route AB, Z PHELPS, PULASKI County. Seal coat on Route AB from I-44 to Route 17, on Route Z from 0.659 miles west of Route J, Pulaski County, to Route J, Phelps County, the total length of improvement being 7.064 miles.

Contract Time: DT - 10/1/2025

Item No.	Description	Quantity	Units
6161005	CONSTRUCTION SIGNS	1,305.000	SQFT
6161025	CHANNELIZER (TRIM LINE)	160.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	4.000	EA
6181000	MOBILIZATION	1.000	LS
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	68,981.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	67,285.000	LF
4091048	EMULSIFIED ASPHALT, SEAL COAT	23,428.000	GAL
4094012	SEAL COAT AGGREGATE, GRADE B2	83,672.000	SQYD
4091048	EMULSIFIED ASPHALT, SEAL COAT	2,740.000	GAL
4094012	SEAL COAT AGGREGATE, GRADE B2	9,787.000	SQYD

() Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
240517-D12		
FAF-52-3 (28)	JCD0121	
JCD0121 - VARIOUS ROUTES - MILLER, LACLEDE, PULASKI, CAMDEN COUTIES		
FAF-52-3 (28)	JCD0121	
ADA improvements		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D12

Contract ID: 240517-D12

Letting Date: May 17, 2024 11:00 AM

Projects: JCD0121

FAF-52-3 (28)

Counties: CAMDEN, LACLEDE, MILLER, PULASKI

District: Central

DBE Goal Percent: 5.00

Description: ****(1): Job JCD0121 Route Various CAMDEN, LACLEDE, MILLER, PULASKI County. ADA improvements in St. Elizabeth, Tuscumbia, Osage Beach, Lebanon, Richland and Dixon, the total length of improvement being 1.247 miles.

Contract Time: DT - 9/1/2025

Item No.	Description	Quantity	Units
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2032000	CLASS C EXCAVATION	640.000	CUYD
2063000	CLASS 3 EXCAVATION	115.000	CUYD
2079903	MISC. LINEAR GRADING FOR ADA, CLASS 1	2,860.000	LF
2079903	MISC. LINEAR GRADING FOR ADA, CLASS 2	369.000	LF
3040504	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK)	4,377.000	SQYD
5021107	CONCRETE PAVEMENT (7 IN. NON-REINF)	274.600	SQYD
5021108	CONCRETE PAVEMENT (8 IN. NON-REINF)	952.900	SQYD
6039902	WATER ADJUSTING FIRE HYDRANT	2.000	EA
6042010	ADJUSTING MANHOLE	1.000	EA
6049902	MISC. ADJUSTING DROP INLET	2.000	EA
6049902	MISC. ADJUSTING TELEPHONE RISER	1.000	EA
6049902	MISC. ADJUSTING WATER VALVE, WATER METER, OR PULL BOX	5.000	EA
6081010	CONCRETE CURB RAMP	621.900	SQYD
6081012	TRUNCATED DOMES	543.000	SQFT
6083006	6 IN. CONCRETE MEDIAN STRIP	54.100	SQYD



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D12

Item No.	Description	Quantity	Units
6084023	SIDEWALK HAND-RAILING WITHOUT BALUSTERS	45.000	LF
6085007	PAVED APPROACH, 7 IN.	294.000	SQYD
6085008	PAVED APPROACH, 8 IN.	164.100	SQYD
6086004	CONCRETE SIDEWALK, 4 IN.	1,755.700	SQYD
6086008	CONCRETE SIDEWALK, 8 IN. CONCRETE SIDEWALK, 8 IN.	3.300	SQYD
6091010	CONCRETE CURB (6 IN. HEIGHT AND UNDER) TYPE S	374.000	LF
6092011	INTEGRAL CURB (6 IN. HEIGHT AND UNDER) TYPE A	145.000	LF
6099903	MISC. CONCRETE CURB AND GUTTER (SPECIAL), 1.5 FT.	77.000	LF
6099903	MISC. CONCRETE CURB AND GUTTER (SPECIAL), 2.0 FT.	329.000	LF
6099903	MISC. CONCRETE CURB AND GUTTER (SPECIAL), 2.5 FT.	520.000	LF
6099903	MISC. MODIFIED INTEGRAL CURB, TYPE A, (OVER 6 IN. HEIGHT)	376.000	LF
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	4.000	EA
6169901	MISC. TEMPORARY TRAFFIC CONTROL	1.000	LS
6169902	MISC. ADA COMPLIANT MOVEABLE BARRICADE	16.000	EA
6181000	MOBILIZATION	1.000	LS
6200009	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 6 IN. WHITE	835.000	LF
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	67.000	LF
6200036	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 30 IN WHITE MIDBLOCK	37.000	EA
6200042	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 12 IN WHITE, YIELD LINE TRIANGLES	19.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D12

Item No.	Description	Quantity	Units
6207001	PAVEMENT MARKING REMOVAL	81.000	LF
6207002	PAVEMENT MARKING REMOVAL (SYMBOLS)	25.000	EA
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	10.000	SQYD
6279901	MISC. CONTACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7250312A	12 IN. PIPE GROUP B	83.000	LF
7250315A	15 IN. PIPE GROUP B	134.000	LF
7250318A	18 IN. PIPE GROUP B	137.000	LF
7320012A	12 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION	4.000	EA
7320015A	15 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION	8.000	EA
7320018A	18 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION	8.000	EA
8031000A	TURF TYPE TALL FESCUE SODDING	708.000	SQYD
8061006	ALTERNATE DITCH CHECK	526.000	LF
8061007A	CURB INLET CHECK	20.000	EA
8061016	SEDIMENT REMOVAL	55.000	CUYD
8061019	SILT FENCE	590.000	LF
9020811	SIGNAL HEAD, TYPE 1S, PEDESTRIAN	5.000	EA
9020821	SIGNAL HEAD, TYPE 11S, PEDESTRIAN	4.000	EA
9022708	POST, SIGNAL 8 FT.	6.000	EA
9025300	CONDUIT, 3 IN., TRENCH WITH TRACER WIRE	174.000	LF
9027300	CONDUIT, 3 IN., PUSHED WITH TRACER WIRE	17.000	LF
9028308	CABLE, 16 AWG 2 CONDUCTOR	1,200.000	LF
9028310	CABLE, 16 AWG 5 CONDUCTOR	730.000	LF
9028500	CABLE, LOOP DETECTOR, IN DUCT	650.000	LF
9028510	CABLE, LOOP DETECTOR, LEAD-IN	210.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-D12

Item No.	Description	Quantity	Units
9029100	BASE, CONCRETE	3.300	CUYD
9029902	MISC. DETECTOR, PUSH BUTTON APS	18.000	EA
9029902	MISC. PEDESTRIAN PUSH BUTTON EXTENSION	10.000	EA
9029903	MISC. REPLACE DAMAGED CONDUIT	50.000	LF
9039902	MISC. RELOCATE EXIST. SIGNS	24.000	EA
9039902	MISC. REMOVE AND RELOCATE EXISTING MAILBOX	1.000	EA

() Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
240517-F01		
I-170-5 (268)	J6I2339	
J6I2339 - ROUTE I-170 - ST LOUIS COUNTY		
I-170-5 (268)	J6I2339	
Access road and ADA improvements		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F01

Contract ID: 240517-F01

Letting Date: May 17, 2024 11:00 AM

Projects: J6I2339

I-170-5 (268)

Counties: ST LOUIS

District: St. Louis

DBE Goal Percent: 9.00

Description: ****(1): Job J6I2339 Route I-170 ST LOUIS County. Access road and ADA improvements from Francis Place to City Water Mains in Clayton, the total length of improvement being 0.031 miles.

Contract Time: DT - 10/1/2024

Item No.	Description	Quantity	Units
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2063000	CLASS 3 EXCAVATION	14.000	CUYD
2063500	CULVERT CLEANOUT	2.000	EA
2071000	LINEAR GRADING CLASS 1	1.600	STA
3040143	TYPE 1 AGGREGATE FOR BASE (4 IN. THICK)	234.000	SQYD
4039910	MISC. TYPE "C" ASPHALTIC CONCRETE	0.400	TONS
5029905	MISC. CONCRETE PAVEMENT (8 IN. NON-REINF)	233.500	SQYD
6039902	WATER ADJUST WATER METER	1.000	EA
6044011	PIPE COLLAR, TYPE A	1.000	EA
6071040	DRIVE GATE (CHAIN-LINK)	2.000	EA
6079902	MISC. REMOVABLE LOCKING BOLLARDS	3.000	EA
6079903	MISC. WOODEN FENCE (72 IN.)	110.000	LF
6081012	TRUNCATED DOMES	34.000	SQFT
6089903	MISC. HANDRAIL WITH BALUSTERS	19.000	LF
6141021	GRATE AND BEARING PLATE (3 FT. X 2 FT. OR 914 MM X 610 MM)	1.000	EA
6169901	MISC. LUMP SUM TEMPORARY TRAFFIC CONTROL	1.000	LS



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F01

Item No.	Description	Quantity	Units
6181000	MOBILIZATION	1.000	LS
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7209904	MISC. MODULAR BLOCK RETAINING WALL	119.000	SQFT
7261024	24 IN. PIPE GROUP A	11.000	LF
7311032	PRECAST CONCRETE DROP INLET 3 FT X 2 FT	4.000	FT
8031000A	TURF TYPE TALL FESCUE SODDING EROSION CONTROL	128.000	SQYD
8061007A	CURB INLET CHECK	1.000	EA
8061016	SEDIMENT REMOVAL	3.000	CUYD
8061017	TEMPORARY SEEDING	0.200	ACRE
8061019	SILT FENCE	215.000	LF
9013002	CONDUIT, 2 IN. RIGID, IN TRENCH	140.000	LF
9015010	TRENCHING TYPE I	140.000	LF
9016110	PULL BOX, PREFORMED CLASS 1	1.000	EA
9017008	CABLE, 8 AWG 1 CONDUCTOR	340.000	LF
9017208	WIRE, 8 AWG, BARE NEUTRAL	170.000	LF
9019902	MISC. INSTALL LIGHT POLE	1.000	EA
9019902	MISC. INSTALL PULL BOX	1.000	EA
9019902	MISC. REMOVE AND RESET LIGHT POLE	1.000	EA

() Item will be bid as lump sum.



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F02

Page 97 of 203

Contract ID

Federal Project Number / State Project Number

Description

240517-F02

J6P3448

J6P3448-VARIOUS ROUTES-ST. LOUIS, ST CHARLES, FRANKLIN, JEFFERSON, ST LOUIS CITY

J6P3448

Job Order Contract for fence repair



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F02

Contract ID: 240517-F02

Letting Date: May 17, 2024 11:00 AM

Projects: J6P3448

J6P3448

Counties: FRANKLIN, JEFFERSON, ST CHARLES, ST LOUIS, ST LOUIS CITY

District: St. Louis

DBE Goal Percent:

Description: ****(1): Job J6P3448 Route Various FRANKLIN, JEFFERSON, ST CHARLES, ST LOUIS, ST LOUIS CITY County. Job Order Contract for fence repair at various locations in the St. Louis District, the total length of improvement being 0 miles.

Contract Time: DT - 6/30/2025

Item No.	Description	Quantity	Units
6189916	MISC. ADJUSTMENT FACTOR	590,909.000	DLR

() Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
240517-F03		
FAS S503(94)	J6P3450	
J6P3450 - VARIOUS ROUTES - VARIOUS COUNTIES		
FAS S503(94)	J6P3450	
Job Order Contract for guard cable repair		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F03

Contract ID: 240517-F03

Letting Date: May 17, 2024 11:00 AM

Projects: J6P3450

FAS S503(94)

Counties: FRANKLIN, JEFFERSON, ST CHARLES, ST LOUIS, ST LOUIS CITY

District: St. Louis

DBE Goal Percent:

Description: ****(1): Job J6P3450 Route Various FRANKLIN, JEFFERSON, ST CHARLES, ST LOUIS, ST LOUIS CITY County. Job Order Contract for guard cable repair at various locations in the St. Louis District, the total length of improvement being 0 miles.

Contract Time: DT - 6/30/2025

Item No.	Description	Quantity	Units
6189916	MISC. ADJUSTMENT FACTOR	909,090.910	DLR

() Item will be bid as lump sum.



Contract ID
Federal Project Number / State Project Number
Description

240517-F04	
FAS-S503 (069)	J6P3454
J6P3454-VARIOUS ROUTES-FRANKLIN, ST LOUIS, ST CHARLES, JEFFERSON, ST LOUIS CITY	
FAS-S503 (069)	J6P3454
Job Order Contract for concrete pavement repair	



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F04

Contract ID: 240517-F04

Letting Date: May 17, 2024 11:00 AM

Projects: J6P3454

FAS-S503 (069)

Counties: FRANKLIN, JEFFERSON, ST CHARLES, ST LOUIS, ST LOUIS CITY

District: St. Louis

DBE Goal Percent:

Description: ****(1): Job J6P3454 Route Various FRANKLIN, JEFFERSON, ST CHARLES, ST LOUIS, ST LOUIS CITY County. Job Order Contract for concrete pavement repair on commission owned roadways in the St Louis District, the total length of improvement being 0 miles.

Contract Time: DT - 6/30/2025

Item No.	Description	Quantity	Units
6189916	MISC. Adjustment Factor	3,200,000.000	DLR

() Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
240517-F05		
FAS S503(95)	J6P3510B	
J6P3510B-VARIOUS ROUTES-ST CHARLES, ST LOUIS, JEFFERSON COUNTIES		
FAS S503(95)	J6P3510B	
ADA and signal improvements		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F05

Contract ID: 240517-F05

Letting Date: May 17, 2024 11:00 AM

Projects: J6P3510B

FAS S503(95)

Counties: JEFFERSON, ST CHARLES, ST LOUIS

District: St. Louis

DBE Goal Percent: 12.00

Description: ****(1): Job J6P3510B Route Various JEFFERSON, ST CHARLES, ST LOUIS County. ADA and signal improvements at various locations in the St. Louis District, the total length of improvement being 0 miles.

Contract Time: DT - 6/30/2026

Item No.	Description	Quantity	Units
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2079909	MISC. LINEAR GRADING, CLASS 2 - MODIFIED	21.000	STA
3040504	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK) LINEAR GRADING, CLASS 2 - MODIFIED	1,734.000	SQYD
5021310	CONCRETE PAVEMENT (10 IN. NON-REINFORCED 15 FT. JOINTS)	718.100	SQYD
6039902	WATER ADJUST TO GRADE WATER VALVE	2.000	EA
6081012	TRUNCATED DOMES ADJUST TO GRADE WATER VALVE	878.000	SQFT
6083006	6 IN. CONCRETE MEDIAN STRIP	19.600	SQYD
6085008	PAVED APPROACH, 8 IN.	392.600	SQYD
6086004	CONCRETE SIDEWALK, 4 IN.	394.800	SQYD
6086007	CONCRETE SIDEWALK, 7 IN.	165.900	SQYD
6089902	MISC. CONCRETE CURB RAMP	27.000	EA
6089902	MISC. CONCRETE CURB RAMP - DECORATIVE CONCRETE	45.000	EA
6089905	MISC. CONCRETE SIDEWALK, 4 IN. - DECORATIVE CONCRETE	43.000	SQYD
6091010	CONCRETE CURB (6 IN. HEIGHT AND UNDER) TYPE	13.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F05

Item No.	Description	Quantity	Units
6092011	S INTEGRAL CURB (6 IN. HEIGHT AND UNDER) TYPE A CONCRETE SIDEWALK, 4 IN. - DECORATIVE CONCRETE	26.000	LF
6169901	MISC. TRAFFIC CONTROL	1.000	LS
6181000	MOBILIZATION	1.000	LS
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	398.000	LF
6200036	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 30 IN WHITE MIDBLOCK	148.000	EA
6200042	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 12 IN WHITE, YIELD LINE TRIANGLES	133.000	EA
6205902A	6 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	2,179.000	LF
6207001	PAVEMENT MARKING REMOVAL	3,130.000	LF
6209901	MISC. TEMPORARY PAVEMENT MARKING PAINT	1.000	LS
6229903	MISC. SIDEWALK EDGE GRINDING	38.000	LF
8031000A	TURF TYPE TALL FESCUE SODDING	484.000	SQYD
8061007A	CURB INLET CHECK	31.000	EA
8061016	SEDIMENT REMOVAL	19.000	CUYD
8061019	SILT FENCE	1,738.000	LF
9022708	POST, SIGNAL 8 FT.	2.000	EA
9025020	CONDUIT, 1 IN., LOOP DETECTOR WITH TRACER WIRE	70.000	LF
9025300	CONDUIT, 3 IN., TRENCH WITH TRACER WIRE	84.000	LF
9025400	CONDUIT, 4 IN., TRENCH WITH TRACER WIRE	35.000	LF
9027300	CONDUIT, 3 IN., PUSHED WITH TRACER WIRE	64.000	LF
9027400	CONDUIT, 4 IN., PUSHED WITH TRACER WIRE	100.000	LF
9028308	CABLE, 16 AWG 2 CONDUCTOR	3,250.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F05

Item No.	Description	Quantity	Units
9028500	CABLE, LOOP DETECTOR, IN DUCT	3,290.000	LF
9029100	BASE, CONCRETE	0.900	CUYD
9029902	MISC. ADJUST PULL BOX TO GRADE	1.000	EA
9029902	MISC. AUDIBLE PEDESTRIAN PUSHBUTTON AND SIGNING WITH VERBAL WALK MESSAGE	27.000	EA
9029902	MISC. COUNTDOWN PEDESTRIAN SIGNAL HEAD, TYPE 1S	4.000	EA
9029902	MISC. LED BLANKOUT SIGN	2.000	EA
9029902	MISC. PEDESTRIAN PUSHBUTTON EXTENSION	3.000	EA
9029902	MISC. PEDESTRIAN PUSHBUTTON STANCHION, 4 FT	16.000	EA
9029902	MISC. REMOVE AND REPLACE CONC. PULL BOX W/PREFORMED CLASS 2 PULL BOX	2.000	EA
9031010	CONCRETE FOOTINGS, EMBEDDED	4.000	CUYD
9031280	2.5 IN. PSST POST - 12 GA.	17.000	LF
9031281A	DRIVEN POST ANCHOR FOR 2.5 IN. PSST - 7 GA.	1.000	EA
9035069A	SHF-FLAT SHEET FLUORESCENT	90.000	SQFT
9039902	MISC. REMOVE AND RELOCATE EXISTING GROUND MOUNTED SIGN	11.000	EA

() Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
240517-F06		
FAS-S503 (066)	J6P3643	
J6P3643 - ROUTE 141,67,30,367,94,79,N - JEFFERSON, ST. LOUIS, ST. CHARLES COUNTIES		
FAS-S503 (066)	J6P3643	
Upgrade wrong way signs		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F06

Contract ID: 240517-F06

Letting Date: May 17, 2024 11:00 AM

Projects: J6P3643

FAS-S503 (066)

Counties: JEFFERSON, ST CHARLES, ST LOUIS

District: St. Louis

DBE Goal Percent:

Description: ****(1): Job J6P3643 Route Various JEFFERSON, ST CHARLES, ST LOUIS County. Upgrade wrong way signs in the St. Louis District near Route 94, Route N, Route 79, Route 367, Route 141, Route 30 and Route 67, the total length of improvement being 54.347 miles.

Contract Time: DT - 11/30/2024

Item No.	Description	Quantity	Units
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
6123001	TRUCK MOUNTED ATTENUATOR (TMA)	1.000	LS
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	4.000	EA
6169901	MISC. TEMPORARY TRAFFIC CONTROL	1.000	LS
6181000	MOBILIZATION	1.000	LS
9031010	CONCRETE FOOTINGS, EMBEDDED	100.500	CUYD
9031210	STRUCTURAL STEEL POSTS	7,330.000	LB
9031220	PIPE POSTS	59,890.000	LB
9031259A	7 FT. CHANNEL POST DELINEATOR, YELLOW/RED	11.000	EA
9035004A	SH-FLAT SHEET	15,998.000	SQFT
9035069A	SHF-FLAT SHEET FLUORESCENT	58.000	SQFT

() Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
240517-F07		
FAS S502(73)	J6S3278	
J6S3278 - ROUTE H - ST. LOUIS CITY		
FAS S502(73)	J6S3278	
Coldmill and resurface, signals and ADA improvements		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F07

Contract ID: 240517-F07

Letting Date: May 17, 2024 11:00 AM

Projects: J6S3278

FAS S502(73)

Counties: ST LOUIS CITY

District: St. Louis

DBE Goal Percent: 12.00

Description: ****(1): Job J6S3278 Route H ST LOUIS CITY County. Coldmill and resurface, signals and ADA improvements from north of Chain of Rocks Drive to Adelaide Avenue, the total length of improvement being 3.629 miles.

Contract Time: DT - 12/1/2025

Item No.	Description	Quantity	Units
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2079909	MISC. MODIFIED LINEAR GRADING	151.000	STA
3040504	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK)	66.700	SQYD
4030132	ASPHALTIC CONCRETE MIXTURE PG 76-22 (SP125BSM MIX)	9,994.500	TONS
4030217	ASPHALTIC CONCRETE MIXTURE PG 76-22 (SP190B MIX)	11,266.300	TONS
4039910	MISC. HIGH TENSILE STRENGTH SYNTHETIC FIBER ASPHALTIC CONCRETE PAVEMENT PG 76-22 (SP125B MIX)	684.600	TONS
4039910	MISC. HIGH TENSILE STRENGTH SYNTHETIC FIBER ASPHALTIC CONCRETE PAVEMENT PG 76-22 (SP190B MIX)	1,397.800	TONS
4071005	TACK COAT	16,719.000	GAL
6039902	WATER ADJUSTING WATER METER	6.000	EA
6039902	WATER ADJUSTING WATER VALVE	1.000	EA
6039932	GAS ADJUSTING GAS VALVE	2.000	EA
6042010	ADJUSTING MANHOLE	4.000	EA
6042020	ADJUSTING BASIN OR INLET	3.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F07

Item No.	Description	Quantity	Units
6081012	TRUNCATED DOMES	20.000	SQFT
6083006	6 IN. CONCRETE MEDIAN STRIP	981.300	SQYD
6086004	CONCRETE SIDEWALK, 4 IN.	66.700	SQYD
6089902	MISC. ADA CURB RAMP WITH TRUNCATED DOMES	1.000	EA
6089905	MISC. CONCRETE CORRUGATED MEDIAN	4,151.100	SQYD
6091010	CONCRETE CURB (6 IN. HEIGHT AND UNDER) TYPE S	573.000	LF
6122009	IMPACT ATTENUATOR 45 MPH (SAND BARREL ARRAY)	2.000	EA
6123001	TRUCK MOUNTED ATTENUATOR (TMA)	1.000	LS
6131010	FURNISHING AND PLACING CONCRETE MATERIAL FOR FULL DEPTH PAVEMENT REPAIR	536.700	SQYD
6131012	SUBGRADE COMPACTION (6 IN. DEPTH) (PAVEMENT REPAIR)	56.000	SQYD
6131013	TYPE 1 OR 5 AGGREGATE FOR BASE (4 IN. THICK) (PAVEMENT REPAIR)	56.000	SQYD
6131014	FULL DEPTH PAVEMENT REPAIR SAW CUT (FOR PERIMETER AND INTERNAL SAW CUTS)	2,351.000	LF
6131015	DOWEL BAR (DRILLING, FURNISHING AND INSTALLATION) FOR FULL DEPTH PAVEMENT REPAIR	633.000	EA
6131017	DOWEL BAR (FURNISHING AND INSTALLATION WITH BASKETS) FOR FULL DEPTH PAVEMENT REPAIR	81.000	EA
6131018	TIE BAR (DRILLING, FURNISHING AND INSTALLATION) FOR FULL DEPTH PAVEMENT REPAIR (TYPE L JOINTS)	313.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	2.000	EA
6169901	MISC. LUMP SUM TEMPORARY TRAFFIC CONTROL	1.000	LS
6173600D	TEMPORARY TRAFFIC BARRIER, CONTRACTOR FURNISHED / RETAINED	700.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F07

Item No.	Description	Quantity	Units
6181000	MOBILIZATION	1.000	LS
6191000	PAVEMENT EDGE TREATMENT	15,026.000	LF
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	190.000	LF
6200021	PREFORMED THERMOPLASTIC PAVEMENT MARKING, LEFT/RIGHT ARROW	131.000	EA
6200024	PREFORMED THERMOPLASTIC PAVEMENT MARKING, STRAIGHT ARROW	2.000	EA
6200030	PREFORMED THERMOPLASTIC PAVEMENT MARKING, WORD (ONLY)	2.000	EA
6200033	PREFORMED THERMOPLASTIC PAVEMENT MARKING, R/R CROSSING MARKER	4.000	EA
6200036	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 30 IN WHITE MIDBLOCK	31.000	EA
6200042	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 12 IN WHITE, YIELD LINE TRIANGLES	32.000	EA
6205309	TEMPORARY REMOVABLE MARKING TAPE, 24 IN., WHITE	33.000	LF
6205901A	4 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	44,982.000	LF
6205902A	6 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	42,849.000	LF
6206108A	8 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	163.000	LF
6206124A	24 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	173.000	LF
6206125A	24 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	161.000	LF
6207001	PAVEMENT MARKING REMOVAL	55,518.000	LF
6208076	4 IN TEMPORARY PAVEMENT MARKING PAINT	111,036.000	LF
6209902	MISC. CURB REFLECTOR	20.000	EA
6209902	MISC. ISLAND TUBULAR MARKERS	14.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F07

Item No.	Description	Quantity	Units
6221001	COLDMILLING BITUMINOUS PAVEMENT FOR REMOVAL OF SURFACING (3 IN. THICK OR LESS)	103,400.000	SQYD
6224010	MODIFIED COLDMILLING (DEPTH TRANSITIONS)	9,878.000	SQYD
6261000A	BITUMINOUS SHOULDER RUMBLE STRIP	8.400	STA
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
8025006	MULCHING	3.800	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	3.800	ACRE
8061016	SEDIMENT REMOVAL	154.000	CUYD
8061019	SILT FENCE	15,026.000	LF
9020113	SIGNAL HEAD, TYPE 3T	1.000	EA
9020115	SIGNAL HEAD, TYPE 5T	1.000	EA
9020123	SIGNAL HEAD, TYPE 33T	1.000	EA
9020223	SIGNAL HEAD, TYPE 33S	2.000	EA
9020513	SIGNAL HEAD, TYPE 3B	4.000	EA
9020514	SIGNAL HEAD, TYPE 4B	3.000	EA
9020515	SIGNAL HEAD, TYPE 5B	1.000	EA
9020833	SH-FLAT SHEET - SIGNAL SIGN	70.000	SQFT
9020834	SIGNAL SIGN, MOUNTING HARDWARE	10.000	EA
9022708	POST, SIGNAL 8 FT.	1.000	EA
9022715	POST, SIGNAL 15 FT.	2.000	EA
9023135	POST, TYPE CL, 35 FT. ARM OR 10.7 M ARM	1.000	EA
9023235	POST, TYPE C, 35 FT. ARM OR 10.7 M ARM	1.000	EA
9023355	POST, TYPE B, LONGEST ARM 55 FT.	1.000	EA
9024283	CONTROLLER ASSEMBLY HOUSING, NEMA TS2 CONTROLLER	2.000	EA
9024944	DETECTOR, VEHICLE INDUCTION LOOP (2 CHANNEL - RACK MOUNTED)	4.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F07

Item No.	Description	Quantity	Units
9025200	CONDUIT, 2 IN., TRENCH WITH TRACER WIRE	42.000	LF
9025300	CONDUIT, 3 IN., TRENCH WITH TRACER WIRE	49.000	LF
9025400	CONDUIT, 4 IN., TRENCH WITH TRACER WIRE	11.000	LF
9026300	CONDUIT, 3 IN., MEDIAN WITH TRACER WIRE	11.000	LF
9027300	CONDUIT, 3 IN., PUSHED WITH TRACER WIRE	460.000	LF
9028208	CABLE, 8 AWG 1 CONDUCTOR, POWER	110.000	LF
9028219	CABLE, 10 AWG 1 CONDUCTOR, POWER	100.000	LF
9028302	CABLE, 12 AWG 2 CONDUCTOR	430.000	LF
9028308	CABLE, 16 AWG 2 CONDUCTOR	560.000	LF
9028310	CABLE, 16 AWG 5 CONDUCTOR	560.000	LF
9028311	CABLE, 16 AWG 7 CONDUCTOR	3,460.000	LF
9028811	PULL BOX, PREFORMED CLASS 2	4.000	EA
9028812	PULL BOX, PREFORMED CLASS 3	1.000	EA
9029100	BASE, CONCRETE	12.940	CUYD
9029901	MISC. TRAFFIC SIGNAL MAINTENANCE & PROGRAMMING	1.000	LS
9029902	MISC. ATC TRAFFIC SIGNAL CONTROLLER	2.000	EA
9029902	MISC. AUDIBLE PEDESTRIAN PUSHBUTTON & SIGNING WITH VERBAL WALK MESSAGE	2.000	EA
9029902	MISC. COMBINATION PAD MOUNTED 120V/240V POWER SUPPLY AND LIGHTING CONTROLLER WITH UPS	1.000	EA
9029902	MISC. COUNTDOWN PEDESTRIAN SIGNAL HEAD, TYPE 1S	2.000	EA
9029902	MISC. NETWORK CONNECTED SIGNAL MONITOR	2.000	EA
9029902	MISC. RELOCATE TRAFFIC SIGNAL HEAD	5.000	EA
9029902	MISC. REMOVE & REPLACE TRAFFIC SIGNAL ARM (35 FT. ARM)	1.000	EA
9029902	MISC. REMOVE & REPLACE TRAFFIC SIGNAL	5.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F07

Item No.	Description	Quantity	Units
9029902	BACKPLATE MISC. SL DISTRICT TRAFFIC SIGNAL DETECTION SYSTEM	2.000	EA
9029903	MISC. CABLE, 12 AWG 7 CONDUCTOR	20.000	LF
9031010	CONCRETE FOOTINGS, EMBEDDED	0.650	CUYD
9031220	PIPE POSTS	370.700	LB
9031270A	2 IN. PSST POST - 12 GA.	437.000	LF
9031271A	DRIVEN POST ANCHOR FOR 2 IN. PSST - 12 GA.	29.000	EA
9031274	CONCRETE POST ANCHOR FOR 2 IN. PSST. - 7 GA.	15.000	EA
9031280	2.5 IN. PSST POST - 12 GA.	138.000	LF
9031281A	DRIVEN POST ANCHOR FOR 2.5 IN. PSST - 7 GA.	12.000	EA
9035004A	SH-FLAT SHEET	323.200	SQFT
9035069A	SHF-FLAT SHEET FLUORESCENT	175.200	SQFT
9109901	MISC. ITS ASSET MANAGEMENT TOOL	1.000	LS
9109902	MISC. INSTALL OR RELOCATE EXISTING COMMUNICATION EQUIPMENT	1.000	EA

() Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
240517-F08		
FAF 367-1(18)...	J6S3279, J6S3416, J6S3416B	
J6S3279,J6S3416,J6S3416B - Routes H, 367, 115 - ST. LOUIS CITY, ST. LOUIS COUNTIES		
FAF 367-1(18)	J6S3279	
Resurface and ADA improvements		
FAF 115-1(48)	J6S3416	
Resurface, signal and ADA improvements		
STBG-9901(658)	J6S3416B	
ADA improvements		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F08

Contract ID: 240517-F08

Letting Date: May 17, 2024 11:00 AM

Projects: J6S3279
J6S3416
J6S3416B

FAF 367-1(18)
FAF 115-1(48)
STBG-9901(658)

Counties: ST LOUIS, ST LOUIS CITY

District: St. Louis

DBE Goal Percent: 11.00

Description: ****(1): Job J6S3279 Route 367 ST LOUIS CITY County. Resurface and ADA improvements from I-70 to Halls Ferry Circle near Ferguson, the total length of improvement being 2.07 miles. ****(2): Job J6S3416 Route 115 ST LOUIS County. Resurface, signal and ADA improvements from Route U (Lucas and Hunt Road) to east of Dardenne Road near Ferguson, the total length of improvement being 1.296 miles. ****(3): Job J6S3416B Route 115 ST LOUIS County. ADA improvements from Route U to the St. Louis City limits, the total length of improvement being 0.653 miles.

Contract Time: DT - 9/1/2026

Item No.	Description	Quantity	Units
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
3040504	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK)	59.000	SQYD
4030109	ASPHALTIC CONCRETE MIXTURE PG 70-22 (SP125CLP MIX)	11,737.400	TONS
4071005	TACK COAT	9,438.000	GAL
6042010	ADJUSTING MANHOLE	1.000	EA
6049902	MISC. PULL BOX ADJUSTMENT	16.000	EA
6081012	TRUNCATED DOMES	24.000	SQFT
6083008	8 IN. CONCRETE MEDIAN STRIP	21.600	SQYD
6086004	CONCRETE SIDEWALK, 4 IN.	59.100	SQYD
6089902	MISC. ADA CURB RAMP	13.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT	2.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F08

Item No.	Description	Quantity	Units
6169901	COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED		
6181000	MISC. TEMPORARY TRAFFIC CONTROL	1.000	LS
6181000	MOBILIZATION	1.000	LS
6200003	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 4 IN., WHITE	617.000	LF
6200006	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 4 IN YELLOW	66.000	LF
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	707.000	LF
6200021	PREFORMED THERMOPLASTIC PAVEMENT MARKING, LEFT/RIGHT ARROW	12.000	EA
6200024	PREFORMED THERMOPLASTIC PAVEMENT MARKING, STRAIGHT ARROW	4.000	EA
6200027	PREFORMED THERMOPLASTIC PAVEMENT MARKING, COMBINATION STR/LT/RT	7.000	EA
6200036	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 30 IN WHITE MIDBLOCK	388.000	EA
6200042	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 12 IN WHITE, YIELD LINE TRIANGLES	57.000	EA
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	35,770.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	17,842.000	LF
6209901	MISC. TEMPORARY PAVEMENT MARKING PAINT	1.000	LS
6209902	MISC. BIKE LANE SYMBOL PAVEMENT MARKING	54.000	EA
6209902	MISC. SHARED LANE SYMBOL PAVEMENT MARKING	8.000	EA
6221001	COLDMILLING BITUMINOUS PAVEMENT FOR REMOVAL OF SURFACING (3 IN. THICK OR LESS)	72,601.000	SQYD
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
9020513	SIGNAL HEAD, TYPE 3B	4.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F08

Item No.	Description	Quantity	Units
9020833	SH-FLAT SHEET - SIGNAL SIGN	84.000	SQFT
9020834	SIGNAL SIGN, MOUNTING HARDWARE	12.000	EA
9022708	POST, SIGNAL 8 FT.	1.000	EA
9024921	ACCESSIBLE PEDESTRIAN SIGNAL	34.000	EA
9025300	CONDUIT, 3 IN., TRENCH WITH TRACER WIRE	109.000	LF
9027300	CONDUIT, 3 IN., PUSHED WITH TRACER WIRE	96.000	LF
9028308	CABLE, 16 AWG 2 CONDUCTOR	2,170.000	LF
9028310	CABLE, 16 AWG 5 CONDUCTOR	260.000	LF
9029100	BASE, CONCRETE	0.400	CUYD
9029901	MISC. TRAFFIC SIGNAL MAINTENANCE AND PROGRAMING	1.000	LS
9029902	MISC. COUNTDOWN PEDESTRIAN SIGNAL HEAD, TYPE 1S	24.000	EA
9029902	MISC. PEDESTRIAN PUSH BUTTON STANCHION	12.000	EA
9029902	MISC. PUSH BUTTON EXTENSION	1.000	EA
9029902	MISC. SL DISTRICT TRAFFIC SIGNAL DETECTION SYSTEM	3.000	EA
9031270A	2 IN. PSST POST - 12 GA.	477.000	LF
9031271A	DRIVEN POST ANCHOR FOR 2 IN. PSST - 12 GA.	44.000	EA
9031280	2.5 IN. PSST POST - 12 GA.	176.000	LF
9031281A	DRIVEN POST ANCHOR FOR 2.5 IN. PSST - 7 GA.	7.000	EA
9035004A	SH-FLAT SHEET	457.000	SQFT
9035069A	SHF-FLAT SHEET FLUORESCENT	255.000	SQFT
3040504	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK)	121.000	SQYD
4030109	ASPHALTIC CONCRETE MIXTURE PG 70-22 (SP125CLP MIX)	269.700	TONS
4071005	TACK COAT	217.000	GAL
5024007	CONCRETE BASE (7 IN. NON-REINF)	31.700	SQYD



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F08

Item No.	Description	Quantity	Units
6042010	ADJUSTING MANHOLE	2.000	EA
6081012	TRUNCATED DOMES	130.000	SQFT
6083006	6 IN. CONCRETE MEDIAN STRIP	440.200	SQYD
6083008	8 IN. CONCRETE MEDIAN STRIP	85.200	SQYD
6086004	CONCRETE SIDEWALK, 4 IN.	109.500	SQYD
6089902	MISC. ADA CURB RAMP	25.000	EA
6091010	CONCRETE CURB (6 IN. HEIGHT AND UNDER) TYPE S	22.000	LF
6092011	INTEGRAL CURB (6 IN. HEIGHT AND UNDER) TYPE A	228.000	LF
6092022	INTEGRAL CURB (OVER 6 IN. HEIGHT) TYPE B	71.000	LF
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	85.000	LF
6200036	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 30 IN WHITE MIDBLOCK	157.000	EA
6209902	MISC. CURB REFLECTORS	273.000	EA
6209902	MISC. ISLAND TUBULAR MARKER	181.000	EA
6221001	COLDMILLING BITUMINOUS PAVEMENT FOR REMOVAL OF SURFACING (3 IN. THICK OR LESS)	1,667.000	SQYD
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2079909	MISC. MODIFIED LINEAR GRADING CLASS 2	105.000	STA
3040504	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK)	15,237.000	SQYD
4011209	BITUMINOUS PAVEMENT MIXTURE PG64-22, (BP-1)	212.000	TONS
4013000	BITUMINOUS PAVEMENT MIXTURE PG64-22 (BASE)	1,001.800	TONS
4030109	ASPHALTIC CONCRETE MIXTURE PG 70-22 (SP125CLP MIX)	4,524.000	TONS
4071007	TACK COAT - NON-TRACKING	4,945.000	GAL
5021108	CONCRETE PAVEMENT (8 IN. NON-REINF)	488.600	SQYD
5021109	CONCRETE PAVEMENT (9 IN. NON-REINF)	232.000	SQYD
6071102	MODIFIED CONCRETE GUTTER TYPE B	338.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F08

Item No.	Description	Quantity	Units
6079903	MISC. REMOVE AND RELOCATE EXISTING FENCE	79.000	LF
6081012	TRUNCATED DOMES	1,099.000	SQFT
6083006	6 IN. CONCRETE MEDIAN STRIP	127.200	SQYD
6085007	PAVED APPROACH, 7 IN.	2,414.300	SQYD
6086004	CONCRETE SIDEWALK, 4 IN.	5,991.100	SQYD
6089902	MISC. CONCRETE CURB RAMP (7 IN. THICK)	70.000	EA
6089902	MISC. CONCRETE STAIRCASE WITH ADA HANDRAILS	9.000	EA
6091010	CONCRETE CURB (6 IN. HEIGHT AND UNDER) TYPE S	9,033.000	LF
6092011	INTEGRAL CURB (6 IN. HEIGHT AND UNDER) TYPE A	713.000	LF
6099903	MISC. MODIFIED CURB AND GUTTER (1' GUTTER)	218.000	LF
6099903	MISC. MODIFIED CURB AND GUTTER (1.5' GUTTER)	160.000	LF
6099903	MISC. MODIFIED CURB AND GUTTER (2' GUTTER)	55.000	LF
6123001	TRUCK MOUNTED ATTENUATOR (TMA)	1.000	LS
6131010	FURNISHING AND PLACING CONCRETE MATERIAL FOR FULL DEPTH PAVEMENT REPAIR	1,120.000	SQYD
6131012	SUBGRADE COMPACTION (6 IN. DEPTH) (PAVEMENT REPAIR)	112.000	SQYD
6131013	TYPE 1 OR 5 AGGREGATE FOR BASE (4 IN. THICK) (PAVEMENT REPAIR)	112.000	SQYD
6131014	FULL DEPTH PAVEMENT REPAIR SAW CUT (FOR PERIMETER AND INTERNAL SAW CUTS)	5,040.000	LF
6131015	DOWEL BAR (DRILLING, FURNISHING AND INSTALLATION) FOR FULL DEPTH PAVEMENT REPAIR	2,800.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED NTCIP COMPLIANT CHANGEABLE MESSAGE SIGN (CONTRACTOR FURNISHED AND RETAINED)	9.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F08

Item No.	Description	Quantity	Units
6169901	MISC. TEMPORARY TRAFFIC CONTROL	1.000	LS
6169902	MISC. DETECTABLE PEDESTRIAN CHANNELIZING BARRICADE	6.000	EA
6181000	MOBILIZATION	1.000	LS
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	246.000	LF
6200021	PREFORMED THERMOPLASTIC PAVEMENT MARKING, LEFT/RIGHT ARROW	11.000	EA
6200024	PREFORMED THERMOPLASTIC PAVEMENT MARKING, STRAIGHT ARROW	3.000	EA
6200030	PREFORMED THERMOPLASTIC PAVEMENT MARKING, WORD (ONLY)	3.000	EA
6200036	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 30 IN WHITE MIDBLOCK	127.000	EA
6200042	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 12 IN WHITE, YIELD LINE TRIANGLES	95.000	EA
6205901A	4 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	15,755.000	LF
6205902A	6 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	17,274.000	LF
6207001	PAVEMENT MARKING REMOVAL	3,600.000	LF
6208076	4 IN TEMPORARY PAVEMENT MARKING PAINT	3,600.000	LF
6209902	MISC. PREFORMED THERMOPLASTIC PAVMENT MARKING, LANE REDUCTION ARROW	1.000	EA
6221001	COLDMILLING BITUMINOUS PAVEMENT FOR REMOVAL OF SURFACING (3 IN. THICK OR LESS)	39,978.000	SQYD
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7110400	SACRIFICIAL GRAFFITI PROTECTION SYSTEM	1.000	LS
7201000	MECHANICALLY STABILIZED EARTH WALL SYSTEMS	1,636.000	SQFT
7209904	MISC. RECONSTRUCT WALL IN PLACE	83.000	SQFT
7209904	MISC. SMALL BLOCK WALL	1,290.000	SQFT



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F08

Item No.	Description	Quantity	Units
8031000A	TURF TYPE TALL FESCUE SODDING	2,640.000	SQYD
8061007A	CURB INLET CHECK	38.000	EA
8061016	SEDIMENT REMOVAL	15.000	CUYD
8061019	SILT FENCE	602.000	LF
9012230	BASE MOUNTED CONTROL STATION 240 VOLT - 4 CIRCUIT	6.000	EA
9013004	CONDUIT, 4 IN. RIGID, IN TRENCH	677.000	LF
9014004	CONDUIT, 4 IN. RIGID, PUSHED	471.000	LF
9015010	TRENCHING TYPE I	3,407.000	LF
9015020	TRENCHING TYPE II	379.000	LF
9016110	PULL BOX, PREFORMED CLASS 1	29.000	EA
9017407	CABLE-CONDUIT, 1 IN., 2 CONDUCTORS AND 1 BARE NEUTRAL, 8 AWG	6,080.000	LF
9018230	POLE FOUNDATION (30 FT. OR 9.0 M MOUNTING HEIGHT)	20.000	EA
9018612	POWER SUPPLY ASSEMBLY, TYPE 2, 240/120 VOLT SERVICE, LIGHTING ONLY COMBINATION PAD MOUNTED PS & LC (120/240V)	6.000	EA
9019902	MISC. 30' ROADWAY TOP MOUNT LUMINAIRE, LED-B	20.000	EA
9019902	MISC. 30' ROADWAY TOP MOUNT POLE	20.000	EA
9020514	SIGNAL HEAD, TYPE 4B	8.000	EA
9020811	SIGNAL HEAD, TYPE 1S, PEDESTRIAN	11.000	EA
9020833	SH-FLAT SHEET - SIGNAL SIGN	60.000	SQFT
9020834	SIGNAL SIGN, MOUNTING HARDWARE	8.000	EA
9022708	POST, SIGNAL 8 FT.	10.000	EA
9025200	CONDUIT, 2 IN., TRENCH WITH TRACER WIRE	259.000	LF
9028308	CABLE, 16 AWG 2 CONDUCTOR	2,460.000	LF
9028310	CABLE, 16 AWG 5 CONDUCTOR	2,470.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F08

Item No.	Description	Quantity	Units
9028311	CABLE, 16 AWG 7 CONDUCTOR	2,160.000	LF
9029100	BASE, CONCRETE	4.400	CUYD
9029902	MISC. AUDIBLE PEDESTRIAN PUSH BUTTON AND SIGNING	16.000	EA
9029902	MISC. RECTANGULAR RAPID FLASHING BEACON ASSEMBLY	3.000	EA
9029903	MISC. REPLACE BROKEN CONDUIT	100.000	LF
9031210	STRUCTURAL STEEL POSTS	40.000	LB
9031241	BREAKAWAY ASSEMBLY (PERFORATED SQUARE STEEL TUBE)	15.000	EA
9031272A	2.25 IN. PSST POST INSERT (6 FT.) - 12 GA.	13.000	EA
9031280	2.5 IN. PSST POST - 12 GA.	1,229.000	LF
9031281A	DRIVEN POST ANCHOR FOR 2.5 IN. PSST - 7 GA.	104.000	EA
9035004A	SH-FLAT SHEET	159.000	SQFT
9035011A	ST-STRUCTURAL	24.000	SQFT
9035069A	SHF-FLAT SHEET FLUORESCENT	9.000	SQFT
9039902	MISC. BOLT DOWN POST BASE	11.000	EA
2063000	CLASS 3 EXCAVATION	37.000	CUYD
6279901	MISC. MSD AS-BUILT SUBMITTALS	1.000	LS
7259903	MISC. 15 IN. PVC PIPE	5.000	LF
7261015	15 IN. PIPE GROUP A	2.000	LF
7319903	MISC. MSD PCC 2 GRATE INLET WITH SIDE INTAKE - 42" BASE	6.000	LF
7319903	MISC. MSD PCC TRAPPED 2 GRATE INLET WITH SIDE INTAKE - 42" BASE	9.000	LF
7319903	MISC. TBR&R PER MSD INSPECTION	9.000	LF
6049902	MISC. ADJUSTING FIRE HYDRANT TO GRADE	5.000	EA
6049902	MISC. ADJUSTING GAS VALVE	60.000	EA
6049902	MISC. ADJUSTING SANITARY SEWER MANHOLE	9.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F08

Item No.	Description	Quantity	Units
6049902	MISC. ADJUSTING STORM SEWER MANHOLE	15.000	EA
6049902	MISC. ADJUSTING TELEPHONE MANHOLE	66.000	EA
6049902	MISC. ADJUSTING WATER MANHOLES, METERS, AND VALVES	99.000	EA
6049902	MISC. RELOCATE EXISTING FIRE HYDRANT	2.000	EA
9019902	MISC. ADJUST GRATE INLET	1.000	EA
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
5021109	CONCRETE PAVEMENT (9 IN. NON-REINF)	17.800	SQYD
6081012	TRUNCATED DOMES	96.000	SQFT
6083006	6 IN. CONCRETE MEDIAN STRIP	36.300	SQYD
6089902	MISC. CONCRETE CURB RAMP (7 IN. THICK)	7.000	EA
6089905	MISC. STAMPED CONCRETE	689.400	SQYD
6200036	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 30 IN WHITE MIDBLOCK	18.000	EA
6200042	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 12 IN WHITE, YIELD LINE TRIANGLES	50.000	EA
6205901A	4 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	400.000	LF
6207001	PAVEMENT MARKING REMOVAL	3,600.000	LF
6208076	4 IN TEMPORARY PAVEMENT MARKING PAINT	3,600.000	LF
9012230	BASE MOUNTED CONTROL STATION 240 VOLT - 4 CIRCUIT	3.000	EA
9013004	CONDUIT, 4 IN. RIGID, IN TRENCH	434.000	LF
9014004	CONDUIT, 4 IN. RIGID, PUSHED	61.000	LF
9015010	TRENCHING TYPE I	4,149.000	LF
9015020	TRENCHING TYPE II	461.000	LF
9016110	PULL BOX, PREFORMED CLASS 1	7.000	EA
9017407	CABLE-CONDUIT, 1 IN., 2 CONDUCTORS AND 1 BARE NEUTRAL, 8 AWG	6,380.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F08

Item No.	Description	Quantity	Units
9018612	POWER SUPPLY ASSEMBLY, TYPE 2, 240/120 VOLT SERVICE, LIGHTING ONLY COMBINATION PAD MOUNTED PS & LC (120/240V)	3.000	EA
9019902	MISC. PEDESTRIAN LIGHT POLE & LUMINAIRE	29.000	EA
9029902	MISC. RECTANGULAR RAPID FLASHING BEACON ASSEMBLY	2.000	EA
9031280	2.5 IN. PSST POST - 12 GA.	44.000	LF
9031281A	DRIVEN POST ANCHOR FOR 2.5 IN. PSST - 7 GA.	4.000	EA
9035004A	SH-FLAT SHEET	36.000	SQFT
2063000	CLASS 3 EXCAVATION	666.000	CUYD
2063500	CULVERT CLEANOUT	1.000	EA
6279901	MISC. MSD AS-BUILT SUBMITTALS	1.000	LS
7259903	MISC. 12 IN. PVC PIPE	17.000	LF
7259903	MISC. 15 IN. PVC PIPE	135.000	LF
7259903	MISC. 18 IN. PVC PIPE	26.000	LF
7259903	MISC. 21 IN. PVC PIPE	51.000	LF
7259903	MISC. 24 IN. PVC PIPE	104.000	LF
7261012	12 IN. PIPE GROUP A	2.000	LF
7261015	15 IN. PIPE GROUP A	2.000	LF
7261018	18 IN. PIPE GROUP A	252.000	LF
7261021	21 IN. PIPE GROUP A	46.000	LF
7261024	24 IN. PIPE GROUP A	19.000	LF
7319903	MISC. MSD PCC 2 GRATE INLET WITH SIDE INTAKE - 42" BASE	38.000	LF
7319903	MISC. MSD PCC DOUBLE STREET INLET	9.000	LF
7319903	MISC. MSD PCC MANHOLE - 48" BASE	45.000	LF
7319903	MISC. MSD PCC SHORT TOP MANHOLE - 48" BASE	3.000	LF
7319903	MISC. MSD PCC TRAPPED 2 GRATE INLET WITH	26.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F08

Item No.	Description	Quantity	Units
7319903	SIDE INTAKE - 42" BASE		
7319903	MISC. TBR&R PER MSD INSPECTION	23.000	LF
7319903	MISC. TRAPPED DOUBLE STREET INLET	27.000	LF

() Item will be bid as lump sum.



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F11

Contract ID	Federal Project Number / State Project Number	Description
240517-F11		
FAF-364-1 (51)	JSL0093	
JSL0093 - ROUTE 364 - ST LOUIS COUNTY		
FAF-364-1 (51)	JSL0093	
Drainage improvement		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F11

Contract ID: 240517-F11

Letting Date: May 17, 2024 11:00 AM

Projects: JSL0093

FAF-364-1 (51)

Counties: ST LOUIS

District: Southeast

DBE Goal Percent:

Description: ****(1): Job JSL0093 Route 364 ST LOUIS County. Drainage improvement at northeast corner of Bennington in Maryland Heights, the total length of improvement being 0.15 miles.

Contract Time: DT - 3/1/2025

Item No.	Description	Quantity	Units
2013000	CLEARING AND GRUBBING	1.000	ACRE
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2031000	CLASS A EXCAVATION	523.000	CUYD
2036000	COMPACTING EMBANKMENT	26.000	CUYD
2063000	CLASS 3 EXCAVATION	49.000	CUYD
2063300	CLASS 4 EXCAVATION	30.000	CUYD
2063500	CULVERT CLEANOUT	2.000	EA
2069901	MISC. DEWATERING	1.000	LS
3040504	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK)	48.000	SQYD
3105002	GRAVEL (A) OR CRUSHED STONE (B)	12.000	TONS
6071012A	CHAIN-LINK FENCE (60 IN.)	306.000	LF
6071040	DRIVE GATE (CHAIN-LINK)	2.000	EA
6085007	PAVED APPROACH, 7 IN.	28.000	SQYD
6086004	CONCRETE SIDEWALK, 4 IN.	20.000	SQYD
6113020	FURNISHING TYPE 2 ROCK BLANKET	548.000	CUYD
6113040	PLACING TYPE 2 ROCK BLANKET	548.000	CUYD
6119905	MISC. PERMANENT EROSION CONTROL MAT	4,809.000	SQYD
6141024	GRATE AND BEARING PLATE (5 FT. X 3 FT. OR 1524	1.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F11

Item No.	Description	Quantity	Units
6149902	MM X 914 MM) MISC. GRATES AND BEARING PLATES (1 FT. X 7 FT. 7 IN.)	2.000	EA
6149902	MISC. GRATES AND BEARING PLATES (5 FT. X 7 FT. 7 IN.)	6.000	EA
6169901	MISC. TEMPORARY TRAFFIC CONTROL	1.000	LS
6181000	MOBILIZATION	1.000	LS
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	822.000	SQYD
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7034041	CLASS B-1 CONCRETE (CULVERTS)	18.300	CUYD
7061030	REINFORCING STEEL (CULVERTS)	2,820.000	LB
7250348A	48 IN. PIPE GROUP B	20.000	LF
7311053	PRECAST CONCRETE DROP INLET 5 FT X 3 FT	11.000	FT
8025006	MULCHING	0.200	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	1.200	ACRE
8061005	ROCK DITCH CHECK	40.000	LF
8061016	SEDIMENT REMOVAL	13.000	CUYD
8061019	SILT FENCE	1,024.000	LF
9029902	MISC. POTHOLING UTILITY FACILITIES	20.000	EA

() Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
240517-F12		
FAF 141-1(58)	JSL0110	
JSL0110 - ROUTE 141 - ST LOUIS COUNTY		
FAF 141-1(58)	JSL0110	
Signal replacements		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F12

Contract ID: 240517-F12

Letting Date: May 17, 2024 11:00 AM

Projects: JSL0110

FAF 141-1(58)

Counties: ST LOUIS

District: St. Louis

DBE Goal Percent:

Description: ****(1): Job JSL0110 Route 141 ST LOUIS County. Signal replacements at various locations from I-64 to Jefferson Co. line near Manchester, the total length of improvement being 11.8 miles.

Contract Time: DT - 3/31/2025

Item No.	Description	Quantity	Units
6169901	MISC. LUMP SUM TEMPORARY TRAFFIC CONTROL	1.000	LS
6181000	MOBILIZATION	1.000	LS
9029901	MISC. TRAFFIC SIGNAL MAINTENANCE AND PROGRAMMING	1.000	LS
9029902	MISC. ATC TRAFFIC SIGNAL CONTROLLER	29.000	EA
9029902	MISC. REMOVAL OF IMPROVEMENTS	1.000	EA
9029902	MISC. REMOVE IN-PAVEMENT WIRELESS DETECTION SYSTEM SENSYS TRAVEL TIME	8.000	EA
9029902	MISC. TRAFFIC SIGNAL ADVANCED DETECTION SYSTEM (2 UNITS)	15.000	EA
9029902	MISC. TRAFFIC SIGNAL ADVANCED DETECTION SYSTEM (3 UNITS)	10.000	EA
9029902	MISC. TRAFFIC SIGNAL ADVANCED DETECTION SYSTEM (4 UNITS)	5.000	EA
9029902	MISC. TRAFFIC SIGNAL VIDEO DETECTION SYSTEM (3 CAMERAS)	12.000	EA
9029902	MISC. TRAFFIC SIGNAL VIDEO DETECTION SYSTEM (4 CAMERAS)	11.000	EA
9029902	MISC. TRAFFIC SIGNAL VIDEO DETECTION SYSTEM (5 CAMERAS)	1.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F12

Item No.	Description	Quantity	Units
9029902	MISC. TRAFFIC SIGNAL VIDEO DETECTION SYSTEM (6 CAMERAS)	6.000	EA
9029903	MISC. 3 INCH CONDUIT, RIGID, IN-TRENCH OR PUSHED	100.000	LF
9029903	MISC. CONDUIT REPAIR	100.000	LF
9108811	PULL BOX, PREFORMED CLASS 2	1.000	EA
9108816	PULL BOX, PREFORMED CLASS 5	1.000	EA
9109901	MISC. AS-BUILT DRAWINGS	1.000	LS
9109902	MISC. PULL ROPES	29.000	EA

() Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
240517-F13		
FAF 30-1(51)	JSL0122	
JSL0122 - VARIOUS ROUTES - ST LOUIS, JEFFERSON, FRANKLIN COUNTIES, AND ST LOUIS CITY		
FAF 30-1(51)	JSL0122	
Fixed Price Variable Scope for crack sealing		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F13

Contract ID: 240517-F13

Letting Date: May 17, 2024 11:00 AM

Projects: JSL0122

FAF 30-1(51)

Counties: FRANKLIN, JEFFERSON, ST LOUIS, ST LOUIS CITY

District: St. Louis

DBE Goal Percent:

Description: ****(1): Job JSL0122 Route Various FRANKLIN, JEFFERSON, ST LOUIS, ST LOUIS CITY County. Fixed Price Variable Scope for crack sealing at various locations in the St Louis District, the total length of improvement being 36.633 miles.

Contract Time: DT - 6/30/2025

Item No.	Description	Quantity	Units
4137000	BITUMINOUS PAVEMENT CRACK FILLING	1,481,079.000	LF
6123001	TRUCK MOUNTED ATTENUATOR (TMA)	1.000	LS
6161099	CHANGEABLE MESSAGE SIGN WITH COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	4.000	EA
6169901	MISC. LUMP SUM TRAFFIC CONTROL	1.000	LS
6181000	MOBILIZATION	1.000	LS

() Item will be bid as lump sum.



Contract ID
Federal Project Number / State Project Number
Description

240517-F14	
IS 270-5(377)	JSL0142
JSL0142-I-270, SOUTH WOODS MILL, I-64, 370, 364, 50, I-44OR-ST. LOUIS, ST CHARLES COUNTIES	
IS 270-5(377)	JSL0142
Fixed Price Variable Scope for pavement repairs	



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F14

Contract ID: 240517-F14

Letting Date: May 17, 2024 11:00 AM

Projects: JSL0142

IS 270-5(377)

Counties: ST CHARLES, ST LOUIS

District: St. Louis

DBE Goal Percent:

Description: ****(1): Job JSL0142 Route Various ST CHARLES, ST LOUIS County. Fixed Price Variable Scope for pavement repairs at various locations in the St. Louis District, the total length of improvement being 20.146 miles.

Contract Time: DT - 11/1/2024

Item No.	Description	Quantity	Units
6123001	TRUCK MOUNTED ATTENUATOR (TMA)	1.000	LS
6139911	MISC. REMOVAL, FURNISHING, AND PLACING, HOT POLYMER CONCRETE PATCHING FOR CLASS A PARTIAL DEPTH	485,898.000	LB
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	8.000	EA
6169901	MISC. LUMP SUM TEMPORARY TRAFFIC CONTROL	1.000	LS
6181000	MOBILIZATION	1.000	LS
9029902	MISC. 6'X15' LOOP DETECTOR	3.000	EA
9029902	MISC. 6'X30' LOOP DETECTOR	3.000	EA
9029902	MISC. 6'X6' LOOP DETECTOR	3.000	EA

() Item will be bid as lump sum.



Contract ID
Federal Project Number / State Project Number
Description

240517-F15	
FAS S504(7)	JSL0144
JSL0144 - VARIOUS ROUTES - JEFFERSON , FRANKLIN COUNTIES	
FAS S504(7)	JSL0144
Fixed Price Variable Scope for seal coat	



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F15

Contract ID: 240517-F15

Letting Date: May 17, 2024 11:00 AM

Projects: JSL0144

FAS S504(7)

Counties: FRANKLIN, JEFFERSON

District: St. Louis

DBE Goal Percent:

Description: ****(1): Job JSL0144 Route 185, E, V, Z, Y, H FRANKLIN, JEFFERSON County. Fixed Price Variable Scope for seal coat on Rte 185 from Campbelton Dr to Rte 50, on Rte E from Miller St to Jefferson Co, on Rte V from Rte E to Rte JJ, on Rte Z from Rte A to Weier Rd, on Rte Y from Rte 21 to Rte 30, and on Rte H from Rte 185 to Rte 50, the total length of improvement being 48.127 miles.

Contract Time: DT - 9/15/2025

Item No.	Description	Quantity	Units
4091048	EMULSIFIED ASPHALT, SEAL COAT	196,480.000	GAL
4094002	SEAL COAT AGGREGATE, GRADE A2	701,713.000	SQYD
6123001	TRUCK MOUNTED ATTENUATOR (TMA)	1.000	LS
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	10.000	EA
6169901	MISC. LUMP SUM TRAFFIC CONTROL	1.000	LS
6181000	MOBILIZATION	1.000	LS
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	134.000	LF
6200042	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 12 IN WHITE, YIELD LINE TRIANGLES	28.000	EA
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	510,966.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	510,966.000	LF

() Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
240517-F16		
FAS S503(93)	JSL0170	
JSL0170 - VARIOUS ROUTES - VARIOUS COUNTIES		
FAS S503(93)	JSL0170	
Job Order Contract for asphalt pavement repair		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F16

Contract ID: 240517-F16

Letting Date: May 17, 2024 11:00 AM

Projects: JSL0170

FAS S503(93)

Counties: FRANKLIN, JEFFERSON, ST CHARLES, ST LOUIS, ST LOUIS CITY

District: St. Louis

DBE Goal Percent:

Description: ****(1): Job JSL0170 Route Various FRANKLIN, JEFFERSON, ST CHARLES, ST LOUIS, ST LOUIS CITY County. Job Order Contract for asphalt pavement repair at various locations in the St. Louis District, the total length of improvement being 0 miles.

Contract Time: DT - 6/30/2025

Item No.	Description	Quantity	Units
6189916	MISC. ADJUSTMENT FACTOR	2,500,000.000	DLR

() Item will be bid as lump sum.



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F17

Page 142 of 203

Contract ID

Federal Project Number / State Project Number

Description

240517-F17

JSLM0044

JSLM0044-VARIOUS ROUTES-ST. LOUIS, ST. CHARLES, FRANKLIN, JEFFERSON, ST. LOUIS CITY

JSLM0044

Job Order Contract for loop detection repair



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-F17

Contract ID: 240517-F17

Letting Date: May 17, 2024 11:00 AM

Projects: JSLM0044

JSLM0044

Counties: FRANKLIN, JEFFERSON, ST CHARLES, ST LOUIS, ST LOUIS CITY

District: St. Louis

DBE Goal Percent:

Description: ****(1): Job JSLM0044 Route Various FRANKLIN, JEFFERSON, ST CHARLES, ST LOUIS, ST LOUIS CITY County. Job Order Contract for loop detection repair at various locations in the St. Louis District, the total length of improvement being 0 miles.

Contract Time: DT - 6/30/2025

Item No.	Description	Quantity	Units
6189916	MISC. Adjustment Factor	65,600.000	DLR

() Item will be bid as lump sum.



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-G03

Contract ID	Federal Project Number / State Project Number	Description
240517-G03	FAS S604(81), FAF-52-2 (10)	J7P3511, J7S3398
		J7P3511, J7S3398 - VARIOUS ROUTES - BATES, BENTON COUNTIES
	FAS S604(81)	J7P3511
	ADA improvements	
	FAF-52-2 (10)	J7S3398
	ADA improvements	



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-G03

Contract ID: 240517-G03

Letting Date: May 17, 2024 11:00 AM

Projects: J7P3511
J7S3398

FAS S604(81)
FAF-52-2 (10)

Counties: BATES, HENRY

District: Southwest

DBE Goal Percent: 6.00

Description: ****(1): Job J7P3511 Route Old 71, 18, BL 49, 5 BATES County. ADA improvements in Adrian and Butler, the total length of improvement being 0.021 miles.****(2): Job J7S3398 Route J HENRY County. ADA improvements from MO 52 to 0.3 miles north of Calhoun, MO, the total length of improvement being 0.3 miles.

Contract Time: DT - 12/1/2024

Item No.	Description	Quantity	Units
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2079909	MISC. ADA LINEAR GRADING	2.800	STA
3040143	TYPE 1 AGGREGATE FOR BASE (4 IN. THICK)	232.000	SQYD
5021108	CONCRETE PAVEMENT (8 IN. NON-REINF)	6.000	SQYD
6081010	CONCRETE CURB RAMP	44.700	SQYD
6081012	TRUNCATED DOMES	139.000	SQFT
6086004	CONCRETE SIDEWALK, 4 IN.	186.600	SQYD
6091010	CONCRETE CURB (6 IN. HEIGHT AND UNDER) TYPE S	52.000	LF
6123001	TRUCK MOUNTED ATTENUATOR (TMA)	1.000	LS
6161005	CONSTRUCTION SIGNS	268.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	2.000	EA
6161025	CHANNELIZER (TRIM LINE)	100.000	EA
6161040	FLASHING ARROW PANEL	2.000	EA
6161047	TYPE III OBJECT MARKER	12.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-G03

Item No.	Description	Quantity	Units
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	2.000	EA
6169902	MISC. ADA COMPLIANT MOVEABLE BARRICADE	16.000	EA
6181000	MOBILIZATION	1.000	LS
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	96.000	LF
6200036	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 30 IN WHITE MIDBLOCK	51.000	EA
6207001	PAVEMENT MARKING REMOVAL	624.000	LF
6207002	PAVEMENT MARKING REMOVAL (SYMBOLS)	7.000	EA
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
8031000A	TURF TYPE TALL FESCUE SODDING	128.000	SQYD
8061007A	CURB INLET CHECK	2.000	EA
9020833	SH-FLAT SHEET - SIGNAL SIGN	8.000	SQFT
9020834	SIGNAL SIGN, MOUNTING HARDWARE	8.000	EA
9022704	POST, SIGNAL 4 FT.	2.000	EA
9024920	DETECTOR, PUSHBUTTON	8.000	EA
9027300	CONDUIT, 3 IN., PUSHED WITH TRACER WIRE	20.000	LF
9028206	CABLE, 6 AWG 1 CONDUCTOR, POWER	50.000	LF
9028308	CABLE, 16 AWG 2 CONDUCTOR	320.000	LF
9029100	BASE, CONCRETE	1.000	CUYD
9039902	MISC. RELOCATED EXISTING SIGNS	1.000	EA
2013000	CLEARING AND GRUBBING	1.000	ACRE
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2079909	MISC. ADA LINEAR GRADING	16.300	STA
3040143	TYPE 1 AGGREGATE FOR BASE (4 IN. THICK)	1,213.000	SQYD



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-G03

Item No.	Description	Quantity	Units
3105003	GRAVEL (A) OR CRUSHED STONE (B)	318.000	SQYD
6081012	TRUNCATED DOMES	40.000	SQFT
6086004	CONCRETE SIDEWALK, 4 IN.	845.600	SQYD
6086008	CONCRETE SIDEWALK, 8 IN.	68.800	SQYD
6161005	CONSTRUCTION SIGNS	244.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	2.000	EA
6161025	CHANNELIZER (TRIM LINE)	100.000	EA
6161040	FLASHING ARROW PANEL	2.000	EA
6161047	TYPE III OBJECT MARKER	12.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	2.000	EA
6169902	MISC. ADA COMPLIANT MOVEABLE BARRICADE	16.000	EA
6181000	MOBILIZATION	1.000	LS
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7250315A	15 IN. PIPE GROUP B	31.000	LF
7319902	MISC. WATER VALVE HEIGHT ADJUSTMENT	1.000	EA
8025006	MULCHING	0.100	ACRE
8031000A	TURF TYPE TALL FESCUE SODDING	906.000	SQYD
8051000A	SEEDING - COOL SEASON GRASSES	0.100	ACRE
8061019	SILT FENCE	150.000	LF

() Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
240517-G04		
FAF 76-1(41)	J7P3548	
J7P3548- ROUTE 76 - TANEY COUNTY		
FAF 76-1(41)	J7P3548	
2 Bridge rehabilitations		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-G04

Contract ID: 240517-G04

Letting Date: May 17, 2024 11:00 AM

Projects: J7P3548

FAF 76-1(41)

Counties: TANEY

District: Southwest

DBE Goal Percent: 6.00

Description: ****(1): Job J7P3548 Route 76 TANEY County. 2 Bridge rehabilitations over Roark Creek and Missouri and Northern Arkansas Railroad near Branson, the total length of improvement being 0.95 miles.

Contract Time: DT - 5/16/2025

Item No.	Description	Quantity	Units
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2029901	MISC. RAILROAD PLAN SUBMITTAL	1.000	LS
6113040	PLACING TYPE 2 ROCK BLANKET	236.000	CUYD
6161005	CONSTRUCTION SIGNS	1,142.000	SQFT
6161025	CHANNELIZER (TRIM LINE)	150.000	EA
6161030	TYPE III MOVEABLE BARRICADE	25.000	EA
6161040	FLASHING ARROW PANEL	1.000	EA
6161099	CHANGEABLE MESSAGE SIGN WITH COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	3.000	EA
6162002	TEMPORARY LONG-TERM RUMBLE STRIPS	1.000	EA
6169901	MISC. CONSTRUCTION FENCING	1.000	LS
6181000	MOBILIZATION	1.000	LS
6240104A	SEPARATION GEOTEXTILE	356.000	SQYD
8025006	MULCHING	0.200	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	0.200	ACRE
8061016	SEDIMENT REMOVAL	2.000	CUYD
8061019	SILT FENCE	184.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-G04

Item No.	Description	Quantity	Units
2069901	MISC. UNCLASSIFIED EXCAVATION	1.000	LS
2164500	REMOVAL OF EXISTING EXPANSION JOINT & ADJACENT CONCRETE	84.000	LF
2169903	MISC. REMOVE AND REPLACE BARRIER CURB	16.000	LF
7032003	CLASS B CONCRETE (SUBSTRUCTURE)	30.600	CUYD
7034214	CLASS B-2 CONCRETE	52.900	CUYD
7101000	REINFORCING STEEL (EPOXY COATED)	6,650.000	LB
7125102	SURFACE PREPARATION FOR APPLYING EPOXY-MASTIC PRIMER	1.000	LS
7125961	GRAY EPOXY-MASTIC PRIMER	1.000	LS
7129901	MISC. RAIL REPAIRS (K24G1004)	1.000	LS
7129903	MISC. STEEL PILE REPAIR	22.000	LF
2069901	MISC. UNCLASSIFIED EXCAVATION	1.000	LS
2164500	REMOVAL OF EXISTING EXPANSION JOINT & ADJACENT CONCRETE	84.000	LF
2169903	MISC. REMOVE AND REPLACE BARRIER CURB	16.000	LF
7032003	CLASS B CONCRETE (SUBSTRUCTURE)	30.600	CUYD
7034214	CLASS B-2 CONCRETE	56.800	CUYD
7101000	REINFORCING STEEL (EPOXY COATED)	6,870.000	LB
7125102	SURFACE PREPARATION FOR APPLYING EPOXY-MASTIC PRIMER	1.000	LS
7125961	GRAY EPOXY-MASTIC PRIMER	1.000	LS
7129903	MISC. STEEL PILE REPAIR	22.000	LF

() Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
240517-G06		
FAS S603(99)	J7S3242	
J7S3242 - VARIOUS ROUTES - BARRY COUNTY		
FAS S603(99)	J7S3242	
ADA improvements		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-G06

Contract ID: 240517-G06

Letting Date: May 17, 2024 11:00 AM

Projects: J7S3242

FAS S603(99)

Counties: BARRY

District: Southwest

DBE Goal Percent: 5.00

Description: ****(1): Job J7S3242 Route BU 37, C, 86, A BARRY County. ADA improvements in Purdy, on Route A and Route 86 in Wheaton, on Route DD in Seligman and on BU 37 in Cassville, the total length of improvement being 1.495 miles.

Contract Time: DT - 11/1/2024

Item No.	Description	Quantity	Units
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2063000	CLASS 3 EXCAVATION	94.000	CUYD
2063500	CULVERT CLEANOUT	4.000	EA
2071000	LINEAR GRADING CLASS 1	12.800	STA
2079903	MISC. LINEAR GRADING FOR ADA FACILITIES	4,340.000	LF
3040143	TYPE 1 AGGREGATE FOR BASE (4 IN. THICK)	3,029.000	SQYD
3105003	GRAVEL (A) OR CRUSHED STONE (B)	20.000	SQYD
6049902	MISC. ADJUST METER OR VALVE	3.000	EA
6049902	MISC. ADJUSTING MANHOLES	1.000	EA
6049902	MISC. CONNECT TO EXISTING PIPE	2.000	EA
6049904	MISC. STEEL PLATE	75.000	SQFT
6071101	MODIFIED CONCRETE GUTTER TYPE A	22.000	LF
6081010	CONCRETE CURB RAMP	102.100	SQYD
6081012	TRUNCATED DOMES	339.000	SQFT
6084023	SIDEWALK HAND-RAILING WITHOUT BALUSTERS	75.000	LF
6085008	PAVED APPROACH, 8 IN.	728.100	SQYD
6086004	CONCRETE SIDEWALK, 4 IN.	1,611.000	SQYD



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-G06

Item No.	Description	Quantity	Units
6086008	CONCRETE SIDEWALK, 8 IN.	538.000	SQYD
6089903	MISC. SIDEWALK JOINT GRINDING	9.000	LF
6089903	MISC. SIDEWALK MANICURING	6,238.000	LF
6091060	PAVED DITCH	50.800	SQYD
6097000	ROCK LINING	2.000	CUYD
6099903	MISC. S-CURB MODIFIED 12" TO 30"	591.000	LF
6116010A	SLOPE PROTECTION	15.000	SQYD
6123001	TRUCK MOUNTED ATTENUATOR (TMA)	1.000	LS
6141021	GRATE AND BEARING PLATE (3 FT. X 2 FT. OR 914 MM X 610 MM)	1.000	EA
6161005	CONSTRUCTION SIGNS	608.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	2.000	EA
6161025	CHANNELIZER (TRIM LINE)	100.000	EA
6161099	CHANGEABLE MESSAGE SIGN WITH COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	2.000	EA
6169902	MISC. ADA COMPLIANT MOVEABLE BARRICADES	10.000	EA
6181000	MOBILIZATION	1.000	LS
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	12.000	LF
6200036	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 30 IN WHITE MIDBLOCK	14.000	EA
6207002	PAVEMENT MARKING REMOVAL (SYMBOLS)	15.000	EA
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7250412	12 IN. PIPE GROUP C	12.000	LF
7250415	15 IN. PIPE GROUP C	223.000	LF
7250418	18 IN. PIPE GROUP C	34.000	LF
7250424	24 IN. PIPE GROUP C	11.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-G06

Item No.	Description	Quantity	Units
7259902	MISC. BOX DRAIN 5"X10"	1.000	EA
7259902	MISC. SCH. 40 4" PVC 90° ELBOW	4.000	EA
7259903	MISC. SCH. 40 4" PVC PIPE	40.000	LF
7311032	PRECAST CONCRETE DROP INLET 3 FT X 2 FT	3.000	FT
7320824A	24 IN. OR ALLOWED SUBSTITUTE GROUP C FLARED END SECTION	1.000	EA
7321013A	15 IN. OR ALLOWED SUBSTITUTE SAFETY SLOPE END SECTION	12.000	EA
7321014A	18 IN. OR ALLOWED SUBSTITUTE SAFETY SLOPE END SECTION	2.000	EA
8025006	MULCHING	1.000	ACRE
8031000A	TURF TYPE TALL FESCUE SODDING	928.000	SQYD
8051000A	SEEDING - COOL SEASON GRASSES	1.000	ACRE
9031241	BREAKAWAY ASSEMBLY (PERFORATED SQUARE STEEL TUBE)	18.000	EA
9031280	2.5 IN. PSST POST - 12 GA.	288.000	LF
9031285	CONCRETE POST ANCHOR FOR 2.5 IN. PSST. - 7 GA.	18.000	EA
9035004A	SH-FLAT SHEET	34.000	SQFT
9035069A	SHF-FLAT SHEET FLUORESCENT	54.000	SQFT

() Item will be bid as lump sum.



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-G08

Contract ID	Federal Project Number / State Project Number	Description
240517-G08	FAS-S604(097), FAS-S604(099)	JSR0048, JSR0092
	JSR0048, JSR0092 - ROUTE 43, 49, TT - JASPER, NEWTON COUNTIES	
	FAS-S604(097)	JSR0048
	Signal improvements	
	FAS-S604(099)	JSR0092
	Add turn lanes and signal improvements	



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-G08

Contract ID: 240517-G08

Letting Date: May 17, 2024 11:00 AM

Projects: JSR0048
JSR0092

FAS-S604(097)
FAS-S604(099)

Counties: JASPER, NEWTON

District: Southwest

DBE Goal Percent: 6.00

Description: ****(1): Job JSR0048 Route 43 JASPER County. Signal improvements on Route 43 at Main Street and Fountain Road in Joplin, the total length of improvement being 0.069 miles.****(2): Job JSR0092 Route 43, LP 49, TT JASPER, NEWTON County. Add turn lanes and signal improvements on Route 43 at 34th Street, on LP 49 at Route TT in Joplin, the total length of improvement being 0.189 miles.

Contract Time: DT - 12/1/2024

Item No.	Description	Quantity	Units
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
6161005	CONSTRUCTION SIGNS	792.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	2.000	EA
6161025	CHANNELIZER (TRIM LINE)	200.000	EA
6161030	TYPE III MOVEABLE BARRICADE	4.000	EA
6161040	FLASHING ARROW PANEL	2.000	EA
6161099	CHANGEABLE MESSAGE SIGN WITH COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	2.000	EA
6162000A	WORK ZONE TRAFFIC SIGNAL SYSTEM	1.000	EA
6181000	MOBILIZATION	1.000	LS
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
8025006	MULCHING	0.100	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	0.100	ACRE



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-G08

Item No.	Description	Quantity	Units
8061005	ROCK DITCH CHECK	80.000	LF
8061016	SEDIMENT REMOVAL	9.000	CUYD
8061019	SILT FENCE	42.000	LF
9020513	SIGNAL HEAD, TYPE 3B	8.000	EA
9020514	SIGNAL HEAD, TYPE 4B	2.000	EA
9020833	SH-FLAT SHEET - SIGNAL SIGN	70.000	SQFT
9020834	SIGNAL SIGN, MOUNTING HARDWARE	8.000	EA
9022651	LUMINAIRE LED-A, 120 VOLT COMPATIBLE	4.000	EA
9023125	POST, TYPE CL, 25 FT. ARM OR 7.6 M ARM	1.000	EA
9023140	POST, TYPE CL, 40 FT. ARM OR 12.2 M ARM	1.000	EA
9023155	POST, TYPE CL, 55 FT. ARM	2.000	EA
9025200	CONDUIT, 2 IN., TRENCH WITH TRACER WIRE	26.000	LF
9025300	CONDUIT, 3 IN., TRENCH WITH TRACER WIRE	113.000	LF
9027300	CONDUIT, 3 IN., PUSHED WITH TRACER WIRE	136.000	LF
9028100	CABLE, 10 AWG 1 CONDUCTOR, POLE AND BRACKET	320.000	LF
9028208	CABLE, 8 AWG 1 CONDUCTOR, POWER	70.000	LF
9028302	CABLE, 12 AWG 2 CONDUCTOR	440.000	LF
9028311	CABLE, 16 AWG 7 CONDUCTOR	1,270.000	LF
9028621	POWER SUPPLY ASSEMBLY, TYPE-2 WITH 120V LIGHTING CONTROL CABINET	1.000	EA
9028820	PULL BOX, CONCRETE, STANDARD	3.000	EA
9028824	PULL BOX, CONCRETE, DOUBLE TYPE B	1.000	EA
9029100	BASE, CONCRETE	14.000	CUYD
9029901	MISC. CONTRACTOR FURNISHED, CONTRACTOR INSTALLED RADAR DETECTION SYSTEM	1.000	LS
9029901	MISC. SIGNAL COMMUNICATION	1.000	LS
9029902	MISC. MCCAIN 2070 CONTROLLER	1.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-G08

Item No.	Description	Quantity	Units
9029902	MISC. MISC UNINTERRUPTABLE POWER SUPPLY (UPS), MOUNTED ON SIGNAL CABINET	1.000	EA
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2035000	UNCLASSIFIED EXCAVATION	1,240.000	CUYD
2036000	COMPACTING EMBANKMENT	442.000	CUYD
2037075	COMPACTING IN CUT	8.300	STA
2063000	CLASS 3 EXCAVATION	85.000	CUYD
3049905	MISC. TYPE 5 AGGREGATE BASE (8 IN. THICK)	2,537.200	SQYD
4010150	TYPE A2 SHOULDER	305.200	SQYD
4019905	MISC. OPTIONAL PAVEMENT	2,232.000	SQYD
6083008	8 IN. CONCRETE MEDIAN STRIP	170.900	SQYD
6096010A	FURNISHING TYPE 1 ROCK DITCH LINER	2.000	CUYD
6096041	PLACING TYPE 1 ROCK DITCH LINER	2.000	CUYD
6097000	ROCK LINING	2.000	CUYD
6141023	GRATE AND BEARING PLATE (5 FT. X 2 FT. OR 1524 MM X 610 MM)	1.000	EA
6161005	CONSTRUCTION SIGNS	1,006.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	8.000	EA
6161025	CHANNELIZER (TRIM LINE)	75.000	EA
6161030	TYPE III MOVEABLE BARRICADE	4.000	EA
6161040	FLASHING ARROW PANEL	2.000	EA
6161099	CHANGEABLE MESSAGE SIGN WITH COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	8.000	EA
6181000	MOBILIZATION	1.000	LS
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	222.000	LF
6200021	PREFORMED THERMOPLASTIC PAVEMENT MARKING, LEFT/RIGHT ARROW	6.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-G08

Item No.	Description	Quantity	Units
6205902A	6 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	2,142.000	LF
6205903A	6 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	755.000	LF
6205906A	12 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	371.000	LF
6207001	PAVEMENT MARKING REMOVAL	673.000	LF
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7261018	18 IN. PIPE GROUP A	82.000	LF
7311052	PRECAST CONCRETE DROP INLET 5 FT X 2 FT	3.000	FT
7320618A	18 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	1.000	EA
8025006	MULCHING	0.800	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	0.400	ACRE
8061005	ROCK DITCH CHECK	114.000	LF
8061016	SEDIMENT REMOVAL	8.000	CUYD
8061017	TEMPORARY SEEDING	0.400	ACRE
8061019	SILT FENCE	310.000	LF
9011030	LIGHTING POLE, 30 FT. OR 9.0 M, TYPE AT	9.000	EA
9011106	BRACKET ARM, 6 FT. OR 1.8 M	1.000	EA
9011108	BRACKET ARM, 8 FT. OR 2.4 M	6.000	EA
9011110	BRACKET ARM, 10 FT. OR 3.0 M	2.000	EA
9011311	LUMINAIRE, LED-A	9.000	EA
9012230	BASE MOUNTED CONTROL STATION 240 VOLT - 4 CIRCUIT	1.000	EA
9013003	CONDUIT, 3 IN. RIGID, IN TRENCH	18.000	LF
9014003	CONDUIT, 3 IN. RIGID, PUSHED	266.000	LF
9015010	TRENCHING TYPE I	1,104.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-G08

Item No.	Description	Quantity	Units
9016120	PULL BOX, CONCRETE, STANDARD	7.000	EA
9017002	CABLE, 2 AWG 1 CONDUCTOR	90.000	LF
9017110	CABLE, 10 AWG 1 CONDUCTOR, POLE AND BRACKET	740.000	LF
9017407	CABLE-CONDUIT, 1 IN., 2 CONDUCTORS AND 1 BARE NEUTRAL, 8 AWG	3,130.000	LF
9018230	POLE FOUNDATION (30 FT. OR 9.0 M MOUNTING HEIGHT)	9.000	EA
9018612	POWER SUPPLY ASSEMBLY, TYPE 2, 240/120 VOLT SERVICE, LIGHTING ONLY	1.000	EA
9028810	PULL BOX, PREFORMED CLASS 1	4.000	EA
9029902	MISC. RETROREFLECTIVE BACKPLATES	13.000	EA
9031220	PIPE POSTS	1,235.000	LB
9031241	BREAKAWAY ASSEMBLY (PERFORATED SQUARE STEEL TUBE)	1.000	EA
9031242	36 IN. SURFACE-MOUNT DELINEATOR POST	18.000	EA
9031259A	7 FT. CHANNEL POST DELINEATOR, YELLOW/RED	8.000	EA
9031270A	2 IN. PSST POST - 12 GA.	96.000	LF
9031274	CONCRETE POST ANCHOR FOR 2 IN. PSST. - 7 GA.	6.000	EA
9031280	2.5 IN. PSST POST - 12 GA.	32.000	LF
9031285	CONCRETE POST ANCHOR FOR 2.5 IN. PSST. - 7 GA.	2.000	EA
9035004A	SH-FLAT SHEET	208.000	SQFT

() Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
240517-G09		
FAS S605(53)	JSR0071	
JSR0071 - VARIOUS ROUTES - VARIOUS COUNTIES		
FAS S605(53)	JSR0071	
Job Order Contracting for guard cable and guardrail repair		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-G09

Contract ID: 240517-G09

Letting Date: May 17, 2024 11:00 AM

Projects: JSR0071

FAS S605(53)

Counties: VARIOUS

District: Southwest

DBE Goal Percent:

Description: ****(1): Job JSR0071 Route Various VARIOUS County. Job Order Contracting for guard cable and guardrail repair at various locations in the Southwest District, the total length of improvement being 0 miles.

Contract Time: DT - 6/30/2025

Item No.	Description	Quantity	Units
6189916	MISC. Adjustment Factor	2,916,666.670	DLR

() Item will be bid as lump sum.



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-G10

Contract ID	Federal Project Number / State Project Number	Description
--------------------	------------------------------------------------------	--------------------

240517-G10		
FAS S605(50)	JSU0072	
JSU0072 - VARIOUS ROUTES - CHRISITIAN, GREENE COUNTIES		
FAS S605(50)	JSU0072	
Job Order Contracting for guard cable and guardrail repair		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-G10

Contract ID: 240517-G10

Letting Date: May 17, 2024 11:00 AM

Projects: JSU0072

FAS S605(50)

Counties: CHRISTIAN, GREENE

District: Southwest

DBE Goal Percent:

Description: ****(1): Job JSU0072 Route Various CHRISTIAN, GREENE County. Job Order Contracting for guard cable and guardrail repair on various routes in Christian and Greene Counties, the total length of improvement being 0 miles.

Contract Time: DT - 6/30/2025

Item No.	Description	Quantity	Units
6189916	MISC. Adjustment Factor	1,250,000.000	DLR

() Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
240517-G11		
FAF 13-3(88)	J7P3484C	
J7P3484C - ROUTE 13 - HENRY COUNTY		
FAF 13-3(88)	J7P3484C	
2 Bridge replacements		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-G11

Contract ID: 240517-G11

Letting Date: May 17, 2024 11:00 AM

Projects: J7P3484C

FAF 13-3(88)

Counties: HENRY

District: Southwest

DBE Goal Percent: 6.00

Description: ****(1): Job J7P3484C Route 13 HENRY County. 2 Bridge replacements from SE 400th to Route 52 near Deepwater, the total length of improvement being 3.679 miles.

Contract Time: DT - 11/1/2025

Item No.	Description	Quantity	Units
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2035000	UNCLASSIFIED EXCAVATION	598.000	CUYD
2035500	EMBANKMENT IN PLACE	4,692.000	CUYD
2036000	COMPACTING EMBANKMENT	508.000	CUYD
2063000	CLASS 3 EXCAVATION	75.000	CUYD
2153000	SHAPING SLOPES, CLASS III	17.000	100F
3040504	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK)	2,625.000	SQYD
3040506	TYPE 5 AGGREGATE FOR BASE (6 IN. THICK)	7,186.000	SQYD
4039905	MISC. OPTIONAL PAVEMENT	9,811.000	SQYD
4071005	TACK COAT	981.000	GAL
6044011	PIPE COLLAR, TYPE A	1.000	EA
6113020	FURNISHING TYPE 2 ROCK BLANKET	16,390.000	CUYD
6113040	PLACING TYPE 2 ROCK BLANKET	16,390.000	CUYD
6122017	IMPACT ATTENUATOR 65 MPH (SAND BARREL ARRAY)	1.000	EA
6122040	WORK ZONE CRASH CUSHION (NARROW)	2.000	EA
6161005	CONSTRUCTION SIGNS	1,532.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	4.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-G11

Item No.	Description	Quantity	Units
6161012	BUOYS (BOATS KEEP OUT)	8.000	EA
6161013	BUOYS (NO WAKE)	10.000	EA
6161014	SPECIAL SIGN ASSEMBLY (BOATS KEEP OUT)	6.000	EA
6161025	CHANNELIZER (TRIM LINE)	198.000	EA
6161030	TYPE III MOVEABLE BARRICADE	26.000	EA
6161040	FLASHING ARROW PANEL	2.000	EA
6161070	TUBULAR MARKER	510.000	EA
6161099	CHANGEABLE MESSAGE SIGN WITH COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	4.000	EA
6162002	TEMPORARY LONG-TERM RUMBLE STRIPS	20.000	EA
6169903	MISC. SEPARATOR CURB W/ DELINEATORS	350.000	LF
6181000	MOBILIZATION	1.000	LS
6200018	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. YELLOW	324.000	LF
6205901A	4 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	53,520.000	LF
6205902A	6 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	58,412.000	LF
6207001	PAVEMENT MARKING REMOVAL	104,246.000	LF
6208064A	TEMPORARY RAISED PAVEMENT MARKER	130.000	EA
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	24,584.000	SQYD
6261000A	BITUMINOUS SHOULDER RUMBLE STRIP	36.000	STA
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7261018	18 IN. PIPE GROUP A	695.000	LF
7261036	36 IN. PIPE GROUP A	40.000	LF
7310060	PRECAST CONCRETE MANHOLE - 60 IN.	1.000	FT
7320018A	18 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED	4.000	EA



Item No.	Description	Quantity	Units
	END SECTION		
8061005	ROCK DITCH CHECK	100.000	LF
8061016	SEDIMENT REMOVAL	112.000	CUYD
8061019	SILT FENCE	1,120.000	LF
8061050	TYPE C BERM	3,075.000	LF
6061060	MGS GUARDRAIL	1,600.000	LF
6061069	MGS BRIDGE APPROACH TRANSITION SECTION (REGULAR/NO CURB)	4.000	EA
9031241	BREAKAWAY ASSEMBLY (PERFORATED SQUARE STEEL TUBE)	3.000	EA
9031280	2.5 IN. PSST POST - 12 GA.	48.000	LF
9031285	CONCRETE POST ANCHOR FOR 2.5 IN. PSST. - 7 GA.	3.000	EA
9035004A	SH-FLAT SHEET	70.000	SQFT
2061000	CLASS 1 EXCAVATION	120.000	CUYD
2065500	TEMPORARY SHORING	1.000	LS
2160500	REMOVAL OF BRIDGES	1.000	LS
5031010A	BRIDGE APPROACH SLAB (MAJOR)	173.000	SQYD
7011110	DRILLED SHAFTS (6 FT. 0 IN. DIA.)	228.000	LF
7011209	ROCK SOCKETS (5 FT 6 IN. DIA.)	117.200	LF
7011300	VIDEO CAMERA INSPECTION	8.000	EA
7011400	FOUNDATION INSPECTION HOLES	197.200	LF
7011600	SONIC LOGGING TESTING	8.000	EA
7021212	GALVANIZED STRUCTURAL STEEL PILES (12 IN)	840.000	LF
7027000	PILE POINT REINFORCEMENT	14.000	EA
7032003	CLASS B CONCRETE (SUBSTRUCTURE)	474.600	CUYD
7034219A	TYPE D BARRIER	1,138.000	LF
7034221	SLAB ON CONCRETE NU-GIRDER	2,402.000	SQYD
7056022	NU 43, PRESTRESSED CONCRETE NU-GIRDER	2,638.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-G11

Item No.	Description	Quantity	Units
7061060	REINFORCING STEEL (BRIDGES)	137,640.000	LB
7061070	MECHANICAL BAR SPLICE	200.000	EA
7123610	SLAB DRAIN	96.000	EA
7151001	VERTICAL DRAIN AT END BENTS	2.000	EA
7161000	PLAIN NEOPRENE BEARING PAD	10.000	EA
7161002	LAMINATED NEOPRENE BEARING PAD	40.000	EA
2061000	CLASS 1 EXCAVATION	70.000	CUYD
2065500	TEMPORARY SHORING	1.000	LS
2160500	REMOVAL OF BRIDGES	1.000	LS
5031010A	BRIDGE APPROACH SLAB (MAJOR)	176.000	SQYD
7011110	DRILLED SHAFTS (6 FT. 0 IN. DIA.)	292.000	LF
7011209	ROCK SOCKETS (5 FT 6 IN. DIA.)	111.200	LF
7011300	VIDEO CAMERA INSPECTION	8.000	EA
7011400	FOUNDATION INSPECTION HOLES	199.200	LF
7011600	SONIC LOGGING TESTING	8.000	EA
7021212	GALVANIZED STRUCTURAL STEEL PILES (12 IN)	620.000	LF
7027000	PILE POINT REINFORCEMENT	10.000	EA
7032003	CLASS B CONCRETE (SUBSTRUCTURE)	400.400	CUYD
7034219A	TYPE D BARRIER	782.000	LF
7034221	SLAB ON CONCRETE NU-GIRDER	1,620.000	SQYD
7056022	NU 43, PRESTRESSED CONCRETE NU-GIRDER	1,418.000	LF
7061060	REINFORCING STEEL (BRIDGES)	135,480.000	LB
7061070	MECHANICAL BAR SPLICE	296.000	EA
7123610	SLAB DRAIN	62.000	EA
7151001	VERTICAL DRAIN AT END BENTS	2.000	EA
7161000	PLAIN NEOPRENE BEARING PAD	8.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-G11

Item No.	Description	Quantity	Units
7161002	LAMINATED NEOPRENE BEARING PAD	32.000	EA

() Item will be bid as lump sum.



Contract ID
Federal Project Number / State Project Number
Description

240517-H03	
FAS S703(47), FAS S703(48)...	J9S3593, J9S3595, J9S3669...
J9S3593, J9S3595, J9S3669, J9S3676 - ROUTE HH, K, O, A - PEMISCOT, DUNKLIN COUNTIES	
FAS S703(47)	J9S3593
Bridge replacement	
FAS S703(48)	J9S3595
Bridge replacement	
FAS S704(28)	J9S3669
Bridge replacement	
FAS S704(55)	J9S3676
3 Bridge replacements (1 with bridge, 2 with culverts)	



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H03

Contract ID: 240517-H03

Letting Date: May 17, 2024 11:00 AM

Projects: J9S3593	FAS S703(47)
J9S3595	FAS S703(48)
J9S3669	FAS S704(28)
J9S3676	FAS S704(55)

Counties: DUNKLIN, PEMISCOT

District: Southeast

DBE Goal Percent: 4.00

Description: ****(1): Job J9S3593 Route HH PEMISCOT County. Bridge replacement over Drainage Ditch No. 85, the total length of improvement being 0.066 miles.****(2): Job J9S3595 Route K PEMISCOT County. Bridge replacement over Main Ditch District No. 8, the total length of improvement being 0.137 miles.****(3): Job J9S3669 Route O PEMISCOT County. Bridge replacement over Pemiscot Bayou 2.75 miles east of I-55, the total length of improvement being 0.06 miles.****(4): Job J9S3676 Route A DUNKLIN County. 3 Bridge replacements (1 with bridge, 2 with culverts) from 3 miles north of Senath to 6 miles north of Senath, the total length of improvement being 0.3 miles.

Contract Time: DT - 6/30/2026

Item No.	Description	Quantity	Units
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2064000	POROUS BACKFILL	55.000	CUYD
2079909	MISC. MODIFIED LINEAR GRADING CLASS 2	5.300	STA
3040506	TYPE 5 AGGREGATE FOR BASE (6 IN. THICK)	567.000	SQYD
3105002	GRAVEL (A) OR CRUSHED STONE (B)	396.000	TONS
4019905	MISC. OPTIONAL PAVEMENT	566.400	SQYD
6113020	FURNISHING TYPE 2 ROCK BLANKET	340.000	CUYD
6113040	PLACING TYPE 2 ROCK BLANKET	340.000	CUYD
6149902	MISC. 18 IN. FLAP GATE	2.000	EA
6149902	MISC. 24 IN. FLAP GATE	1.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H03

Item No.	Description	Quantity	Units
6149902	MISC. 36 IN. FLAP GATE	1.000	EA
6161005	CONSTRUCTION SIGNS	109.000	SQFT
6161030	TYPE III MOVEABLE BARRICADE	6.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	2.000	EA
6181000	MOBILIZATION	1.000	LS
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	360.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	2,445.000	LF
6207001	PAVEMENT MARKING REMOVAL	3,500.000	LF
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	689.000	SQYD
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7250418	18 IN. PIPE GROUP C	161.000	LF
7250424	24 IN. PIPE GROUP C	85.000	LF
7250436	36 IN. PIPE GROUP C	76.000	LF
8025006	MULCHING	1.600	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	1.000	ACRE
8061005	ROCK DITCH CHECK	44.000	LF
8061016	SEDIMENT REMOVAL	8.000	CUYD
8061017	TEMPORARY SEEDING	0.600	ACRE
8061019	SILT FENCE	364.000	LF
8061050	TYPE C BERM	150.000	LF
9031270A	2 IN. PSST POST - 12 GA.	49.000	LF
9031271A	DRIVEN POST ANCHOR FOR 2 IN. PSST - 12 GA.	12.000	EA
9035069A	SHF-FLAT SHEET FLUORESCENT	36.000	SQFT



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H03

Item No.	Description	Quantity	Units
2061000	CLASS 1 EXCAVATION	60.000	CUYD
2160500	REMOVAL OF BRIDGES	1.000	LS
5031011A	BRIDGE APPROACH SLAB (MINOR ROAD)	108.000	SQYD
7021314	GALVANIZED CAST-IN-PLACE CONCRETE PILES (14 IN)	348.000	LF
7025001	DYNAMIC PILE TESTING	2.000	EA
7027000	PILE POINT REINFORCEMENT	12.000	EA
7032003	CLASS B CONCRETE (SUBSTRUCTURE)	23.400	CUYD
7034216	TYPE H BARRIER	179.000	LF
7034222	SLAB ON CONCRETE BEAM	215.000	SQYD
7056050A	27 IN., PRESTRESSED CONCRETE SPREAD BOX BEAM	212.000	LF
7123610	SLAB DRAIN	12.000	EA
7151001	VERTICAL DRAIN AT END BENTS	2.000	EA
7161000	PLAIN NEOPRENE BEARING PAD	6.000	EA
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2064000	POROUS BACKFILL	55.000	CUYD
2079909	MISC. MODIFIED LINEAR GRADING CLASS 2	7.700	STA
3040506	TYPE 5 AGGREGATE FOR BASE (6 IN. THICK)	1,294.000	SQYD
3105002	GRAVEL (A) OR CRUSHED STONE (B)	26.000	TONS
4019905	MISC. OPTIONAL PAVEMENT	1,293.800	SQYD
6113020	FURNISHING TYPE 2 ROCK BLANKET	2,841.000	CUYD
6113040	PLACING TYPE 2 ROCK BLANKET	2,841.000	CUYD
6161005	CONSTRUCTION SIGNS	109.000	SQFT
6161030	TYPE III MOVEABLE BARRICADE	6.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	2.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H03

Item No.	Description	Quantity	Units
6181000	MOBILIZATION	1.000	LS
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	1,446.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	904.000	LF
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	3,189.000	SQYD
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
8025006	MULCHING	2.400	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	1.200	ACRE
8061005	ROCK DITCH CHECK	108.000	LF
8061016	SEDIMENT REMOVAL	20.000	CUYD
8061017	TEMPORARY SEEDING	1.200	ACRE
8061019	SILT FENCE	1,011.000	LF
8061050	TYPE C BERM	362.000	LF
9031270A	2 IN. PSST POST - 12 GA.	49.000	LF
9031271A	DRIVEN POST ANCHOR FOR 2 IN. PSST - 12 GA.	12.000	EA
9035069A	SHF-FLAT SHEET FLUORESCENT	36.000	SQFT
2061000	CLASS 1 EXCAVATION	60.000	CUYD
2160500	REMOVAL OF BRIDGES	1.000	LS
5031011A	BRIDGE APPROACH SLAB (MINOR ROAD)	109.000	SQYD
7021316	GALVANIZED CAST-IN-PLACE CONCRETE PILES (16 IN)	1,248.000	LF
7025001	DYNAMIC PILE TESTING	4.000	EA
7025004	DYNAMIC PILE RESTRIKE TESTING	4.000	EA
7027000	PILE POINT REINFORCEMENT	24.000	EA
7032003	CLASS B CONCRETE (SUBSTRUCTURE)	51.000	CUYD
7034216	TYPE H BARRIER	360.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H03

Item No.	Description	Quantity	Units
7034222	SLAB ON CONCRETE BEAM	483.000	SQYD
7056049	21 IN., PRESTRESSED CONCRETE SPREAD BOX BEAM	478.000	LF
7061060	REINFORCING STEEL (BRIDGES)	7,780.000	LB
7123610	SLAB DRAIN	16.000	EA
7151001	VERTICAL DRAIN AT END BENTS	2.000	EA
7161000	PLAIN NEOPRENE BEARING PAD	6.000	EA
7161002	LAMINATED NEOPRENE BEARING PAD	12.000	EA
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2031000	CLASS A EXCAVATION	173.000	CUYD
2035500	EMBANKMENT IN PLACE	1,792.000	CUYD
2036000	COMPACTING EMBANKMENT	145.000	CUYD
3040506	TYPE 5 AGGREGATE FOR BASE (6 IN. THICK)	867.000	SQYD
3105002	GRAVEL (A) OR CRUSHED STONE (B)	38.000	TONS
4019905	MISC. OPTIONAL PAVEMENT	867.000	SQYD
6096020	FURNISHING TYPE 2 ROCK DITCH LINER	30.000	CUYD
6096042	PLACING TYPE 2 ROCK DITCH LINER	30.000	CUYD
6113010	FURNISHING TYPE 1 ROCK BLANKET	136.000	CUYD
6113030	PLACING TYPE 1 ROCK BLANKET	136.000	CUYD
6161005	CONSTRUCTION SIGNS	197.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	2.000	EA
6161030	TYPE III MOVEABLE BARRICADE	10.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	2.000	EA
6181000	MOBILIZATION	1.000	LS
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	1,000.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H03

Item No.	Description	Quantity	Units
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	539.000	LF
6207001	PAVEMENT MARKING REMOVAL	3,000.000	LF
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	204.000	SQYD
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7250424	24 IN. PIPE GROUP C	52.000	LF
7250430	30 IN. PIPE GROUP C	61.000	LF
7250436	36 IN. PIPE GROUP C	188.000	LF
8025006	MULCHING	1.000	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	1.000	ACRE
8061005	ROCK DITCH CHECK	32.000	LF
8061016	SEDIMENT REMOVAL	6.000	CUYD
8061019	SILT FENCE	554.000	LF
2063300	CLASS 4 EXCAVATION	160.000	CUYD
2069901	MISC. DEWATERING	1.000	LS
2160500	REMOVAL OF BRIDGES	1.000	LS
7034040	CLASS B-1 CONCRETE (CULVERTS-BRIDGE)	123.100	CUYD
7061020	REINFORCING STEEL (CULVERTS-BRIDGE)	24,900.000	LB
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2031000	CLASS A EXCAVATION	2,610.000	CUYD
2036000	COMPACTING EMBANKMENT	490.000	CUYD
2037075	COMPACTING IN CUT	7.200	STA
2063300	CLASS 4 EXCAVATION	163.000	CUYD
2064000	POROUS BACKFILL	310.000	CUYD
2069901	MISC. DEWATERING	1.000	LS
2160500	REMOVAL OF BRIDGES	1.000	LS



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H03

Item No.	Description	Quantity	Units
3040506	TYPE 5 AGGREGATE FOR BASE (6 IN. THICK)	3,492.000	SQYD
3105002	GRAVEL (A) OR CRUSHED STONE (B)	32.000	TONS
4019905	MISC. OPTIONAL PAVEMENT	3,492.000	SQYD
6096020	FURNISHING TYPE 2 ROCK DITCH LINER	100.000	CUYD
6096042	PLACING TYPE 2 ROCK DITCH LINER	100.000	CUYD
6113010	FURNISHING TYPE 1 ROCK BLANKET	800.000	CUYD
6113030	PLACING TYPE 1 ROCK BLANKET	800.000	CUYD
6161005	CONSTRUCTION SIGNS	936.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	2.000	EA
6161030	TYPE III MOVEABLE BARRICADE	14.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	2.000	EA
6181000	MOBILIZATION	1.000	LS
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	2,842.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	1,355.000	LF
6207001	PAVEMENT MARKING REMOVAL	3,887.000	LF
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	2,205.000	SQYD
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7034041	CLASS B-1 CONCRETE (CULVERTS)	165.500	CUYD
7061030	REINFORCING STEEL (CULVERTS)	31,670.000	LB
7250418	18 IN. PIPE GROUP C	166.000	LF
7250424	24 IN. PIPE GROUP C	194.000	LF
7250436	36 IN. PIPE GROUP C	147.000	LF
8025006	MULCHING	2.500	ACRE



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H03

Item No.	Description	Quantity	Units
8051000A	SEEDING - COOL SEASON GRASSES	1.500	ACRE
8061005	ROCK DITCH CHECK	72.000	LF
8061016	SEDIMENT REMOVAL	55.000	CUYD
8061017	TEMPORARY SEEDING	1.000	ACRE
8061019	SILT FENCE	2,901.000	LF
8061050	TYPE C BERM	74.000	LF
6061075	MGS LONG SPAN GUARDRAIL SECTION	9.000	EA
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	2.000	EA
9031270A	2 IN. PSST POST - 12 GA.	75.000	LF
9031271A	DRIVEN POST ANCHOR FOR 2 IN. PSST - 12 GA.	12.000	EA
9035069A	SHF-FLAT SHEET FLUORESCENT	36.000	SQFT
2061000	CLASS 1 EXCAVATION	70.000	CUYD
2160500	REMOVAL OF BRIDGES	1.000	LS
5031011A	BRIDGE APPROACH SLAB (MINOR ROAD)	108.000	SQYD
7021316	GALVANIZED CAST-IN-PLACE CONCRETE PILES (16 IN)	660.000	LF
7025001	DYNAMIC PILE TESTING	2.000	EA
7032003	CLASS B CONCRETE (SUBSTRUCTURE)	25.000	CUYD
7034216	TYPE H BARRIER	185.000	LF
7034222	SLAB ON CONCRETE BEAM	221.000	SQYD
7056050A	27 IN., PRESTRESSED CONCRETE SPREAD BOX BEAM	291.000	LF
7123610	SLAB DRAIN	7.000	EA
7151001	VERTICAL DRAIN AT END BENTS	2.000	EA
7161000	PLAIN NEOPRENE BEARING PAD	8.000	EA

() Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
240517-H04		
FAS S703(74)	J9S3610	
J9S3610 - ROUTE 221 - ST. FRANCOIS COUNTY		
FAS S703(74)	J9S3610	
Resurface		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H04

Contract ID: 240517-H04

Letting Date: May 17, 2024 11:00 AM

Projects: J9S3610

FAS S703(74)

Counties: IRON, ST FRANCOIS

District: Southeast

DBE Goal Percent: 5.00

Description: ****(1): Job J9S3610 Route 221 IRON, ST FRANCOIS County. Resurface from Route 67 to Route 21 near Doe Run in Pilot Knob, the total length of improvement being 15.77 miles.

Contract Time: DT - 11/1/2025

Item No.	Description	Quantity	Units
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2024013	REMOVAL OF SURFACING ACM (FRIABLE)	120.000	SQFT
2024070	REMOVAL OF FLOOR SHEETING ACM ON WOOD (FRIABLE)	6.000	SQFT
2026050	TANK PIT WATER DISPOSAL	750.000	GAL
2027000	DISPOSAL AND PLUGGING OF WELLS	1.000	EA
2028000	PLUGGING AND DISPOSAL OF SEPTIC TANKS	1.000	EA
2029950	DEMOLITION AND REMOVAL OF BUILDINGS Parcel 9	1.000	LS
2031000	CLASS A EXCAVATION	16,904.000	CUYD
2032000	CLASS C EXCAVATION	30,855.000	CUYD
2035500	EMBANKMENT IN PLACE	3,412.000	CUYD
2036000	COMPACTING EMBANKMENT	48,003.000	CUYD
2037075	COMPACTING IN CUT	31.000	STA
2063000	CLASS 3 EXCAVATION	501.000	CUYD
2072000	LINEAR GRADING CLASS 2	20.400	STA
2159903	MISC. MISC.(Modified Shaping Slopes, Class III)	480.000	LF
3040504	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK)	2,976.000	SQYD
3040506	TYPE 5 AGGREGATE FOR BASE (6 IN. THICK)	15,004.000	SQYD



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H04

Item No.	Description	Quantity	Units
3049910	MISC. MISC.(Permanent Aggregate Edge Treatment)	428.000	TONS
3105003	GRAVEL (A) OR CRUSHED STONE (B)	328.000	SQYD
4013010	BITUMINOUS PAVEMENT MIXTURE PG64-22 (BASE WIDENING)	154.000	TONS
4030001	ASPHALTIC CONCRETE MIXTURE PG 64-22 (SP095C MIX)	25,286.000	TONS
4071005	TACK COAT	21,384.000	GAL
6119910	MISC. MISC. (Type 2 Rock Ditch Liner)	469.000	TONS
6123001	TRUCK MOUNTED ATTENUATOR (TMA)	1.000	LS
6161005	CONSTRUCTION SIGNS	2,083.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	10.000	EA
6161030	TYPE III MOVEABLE BARRICADE	10.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	6.000	EA
6173100	CONCRETE TRAFFIC BARRIER, TYPE D	30.000	LF
6181000	MOBILIZATION	1.000	LS
6181020	ADDITIONAL MOBILIZATION FOR SEEDING	2.000	EA
6200021	PREFORMED THERMOPLASTIC PAVEMENT MARKING, LEFT/RIGHT ARROW	22.000	EA
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	166,542.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	137,332.000	LF
6221001	COLDMILLING BITUMINOUS PAVEMENT FOR REMOVAL OF SURFACING (3 IN. THICK OR LESS)	188.000	SQYD
6224010	MODIFIED COLDMILLING (DEPTH TRANSITIONS)	6,856.000	SQYD
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	965.000	SQYD
6261000A	BITUMINOUS SHOULDER RUMBLE STRIP	1,423.000	STA
6261001	BITUMINOUS CENTERLINE RUMBLE STRIP	661.000	STA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H04

Item No.	Description	Quantity	Units
6269903	MISC. Transverse Rumble Strips	426.000	LF
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7250318A	18 IN. PIPE GROUP B	774.000	LF
7250324A	24 IN. PIPE GROUP B	124.000	LF
7250336A	36 IN. PIPE GROUP B	69.000	LF
7261018	18 IN. PIPE GROUP A	109.000	LF
7261036	36 IN. PIPE GROUP A	127.000	LF
7261060	60 IN. PIPE GROUP A	132.000	LF
7261072	72 IN. PIPE GROUP A	167.000	LF
7320618A	18 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	2.000	EA
7320636A	36 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	2.000	EA
7320660A	60 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	2.000	EA
7320672A	72 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	4.000	EA
7322018A	BEVELED PIPE END TREATMENT FOR 18 IN. OR ALLOWED SUBSTITUTE PIPE	24.000	EA
7322024A	BEVELED PIPE END TREATMENT FOR 24 IN. OR ALLOWED SUBSTITUTE PIPE	2.000	EA
7322036A	BEVELED PIPE END TREATMENT FOR 36 IN. OR ALLOWED SUBSTITUTE PIPE	2.000	EA
8025006	MULCHING	9.200	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	5.200	ACRE
8052000A	SEEDING - WARM SEASON GRASSES	4.000	ACRE
8061005	ROCK DITCH CHECK	1,320.000	LF
8061016	SEDIMENT REMOVAL	121.000	CUYD
8061017	TEMPORARY SEEDING	6.000	ACRE



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H04

Item No.	Description	Quantity	Units
8061019	SILT FENCE	3,300.000	LF
4010101	8 INCHES, BITUMINOUS PAVEMENT	14,574.200	SQYD
5021331	CONCRETE PAVEMENT (7 1/2 IN. NON-REINFORCED, 15 FT. JOINTS)	14,574.200	SQYD
6061061	MGS GUARDRAIL, 8 FT. POSTS, 6 FT. - 3 IN. SPACING	88.000	LF
6061069	MGS BRIDGE APPROACH TRANSITION SECTION (REGULAR/NO CURB)	3.000	EA
6061070	MGS VERTICAL CONCRETE BARRIER TRANSITION	2.000	EA
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	5.000	EA
6063020	TYPE C CRASHWORTHY END TERMINAL (MASH)	1.000	EA
2169903	MISC. REMOVAL OF EXISTING RAIL	424.000	LF
7034600	CURB BLOCKOUT	430.000	LF

() Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
240517-H05		
FAS S705(77)	J9S3821	
J9S3821-ROUTE B-PERRY, CAPE GIRARDEAU COUNTIES		
FAS S705(77)	J9S3821	
Resurface		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H05

Contract ID: 240517-H05

Letting Date: May 17, 2024 11:00 AM

Projects: J9S3821

FAS S705(77)

Counties: CAPE GIRARDEAU, PERRY

District: Southeast

DBE Goal Percent: 3.00

Description: ****(1): Job J9S3821 Route B CAPE GIRARDEAU, PERRY County. Resurface from Perryville city limits to Route KK, the total length of improvement being 10.87 miles.

Contract Time: DT - 11/1/2025

Item No.	Description	Quantity	Units
3049910	MISC. PERMANENT AGGREGATE EDGE TREATMENT	1,989.000	TONS
3105002	GRAVEL (A) OR CRUSHED STONE (B)	100.000	TONS
4020520	BITUMINOUS PAVEMENT MIXTURE PG64-22 (SURFACE LEVELING)	10,140.300	TONS
4071005	TACK COAT	12,421.000	GAL
4091048	EMULSIFIED ASPHALT, SEAL COAT	189.000	GAL
4094021	SEAL COAT AGGREGATE, GRADE C	629.000	SQYD
6161005	CONSTRUCTION SIGNS	1,578.000	SQFT
6161025	CHANNELIZER (TRIM LINE)	175.000	EA
6181000	MOBILIZATION	1.000	LS
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	114,650.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	107,731.000	LF
6206108A	8 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	2,060.000	LF
6221001	COLDMILLING BITUMINOUS PAVEMENT FOR REMOVAL OF SURFACING (3 IN. THICK OR LESS)	629.000	SQYD
6224010	MODIFIED COLDMILLING (DEPTH TRANSITIONS)	3,535.000	SQYD
6261000A	BITUMINOUS SHOULDER RUMBLE STRIP	979.600	STA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H05

Page 187 of 203

() Item will be bid as lump sum.



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H06

Contract ID	Federal Project Number / State Project Number	Description
240517-H06	FAF-32-3 (28), FAF 67-3 (145)	JSE0121
	JSE0099, JSE0121-VARIOUS ROUTES-VARIOUS COUNTIES	
	FAF 67-3 (145)	JSE0099
	ITS maintenance	
	FAF-32-3 (28)	JSE0121
	ITS maintenance	



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H06

Contract ID: 240517-H06

Letting Date: May 17, 2024 11:00 AM

Projects: JSE0099
JSE0121

FAF 67-3 (145)
FAF-32-3 (28)

Counties: BUTLER, CAPE GIRARDEAU, NEW MADRID,
PERRY, ST FRANCOIS, STE GENEVIEVE

District: Southeast

DBE Goal Percent:

Description: ****(1): Job JSE0099 Route 32, 67, 72 ST FRANCOIS, STE GENEVIEVE County. ITS maintenance at various locations along Routes 32, 67 and 72, the total length of improvement being 0 miles.****(2): Job JSE0121 Route 60,61,51,67,72,I-55 BUTLER, CAPE GIRARDEAU, NEW MADRID, PERRY County. ITS maintenance at various locations along Routes 60, 61, 51, 67, 72 and I-55, the total length of improvement being 0 miles.

Contract Time: DT - 11/1/2024

Item No.	Description	Quantity	Units
6123001	TRUCK MOUNTED ATTENUATOR (TMA)	1.000	LS
6161005	CONSTRUCTION SIGNS	819.000	SQFT
6161025	CHANNELIZER (TRIM LINE)	150.000	EA
6161030	TYPE III MOVEABLE BARRICADE	6.000	EA
6161033	DIRECTIONAL INDICATOR BARRICADE	28.000	EA
6161040	FLASHING ARROW PANEL	2.000	EA
6181000	MOBILIZATION	1.000	LS
9029902	MISC. INSTALL ETHERNET SWITCH AND POWER SUPPLY	1.000	EA
9108208	CABLE, 8 AWG, 1 CONDUCTOR, POWER	900.000	LF
9108408	WIRE, 8 AWG, BARE NEUTRAL	300.000	LF
9108810	PULL BOX, PREFORMED CLASS 1	2.000	EA
9108811	PULL BOX, PREFORMED CLASS 2	46.000	EA
9109902	MISC. CCTV BATTERY BACKUP, POLE MOUNTED	1.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H06

Item No.	Description	Quantity	Units
9109902	MISC. CCTV CAMERA TERMINAL CABINET, POLE MOUNTED	1.000	EA
9109902	MISC. INSTALL CCTV CAMERA ASSEMBLY	1.000	EA
9109902	MISC. INSTALL CCTV CONCRETE POLE	1.000	EA
9109902	MISC. MODIFY EXISTING POWER SUPPLY	1.000	EA
9109903	MISC. CONDUIT, 2 IN., HDPE, DIRECTIONAL DRILLED	1,440.000	LF
9109903	MISC. CONDUIT, 2 IN., HDPE, IN TRENCH	24,660.000	LF
9109903	MISC. CONDUIT, 2 IN., HDPE, ON STRUCTURE	460.000	LF
9109903	MISC. FIBER OPTIC CABLE, 24-FIBER SINGLE MODE	29,040.000	LF
6123001	TRUCK MOUNTED ATTENUATOR (TMA)	1.000	LS
6161005	CONSTRUCTION SIGNS	819.000	SQFT
6161025	CHANNELIZER (TRIM LINE)	150.000	EA
6161030	TYPE III MOVEABLE BARRICADE	6.000	EA
6161033	DIRECTIONAL INDICATOR BARRICADE	28.000	EA
6161040	FLASHING ARROW PANEL	2.000	EA
6181000	MOBILIZATION	1.000	LS
9029902	MISC. INSTALL ETHERNET SWITCH AND POWER SUPPLY	8.000	EA
9108208	CABLE, 8 AWG, 1 CONDUCTOR, POWER	11,340.000	LF
9108408	WIRE, 8 AWG, BARE NEUTRAL	3,780.000	LF
9108621	POWER SUPPLY ASSEMBLY, TYPE 2, 240/120 VOLT SERVICE, ITS	1.000	EA
9108810	PULL BOX, PREFORMED CLASS 1	15.000	EA
9108811	PULL BOX, PREFORMED CLASS 2	74.000	EA
9109902	MISC. CCTV BATTERY BACKUP, POLE MOUNTED	10.000	EA
9109902	MISC. CCTV CAMERA TERMINAL CABINET, POLE MOUNTED	10.000	EA
9109902	MISC. INSTALL CCTV CAMERA ASSEMBLY	10.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H06

Item No.	Description	Quantity	Units
9109902	MISC. INSTALL CCTV CONCRETE POLE	10.000	EA
9109902	MISC. MODIFY EXISTING POWER SUPPLY	9.000	EA
9109903	MISC. CONDUIT, 2 IN., HDPE, DIRECTIONAL DRILLED	6,460.000	LF
9109903	MISC. CONDUIT, 2 IN., HDPE, IN TRENCH	32,310.000	LF
9109903	MISC. CONDUIT, 2 IN., HDPE, ON STRUCTURE	460.000	LF
9109903	MISC. FIBER OPTIC CABLE, 24-FIBER SINGLE MODE	41,390.000	LF

() Item will be bid as lump sum.



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H07

Contract ID	Federal Project Number / State Project Number	Description
240517-H07		
FAF 51-2(46)	JSE0113	
JSE0113 - ROUTE 51 - BOLLINGER COUNTY		
FAF 51-2(46)	JSE0113	
Coldmill, resurface and shoulder repair		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H07

Contract ID: 240517-H07

Letting Date: May 17, 2024 11:00 AM

Projects: JSE0113

FAF 51-2(46)

Counties: BOLLINGER, STODDARD

District: Southeast

DBE Goal Percent: 4.00

Description: ****(1): Job JSE0113 Route 51 BOLLINGER, STODDARD County. Resurface from Route 91 to Route 60 near Puxico, the total length of improvement being 36.092 miles.

Contract Time: DT - 11/1/2025

Item No.	Description	Quantity	Units
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2072000	LINEAR GRADING CLASS 2	58.500	STA
2159903	MISC. MODIFIED SHAPING SLOPED CLASS III	1,250.000	LF
3040506	TYPE 5 AGGREGATE FOR BASE (6 IN. THICK)	3,935.000	SQYD
3049910	MISC. PERMANENT AGGREGATE EDGE TREATMENT	5,629.400	TONS
3105002	GRAVEL (A) OR CRUSHED STONE (B)	550.000	TONS
4010150	TYPE A2 SHOULDER	3,935.000	SQYD
4011211	BITUMINOUS PAVEMENT MIXTURE PG64-22, (BP-2)	26,714.100	TONS
4020520	BITUMINOUS PAVEMENT MIXTURE PG64-22 (SURFACE LEVELING)	18,013.100	TONS
4071005	TACK COAT	45,363.000	GAL
4091048	EMULSIFIED ASPHALT, SEAL COAT	377.000	GAL
4094011	SEAL COAT AGGREGATE, GRADE B1	992.000	SQYD
6161005	CONSTRUCTION SIGNS	2,658.000	SQFT
6161025	CHANNELIZER (TRIM LINE)	174.000	EA
6161033	DIRECTIONAL INDICATOR BARRICADE	19.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	2.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H07

Item No.	Description	Quantity	Units
6181000	MOBILIZATION	1.000	LS
6200012	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 12 IN WHITE	11.000	LF
6205902A	6 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	4,586.000	LF
6205903A	6 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	464.000	LF
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	358,426.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	184,436.000	LF
6221001	COLDMILLING BITUMINOUS PAVEMENT FOR REMOVAL OF SURFACING (3 IN. THICK OR LESS)	30,243.000	SQYD
6224010	MODIFIED COLDMILLING (DEPTH TRANSITIONS)	5,223.000	SQYD
6261000A	BITUMINOUS SHOULDER RUMBLE STRIP	3,680.500	STA
8025006	MULCHING	1.200	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	1.200	ACRE
8061005	ROCK DITCH CHECK	20.000	LF
8061019	SILT FENCE	5,347.000	LF
6061060	MGS GUARDRAIL	800.000	LF
6061069	MGS BRIDGE APPROACH TRANSITION SECTION (REGULAR/NO CURB)	4.000	EA
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	4.000	EA
9031270A	2 IN. PSST POST - 12 GA.	906.000	LF
9031271A	DRIVEN POST ANCHOR FOR 2 IN. PSST - 12 GA.	110.000	EA
9035069A	SHF-FLAT SHEET FLUORESCENT	366.000	SQFT

() Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
-------------	-----------------------------------------------	-------------

240517-H08		
FAS S705(28)	JSE0169	
JSE0169 - VARIOUS ROUTES - BUTLER, HOWELL, OREGON, ST FRANCOIS, STODDARD COUNTIES		
FAS S705(28)	JSE0169	
Lighting improvements		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H08

Contract ID: 240517-H08

Letting Date: May 17, 2024 11:00 AM

Projects: JSE0169

FAS S705(28)

Counties: BUTLER, HOWELL, OREGON, ST FRANCOIS,
STODDARD

District: Southeast

DBE Goal Percent:

Description: ****(1): Job JSE0169 Route 60, 63, 67, PP BUTLER, HOWELL, OREGON, ST FRANCOIS, STODDARD County. Lighting improvements at various locations in the Southeast District, the total length of improvement being 0 miles.

Contract Time: DT - 11/1/2025

Item No.	Description	Quantity	Units
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
6123001	TRUCK MOUNTED ATTENUATOR (TMA)	1.000	LS
6169901	MISC. TEMPORARY TRAFFIC CONTROL	1.000	LS
6181000	MOBILIZATION	1.000	LS
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
8025006	MULCHING	1.700	ACRE
8031000A	TURF TYPE TALL FESCUE SODDING	25.000	SQYD
8051000A	SEEDING - COOL SEASON GRASSES	1.700	ACRE
8061005	ROCK DITCH CHECK	500.000	LF
8061019	SILT FENCE	1,000.000	LF
9011010	RELOCATED POLE	1.000	EA
9011062	LIGHTING POLE, 45 FT. OR 13.5 M, TYPE AT DESIGN 2	76.000	EA
9011115	BRACKET ARM, 15 FT. OR 4.6 M	76.000	EA
9011313	LUMINAIRE, LED-C	96.000	EA
9012230	BASE MOUNTED CONTROL STATION 240 VOLT - 4	17.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H08

Item No.	Description	Quantity	Units
	CIRCUIT		
9013002	CONDUIT, 2 IN. RIGID, IN TRENCH	666.000	LF
9013004	CONDUIT, 4 IN. RIGID, IN TRENCH	645.000	LF
9014003	CONDUIT, 3 IN. RIGID, PUSHED	5,610.000	LF
9015010	TRENCHING TYPE I	10,336.000	LF
9016110	PULL BOX, PREFORMED CLASS 1	67.000	EA
9016112	PULL BOX, PREFORMED CLASS 3	19.000	EA
9017002	CABLE, 2 AWG 1 CONDUCTOR	2,750.000	LF
9017110	CABLE, 10 AWG 1 CONDUCTOR, POLE AND BRACKET	8,910.000	LF
9017404	CABLE-CONDUIT, 1 IN., 2 CONDUCTORS AND 1 BARE NEUTRAL, 6 AWG	5,760.000	LF
9017407	CABLE-CONDUIT, 1 IN., 2 CONDUCTORS AND 1 BARE NEUTRAL, 8 AWG	12,990.000	LF
9018245	POLE FOUNDATION (45 FT. OR 13.5 M MOUNTING HEIGHT)	77.000	EA
9018612	POWER SUPPLY ASSEMBLY, TYPE 2, 240/120 VOLT SERVICE, LIGHTING ONLY	5.000	EA

() Item will be bid as lump sum.



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H09

Contract ID	Federal Project Number / State Project Number	Description
240517-H09	JSEM0040	JSEM0040 - ROUTE 5 - DOUGLAS COUNTY
	JSEM0040	Slope repair



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H09

Contract ID: 240517-H09

Letting Date: May 17, 2024 11:00 AM

Projects: JSEM0040

JSEM0040

Counties: DOUGLAS

District: Southeast

DBE Goal Percent:

Description: ****(1): Job JSEM0040 Route 5 DOUGLAS County. Slope repair at Bryant Creek 6.25 miles north of Ava, the total length of improvement being 0.138 miles.

Contract Time: DT - 11/1/2024

Item No.	Description	Quantity	Units
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2061000	CLASS 1 EXCAVATION	430.000	CUYD
2072000	LINEAR GRADING CLASS 2	8.700	STA
3105002	GRAVEL (A) OR CRUSHED STONE (B)	151.000	TONS
6119907	MISC. FURNISHING AND PLACING ROCK BLANKET	1,060.000	CUYD
6161005	CONSTRUCTION SIGNS	48.000	SQFT
6161025	CHANNELIZER (TRIM LINE)	10.000	EA
6161030	TYPE III MOVEABLE BARRICADE	3.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	2.000	EA
6181000	MOBILIZATION	1.000	LS
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
8025006	MULCHING	0.300	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	0.300	ACRE
8061005	ROCK DITCH CHECK	100.000	LF
8061016	SEDIMENT REMOVAL	16.000	CUYD
8061019	SILT FENCE	740.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H09

Item No.	Description	Quantity	Units
8061050	TYPE C BERM	500.000	LF

() Item will be bid as lump sum.



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H10

Page 201 of 203

Contract ID	Federal Project Number / State Project Number	Description
240517-H10	JSEM0048	JSEM0048-ROUTE HH-NEW MADRID COUNTY
	JSEM0048	Culvert replacement



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H10

Contract ID: 240517-H10

Letting Date: May 17, 2024 11:00 AM

Projects: JSEM0048

JSEM0048

Counties: NEW MADRID

District: Southeast

DBE Goal Percent:

Description: ****(1): Job JSEM0048 Route HH NEW MADRID County. Culvert replacement at County Road 609, the total length of improvement being 0.022 miles.

Contract Time: DT - 11/1/2024

Item No.	Description	Quantity	Units
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2063000	CLASS 3 EXCAVATION	97.000	CUYD
3105002	GRAVEL (A) OR CRUSHED STONE (B)	23.000	TONS
6096020	FURNISHING TYPE 2 ROCK DITCH LINER	40.000	CUYD
6096042	PLACING TYPE 2 ROCK DITCH LINER	40.000	CUYD
6141024	GRATE AND BEARING PLATE (5 FT. X 3 FT. OR 1524 MM X 914 MM)	1.000	EA
6161005	CONSTRUCTION SIGNS	192.000	SQFT
6161025	CHANNELIZER (TRIM LINE)	25.000	EA
6181000	MOBILIZATION	1.000	LS
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	100.000	SQYD
7261048	48 IN. PIPE GROUP A	58.000	LF
7311053	PRECAST CONCRETE DROP INLET 5 FT X 3 FT	5.000	FT
7320648A	48 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	1.000	EA
8025006	MULCHING	1.000	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	1.000	ACRE
8061005	ROCK DITCH CHECK	36.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 240517-H10

Page 203 of 203

() Item will be bid as lump sum.