

Notice to Contractors -- Letting July 08, 2024

Sealed proposals for furnishing all labor, material, equipment and other things necessary for the work described herein will be received by the undersigned at the General Office of the Department of Highway until 11:00 AM on July 08, 2024 and publically opened.

Soil borings are generally available on all grading or bridge projects. They are free. They may be ordered at (999) 999-9999. There will be no refunds for plans or proposals. Please put the invoice number on all checks when paying for plans, proposals and specifications.

Quantities shown herein are for information only and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

Contract ID	Federal Project Number / State Project Number	Description
240708-B01		
FAS-S203 (011)	JNE0140	
JNE0140 - ROUTE A - ADAIR COUNTY		
FAS-S203 (011)	JNE0140	
Bridge improvements		



Missouri Department of Transportation

Notice To Contractors - Contract ID 240708-B01

Contract ID: 240708-B01

Letting Date: July 08, 2024 11:00 AM

Projects: JNE0140

FAS-S203 (011)

Counties: ADAIR

District: Northeast

DBE Goal Percent:

Description: ****(1): Job JNE0140 Route A ADAIR County. Bridge improvements over North Fork South Fabius River 1.2 miles west of Route J near Willmathsville, the total length of improvement being 0.101 miles.

Contract Time: DT - 12/1/2024

Item No.	Description	Quantity	Units
2013000	CLEARING AND GRUBBING	1.000	ACRE
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2031000	CLASS A EXCAVATION	311.000	CUYD
2035500	EMBANKMENT IN PLACE	731.000	CUYD
2036000	COMPACTING EMBANKMENT	275.000	CUYD
2101006A	SUBGRADE COMPACTION (6-INCH DEPTH)	3.000	100F
3040143	TYPE 1 AGGREGATE FOR BASE (4 IN. THICK)	607.000	SQYD
4010103	10 INCHES, BITUMINOUS PAVEMENT	607.000	SQYD
4071005	TACK COAT	108.000	GAL
6115030A	HEAVY STONE REVETMENT	1,050.000	SQYD
6181000	MOBILIZATION	1.000	LS
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	2,368.000	LF
6207001	PAVEMENT MARKING REMOVAL	381.000	LF
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	1,050.000	SQYD
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
8025006	MULCHING	1.100	ACRE



Missouri Department of Transportation

Notice To Contractors - Contract ID 240708-B01

Item No.	Description	Quantity	Units
8051000A	SEEDING - COOL SEASON GRASSES	0.600	ACRE
8061005	ROCK DITCH CHECK	10.000	LF
8061016	SEDIMENT REMOVAL	10.000	CUYD
8061017	TEMPORARY SEEDING	0.600	ACRE
8061019	SILT FENCE	842.000	LF
8061050	TYPE C BERM	275.000	LF
6061060	MGS GUARDRAIL	163.000	LF
6061069	MGS BRIDGE APPROACH TRANSITION SECTION (REGULAR/NO CURB)	4.000	EA
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	4.000	EA
2061000	CLASS 1 EXCAVATION	75.000	CUYD
5031011A	BRIDGE APPROACH SLAB (MINOR ROAD)	109.000	SQYD
7021316	GALVANIZED CAST-IN-PLACE CONCRETE PILES (16 IN)	1,099.000	LF
7025001	DYNAMIC PILE TESTING	3.000	EA
7025004	DYNAMIC PILE RESTRIKE TESTING	3.000	EA
7027000	PILE POINT REINFORCEMENT	14.000	EA
7029902	MISC. PILE POINT REINFORCEMENT (36 IN CAST-IN-PLACE CONCRETE PILES)	4.000	EA
7029903	MISC. GALVANIZED CAST-IN-PLACE CONCRETE PILES (36 IN)	300.000	LF
7032003	CLASS B CONCRETE (SUBSTRUCTURE)	51.200	CUYD
7034219A	TYPE D BARRIER	396.000	LF
7034221	SLAB ON CONCRETE NU-GIRDER	524.000	SQYD
7056022	NU 43, PRESTRESSED CONCRETE NU-GIRDER	523.000	LF
7061060	REINFORCING STEEL (BRIDGES)	6,530.000	LB
7123610	SLAB DRAIN	12.000	EA
7151001	VERTICAL DRAIN AT END BENTS	2.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 240708-B01

Item No.	Description	Quantity	Units
7161000	PLAIN NEOPRENE BEARING PAD	6.000	EA
7161002	LAMINATED NEOPRENE BEARING PAD	6.000	EA

() Item will be bid as lump sum.