

## Notice to Contractors -- Letting February 21, 2025

Sealed proposals for furnishing all labor, material, equipment and other things necessary for the work described herein will be received by the undersigned at the General Office of the Department of Highway until 11:00 AM on February 21, 2025 and publically opened.

Soil borings are generally available on all grading or bridge projects. They are free. They may be ordered at (999) 999-9999. There will be no refunds for plans or proposals. Please put the invoice number on all checks when paying for plans, proposals and specifications.

Quantities shown herein are for information only and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

Contract ID	Federal Project Number / State Project Number	Description
250221-A01		
FAS - S102(073)	JNW0020	
JNW0020 - ROUTE 46, W - WORTH COUNTY		
FAS - S102(073)	JNW0020	
2 Bridge replacements		



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-A01

**Contract ID:** 250221-A01

**Letting Date:** February 21, 2025 11:00 AM

**Projects:** JNW0020

FAS - S102(073)

**Counties:** WORTH

**District:** Northwest

**DBE Goal Percent:** 3.00

**Description:** \*\*\*\*(1): Job JNW0020 Route 46, W WORTH County. 2 Bridge replacements on Route 46 over Marlowe Branch and on Route W over the West Fork Grand River, the total length of improvement being 0.339 miles.

**Contract Time:** DT - 6/15/2026

Item No.	Description	Quantity	Units
1081000	SIGNET DBE REPORTING	1.000	LS
2013000	CLEARING AND GRUBBING	2.000	ACRE
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2035000	UNCLASSIFIED EXCAVATION	625.000	CUYD
2035500	EMBANKMENT IN PLACE	3,815.000	CUYD
2036000	COMPACTING EMBANKMENT	389.000	CUYD
2037075	COMPACTING IN CUT	2.100	STA
2153000	SHAPING SLOPES, CLASS III	3.000	100F
3040143	TYPE 1 AGGREGATE FOR BASE (4 IN. THICK)	3,522.000	SQYD
3105003	GRAVEL (A) OR CRUSHED STONE (B)	179.000	SQYD
4010150	TYPE A2 SHOULDER	379.900	SQYD
4010151	TYPE A3 SHOULDER	267.900	SQYD
4011231	BITUMINOUS PAVEMENT MIXTURE PG58-28H, (BP-1)	14.400	TONS
4019905	MISC. Optional Pavement	2,873.600	SQYD
4071005	TACK COAT	16.000	GAL
6113020	FURNISHING TYPE 2 ROCK BLANKET	945.000	CUYD
6113040	PLACING TYPE 2 ROCK BLANKET	945.000	CUYD



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-A01

Item No.	Description	Quantity	Units
6161005	CONSTRUCTION SIGNS	510.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	3.000	EA
6161030	TYPE III MOVEABLE BARRICADE	10.000	EA
6161099	CHANGEABLE MESSAGE SIGN WITH COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	5.000	EA
6181000	MOBILIZATION	1.000	LS
6181020	ADDITIONAL MOBILIZATION FOR SEEDING	3.000	EA
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	3,581.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	2,519.000	LF
6224010	MODIFIED COLDMILLING (DEPTH TRANSITIONS)	152.000	SQYD
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	1,417.000	SQYD
6269909	MISC. Rumble Strips Optional Pavement	152.800	STA
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7250415	15 IN. PIPE GROUP C	56.000	LF
7320815A	15 IN. OR ALLOWED SUBSTITUTE GROUP C FLARED END SECTION	4.000	EA
8025006	MULCHING	1.200	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	1.200	ACRE
8061005	ROCK DITCH CHECK	315.000	LF
8061016	SEDIMENT REMOVAL	50.000	CUYD
8061019	SILT FENCE	2,451.000	LF
8061050	TYPE C BERM	485.000	LF
6061060	MGS GUARDRAIL	275.000	LF
6061068	MGS BRIDGE APPROACH TRANSITION SECTION (EXTENDED CURB)	4.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-A01

Item No.	Description	Quantity	Units
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	4.000	EA
9031250A	U-CHANNEL POST, 3 LB	192.000	LF
9035004A	SH-FLAT SHEET	36.000	SQFT
2061000	CLASS 1 EXCAVATION	95.000	CUYD
2160500	REMOVAL OF BRIDGES	1.000	LS
5031011A	BRIDGE APPROACH SLAB (MINOR ROAD)	126.000	SQYD
7021214	GALVANIZED STRUCTURAL STEEL PILES (14 IN)	1,376.000	LF
7025002	PILE WAVE ANALYSIS	2.000	EA
7027000	PILE POINT REINFORCEMENT	16.000	EA
7032003	CLASS B CONCRETE (SUBSTRUCTURE)	97.700	CUYD
7034212	SLAB ON STEEL	486.000	SQYD
7034219A	TYPE D BARRIER	315.000	LF
7061060	REINFORCING STEEL (BRIDGES)	4,620.000	LB
7110500	TEMPORARY COATING - CONCRETE BENTS AND PIERS (WEATHERING STEEL)	1.000	LS
7121113	FABRICATED STRUCTURAL LOW ALLOY STEEL (I- BEAM) A709, GRADE 50W	69,990.000	LB
7123610	SLAB DRAIN	22.000	EA
7151001	VERTICAL DRAIN AT END BENTS	2.000	EA
7161003	LAMINATED NEOPRENE BEARING PAD (TAPERED)	24.000	EA
2061000	CLASS 1 EXCAVATION	80.000	CUYD
2160500	REMOVAL OF BRIDGES	1.000	LS
5031011A	BRIDGE APPROACH SLAB (MINOR ROAD)	109.000	SQYD
7011106	DRILLED SHAFTS (4 FT. 0 IN. DIA.)	80.000	LF
7011205	ROCK SOCKETS (3 FT 6 IN. DIA.)	98.000	LF
7011300	VIDEO CAMERA INSPECTION	4.000	EA
7011400	FOUNDATION INSPECTION HOLES	138.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-A01

Item No.	Description	Quantity	Units
7011600	SONIC LOGGING TESTING	4.000	EA
7021212	GALVANIZED STRUCTURAL STEEL PILES (12 IN)	372.000	LF
7025001	DYNAMIC PILE TESTING	2.000	EA
7026000	PRE-BORE FOR PILING	190.000	LF
7027000	PILE POINT REINFORCEMENT	8.000	EA
7032003	CLASS B CONCRETE (SUBSTRUCTURE)	102.600	CUYD
7034219A	TYPE D BARRIER	607.000	LF
7034221	SLAB ON CONCRETE NU-GIRDER	837.000	SQYD
7056022	NU 43, PRESTRESSED CONCRETE NU-GIRDER	840.000	LF
7061060	REINFORCING STEEL (BRIDGES)	33,250.000	LB
7151001	VERTICAL DRAIN AT END BENTS	2.000	EA
7161002	LAMINATED NEOPRENE BEARING PAD	12.000	EA
7161003	LAMINATED NEOPRENE BEARING PAD (TAPERED)	6.000	EA

( ) Item will be bid as lump sum.



**Missouri Department of Transportation**

**Notice To Contractors - Contract ID 250221-B01**

<b>Contract ID</b>	<b>Federal Project Number / State Project Number</b>	<b>Description</b>
250221-B01		
FAS-S202(068)	J2S2160	
J2S2160 - ROUTE J - MACON COUNTY		
FAS-S202(068)	J2S2160	
Bridge replacement		



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B01

**Contract ID:** 250221-B01

**Letting Date:** February 21, 2025 11:00 AM

**Projects:** J2S2160

FAS-S202(068)

**Counties:** MACON

**District:** Northeast

**DBE Goal Percent:** 3.00

**Description:** \*\*\*\*(1): Job J2S2160 Route J MACON County. Bridge replacement over Mussel Fork Creek 0.8 mile east of Route 129 near New Boston, the total length of improvement being 0.17 miles.

**Contract Time:** DT - 12/1/2025

Item No.	Description	Quantity	Units
1081000	SIGNET DBE REPORTING	1.000	LS
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2031000	CLASS A EXCAVATION	1,308.000	CUYD
2035500	EMBANKMENT IN PLACE	298.000	CUYD
2036000	COMPACTING EMBANKMENT	1,169.000	CUYD
2072000	LINEAR GRADING CLASS 2	1.700	STA
2101006A	SUBGRADE COMPACTION (6-INCH DEPTH)	6.300	100F
3040143	TYPE 1 AGGREGATE FOR BASE (4 IN. THICK)	1,655.000	SQYD
3105003	GRAVEL (A) OR CRUSHED STONE (B)	737.000	SQYD
4010103	10 INCHES, BITUMINOUS PAVEMENT	1,655.000	SQYD
4071005	TACK COAT	298.000	GAL
6096010A	FURNISHING TYPE 1 ROCK DITCH LINER	29.000	CUYD
6096041	PLACING TYPE 1 ROCK DITCH LINER	29.000	CUYD
6115030A	HEAVY STONE REVETMENT	1,513.000	SQYD
6161005	CONSTRUCTION SIGNS	218.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	3.000	EA
6161010	RELOCATED SIGNS	64.000	SQFT



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B01

Item No.	Description	Quantity	Units
6161030	TYPE III MOVEABLE BARRICADE	15.000	EA
6181000	MOBILIZATION	1.000	LS
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	2,610.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	2,610.000	LF
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	2,306.000	SQYD
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7250418	18 IN. PIPE GROUP C	106.000	LF
8059901	MISC. SEEDING AND MULCHING	1.000	LS
8061005	ROCK DITCH CHECK	100.000	LF
8061016	SEDIMENT REMOVAL	23.000	CUYD
8061019	SILT FENCE	1,272.000	LF
8061050	TYPE C BERM	340.000	LF
9031270A	2 IN. PSST POST - 12 GA.	240.000	LF
9031271A	DRIVEN POST ANCHOR FOR 2 IN. PSST - 12 GA.	15.000	EA
9035069A	SHF-FLAT SHEET FLUORESCENT	36.000	SQFT
2061000	CLASS 1 EXCAVATION	80.000	CUYD
2160500	REMOVAL OF BRIDGES	1.000	LS
5031011A	BRIDGE APPROACH SLAB (MINOR ROAD)	109.000	SQYD
7011108	DRILLED SHAFTS (5 FT. 0 IN. DIA.)	107.000	LF
7011207	ROCK SOCKETS (4 FT 6 IN. DIA.)	91.000	LF
7011300	VIDEO CAMERA INSPECTION	4.000	EA
7011400	FOUNDATION INSPECTION HOLES	131.000	LF
7011600	SONIC LOGGING TESTING	4.000	EA
7021212	GALVANIZED STRUCTURAL STEEL PILES (12 IN)	300.000	LF
7027000	PILE POINT REINFORCEMENT	8.000	EA





Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B01

Item No.	Description	Quantity	Units
7032003	CLASS B CONCRETE (SUBSTRUCTURE)	106.300	CUYD
7034216	TYPE H BARRIER	574.000	LF
7034221	SLAB ON CONCRETE NU-GIRDER	785.000	SQYD
7056022	NU 43, PRESTRESSED CONCRETE NU-GIRDER	779.000	LF
7061060	REINFORCING STEEL (BRIDGES)	35,620.000	LB
7123610	SLAB DRAIN	42.000	EA
7151001	VERTICAL DRAIN AT END BENTS	2.000	EA
7161000	PLAIN NEOPRENE BEARING PAD	6.000	EA
7161002	LAMINATED NEOPRENE BEARING PAD	12.000	EA

( ) Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
250221-B02		
FAS S202(56), (57)	J2S3438, J2S3439	
J2S3438, J2S3439 - ROUTE A/B, E/Y - WAREN, MONTGOMERY COUNTIES		
FAS S202(56)	J2S3438	
Bridge replacement		
FAS S202(57)	J2S3439	
Bridge replacement		



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B02

Contract ID: 250221-B02

Letting Date: February 21, 2025 11:00 AM

Projects: J2S3438  
J2S3439

FAS S202(56)  
FAS S202(57)

Counties: MONTGOMERY, WARREN

District: Northeast

DBE Goal Percent: 9.00

Description: \*\*\*\*(1): Job J2S3438 Route A WARREN County. Bridge replacement over I-70 near Pendleton, the total length of improvement being 0.576 miles.\*\*\*\*(2): Job J2S3439 Route E MONTGOMERY County. Bridge replacement over I-70 in Jonesburg, the total length of improvement being 0.262 miles.

Contract Time: DT - 12/1/2026

Item No.	Description	Quantity	Units
1081000	SIGNET DBE REPORTING	1.000	LS
2010000	MOWING	104.800	ACRE
2013000	CLEARING AND GRUBBING	0.500	ACRE
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2031000	CLASS A EXCAVATION	37,460.000	CUYD
2035500	EMBANKMENT IN PLACE	22,927.000	CUYD
2036000	COMPACTING EMBANKMENT	32,575.000	CUYD
2037075	COMPACTING IN CUT	23.800	STA
2063000	CLASS 3 EXCAVATION	765.000	CUYD
2142000	FURNISHING ROCK FILL	9,361.000	CUYD
2143000	PLACING ROCK FILL	9,361.000	CUYD
2153000	SHAPING SLOPES, CLASS III	24.000	100F
3030600	FURNISHING ROCK BASE MATERIAL	27,769.000	SQYD
3030610A	PLACING ROCK BASE	27,769.000	SQYD
3040506	TYPE 5 AGGREGATE FOR BASE (6 IN. THICK)	49.000	SQYD



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B02

Item No.	Description	Quantity	Units
3105002	GRAVEL (A) OR CRUSHED STONE (B)	18.000	TONS
4019901	MISC. TEMPORARY CONNECTION	1.000	LS
4019905	MISC. OPTIONAL PAVEMENT	2,405.600	SQYD
5021310	CONCRETE PAVEMENT (10 IN. NON-REINFORCED 15 FT. JOINTS)	23,636.900	SQYD
5021340	TYPE A2 SHOULDER	711.800	SQYD
5041000	CONCRETE APPROACH PAVEMENT	186.600	SQYD
6042010	ADJUSTING MANHOLE	1.000	EA
6044011	PIPE COLLAR, TYPE A	3.000	EA
6083003	3 IN. CONCRETE MEDIAN STRIP	43.300	SQYD
6083006	6 IN. CONCRETE MEDIAN STRIP	136.700	SQYD
6085007	PAVED APPROACH, 7 IN.	48.900	SQYD
6096020	FURNISHING TYPE 2 ROCK DITCH LINER	778.000	CUYD
6096030A	FURNISHING TYPE 3 ROCK DITCH LINER	442.000	CUYD
6096042	PLACING TYPE 2 ROCK DITCH LINER	778.000	CUYD
6096043	PLACING TYPE 3 ROCK DITCH LINER	442.000	CUYD
6096050	BEDDING MATERIAL FOR ROCK DITCH LINER	161.000	CUYD
6097000	ROCK LINING	69.000	CUYD
6113020	FURNISHING TYPE 2 ROCK BLANKET	1,751.000	CUYD
6113040	PLACING TYPE 2 ROCK BLANKET	1,751.000	CUYD
6122019	IMPACT ATTENUATOR 70 MPH (SAND BARREL ARRAY)	4.000	EA
6122020	REPLACEMENT SAND BARREL	4.000	EA
6123001	TRUCK MOUNTED ATTENUATOR (TMA)	1.000	LS
6143014	MANHOLE FRAME AND COVER, TYPE 4	2.000	EA
6151000	OFFICE FOR ENGINEER	12.000	MO
6161070	TUBULAR MARKER	9.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B02

Item No.	Description	Quantity	Units
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	10.000	EA
6169901	MISC. LUMP SUM TEMPORARY TRAFFIC CONTROL	1.000	LS
6173600D	TEMPORARY TRAFFIC BARRIER, CONTRACTOR FURNISHED / RETAINED	2,288.000	LF
6181000	MOBILIZATION	1.000	LS
6181020	ADDITIONAL MOBILIZATION FOR SEEDING	5.000	EA
6200012	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 12 IN WHITE	80.000	LF
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	244.000	LF
6200018	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. YELLOW	252.000	LF
6200021	PREFORMED THERMOPLASTIC PAVEMENT MARKING, LEFT/RIGHT ARROW	10.000	EA
6200027	PREFORMED THERMOPLASTIC PAVEMENT MARKING, COMBINATION STR/LT/RT	3.000	EA
6200030	PREFORMED THERMOPLASTIC PAVEMENT MARKING, WORD (ONLY)	6.000	EA
6200042	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 12 IN WHITE, YIELD LINE TRIANGLES	33.000	EA
6205901A	4 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	11,138.000	LF
6205902A	6 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	8,588.000	LF
6205903A	6 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	1,154.000	LF
6209903	MISC. 4 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	3,990.000	LF
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	8,955.000	SQYD
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B02

Item No.	Description	Quantity	Units
7250324A	24 IN. PIPE GROUP B	64.000	LF
7250348A	48 IN. PIPE GROUP B	68.000	LF
7250415	15 IN. PIPE GROUP C	32.000	LF
7261018	18 IN. PIPE GROUP A	62.000	LF
7261024	24 IN. PIPE GROUP A	11.000	LF
7261030	30 IN. PIPE GROUP A	85.000	LF
7261036	36 IN. PIPE GROUP A	485.000	LF
7310048	PRECAST CONCRETE MANHOLE - 48 IN.	5.000	FT
7310060	PRECAST CONCRETE MANHOLE - 60 IN.	13.000	FT
7320024A	24 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION	1.000	EA
7320048A	48 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION	2.000	EA
7320618A	18 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	1.000	EA
7320630A	30 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	2.000	EA
7320636A	36 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	3.000	EA
7321013A	15 IN. OR ALLOWED SUBSTITUTE SAFETY SLOPE END SECTION	2.000	EA
7321016A	24 IN. OR ALLOWED SUBSTITUTE SAFETY SLOPE END SECTION	1.000	EA
8025006	MULCHING	9.900	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	9.900	ACRE
8061004	SEDIMENT TRAP ROCK	10.200	CUYD
8061005	ROCK DITCH CHECK	474.000	LF
8061011	SLOPE DRAINS	129.000	LF
8061016	SEDIMENT REMOVAL	141.000	CUYD



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B02

Item No.	Description	Quantity	Units
8061017	TEMPORARY SEEDING	9.900	ACRE
8061019	SILT FENCE	5,240.000	LF
8064128	TYPE 1 TURF REINFORCEMENT MAT	1,823.000	SQYD
6061060	MGS GUARDRAIL	2,338.000	LF
6061069	MGS BRIDGE APPROACH TRANSITION SECTION (REGULAR/NO CURB)	4.000	EA
6061080	MGS END ANCHOR	6.000	EA
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	8.000	EA
7032002	CLASS B CONCRETE (MISC)	4.900	CUYD
9012230	BASE MOUNTED CONTROL STATION 240 VOLT - 4 CIRCUIT	1.000	EA
9013002	CONDUIT, 2 IN. RIGID, IN TRENCH	623.000	LF
9013003	CONDUIT, 3 IN. RIGID, IN TRENCH	196.000	LF
9013004	CONDUIT, 4 IN. RIGID, IN TRENCH	37.000	LF
9014004	CONDUIT, 4 IN. RIGID, PUSHED	1,093.000	LF
9015010	TRENCHING TYPE I	1,194.000	LF
9016110	PULL BOX, PREFORMED CLASS 1	15.000	EA
9016111	PULL BOX, PREFORMED CLASS 2	1.000	EA
9017002	CABLE, 2 AWG 1 CONDUCTOR	2,835.000	LF
9017008	CABLE, 8 AWG 1 CONDUCTOR	4,518.000	LF
9017110	CABLE, 10 AWG 1 CONDUCTOR, POLE AND BRACKET	1,200.000	LF
9017206	WIRE, 6 AWG, BARE NEUTRAL	945.000	LF
9017208	WIRE, 8 AWG, BARE NEUTRAL	1,324.000	LF
9017407	CABLE-CONDUIT, 1 IN., 2 CONDUCTORS AND 1 BARE NEUTRAL, 8 AWG	1,318.000	LF
9018245	POLE FOUNDATION (45 FT. OR 13.5 M MOUNTING HEIGHT)	8.000	EA
9018610	POWER SUPPLY ASSEMBLY, TYPE 1, 240/120 VOLT	1.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B02

Item No.	Description	Quantity	Units
	SERVICE, LIGHTING ONLY		
9019902	MISC. TOP MOUNT LIGHT POLE, 45 FT.	8.000	EA
9019902	MISC. TOP MOUNTED LED-C LUMINAIRE	8.000	EA
9031010	CONCRETE FOOTINGS, EMBEDDED	8.300	CUYD
9031210	STRUCTURAL STEEL POSTS	3,660.000	LB
9031220	PIPE POSTS	1,171.000	LB
9031241	BREAKAWAY ASSEMBLY (PERFORATED SQUARE STEEL TUBE)	2.000	EA
9031252	7 FT. CHANNEL POST DELINEATOR, DOUBLE STACKED WHITE	16.000	EA
9031256	7 FT. CHANNEL POST DELINEATOR, WHITE	22.000	EA
9031257A	7 FT. CHANNEL POST DELINEATOR, YELLOW	8.000	EA
9031258	7 FT. CHANNEL POST DELINEATOR, WHITE/RED	20.000	EA
9031259A	7 FT. CHANNEL POST DELINEATOR, YELLOW/RED	8.000	EA
9031270A	2 IN. PSST POST - 12 GA.	407.000	LF
9031271A	DRIVEN POST ANCHOR FOR 2 IN. PSST - 12 GA.	21.000	EA
9031272A	2.25 IN. PSST POST INSERT (6 FT.) - 12 GA.	2.000	EA
9031274	CONCRETE POST ANCHOR FOR 2 IN. PSST. - 7 GA.	20.000	EA
9031280	2.5 IN. PSST POST - 12 GA.	92.000	LF
9031281A	DRIVEN POST ANCHOR FOR 2.5 IN. PSST - 7 GA.	4.000	EA
9031285	CONCRETE POST ANCHOR FOR 2.5 IN. PSST. - 7 GA.	4.000	EA
9035004A	SH-FLAT SHEET	443.000	SQFT
9035011A	ST-STRUCTURAL	464.000	SQFT
9035069A	SHF-FLAT SHEET FLUORESCENT	109.000	SQFT
2061000	CLASS 1 EXCAVATION	115.000	CUYD
2160500	REMOVAL OF BRIDGES	1.000	LS
5031010A	BRIDGE APPROACH SLAB (MAJOR)	249.000	SQYD
7021212	GALVANIZED STRUCTURAL STEEL PILES (12 IN)	1,266.000	LF





Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B02

Item No.	Description	Quantity	Units
7021316	GALVANIZED CAST-IN-PLACE CONCRETE PILES (16 IN)	2,950.000	LF
7025001	DYNAMIC PILE TESTING	5.000	EA
7026000	PRE-BORE FOR PILING	216.000	LF
7027000	PILE POINT REINFORCEMENT	42.000	EA
7032003	CLASS B CONCRETE (SUBSTRUCTURE)	366.300	CUYD
7034219A	TYPE D BARRIER	498.000	LF
7034221	SLAB ON CONCRETE NU-GIRDER	1,512.000	SQYD
7056021	NU 35, PRESTRESSED CONCRETE NU-GIRDER	1,143.000	LF
7071000	CONDUIT SYSTEM ON STRUCTURE	1.000	LS
7101000	REINFORCING STEEL (EPOXY COATED)	20,340.000	LB
7110200	PROTECTIVE COATING - CONCRETE BENTS AND PIERS (EPOXY)	1.000	LS
7151001	VERTICAL DRAIN AT END BENTS	2.000	EA
7161000	PLAIN NEOPRENE BEARING PAD	10.000	EA
7161002	LAMINATED NEOPRENE BEARING PAD	30.000	EA
2010000	MOWING	25.800	ACRE
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2031000	CLASS A EXCAVATION	6,866.000	CUYD
2036000	COMPACTING EMBANKMENT	4,345.000	CUYD
2071000	LINEAR GRADING CLASS 1	2.600	STA
2101006A	SUBGRADE COMPACTION (6-INCH DEPTH)	9.400	100F
2142000	FURNISHING ROCK FILL	4,494.000	CUYD
2143000	PLACING ROCK FILL	4,494.000	CUYD
2153000	SHAPING SLOPES, CLASS III	24.000	100F
3030600	FURNISHING ROCK BASE MATERIAL	6,233.000	SQYD
3030610A	PLACING ROCK BASE	6,233.000	SQYD



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B02

Item No.	Description	Quantity	Units
4019905	MISC. OPTIONAL PAVEMENT	5,106.000	SQYD
5021340	TYPE A2 SHOULDER	917.100	SQYD
5041000	CONCRETE APPROACH PAVEMENT	170.100	SQYD
6091060	PAVED DITCH	140.000	SQYD
6113020	FURNISHING TYPE 2 ROCK BLANKET	1,107.000	CUYD
6113040	PLACING TYPE 2 ROCK BLANKET	1,107.000	CUYD
6122019	IMPACT ATTENUATOR 70 MPH (SAND BARREL ARRAY)	4.000	EA
6122020	REPLACEMENT SAND BARREL	4.000	EA
6123001	TRUCK MOUNTED ATTENUATOR (TMA)	1.000	LS
6151000	OFFICE FOR ENGINEER	7.000	MO
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	4.000	EA
6169901	MISC. LUMP SUM TEMPORARY TRAFFIC CONTROL	1.000	LS
6173600D	TEMPORARY TRAFFIC BARRIER, CONTRACTOR FURNISHED / RETAINED	2,288.000	LF
6181000	MOBILIZATION	1.000	LS
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	66.000	LF
6205901A	4 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	1,250.000	LF
6205902A	6 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	2,529.000	LF
6205903A	6 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	717.000	LF
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	4,229.000	SQYD
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
8025006	MULCHING	1.600	ACRE



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B02

Item No.	Description	Quantity	Units
8051000A	SEEDING - COOL SEASON GRASSES	1.600	ACRE
8061004	SEDIMENT TRAP ROCK	3.400	CUYD
8061005	ROCK DITCH CHECK	36.000	LF
8061016	SEDIMENT REMOVAL	30.000	CUYD
8061017	TEMPORARY SEEDING	1.600	ACRE
8061019	SILT FENCE	2,201.000	LF
8064128	TYPE 1 TURF REINFORCEMENT MAT	547.000	SQYD
6061060	MGS GUARDRAIL	4,638.000	LF
6061069	MGS BRIDGE APPROACH TRANSITION SECTION (REGULAR/NO CURB)	4.000	EA
6061080	MGS END ANCHOR	6.000	EA
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	7.000	EA
6063016	TYPE B CRASHWORTHY END TERMINAL	2.000	EA
7032002	CLASS B CONCRETE (MISC)	2.500	CUYD
9012230	BASE MOUNTED CONTROL STATION 240 VOLT - 4 CIRCUIT	1.000	EA
9013002	CONDUIT, 2 IN. RIGID, IN TRENCH	128.000	LF
9013003	CONDUIT, 3 IN. RIGID, IN TRENCH	144.000	LF
9014004	CONDUIT, 4 IN. RIGID, PUSHED	442.000	LF
9015010	TRENCHING TYPE I	621.000	LF
9016110	PULL BOX, PREFORMED CLASS 1	7.000	EA
9016111	PULL BOX, PREFORMED CLASS 2	1.000	EA
9017002	CABLE, 2 AWG 1 CONDUCTOR	384.000	LF
9017008	CABLE, 8 AWG 1 CONDUCTOR	1,924.000	LF
9017110	CABLE, 10 AWG 1 CONDUCTOR, POLE AND BRACKET	600.000	LF
9017206	WIRE, 6 AWG, BARE NEUTRAL	128.000	LF
9017208	WIRE, 8 AWG, BARE NEUTRAL	924.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B02

Item No.	Description	Quantity	Units
9017407	CABLE-CONDUIT, 1 IN., 2 CONDUCTORS AND 1 BARE NEUTRAL, 8 AWG	692.000	LF
9018245	POLE FOUNDATION (45 FT. OR 13.5 M MOUNTING HEIGHT)	4.000	EA
9018610	POWER SUPPLY ASSEMBLY, TYPE 1, 240/120 VOLT SERVICE, LIGHTING ONLY	1.000	EA
9019902	MISC. TOP MOUNT LIGHT POLE, 45 FT.	4.000	EA
9019902	MISC. TOP MOUNTED LED-C LUMINAIRE	4.000	EA
9031010	CONCRETE FOOTINGS, EMBEDDED	6.000	CUYD
9031210	STRUCTURAL STEEL POSTS	3,041.000	LB
9031220	PIPE POSTS	652.000	LB
9031241	BREAKAWAY ASSEMBLY (PERFORATED SQUARE STEEL TUBE)	2.000	EA
9031252	7 FT. CHANNEL POST DELINEATOR, DOUBLE STACKED WHITE	12.000	EA
9031256	7 FT. CHANNEL POST DELINEATOR, WHITE	21.000	EA
9031257A	7 FT. CHANNEL POST DELINEATOR, YELLOW	8.000	EA
9031258	7 FT. CHANNEL POST DELINEATOR, WHITE/RED	24.000	EA
9031259A	7 FT. CHANNEL POST DELINEATOR, YELLOW/RED	8.000	EA
9031270A	2 IN. PSST POST - 12 GA.	137.000	LF
9031271A	DRIVEN POST ANCHOR FOR 2 IN. PSST - 12 GA.	1.000	EA
9031272A	2.25 IN. PSST POST INSERT (6 FT.) - 12 GA.	2.000	EA
9031274	CONCRETE POST ANCHOR FOR 2 IN. PSST. - 7 GA.	12.000	EA
9031280	2.5 IN. PSST POST - 12 GA.	51.000	LF
9031285	CONCRETE POST ANCHOR FOR 2.5 IN. PSST. - 7 GA.	4.000	EA
9035004A	SH-FLAT SHEET	266.000	SQFT
9035011A	ST-STRUCTURAL	380.000	SQFT
2061000	CLASS 1 EXCAVATION	60.000	CUYD
2160500	REMOVAL OF BRIDGES	1.000	LS



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B02

Item No.	Description	Quantity	Units
5031011A	BRIDGE APPROACH SLAB (MINOR ROAD)	196.000	SQYD
7021212	GALVANIZED STRUCTURAL STEEL PILES (12 IN)	540.000	LF
7021214	GALVANIZED STRUCTURAL STEEL PILES (14 IN)	2,115.000	LF
7025001	DYNAMIC PILE TESTING	5.000	EA
7027000	PILE POINT REINFORCEMENT	37.000	EA
7032003	CLASS B CONCRETE (SUBSTRUCTURE)	283.700	CUYD
7034219A	TYPE D BARRIER	498.000	LF
7034221	SLAB ON CONCRETE NU-GIRDER	1,203.000	SQYD
7056021	NU 35, PRESTRESSED CONCRETE NU-GIRDER	914.000	LF
7071000	CONDUIT SYSTEM ON STRUCTURE	1.000	LS
7101000	REINFORCING STEEL (EPOXY COATED)	14,720.000	LB
7110200	PROTECTIVE COATING - CONCRETE BENTS AND PIERS (EPOXY)	1.000	LS
7151001	VERTICAL DRAIN AT END BENTS	2.000	EA
7161000	PLAIN NEOPRENE BEARING PAD	8.000	EA
7161002	LAMINATED NEOPRENE BEARING PAD	24.000	EA

( ) Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
250221-B03	FAS-S203 (008), FAS-S202 (097)	JNE0053, JNE0154
	JNE0053, JNE0154 - ROUTE K - MONTGOMERY	
	FAS-S203 (008)	JNE0053
	Bridge replacement	
	FAS-S202 (097)	JNE0154
	Bridge replacement	



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B03

Contract ID: 250221-B03

Letting Date: February 21, 2025 11:00 AM

Projects: JNE0053  
JNE0154

FAS-S203 (008)  
FAS-S202 (097)

Counties: MONTGOMERY

District: Northeast

DBE Goal Percent: 4.00

Description: \*\*\*\*(1): Job JNE0053 Route K MONTGOMERY County. Bridge replacement over Dry Fork Creek 1.8 miles west of Route 19 near Big Spring, the total length of improvement being 0.191 miles.\*\*\*\*(2): Job JNE0154 Route K MONTGOMERY County. Bridge replacement over Loutre River 0.4 miles west of Route 19 near Big Spring, the total length of improvement being 0.182 miles.

Contract Time: DT - 9/1/2026 Days

Item No.	Description	Quantity	Units
1081000	SIGNET DBE REPORTING	1.000	LS
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2031000	CLASS A EXCAVATION	1,366.000	CUYD
2036000	COMPACTING EMBANKMENT	924.000	CUYD
2063000	CLASS 3 EXCAVATION	51.000	CUYD
2101006A	SUBGRADE COMPACTION (6-INCH DEPTH)	9.000	100F
2142000	FURNISHING ROCK FILL	262.000	CUYD
2143000	PLACING ROCK FILL	262.000	CUYD
3040143	TYPE 1 AGGREGATE FOR BASE (4 IN. THICK)	2,009.000	SQYD
3105002	GRAVEL (A) OR CRUSHED STONE (B)	25.000	TONS
4039905	MISC. OPTIONAL PAVEMENT	2,009.000	SQYD
6113020	FURNISHING TYPE 2 ROCK BLANKET	243.000	CUYD
6113040	PLACING TYPE 2 ROCK BLANKET	243.000	CUYD
6161005	CONSTRUCTION SIGNS	186.000	SQFT



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B03

Item No.	Description	Quantity	Units
6161008	ADVANCED WARNING RAIL SYSTEM	2.000	EA
6161010	RELOCATED SIGNS	64.000	SQFT
6161025	CHANNELIZER (TRIM LINE)	25.000	EA
6161030	TYPE III MOVEABLE BARRICADE	12.000	EA
6181000	MOBILIZATION	1.000	LS
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	1,561.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	2,021.000	LF
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	560.000	SQYD
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7250424	24 IN. PIPE GROUP C	127.000	LF
7320824A	24 IN. OR ALLOWED SUBSTITUTE GROUP C FLARED END SECTION	4.000	EA
8059901	MISC. SEEDING AND MULCHING	1.000	LS
8061005	ROCK DITCH CHECK	92.000	LF
8061016	SEDIMENT REMOVAL	20.000	CUYD
8061019	SILT FENCE	880.000	LF
8061050	TYPE C BERM	313.000	LF
6061060	MGS GUARDRAIL	38.000	LF
6061061	MGS GUARDRAIL, 8 FT. POSTS, 6 FT. - 3 IN. SPACING	100.000	LF
6061069	MGS BRIDGE APPROACH TRANSITION SECTION (REGULAR/NO CURB)	3.000	EA
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	3.000	EA
9031270A	2 IN. PSST POST - 12 GA.	33.000	LF
9031271A	DRIVEN POST ANCHOR FOR 2 IN. PSST - 12 GA.	3.000	EA
9035069A	SHF-FLAT SHEET FLUORESCENT	9.000	SQFT





Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B03

Item No.	Description	Quantity	Units
9039902	MISC. REINSTALLING EXISTING SIGNS	1.000	EA
2061000	CLASS 1 EXCAVATION	215.000	CUYD
2160500	REMOVAL OF BRIDGES	1.000	LS
5031011A	BRIDGE APPROACH SLAB (MINOR ROAD)	116.000	SQYD
7021212	GALVANIZED STRUCTURAL STEEL PILES (12 IN)	534.000	LF
7021214	GALVANIZED STRUCTURAL STEEL PILES (14 IN)	834.000	LF
7027000	PILE POINT REINFORCEMENT	30.000	EA
7032003	CLASS B CONCRETE (SUBSTRUCTURE)	164.700	CUYD
7034216	TYPE H BARRIER	511.000	LF
7034222	SLAB ON CONCRETE BEAM	807.000	SQYD
7056050A	27 IN., PRESTRESSED CONCRETE SPREAD BOX BEAM	744.000	LF
7061060	REINFORCING STEEL (BRIDGES)	12,820.000	LB
7151001	VERTICAL DRAIN AT END BENTS	2.000	EA
7161000	PLAIN NEOPRENE BEARING PAD	6.000	EA
7161002	LAMINATED NEOPRENE BEARING PAD	18.000	EA
2013000	CLEARING AND GRUBBING	1.000	ACRE
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2031000	CLASS A EXCAVATION	2,623.000	CUYD
2035500	EMBANKMENT IN PLACE	1,415.000	CUYD
2036000	COMPACTING EMBANKMENT	2,321.000	CUYD
2101006A	SUBGRADE COMPACTION (6-INCH DEPTH)	3.000	100F
2142000	FURNISHING ROCK FILL	215.000	CUYD
2143000	PLACING ROCK FILL	215.000	CUYD
3040143	TYPE 1 AGGREGATE FOR BASE (4 IN. THICK)	582.000	SQYD
3105002	GRAVEL (A) OR CRUSHED STONE (B)	19.000	TONS
4019905	MISC. OPTIONAL PAVEMENT	581.300	SQYD



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B03

Item No.	Description	Quantity	Units
6096020	FURNISHING TYPE 2 ROCK DITCH LINER	107.000	CUYD
6096042	PLACING TYPE 2 ROCK DITCH LINER	107.000	CUYD
6113020	FURNISHING TYPE 2 ROCK BLANKET	1,182.000	CUYD
6113040	PLACING TYPE 2 ROCK BLANKET	1,182.000	CUYD
6161005	CONSTRUCTION SIGNS	199.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	2.000	EA
6161010	RELOCATED SIGNS	64.000	SQFT
6161030	TYPE III MOVEABLE BARRICADE	13.000	EA
6181000	MOBILIZATION	1.000	LS
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	1,918.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	1,017.000	LF
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	1,934.000	SQYD
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
8059901	MISC. SEEDING AND MULCHING	1.000	LS
8061005	ROCK DITCH CHECK	375.000	LF
8061016	SEDIMENT REMOVAL	34.000	CUYD
8061019	SILT FENCE	872.000	LF
8061050	TYPE C BERM	394.000	LF
8064138	TYPE 2D EROSION CONTROL BLANKET	1,756.000	SQYD
6061060	MGS GUARDRAIL	38.000	LF
6061061	MGS GUARDRAIL, 8 FT. POSTS, 6 FT. - 3 IN. SPACING	325.000	LF
6061069	MGS BRIDGE APPROACH TRANSITION SECTION (REGULAR/NO CURB)	4.000	EA
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	4.000	EA
9031270A	2 IN. PSST POST - 12 GA.	32.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B03

Item No.	Description	Quantity	Units
9031271A	DRIVEN POST ANCHOR FOR 2 IN. PSST - 12 GA.	2.000	EA
9031280	2.5 IN. PSST POST - 12 GA.	48.000	LF
9031281A	DRIVEN POST ANCHOR FOR 2.5 IN. PSST - 7 GA.	3.000	EA
9039902	MISC. RELOCATE SIGNS	5.000	EA
2061000	CLASS 1 EXCAVATION	100.000	CUYD
2160500	REMOVAL OF BRIDGES	1.000	LS
5031011A	BRIDGE APPROACH SLAB (MINOR ROAD)	117.000	SQYD
7011108	DRILLED SHAFTS (5 FT. 0 IN. DIA.)	188.800	LF
7011207	ROCK SOCKETS (4 FT 6 IN. DIA.)	40.000	LF
7011300	VIDEO CAMERA INSPECTION	4.000	EA
7011400	FOUNDATION INSPECTION HOLES	80.000	LF
7011600	SONIC LOGGING TESTING	4.000	EA
7021212	GALVANIZED STRUCTURAL STEEL PILES (12 IN)	540.000	LF
7027000	PILE POINT REINFORCEMENT	10.000	EA
7032003	CLASS B CONCRETE (SUBSTRUCTURE)	112.300	CUYD
7034219A	TYPE D BARRIER	736.000	LF
7034221	SLAB ON CONCRETE NU-GIRDER	1,093.000	SQYD
7056023	NU 53, PRESTRESSED CONCRETE NU-GIRDER	1,359.000	LF
7061060	REINFORCING STEEL (BRIDGES)	31,640.000	LB
7123301	STEEL INTERMEDIATE DIAPHRAGM FOR P/S CONCRETE GIRDERS	18.000	EA
7123610	SLAB DRAIN	12.000	EA
7151001	VERTICAL DRAIN AT END BENTS	2.000	EA
7161000	PLAIN NEOPRENE BEARING PAD	8.000	EA
7161002	LAMINATED NEOPRENE BEARING PAD	16.000	EA

( ) Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
250221-B04		
FAS-203(41)	JNE0181	
JNE0181 - ROUTE D,D - RALLS, PIKE COUNTIES		
FAS-203(41)	JNE0181	
2 Bridge paintings		



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B04

**Contract ID:** 250221-B04

**Letting Date:** February 21, 2025 11:00 AM

**Projects:** JNE0181

FAS-203(41)

**Counties:** PIKE, RALLS

**District:** Northeast

**DBE Goal Percent:**

**Description:** \*\*\*\*(1): Job JNE0181 Route D, D, FF/D,D PIKE, RALLS County. 2 Bridge paintings on Route D over Route 61 in Eolia and on Route D over Lick Creek 1.2 miles west of Route 19 near Perry, the total length of improvement being 0.13 miles.

**Contract Time:** DT - 11/1/2025

Item No.	Description	Quantity	Units
4011209	BITUMINOUS PAVEMENT MIXTURE PG64-22, (BP-1)	259.800	TONS
4071005	TACK COAT	120.000	GAL
6161005	CONSTRUCTION SIGNS	1,042.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	2.000	EA
6161025	CHANNELIZER (TRIM LINE)	70.000	EA
6161030	TYPE III MOVEABLE BARRICADE	10.000	EA
6161033	DIRECTIONAL INDICATOR BARRICADE	36.000	EA
6161040	FLASHING ARROW PANEL	2.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	2.000	EA
6162002	TEMPORARY LONG-TERM RUMBLE STRIPS	8.000	EA
6181000	MOBILIZATION	1.000	LS
6221003	COLDMILLING BITUMINOUS PAVEMENT FOR REMOVAL OF SURFACING (GREATER THAN 3 IN. THICK)	800.000	SQYD
7110200	PROTECTIVE COATING - CONCRETE BENTS AND PIERS (EPOXY)	1.000	LS
7125200	SURFACE PREPARATION FOR RECOATING	18,700.000	SQFT



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B04

Item No.	Description	Quantity	Units
	STRUCTURAL STEEL		
7125209	FIELD APPLICATION OF ORGANIC ZINC PRIMER	18,700.000	SQFT
7125365A	INTERMEDIATE FIELD COAT (SYSTEM G)	18,700.000	SQFT
7125370A	FINISH FIELD COAT (SYSTEM G)	4,700.000	SQFT
7125200	SURFACE PREPARATION FOR RECOATING STRUCTURAL STEEL	2,700.000	SQFT
7125209	FIELD APPLICATION OF ORGANIC ZINC PRIMER	2,700.000	SQFT
7125365A	INTERMEDIATE FIELD COAT (SYSTEM G)	700.000	SQFT
7125370A	FINISH FIELD COAT (SYSTEM G)	700.000	SQFT

( ) Item will be bid as lump sum.



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B05

Contract ID	Federal Project Number / State Project Number	Description
250221-B05		
FAF 136-3(18)	JNE0182	
JNE0182 - ROUTES 136, 11, P, 156 - CLARK, KNOX COUNTY		
FAF 136-3(18)	JNE0182	
4 Bridge paintings		



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B05

**Contract ID:** 250221-B05

**Letting Date:** February 21, 2025 11:00 AM

**Projects:** JNE0182

FAF 136-3(18)

**Counties:** CLARK, KNOX

**District:** Northeast

**DBE Goal Percent:**

**Description:** \*\*\*\*(1): Job JNE0182 Route 136, 11, P, 156 CLARK, KNOX County. 4 Bridge paintings on Route 136 over BNSF Railway in Medill, on Route P over BNSF Railway near Kenwood, on Route 11 over North Fork South Fabius River near Baring and on Route 156 over North River, the total length of improvement being 0.11 miles.

**Contract Time:** DT - 11/1/2025

Item No.	Description	Quantity	Units
6161005	CONSTRUCTION SIGNS	641.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	2.000	EA
6161025	CHANNELIZER (TRIM LINE)	90.000	EA
6161030	TYPE III MOVEABLE BARRICADE	10.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	6.000	EA
6162000A	WORK ZONE TRAFFIC SIGNAL SYSTEM	3.000	EA
6162002	TEMPORARY LONG-TERM RUMBLE STRIPS	12.000	EA
6181000	MOBILIZATION	1.000	LS
6205301B	TEMPORARY REMOVABLE MARKING TAPE 4 IN., WHITE	2,975.000	LF
6205303B	TEMPORARY REMOVABLE MARKING TAPE 4 IN., YELLOW	6,000.000	LF
6205309	TEMPORARY REMOVABLE MARKING TAPE, 24 IN., WHITE	72.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	2,590.000	LF





Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B05

Item No.	Description	Quantity	Units
6207001	PAVEMENT MARKING REMOVAL	10,022.000	LF
7125200	SURFACE PREPARATION FOR RECOATING STRUCTURAL STEEL	5,100.000	SQFT
7125201	SURFACE PREPARATION FOR OVERCOATING STRUCTURAL STEEL (SYSTEM G)	3,200.000	SQFT
7125209	FIELD APPLICATION OF ORGANIC ZINC PRIMER	5,100.000	SQFT
7125365A	INTERMEDIATE FIELD COAT (SYSTEM G)	4,500.000	SQFT
7125370A	FINISH FIELD COAT (SYSTEM G)	1,900.000	SQFT
7125200	SURFACE PREPARATION FOR RECOATING STRUCTURAL STEEL	2,600.000	SQFT
7125201	SURFACE PREPARATION FOR OVERCOATING STRUCTURAL STEEL (SYSTEM G)	1,700.000	SQFT
7125209	FIELD APPLICATION OF ORGANIC ZINC PRIMER	2,600.000	SQFT
7125365A	INTERMEDIATE FIELD COAT (SYSTEM G)	2,600.000	SQFT
7125370A	FINISH FIELD COAT (SYSTEM G)	1,400.000	SQFT
7125102	SURFACE PREPARATION FOR APPLYING EPOXY- MASTIC PRIMER	1.000	LS
7125200	SURFACE PREPARATION FOR RECOATING STRUCTURAL STEEL	3,000.000	SQFT
7125209	FIELD APPLICATION OF ORGANIC ZINC PRIMER	3,000.000	SQFT
7125365A	INTERMEDIATE FIELD COAT (SYSTEM G)	800.000	SQFT
7125370A	FINISH FIELD COAT (SYSTEM G)	800.000	SQFT
7125960	ALUMINUM EPOXY-MASTIC PRIMER	1.000	LS
7125200	SURFACE PREPARATION FOR RECOATING STRUCTURAL STEEL	4,100.000	SQFT
7125209	FIELD APPLICATION OF ORGANIC ZINC PRIMER	4,100.000	SQFT
7125365A	INTERMEDIATE FIELD COAT (SYSTEM G)	1,100.000	SQFT
7125370A	FINISH FIELD COAT (SYSTEM G)	1,100.000	SQFT



**Missouri Department of Transportation**

**Notice To Contractors - Contract ID 250221-B05**

**Page 34 of 115**

---

**( ) Item will be bid as lump sum.**



Contract ID	Federal Project Number / State Project Number	Description
250221-B06		
FAF 36-3(81)	JNE0210	
JNE0210 - ROUTE 36 - MARION, SHELBY COUNTIES		
FAF 36-3(81)	JNE0210	
Resurface		



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B06

**Contract ID:** 250221-B06

**Letting Date:** February 21, 2025 11:00 AM

**Projects:** JNE0210

FAF 36-3(81)

**Counties:** MARION, SHELBY

**District:** Northeast

**DBE Goal Percent:**

**Description:** \*\*\*\*(1): Job JNE0210 Route 36 MARION, SHELBY County. Resurface from Route 24 to the Macon County line near Clarence, the total length of improvement being 32.151 miles.

**Contract Time:** DT - 11/1/2025

Item No.	Description	Quantity	Units
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2153000	SHAPING SLOPES, CLASS III	23.000	100F
3105002	GRAVEL (A) OR CRUSHED STONE (B)	58.000	TONS
4011209	BITUMINOUS PAVEMENT MIXTURE PG64-22, (BP-1)	31,598.300	TONS
4030103	ASPHALTIC CONCRETE MIXTURE PG 70-22 (SP125C MIX)	98,316.500	TONS
4071007	TACK COAT - NON-TRACKING	85,400.000	GAL
5041000	CONCRETE APPROACH PAVEMENT	527.700	SQYD
6059902	MISC. PAVEMENT UNDERDRAIN	122.000	EA
6131010	FURNISHING AND PLACING CONCRETE MATERIAL FOR FULL DEPTH PAVEMENT REPAIR	2,627.200	SQYD
6131012	SUBGRADE COMPACTION (6 IN. DEPTH) (PAVEMENT REPAIR)	263.000	SQYD
6131013	TYPE 1 OR 5 AGGREGATE FOR BASE (4 IN. THICK) (PAVEMENT REPAIR)	263.000	SQYD
6131014	FULL DEPTH PAVEMENT REPAIR SAW CUT (FOR PERIMETER AND INTERNAL SAW CUTS)	10,862.000	LF
6131015	DOWEL BAR (DRILLING, FURNISHING AND INSTALLATION) FOR FULL DEPTH PAVEMENT REPAIR	5,880.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B06

Item No.	Description	Quantity	Units
6131017	DOWEL BAR (FURNISHING AND INSTALLATION WITH BASKETS) FOR FULL DEPTH PAVEMENT REPAIR	12.000	EA
6133018	FURNISHING AND PLACING BITUMINOUS MATERIAL FOR CLASS B PARTIAL DEPTH PAVEMENT REPAIR	69.400	TONS
6133019	REMOVAL FOR CLASS B PARTIAL DEPTH PAVEMENT REPAIR	290.000	SQYD
6134002	CROSS STITCH TIE BAR	630.000	EA
6161005	CONSTRUCTION SIGNS	1,756.000	SQFT
6161025	CHANNELIZER (TRIM LINE)	400.000	EA
6161030	TYPE III MOVEABLE BARRICADE	10.000	EA
6161033	DIRECTIONAL INDICATOR BARRICADE	36.000	EA
6161040	FLASHING ARROW PANEL	2.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	2.000	EA
6181000	MOBILIZATION	1.000	LS
6191000	PAVEMENT EDGE TREATMENT	340.000	LF
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	48.000	LF
6200021	PREFORMED THERMOPLASTIC PAVEMENT MARKING, LEFT/RIGHT ARROW	22.000	EA
6205902A	6 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	164,384.000	LF
6205903A	6 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	126,412.000	LF
6205906A	12 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	1,875.000	LF
6206108A	8 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	805.000	LF
6209901	MISC. TEMPORARY PAVEMENT MARKING PAINT	1.000	LS
6221003	COLDMILLING BITUMINOUS PAVEMENT FOR	274.000	SQYD



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B06

Item No.	Description	Quantity	Units
	REMOVAL OF SURFACING (GREATER THAN 3 IN. THICK)		
6224010	MODIFIED COLDMILLING (DEPTH TRANSITIONS)	28,825.000	SQYD
6261000A	BITUMINOUS SHOULDER RUMBLE STRIP	2,230.000	STA
6061060	MGS GUARDRAIL	1,175.000	LF
6061068	MGS BRIDGE APPROACH TRANSITION SECTION (EXTENDED CURB)	4.000	EA
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	4.000	EA
9031010	CONCRETE FOOTINGS, EMBEDDED	4.800	CUYD
9031241	BREAKAWAY ASSEMBLY (PERFORATED SQUARE STEEL TUBE)	25.000	EA
9031242	36 IN. SURFACE-MOUNT DELINEATOR POST	6.000	EA

( ) Item will be bid as lump sum.



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B07

Page 39 of 115

Contract ID	Federal Project Number / State Project Number	Description
250221-B07	JNEM0062	JNEM0062-ROUTE 47-WARREN COUNTY
	JNEM0062	Relocate signal cabinet



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B07

**Contract ID:** 250221-B07

**Letting Date:** February 21, 2025 11:00 AM

**Projects:** JNEM0062

JNEM0062

**Counties:** WARREN

**District:** Northeast

**DBE Goal Percent:**

**Description:** \*\*\*\*(1): Job JNEM0062 Route 47 WARREN County. Relocate signal cabinet at the eastbound I-70 ramp in Warrenton, the total length of improvement being 0.038 miles.

**Contract Time:** DT - 10/1/2025

Item No.	Description	Quantity	Units
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
3040193	TYPE 1 AGGREGATE FOR BASE (9 IN. THICK)	14.000	SQYD
6083008	8 IN. CONCRETE MEDIAN STRIP	14.000	SQYD
6161005	CONSTRUCTION SIGNS	70.000	SQFT
6161025	CHANNELIZER (TRIM LINE)	34.000	EA
6161030	TYPE III MOVEABLE BARRICADE	4.000	EA
6161099	CHANGEABLE MESSAGE SIGN WITH COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	1.000	EA
6181000	MOBILIZATION	1.000	LS
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
8059901	MISC. Seeding and Mulching	1.000	LS
9025200	CONDUIT, 2 IN., TRENCH WITH TRACER WIRE	124.000	LF
9027400	CONDUIT, 4 IN., PUSHED WITH TRACER WIRE	104.000	LF
9028208	CABLE, 8 AWG 1 CONDUCTOR, POWER	490.000	LF
9028302	CABLE, 12 AWG 2 CONDUCTOR	450.000	LF
9028311	CABLE, 16 AWG 7 CONDUCTOR	690.000	LF
9028510	CABLE, LOOP DETECTOR, LEAD-IN	230.000	LF





Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-B07

Item No.	Description	Quantity	Units
9028810	PULL BOX, PREFORMED CLASS 1	1.000	EA
9029100	BASE, CONCRETE	2.000	CUYD
9029901	MISC. Installing Commission Furnished Signal Cabinet	1.000	LS

( ) Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
250221-C01		
FAS-S304 (003)	J3S3178	
J3S3178 - ROUTE T - RAY COUNTY		
FAS-S304 (003)	J3S3178	
Bridge replacement		



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-C01

**Contract ID:** 250221-C01

**Letting Date:** February 21, 2025 11:00 AM

**Projects:** J3S3178

FAS-S304 (003)

**Counties:** RAY

**District:** Kansas City

**DBE Goal Percent:** 7.00

**Description:** \*\*\*\*(1): Job J3S3178 Route T RAY County. Bridge replacement over Panther Creek at Triple Springs Road near Fleming, the total length of improvement being 0.07 miles.

**Contract Time:** DT - 9/1/2025

Item No.	Description	Quantity	Units
1081000	SIGNET DBE REPORTING	1.000	LS
2013000	CLEARING AND GRUBBING	1.000	ACRE
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2031000	CLASS A EXCAVATION	774.000	CUYD
2036000	COMPACTING EMBANKMENT	259.000	CUYD
2037075	COMPACTING IN CUT	3.100	STA
3040143	TYPE 1 AGGREGATE FOR BASE (4 IN. THICK)	1,252.000	SQYD
4019905	MISC. OPTIONAL PAVEMENT	787.500	SQYD
5021306	CONCRETE PAVEMENT (6 IN. NON-REINFORCED, 15 FT. JOINTS)	72.500	SQYD
6113020	FURNISHING TYPE 2 ROCK BLANKET	268.000	CUYD
6113040	PLACING TYPE 2 ROCK BLANKET	268.000	CUYD
6161005	CONSTRUCTION SIGNS	558.000	SQFT
6161030	TYPE III MOVEABLE BARRICADE	15.000	EA
6161099	CHANGEABLE MESSAGE SIGN WITH COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	4.000	EA
6181000	MOBILIZATION	1.000	LS
6181020	ADDITIONAL MOBILIZATION FOR SEEDING	2.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-C01

Item No.	Description	Quantity	Units
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	763.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	763.000	LF
6240104A	SEPARATION GEOTEXTILE	402.000	SQYD
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7250415	15 IN. PIPE GROUP C	28.000	LF
7320815A	15 IN. OR ALLOWED SUBSTITUTE GROUP C FLARED END SECTION	2.000	EA
7320824A	24 IN. OR ALLOWED SUBSTITUTE GROUP C FLARED END SECTION	2.000	EA
8025006	MULCHING	1.400	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	0.700	ACRE
8061003	SEDIMENT TRAP EXCAVATION	15.000	CUYD
8061004	SEDIMENT TRAP ROCK	15.000	CUYD
8061005	ROCK DITCH CHECK	48.000	LF
8061016	SEDIMENT REMOVAL	10.000	CUYD
8061017	TEMPORARY SEEDING	0.700	ACRE
8061019	SILT FENCE	371.000	LF
8061050	TYPE C BERM	270.000	LF
8064140	TYPE 3B EROSION CONTROL BLANKET	857.800	SQYD
6061010	GUARDRAIL TYPE A	75.000	LF
6062303	ASYMMETRICAL TRANSITION SECTION, 6.5 FT. POSTS	3.000	EA
6062400	BRIDGE ANCHOR SECTION (THRIE BEAM)	3.000	EA
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	1.000	EA
6066610	END ANCHOR	2.000	EA
9031241	BREAKAWAY ASSEMBLY (PERFORATED SQUARE	1.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-C01

Item No.	Description	Quantity	Units
	STEEL TUBE)		
9031272A	2.25 IN. PSST POST INSERT (6 FT.) - 12 GA.	1.000	EA
9031280	2.5 IN. PSST POST - 12 GA.	64.000	LF
9031285	CONCRETE POST ANCHOR FOR 2.5 IN. PSST. - 7 GA.	4.000	EA
9035004A	SH-FLAT SHEET	29.000	SQFT
2061000	CLASS 1 EXCAVATION	90.000	CUYD
2160500	REMOVAL OF BRIDGES	1.000	LS
5031011A	BRIDGE APPROACH SLAB (MINOR ROAD)	113.000	SQYD
7021214	GALVANIZED STRUCTURAL STEEL PILES (14 IN)	224.000	LF
7027000	PILE POINT REINFORCEMENT	8.000	EA
7032003	CLASS B CONCRETE (SUBSTRUCTURE)	43.800	CUYD
7034213	SLAB ON CONCRETE I-GIRDER	201.000	SQYD
7034216	TYPE H BARRIER	185.000	LF
7056001	TYPE 3 (39 IN.), PRESTRESSED CONCRETE I-GIRDER	199.000	LF
7123301	STEEL INTERMEDIATE DIAPHRAGM FOR P/S CONCRETE GIRDERS	2.000	EA
7151001	VERTICAL DRAIN AT END BENTS	2.000	EA
7161000	PLAIN NEOPRENE BEARING PAD	3.000	EA
7161002	LAMINATED NEOPRENE BEARING PAD	3.000	EA

( ) Item will be bid as lump sum.



**Missouri Department of Transportation**

**Notice To Contractors - Contract ID 250221-C02**

<b>Contract ID</b>	<b>Federal Project Number / State Project Number</b>	<b>Description</b>
250221-C02	FAF-50-2 (70), FAF-50-2 (71)	JKR0136, JKR0137
	JKR0136, JKR0137 - ROUTES 50, BUS 50 - JOHNSON COUNTY	
	FAF-50-2 (70)	JKR0136
	Intersection improvements and add J-Turns	
	FAF-50-2 (71)	JKR0137
	Intersection improvement	



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-C02

**Contract ID:** 250221-C02

**Letting Date:** February 21, 2025 11:00 AM

**Projects:** JKR0136  
JKR0137

FAF-50-2 (70)  
FAF-50-2 (71)

**Counties:** JOHNSON

**District:** Kansas City

**DBE Goal Percent:** 3.00

**Description:** \*\*\*\*(1): Job JKR0136 Route 50 JOHNSON County. Intersection improvements and add J-Turns 0.7 mile east of Rte. 58 and 0.2 mile east of Northwest 121st Road, the total length of improvement being 3.45 miles.\*\*\*\*(2): Job JKR0137 Route 50 JOHNSON County. Intersection improvement West Intersection of Bus 50 and Rte 50, the total length of improvement being 0.852 miles.

**Contract Time:** DT - 12/1/2025

Item No.	Description	Quantity	Units
1081000	SIGNET DBE REPORTING	1.000	LS
2013000	CLEARING AND GRUBBING	2.000	ACRE
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2035000	UNCLASSIFIED EXCAVATION	23,117.000	CUYD
2035500	EMBANKMENT IN PLACE	1,310.000	CUYD
2036000	COMPACTING EMBANKMENT	19,416.000	CUYD
2037075	COMPACTING IN CUT	10.200	STA
2063000	CLASS 3 EXCAVATION	1,537.000	CUYD
2063500	CULVERT CLEANOUT	1.000	EA
2071000	LINEAR GRADING CLASS 1	19.200	STA
2101006A	SUBGRADE COMPACTION (6-INCH DEPTH)	227.000	100F
3040504	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK)	2,255.000	SQYD
3040506	TYPE 5 AGGREGATE FOR BASE (6 IN. THICK)	49,981.000	SQYD
4019905	MISC. OPTIONAL PAVEMENT	2,254.700	SQYD



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-C02

Item No.	Description	Quantity	Units
6044011	PIPE COLLAR, TYPE A	9.000	EA
6083006	6 IN. CONCRETE MEDIAN STRIP	160.800	SQYD
6097000	ROCK LINING	6.000	CUYD
6143012	MANHOLE FRAME AND COVER, TYPE 2	1.000	EA
6161005	CONSTRUCTION SIGNS	1,520.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	12.000	EA
6161025	CHANNELIZER (TRIM LINE)	170.000	EA
6161030	TYPE III MOVEABLE BARRICADE	33.000	EA
6161033	DIRECTIONAL INDICATOR BARRICADE	28.000	EA
6161040	FLASHING ARROW PANEL	2.000	EA
6161055	SEQUENTIAL FLASHING WARNING LIGHT	28.000	EA
6161070	TUBULAR MARKER	216.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	8.000	EA
6181000	MOBILIZATION	1.000	LS
6181020	ADDITIONAL MOBILIZATION FOR SEEDING	4.000	EA
6191000	PAVEMENT EDGE TREATMENT	23,922.000	LF
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	220.000	LF
6200021	PREFORMED THERMOPLASTIC PAVEMENT MARKING, LEFT/RIGHT ARROW	44.000	EA
6200042	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 12 IN WHITE, YIELD LINE TRIANGLES	48.000	EA
6205301B	TEMPORARY REMOVABLE MARKING TAPE 4 IN., WHITE	9,409.000	LF
6205303B	TEMPORARY REMOVABLE MARKING TAPE 4 IN., YELLOW	18,072.000	LF
6205902A	6 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	14,277.000	LF





Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-C02

Item No.	Description	Quantity	Units
6205903A	6 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	16,373.000	LF
6205906A	12 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	6,573.000	LF
6207001	PAVEMENT MARKING REMOVAL	1,764.000	LF
6208076	4 IN TEMPORARY PAVEMENT MARKING PAINT	1,764.000	LF
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7250315A	15 IN. PIPE GROUP B	679.000	LF
7261015	15 IN. PIPE GROUP A	231.000	LF
7261018	18 IN. PIPE GROUP A	1,290.000	LF
7261024	24 IN. PIPE GROUP A	14.000	LF
7261030	30 IN. PIPE GROUP A	25.000	LF
7261036	36 IN. PIPE GROUP A	109.000	LF
7311053	PRECAST CONCRETE DROP INLET 5 FT X 3 FT	51.000	FT
7320615A	15 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	4.000	EA
7320618A	18 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	21.000	EA
7320624A	24 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	1.000	EA
7320630A	30 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	1.000	EA
7320636A	36 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	3.000	EA
8025006	MULCHING	11.000	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	11.000	ACRE
8061004	SEDIMENT TRAP ROCK	15.000	CUYD
8061005	ROCK DITCH CHECK	795.000	LF
8061006	ALTERNATE DITCH CHECK	1,926.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-C02

Item No.	Description	Quantity	Units
8061016	SEDIMENT REMOVAL	275.000	CUYD
8061017	TEMPORARY SEEDING	2.800	ACRE
8061019	SILT FENCE	8,495.000	LF
8064135	TYPE 2A EROSION CONTROL BLANKET	53,010.000	SQYD
9011062	LIGHTING POLE, 45 FT. OR 13.5 M, TYPE AT DESIGN 2	14.000	EA
9011115	BRACKET ARM, 15 FT. OR 4.6 M	14.000	EA
9011312	LUMINAIRE, LED-B	14.000	EA
9014004	CONDUIT, 4 IN. RIGID, PUSHED	1,660.000	LF
9016110	PULL BOX, PREFORMED CLASS 1	25.000	EA
9016111	PULL BOX, PREFORMED CLASS 2	5.000	EA
9017110	CABLE, 10 AWG 1 CONDUCTOR, POLE AND BRACKET	1,680.000	LF
9017407	CABLE-CONDUIT, 1 IN., 2 CONDUCTORS AND 1 BARE NEUTRAL, 8 AWG	11,690.000	LF
9018245	POLE FOUNDATION (45 FT. OR 13.5 M MOUNTING HEIGHT)	14.000	EA
9018612	POWER SUPPLY ASSEMBLY, TYPE 2, 240/120 VOLT SERVICE, LIGHTING ONLY	3.000	EA
9031010	CONCRETE FOOTINGS, EMBEDDED	5.700	CUYD
9031210	STRUCTURAL STEEL POSTS	2,490.000	LB
9031220	PIPE POSTS	2,800.000	LB
9031270A	2 IN. PSST POST - 12 GA.	2,040.000	LF
9031271A	DRIVEN POST ANCHOR FOR 2 IN. PSST - 12 GA.	136.000	EA
9031280	2.5 IN. PSST POST - 12 GA.	420.000	LF
9031281A	DRIVEN POST ANCHOR FOR 2.5 IN. PSST - 7 GA.	28.000	EA
9035004A	SH-FLAT SHEET	1,992.000	SQFT
9035069A	SHF-FLAT SHEET FLUORESCENT	27.000	SQFT
4030409	12 INCHES, ASPHALTIC CONCRETE PAVEMENT	3,692.800	SQYD



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-C02

Item No.	Description	Quantity	Units
5021333	SP125C CONCRETE PAVEMENT (9 1/2 IN. NON-REINFORCED, 15 FT. JOINTS)	3,692.800	SQYD
4010150	TYPE A2 SHOULDER	1,025.700	SQYD
6261000A	BITUMINOUS SHOULDER RUMBLE STRIP	16.900	STA
5021340	TYPE A2 SHOULDER	1,025.700	SQYD
6262000A	PORTLAND CEMENT CONCRETE SHOULDER RUMBLE STRIP	16.900	STA
4030403	10 INCHES, ASPHALTIC CONCRETE PAVEMENT SP125C	35,497.500	SQYD
5021308	CONCRETE PAVEMENT (8 IN. NON-REINFORCED, 15 FT. JOINTS)	35,497.500	SQYD
4010150	TYPE A2 SHOULDER	9,764.400	SQYD
5021340	TYPE A2 SHOULDER	9,764.400	SQYD
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2035000	UNCLASSIFIED EXCAVATION	5,303.000	CUYD
2036000	COMPACTING EMBANKMENT	4,507.000	CUYD
2037075	COMPACTING IN CUT	8.400	STA
2063000	CLASS 3 EXCAVATION	189.000	CUYD
2063500	CULVERT CLEANOUT	1.000	EA
2101006A	SUBGRADE COMPACTION (6-INCH DEPTH)	47.000	100F
3040506	TYPE 5 AGGREGATE FOR BASE (6 IN. THICK)	11,352.000	SQYD
6044011	PIPE COLLAR, TYPE A	3.000	EA
6083006	6 IN. CONCRETE MEDIAN STRIP	517.000	SQYD
6097000	ROCK LINING	2.000	CUYD
6161005	CONSTRUCTION SIGNS	834.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	6.000	EA
6161025	CHANNELIZER (TRIM LINE)	44.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-C02

Item No.	Description	Quantity	Units
6161030	TYPE III MOVEABLE BARRICADE	9.000	EA
6161033	DIRECTIONAL INDICATOR BARRICADE	28.000	EA
6161040	FLASHING ARROW PANEL	2.000	EA
6161055	SEQUENTIAL FLASHING WARNING LIGHT	28.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	6.000	EA
6181000	MOBILIZATION	1.000	LS
6181020	ADDITIONAL MOBILIZATION FOR SEEDING	1.000	EA
6191000	PAVEMENT EDGE TREATMENT	4,996.000	LF
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	12.000	LF
6200021	PREFORMED THERMOPLASTIC PAVEMENT MARKING, LEFT/RIGHT ARROW	4.000	EA
6205902A	6 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	4,038.000	LF
6205903A	6 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	2,624.000	LF
6205906A	12 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	1,676.000	LF
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7261018	18 IN. PIPE GROUP A	188.000	LF
7261030	30 IN. PIPE GROUP A	17.000	LF
7261036	36 IN. PIPE GROUP A	14.000	LF
7320618A	18 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	3.000	EA
7320630A	30 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	1.000	EA
7320636A	36 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	1.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-C02

Item No.	Description	Quantity	Units
8025006	MULCHING	1.300	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	1.300	ACRE
8061004	SEDIMENT TRAP ROCK	2.000	CUYD
8061005	ROCK DITCH CHECK	150.000	LF
8061006	ALTERNATE DITCH CHECK	360.000	LF
8061007A	CURB INLET CHECK	2.000	EA
8061016	SEDIMENT REMOVAL	68.000	CUYD
8061017	TEMPORARY SEEDING	0.300	ACRE
8061019	SILT FENCE	1,328.000	LF
8064135	TYPE 2A EROSION CONTROL BLANKET	6,292.000	SQYD
6061060	MGS GUARDRAIL	550.000	LF
6061080	MGS END ANCHOR	1.000	EA
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	2.000	EA
9011062	LIGHTING POLE, 45 FT. OR 13.5 M, TYPE AT DESIGN 2	4.000	EA
9011115	BRACKET ARM, 15 FT. OR 4.6 M	4.000	EA
9011312	LUMINAIRE, LED-B	4.000	EA
9014003	CONDUIT, 3 IN. RIGID, PUSHED	348.000	LF
9016110	PULL BOX, PREFORMED CLASS 1	1.000	EA
9017110	CABLE, 10 AWG 1 CONDUCTOR, POLE AND BRACKET	480.000	LF
9017407	CABLE-CONDUIT, 1 IN., 2 CONDUCTORS AND 1 BARE NEUTRAL, 8 AWG	1,300.000	LF
9018245	POLE FOUNDATION (45 FT. OR 13.5 M MOUNTING HEIGHT)	4.000	EA
9018612	POWER SUPPLY ASSEMBLY, TYPE 2, 240/120 VOLT SERVICE, LIGHTING ONLY	1.000	EA
9031010	CONCRETE FOOTINGS, EMBEDDED	0.700	CUYD
9031210	STRUCTURAL STEEL POSTS	700.000	LB



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-C02

Item No.	Description	Quantity	Units
9031220	PIPE POSTS	160.000	LB
9031270A	2 IN. PSST POST - 12 GA.	540.000	LF
9031271A	DRIVEN POST ANCHOR FOR 2 IN. PSST - 12 GA.	36.000	EA
9035004A	SH-FLAT SHEET	437.000	SQFT
9035069A	SHF-FLAT SHEET FLUORESCENT	18.000	SQFT
4030403	10 INCHES, ASPHALTIC CONCRETE PAVEMENT SP125C ALTERNATE PAVEMENT [ASPHALTIC PAVEMENT 10 IN.]	8,773.100	SQYD
5021308	CONCRETE PAVEMENT (8 IN. NON-REINFORCED, 15 FT. JOINTS)	8,773.100	SQYD
4010150	TYPE A2 SHOULDER	2,579.300	SQYD
5021340	TYPE A2 SHOULDER	2,579.300	SQYD

( ) Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
250221-C03		
FAS-S303 (096)	JKU0009	
JKU0009-ROUTE 273-PLATTE COUNTY		
FAS-S303 (096)	JKU0009	
Intersection turn lanes		



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-C03

**Contract ID:** 250221-C03

**Letting Date:** February 21, 2025 11:00 AM

**Projects:** JKU0009

FAS-S303 (096)

**Counties:** PLATTE

**District:** Kansas City

**DBE Goal Percent:** 7.00

**Description:** \*\*\*\*(1): Job JKU0009 Route 273 PLATTE County. Intersection turn lanes at Route 273 and at Route 371, the total length of improvement being 0.305 miles.

**Contract Time:** DT - 12/1/2025

Item No.	Description	Quantity	Units
1081000	SIGNET DBE REPORTING	1.000	LS
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2031000	CLASS A EXCAVATION	1,491.000	CUYD
2036000	COMPACTING EMBANKMENT	165.000	CUYD
2063000	CLASS 3 EXCAVATION	17.000	CUYD
2063500	CULVERT CLEANOUT	2.000	EA
3040504	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK)	32.000	SQYD
3040506	TYPE 5 AGGREGATE FOR BASE (6 IN. THICK)	3,136.000	SQYD
4010150	TYPE A2 SHOULDER	499.100	SQYD
4019905	MISC. OPTIONAL PAVEMENT	2,333.200	SQYD
5029905	MISC. 8 IN. TINTED CONCRETE TRUCK APRON	308.100	SQYD
6044011	PIPE COLLAR, TYPE A	1.000	EA
6072010	WOVEN WIRE FENCE	123.000	LF
6083006	6 IN. CONCRETE MEDIAN STRIP	123.800	SQYD
6086004	CONCRETE SIDEWALK, 4 IN.	45.100	SQYD
6092011	INTEGRAL CURB (6 IN. HEIGHT AND UNDER) TYPE A	336.000	LF
6096010A	FURNISHING TYPE 1 ROCK DITCH LINER	2.000	CUYD
6096041	PLACING TYPE 1 ROCK DITCH LINER	2.000	CUYD





Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-C03

Item No.	Description	Quantity	Units
6097000	ROCK LINING	3.000	CUYD
6099903	MISC. CURB AND GUTTER APWA TYPE CG-1	498.000	LF
6099903	MISC. MODIFIED APWA CURB & GUTTER, TYPE CG-1	371.000	LF
6161005	CONSTRUCTION SIGNS	690.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	4.000	EA
6161025	CHANNELIZER (TRIM LINE)	61.000	EA
6161030	TYPE III MOVEABLE BARRICADE	6.000	EA
6161040	FLASHING ARROW PANEL	2.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	4.000	EA
6162002	TEMPORARY LONG-TERM RUMBLE STRIPS	8.000	EA
6181000	MOBILIZATION	1.000	LS
6181020	ADDITIONAL MOBILIZATION FOR SEEDING	4.000	EA
6191000	PAVEMENT EDGE TREATMENT	1,515.000	LF
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	136.000	LF
6200018	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. YELLOW	176.000	LF
6200021	PREFORMED THERMOPLASTIC PAVEMENT MARKING, LEFT/RIGHT ARROW	15.000	EA
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	4,156.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	5,681.000	LF
6207001	PAVEMENT MARKING REMOVAL	9,770.000	LF
6207002	PAVEMENT MARKING REMOVAL (SYMBOLS)	43.000	EA
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	13.000	SQYD
6274000	CONTRACTOR FURNISHED SURVEYING AND	1.000	LS



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-C03

Item No.	Description	Quantity	Units
	STAKING		
7261015	15 IN. PIPE GROUP A	14.000	LF
7319913	MISC. APWA TYPE 1- 5 ft. x 3 ft. curb inlet	4.000	FT
7320618A	18 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	1.000	EA
8051000A	SEEDING - COOL SEASON GRASSES	0.500	ACRE
8061005	ROCK DITCH CHECK	54.000	LF
8061006	ALTERNATE DITCH CHECK	12.000	LF
8061007A	CURB INLET CHECK	1.000	EA
8061016	SEDIMENT REMOVAL	22.000	CUYD
8061019	SILT FENCE	1,753.000	LF
8064137	TYPE 2C EROSION CONTROL BLANKET	2,316.000	SQYD
9011030	LIGHTING POLE, 30 FT. OR 9.0 M, TYPE AT	8.000	EA
9011115	BRACKET ARM, 15 FT. OR 4.6 M	8.000	EA
9011311	LUMINAIRE, LED-A	8.000	EA
9012230	BASE MOUNTED CONTROL STATION 240 VOLT - 4 CIRCUIT	1.000	EA
9013003	CONDUIT, 3 IN. RIGID, IN TRENCH	119.000	LF
9014004	CONDUIT, 4 IN. RIGID, PUSHED	534.000	LF
9015010	TRENCHING TYPE I	1,008.000	LF
9016111	PULL BOX, PREFORMED CLASS 2	7.000	EA
9017002	CABLE, 2 AWG 1 CONDUCTOR	220.000	LF
9017110	CABLE, 10 AWG 1 CONDUCTOR, POLE AND BRACKET	720.000	LF
9017407	CABLE-CONDUIT, 1 IN., 2 CONDUCTORS AND 1 BARE NEUTRAL, 8 AWG	2,620.000	LF
9018230	POLE FOUNDATION (30 FT. OR 9.0 M MOUNTING HEIGHT)	8.000	EA
9020213	SIGNAL HEAD, TYPE 3S	1.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-C03

Item No.	Description	Quantity	Units
9020513	SIGNAL HEAD, TYPE 3B	7.000	EA
9020514	SIGNAL HEAD, TYPE 4B	4.000	EA
9020833	SH-FLAT SHEET - SIGNAL SIGN	62.000	SQFT
9020834	SIGNAL SIGN, MOUNTING HARDWARE	8.000	EA
9023225	POST, TYPE C, 25 FT. ARM OR 7.6 M ARM	1.000	EA
9023230	POST, TYPE C, 30 FT. ARM OR 9.1 M ARM	1.000	EA
9023240	POST, TYPE C, 40 FT. ARM OR 12.2 M ARM	2.000	EA
9025300	CONDUIT, 3 IN., TRENCH WITH TRACER WIRE	236.000	LF
9027400	CONDUIT, 4 IN., PUSHED WITH TRACER WIRE	280.000	LF
9028208	CABLE, 8 AWG 1 CONDUCTOR, POWER	230.000	LF
9028311	CABLE, 16 AWG 7 CONDUCTOR	1,450.000	LF
9028621	POWER SUPPLY ASSEMBLY, TYPE-2 WITH 120V LIGHTING CONTROL CABINET	1.000	EA
9028811	PULL BOX, PREFORMED CLASS 2	6.000	EA
9028812	PULL BOX, PREFORMED CLASS 3	1.000	EA
9029100	BASE, CONCRETE	16.500	CUYD
9029902	MISC. TS2/EV CABINET ASSEMBLY (WITHOUT CONTROLLER)	1.000	EA
9031010	CONCRETE FOOTINGS, EMBEDDED	3.100	CUYD
9031220	PIPE POSTS	1,910.000	LB
9035004A	SH-FLAT SHEET	120.000	SQFT
9035069A	SHF-FLAT SHEET FLUORESCENT	55.000	SQFT
9109902	MISC. CAMERA AND RADIO POLE RISER, 20 FT.	1.000	EA
9109902	MISC. CELL PHONE NETWORK ROUTER AND ALL ASSOCIATED EQUIPMENT	1.000	EA
9109902	MISC. KC DISTRICT VIDEO DETECTION SYSTEM	1.000	EA
9109902	MISC. TOP MOUNTED CCTV CAMERA ASSEMBLY	1.000	EA



**Missouri Department of Transportation**

**Notice To Contractors - Contract ID 250221-C03**

**Page 60 of 115**

---

**( ) Item will be bid as lump sum.**



**Missouri Department of Transportation**

**Notice To Contractors - Contract ID 250221-C04**

<b>Contract ID</b>	<b>Federal Project Number / State Project Number</b>	<b>Description</b>
250221-C04		
IS 029-1(141)	JKU0370	
JKU0370-VARIOUS ROUTES-JACKSON, CLAY COUNTIES		
IS 029-1(141)	JKU0370	
High friction surface treatment		



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-C04

Contract ID: 250221-C04

Letting Date: February 21, 2025 11:00 AM

Projects: JKU0370

IS 029-1(141)

Counties: CLAY, JACKSON

District: Kansas City

DBE Goal Percent:

Description: \*\*\*\*(1): Job JKU0370 Route Various CLAY, JACKSON County. High friction surface treatment at various interchanges in the urban Kansas City District, the total length of improvement being 0.878 miles.

Contract Time: DT - 11/1/2025

Item No.	Description	Quantity	Units
4139905	MISC. HIGH FRICTION SURFACE TREATMENT-BAUXITE	9,395.000	SQYD
6161005	CONSTRUCTION SIGNS	490.000	SQFT
6161025	CHANNELIZER (TRIM LINE)	70.000	EA
6161030	TYPE III MOVEABLE BARRICADE	4.000	EA
6161040	FLASHING ARROW PANEL	2.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	4.000	EA
6181000	MOBILIZATION	1.000	LS
6205902A	6 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	4,663.000	LF
6205903A	6 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	2,808.000	LF
6205906A	12 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	1,954.000	LF

( ) Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
250221-D01		
FAS S402(66)	J5S3506	
J5s3506 - ROUTE C - WASHINGTON COUNTY		
FAS S402(66)	J5S3506	
Bridge replacement		



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-D01

**Contract ID:** 250221-D01

**Letting Date:** February 21, 2025 11:00 AM

**Projects:** J5S3506

FAS S402(66)

**Counties:** WASHINGTON

**District:** Central

**DBE Goal Percent:** 4.00

**Description:** \*\*\*\*(1): Job J5S3506 Route C WASHINGTON County. Bridge replacement over the Big River near Belgrade, 3.8 Miles West of Caledonia, the total length of improvement being 0.192 miles.

**Contract Time:** DT - 12/1/2025

Item No.	Description	Quantity	Units
1041000	TEMPORARY SURFACING	46.000	CUYD
1081000	SIGNET DBE REPORTING	1.000	LS
1091030	2 IN. ALUMINUM CAP WITH MODOT R/W IMPRINT	11.000	EA
1091031	6 FT. WHITE CARSONITE POST WITH MODOT R/W STICKER	11.000	EA
1091032	24 IN. SURVEY PIN	11.000	EA
2013000	CLEARING AND GRUBBING	1.000	ACRE
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2035000	UNCLASSIFIED EXCAVATION	1,087.000	CUYD
2035500	EMBANKMENT IN PLACE	3,233.000	CUYD
2036000	COMPACTING EMBANKMENT	3,306.000	CUYD
2037075	COMPACTING IN CUT	7.100	STA
2063000	CLASS 3 EXCAVATION	6.000	CUYD
2071000	LINEAR GRADING CLASS 1	2.700	STA
3040143	TYPE 1 AGGREGATE FOR BASE (4 IN. THICK)	2,256.000	SQYD
3107003	GRAVEL (A) OR CRUSHED STONE (B) OR CHAT (C)	66.000	SQYD
4010151	TYPE A3 SHOULDER	264.800	SQYD





Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-D01

Item No.	Description	Quantity	Units
4039905	MISC. OPTIONAL PAVT. (5.75" PORTLAND CEMENT CONCRETE PAVT. OR 5.75" ASPHALTIC CONCRETE PAVT.)	356.000	SQYD
4039905	MISC. OPTIONAL PAVT. (8" PORTLAND CEMENT CONCRETE PAVT. OR 10" ASPHALTIC CONCRETE PAVT.)	1,634.600	SQYD
6096010A	FURNISHING TYPE 1 ROCK DITCH LINER	2.000	CUYD
6096041	PLACING TYPE 1 ROCK DITCH LINER	2.000	CUYD
6113020	FURNISHING TYPE 2 ROCK BLANKET	680.000	CUYD
6113040	PLACING TYPE 2 ROCK BLANKET	680.000	CUYD
6161005	CONSTRUCTION SIGNS	774.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	2.000	EA
6161030	TYPE III MOVEABLE BARRICADE	10.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	3.000	EA
6181000	MOBILIZATION	1.000	LS
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	2,033.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	2,033.000	LF
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	1,036.000	SQYD
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7250418	18 IN. PIPE GROUP C	35.000	LF
7320818A	18 IN. OR ALLOWED SUBSTITUTE GROUP C FLARED END SECTION	2.000	EA
8025006	MULCHING	0.900	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	0.900	ACRE
8061005	ROCK DITCH CHECK	66.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-D01

Item No.	Description	Quantity	Units
8061006	ALTERNATE DITCH CHECK	30.000	LF
8061010A	TYPE B BERM	94.000	LF
8061011	SLOPE DRAINS	64.000	LF
8061016	SEDIMENT REMOVAL	26.000	CUYD
8061019	SILT FENCE	1,625.000	LF
8061050	TYPE C BERM	305.000	LF
6061060	MGS GUARDRAIL	25.000	LF
6061069	MGS BRIDGE APPROACH TRANSITION SECTION (REGULAR/NO CURB)	4.000	EA
6061080	MGS END ANCHOR	1.000	EA
6063015	TYPE A CRASHWORTHY END TERMINAL	3.000	EA
9031280	2.5 IN. PSST POST - 12 GA.	16.000	LF
9031281A	DRIVEN POST ANCHOR FOR 2.5 IN. PSST - 7 GA.	1.000	EA
9035004A	SH-FLAT SHEET	9.000	SQFT
2061000	CLASS 1 EXCAVATION	80.000	CUYD
2160500	REMOVAL OF BRIDGES	1.000	LS
5031011A	BRIDGE APPROACH SLAB (MINOR ROAD)	121.000	SQYD
7011106	DRILLED SHAFTS (4 FT. 0 IN. DIA.)	95.700	LF
7011205	ROCK SOCKETS (3 FT 6 IN. DIA.)	72.000	LF
7011300	VIDEO CAMERA INSPECTION	6.000	EA
7011400	FOUNDATION INSPECTION HOLES	132.000	LF
7011600	SONIC LOGGING TESTING	6.000	EA
7021212	GALVANIZED STRUCTURAL STEEL PILES (12 IN)	156.000	LF
7026000	PRE-BORE FOR PILING	76.000	LF
7027000	PILE POINT REINFORCEMENT	8.000	EA
7032003	CLASS B CONCRETE (SUBSTRUCTURE)	82.000	CUYD
7034216	TYPE H BARRIER	657.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-D01

Item No.	Description	Quantity	Units
7034221	SLAB ON CONCRETE NU-GIRDER	973.000	SQYD
7056022	NU 43, PRESTRESSED CONCRETE NU-GIRDER	906.000	LF
7061060	REINFORCING STEEL (BRIDGES)	29,270.000	LB
7123610	SLAB DRAIN	54.000	EA
7151001	VERTICAL DRAIN AT END BENTS	2.000	EA
7161000	PLAIN NEOPRENE BEARING PAD	6.000	EA
7161002	LAMINATED NEOPRENE BEARING PAD	6.000	EA
7162000	LAMINATED NEOPRENE BEARING PAD ASSEMBLY	12.000	EA

( ) Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
250221-D02		
FAS S403(7)	J5S3533	
J5S3533 - ROUTES OR I-44 - CRAWFORD COUNTY		
FAS S403(7)	J5S3533	
Bridge deck replacement		



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-D02

**Contract ID:** 250221-D02

**Letting Date:** February 21, 2025 11:00 AM

**Projects:** J5S3533

FAS S403(7)

**Counties:** CRAWFORD

**District:** Central

**DBE Goal Percent:** 4.00

**Description:** \*\*\*\*(1): Job J5S3533 Route OR 44 CRAWFORD County. Bridge deck replacement on I-44 South Outer Road over Little Bourbeuse River, the total length of improvement being 0.054 miles.

**Contract Time:** DT - 12/1/2025

Item No.	Description	Quantity	Units
1081000	SIGNET DBE REPORTING	1.000	LS
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2153000	SHAPING SLOPES, CLASS III	4.000	100F
4011209	BITUMINOUS PAVEMENT MIXTURE PG64-22, (BP-1)	27.000	TONS
4071005	TACK COAT	24.000	GAL
6113020	FURNISHING TYPE 2 ROCK BLANKET	303.000	CUYD
6113040	PLACING TYPE 2 ROCK BLANKET	303.000	CUYD
6161005	CONSTRUCTION SIGNS	109.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	2.000	EA
6161030	TYPE III MOVEABLE BARRICADE	10.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	2.000	EA
6181000	MOBILIZATION	1.000	LS
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	575.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	72.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-D02

Item No.	Description	Quantity	Units
6221001	COLDMILLING BITUMINOUS PAVEMENT FOR REMOVAL OF SURFACING (3 IN. THICK OR LESS)	244.000	SQYD
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	624.000	SQYD
8025006	MULCHING	0.300	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	0.300	ACRE
8061005	ROCK DITCH CHECK	80.000	LF
8061016	SEDIMENT REMOVAL	11.000	CUYD
8061019	SILT FENCE	262.000	LF
6061069	MGS BRIDGE APPROACH TRANSITION SECTION (REGULAR/NO CURB)	4.000	EA
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	4.000	EA
2024043	REMOVAL OF MISCELLANEOUS ACM (NON-FRIABLE)	13.000	SQFT
2162500	REMOVAL OF EXISTING BRIDGE DECK	4,242.000	SQFT
5031011A	BRIDGE APPROACH SLAB (MINOR ROAD)	118.000	SQYD
7034212	SLAB ON STEEL	470.000	SQYD
7034219A	TYPE D BARRIER	294.000	LF
7110200	PROTECTIVE COATING - CONCRETE BENTS AND PIERS (EPOXY)	1.000	LS
7123610	SLAB DRAIN	22.000	EA
7125201	SURFACE PREPARATION FOR OVERCOATING STRUCTURAL STEEL (SYSTEM G)	3,600.000	SQFT
7125365A	INTERMEDIATE FIELD COAT (SYSTEM G)	3,600.000	SQFT
7125370A	FINISH FIELD COAT (SYSTEM G)	1,000.000	SQFT
7126000	NON-DESTRUCTIVE TESTING	52.000	LF
7151001	VERTICAL DRAIN AT END BENTS	2.000	EA

( ) Item will be bid as lump sum.



Contract ID
Federal Project Number / State Project Number
Description

250221-D03	
FAS S403(81), (79), (80)	J5S3545, J5S3550, J5S3579
J5S3545, J5S3550, J5S3579 - ROUTES BEAMER LANE, C, FF - CRAWFORD COUNTY	
FAS S403(81)	J5S3545
Bridge rehabilitation	
FAS S403(79)	J5S3550
Bridge rehabilitation	
FAS S403(80)	J5S3579
Bridge rehabilitation	



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-D03

Contract ID: 250221-D03

Letting Date: February 21, 2025 11:00 AM

Projects: J5S3545  
J5S3550  
J5S3579

FAS S403(81)  
FAS S403(79)  
FAS S403(80)

Counties: CRAWFORD

District: Central

DBE Goal Percent: 5.00

Description: \*\*\*\*(1): Job J5S3545 Route Beamer Lane CRAWFORD County. Bridge rehabilitation on Beamer Lane over I-44 west of Cuba, the total length of improvement being 0.039 miles.  
\*\*\*\*(2): Job J5S3550 Route C CRAWFORD County. Bridge rehabilitation on Route C over I-44 in Bourbon, the total length of improvement being 0.046 miles. \*\*\*\*(3): Job J5S3579 Route FF CRAWFORD County. Bridge rehabilitation on Route FF over I-44 west of Sullivan, the total length of improvement being 0.046 miles.

Contract Time: DT - 12/1/2025

Item No.	Description	Quantity	Units
1081000	SIGNET DBE REPORTING	1.000	LS
6096010A	FURNISHING TYPE 1 ROCK DITCH LINER	3.000	CUYD
6096041	PLACING TYPE 1 ROCK DITCH LINER	3.000	CUYD
6161005	CONSTRUCTION SIGNS	409.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	2.000	EA
6161025	CHANNELIZER (TRIM LINE)	58.000	EA
6161030	TYPE III MOVEABLE BARRICADE	7.000	EA
6161040	FLASHING ARROW PANEL	2.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	1.000	EA
6181000	MOBILIZATION	1.000	LS
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	18.000	SQYD





Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-D03

Item No.	Description	Quantity	Units
8059901	MISC. MULCHING	1.000	LS
8059901	MISC. SEEDING - COOL SEASON MIXTURE	1.000	LS
8061006	ALTERNATE DITCH CHECK	20.000	LF
8061016	SEDIMENT REMOVAL	3.000	CUYD
8061019	SILT FENCE	115.000	LF
2161500	REMOVAL OF SEAL COAT OR POLYMER WEARING SURFACE	80.000	SQFT
4091048	EMULSIFIED ASPHALT, SEAL COAT	239.000	GAL
4094001	SEAL COAT AGGREGATE, GRADE A1	597.000	SQYD
7040101	SUBSTRUCTURE REPAIR (FORMED)	4.000	SQFT
7040104	HALF-SOLE REPAIR	100.000	SQFT
7040106	FULL DEPTH REPAIR	100.000	SQFT
7040110	EPOXY PRESSURE INJECTING	10.000	LF
7040112	DECK REPAIR WITH VOID TUBE REPLACEMENT	50.000	SQFT
7040113	CLEANING AND EPOXY COATING	1,739.000	SQFT
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2069902	MISC. DRAIN BASIN CLEANOUT	4.000	EA
2153000	SHAPING SLOPES, CLASS III	12.000	100F
4020520	BITUMINOUS PAVEMENT MIXTURE PG64-22 (SURFACE LEVELING)	12.300	TONS
4071005	TACK COAT	22.000	GAL
6113020	FURNISHING TYPE 2 ROCK BLANKET	271.000	CUYD
6113040	PLACING TYPE 2 ROCK BLANKET	271.000	CUYD
6161005	CONSTRUCTION SIGNS	503.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	2.000	EA
6161025	CHANNELIZER (TRIM LINE)	114.000	EA
6161030	TYPE III MOVEABLE BARRICADE	10.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-D03

Item No.	Description	Quantity	Units
6161040	FLASHING ARROW PANEL	2.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	5.000	EA
6181000	MOBILIZATION	1.000	LS
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	486.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	486.000	LF
6221001	COLDMILLING BITUMINOUS PAVEMENT FOR REMOVAL OF SURFACING (3 IN. THICK OR LESS)	222.000	SQYD
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	483.000	SQYD
8059901	MISC. MULCHING	1.000	LS
8059901	MISC. SEEDING - COOL SEASON MIXTURE	1.000	LS
8061006	ALTERNATE DITCH CHECK	40.000	LF
8061016	SEDIMENT REMOVAL	6.000	CUYD
8061019	SILT FENCE	208.000	LF
6061060	MGS GUARDRAIL	750.000	LF
6061069	MGS BRIDGE APPROACH TRANSITION SECTION (REGULAR/NO CURB)	2.000	EA
6061080	MGS END ANCHOR	1.000	EA
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	1.000	EA
6069901	MISC. METAL BEAM GUARD FENCE THRIE-BEAM TRANSITION	1.000	LS
2161001	TOTAL SURFACE HYDRO DEMOLITION	847.000	SQYD
2161502	REMOVAL OF CONCRETE WEARING SURFACE	7,620.000	SQFT
2161503	REMOVAL OF EXISTING DECK REPAIR	850.000	SQFT
5052000	LATEX MODIFIED CONCRETE WEARING SURFACE	847.000	SQYD
7031004	DIAMOND GRINDING	847.000	SQYD



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-D03

Item No.	Description	Quantity	Units
7034600	CURB BLOCKOUT	403.000	LF
7040106	FULL DEPTH REPAIR	50.000	SQFT
7040110	EPOXY PRESSURE INJECTING	10.000	LF
7040112	DECK REPAIR WITH VOID TUBE REPLACEMENT	100.000	SQFT
7040113	CLEANING AND EPOXY COATING	1,515.000	SQFT
5050004	SUPPLEMENTARY WEARING SURFACE MATERIAL	8.000	CY
7040104	HALF-SOLE REPAIR	100.000	SQFT
5050004	SUPPLEMENTARY WEARING SURFACE MATERIAL	11.000	CY
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2069902	MISC. DRAIN BASIN CLEANOUT	4.000	EA
2153000	SHAPING SLOPES, CLASS III	4.000	100F
4020520	BITUMINOUS PAVEMENT MIXTURE PG64-22 (SURFACE LEVELING)	8.600	TONS
4071005	TACK COAT	16.000	GAL
6113020	FURNISHING TYPE 2 ROCK BLANKET	189.000	CUYD
6113040	PLACING TYPE 2 ROCK BLANKET	189.000	CUYD
6161005	CONSTRUCTION SIGNS	393.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	1.000	EA
6161025	CHANNELIZER (TRIM LINE)	58.000	EA
6161030	TYPE III MOVEABLE BARRICADE	8.000	EA
6161040	FLASHING ARROW PANEL	2.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	3.000	EA
6181000	MOBILIZATION	1.000	LS
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	486.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT	486.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-D03

Item No.	Description	Quantity	Units
6221001	MARKING PAINT, TYPE P BEADS		
6221001	COLDMILLING BITUMINOUS PAVEMENT FOR REMOVAL OF SURFACING (3 IN. THICK OR LESS)	156.000	SQYD
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	256.000	SQYD
8059901	MISC. MULCHING	1.000	LS
8059901	MISC. SEEDING - COOL SEASON MIXTURE	1.000	LS
8061006	ALTERNATE DITCH CHECK	40.000	LF
8061016	SEDIMENT REMOVAL	6.000	CUYD
8061019	SILT FENCE	202.000	LF
6061069	MGS BRIDGE APPROACH TRANSITION SECTION (REGULAR/NO CURB)	2.000	EA
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	2.000	EA
6069901	MISC. METAL BEAM GUARD FENCE THRIE-BEAM TRANSITION	1.000	LS
2161001	TOTAL SURFACE HYDRO DEMOLITION	586.000	SQYD
2161502	REMOVAL OF CONCRETE WEARING SURFACE	5,274.000	SQFT
2161503	REMOVAL OF EXISTING DECK REPAIR	51.000	SQFT
5052000	LATEX MODIFIED CONCRETE WEARING SURFACE	586.000	SQYD
7031004	DIAMOND GRINDING	586.000	SQYD
7034600	CURB BLOCKOUT	377.000	LF
7040106	FULL DEPTH REPAIR	50.000	SQFT
7040112	DECK REPAIR WITH VOID TUBE REPLACEMENT	50.000	SQFT
7040113	CLEANING AND EPOXY COATING	2,540.000	SQFT
5050004	SUPPLEMENTARY WEARING SURFACE MATERIAL	4.000	CY
7040104	HALF-SOLE REPAIR	50.000	SQFT
5050004	SUPPLEMENTARY WEARING SURFACE MATERIAL	5.000	CY

( ) Item will be bid as lump sum.



**Missouri Department of Transportation**

**Notice To Contractors - Contract ID 250221-D04**

<b>Contract ID</b>	<b>Federal Project Number / State Project Number</b>	<b>Description</b>
250221-D04		
FAF 41-1(15)	JCD0062	
JCD0062 - ROUTE 41 - COOPER COUNTY		
FAF 41-1(15)	JCD0062	
Bridge rehabilitation		



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-D04

**Contract ID:** 250221-D04

**Letting Date:** February 21, 2025 11:00 AM

**Projects:** JCD0062

FAF 41-1(15)

**Counties:** COOPER

**District:** Central

**DBE Goal Percent:**

**Description:** \*\*\*\*(1): Job JCD0062 Route 41 COOPER County. Bridge rehabilitation over Lamine River near Lamine, the total length of improvement being 0.185 miles.

**Contract Time:** DT - 12/1/2025

Item No.	Description	Quantity	Units
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2153000	SHAPING SLOPES, CLASS III	4.000	100F
6161005	CONSTRUCTION SIGNS	161.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	2.000	EA
6161025	CHANNELIZER (TRIM LINE)	38.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	2.000	EA
6181000	MOBILIZATION	1.000	LS
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	901.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	901.000	LF
6061060	MGS GUARDRAIL	563.000	LF
6061068	MGS BRIDGE APPROACH TRANSITION SECTION (EXTENDED CURB)	4.000	EA
6061080	MGS END ANCHOR	1.000	EA
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	3.000	EA
7040163	CONCRETE CRACK FILLER	1,602.000	SQYD



**Missouri Department of Transportation**

**Notice To Contractors - Contract ID 250221-D04**

**Page 79 of 115**

---

**( ) Item will be bid as lump sum.**



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-D05

Contract ID	Federal Project Number / State Project Number	Description
250221-D05		
IS-70-3 (299)	JCD0091	
JCD0091 - ROUTE I-70, I-44 - VARIOUS COUNTIES		
IS-70-3 (299)	JCD0091	
Sign replacement		





Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-D05

Contract ID: 250221-D05

Letting Date: February 21, 2025 11:00 AM

Projects: JCD0091

IS-70-3 (299)

Counties: BOONE, CALLAWAY, COOPER, CRAWFORD, LACLEDE, PHELPS, PULASKI

District: Central

DBE Goal Percent:

Description: \*\*\*\*(1): Job JCD0091 Route I-70, I-44 BOONE, CALLAWAY, COOPER, CRAWFORD, LACLEDE, PHELPS, PULASKI County. Sign replacement at various locations on I-70 and I-44 within the Central District, the total length of improvement being 315.27 miles.

Contract Time: DT - 5/1/2026

Item No.	Description	Quantity	Units
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
6161005	CONSTRUCTION SIGNS	683.000	SQFT
6161025	CHANNELIZER (TRIM LINE)	138.000	EA
6161033	DIRECTIONAL INDICATOR BARRICADE	28.000	EA
6161040	FLASHING ARROW PANEL	2.000	EA
6161055	SEQUENTIAL FLASHING WARNING LIGHT	28.000	EA
6181000	MOBILIZATION	1.000	LS
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
9031005	SQUARE STEEL SIGN POST (4IN.) BASE	23.000	EA
9031010	CONCRETE FOOTINGS, EMBEDDED	53.500	CUYD
9031210	STRUCTURAL STEEL POSTS	41,570.000	LB
9031230	4 IN. SQUARE STEEL POST	419.000	LF
9035011A	ST-STRUCTURAL	9,181.000	SQFT
9035071A	STF-STRUCTURAL FLUORESCENT	90.000	SQFT

( ) Item will be bid as lump sum.



**Missouri Department of Transportation**

**Notice To Contractors - Contract ID 250221-D05**

**Page 82 of 115**

---



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-D06

Contract ID	Federal Project Number / State Project Number	Description
250221-D06		
FAS S403(55)	JCD0101	
JCD0101 - ROUTES OR 44 - LACLEDE COUNTY		
FAS S403(55)	JCD0101	
Bridge replacement		



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-D06

**Contract ID:** 250221-D06

**Letting Date:** February 21, 2025 11:00 AM

**Projects:** JCD0101

FAS S403(55)

**Counties:** LACLEDE

**District:** Central

**DBE Goal Percent:** 4.00

**Description:** \*\*\*\*(1): Job JCD0101 Route SOR 44 LACLEDE County. Bridge replacement over Bear Creek east of Lebanon, the total length of improvement being 0.142 miles.

**Contract Time:** DT - 12/1/2025

Item No.	Description	Quantity	Units
1081000	SIGNET DBE REPORTING	1.000	LS
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2031000	CLASS A EXCAVATION	386.000	CUYD
2036000	COMPACTING EMBANKMENT	196.000	CUYD
2101006A	SUBGRADE COMPACTION (6-INCH DEPTH)	6.000	100F
3040504	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK)	1,546.000	SQYD
4019905	MISC. OPTIONAL PAVEMENT	1,546.300	SQYD
6113020	FURNISHING TYPE 2 ROCK BLANKET	821.000	CUYD
6113040	PLACING TYPE 2 ROCK BLANKET	821.000	CUYD
6161005	CONSTRUCTION SIGNS	426.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	3.000	EA
6161025	CHANNELIZER (TRIM LINE)	40.000	EA
6161030	TYPE III MOVEABLE BARRICADE	10.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	3.000	EA
6181000	MOBILIZATION	1.000	LS
6181020	ADDITIONAL MOBILIZATION FOR SEEDING	4.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-D06

Item No.	Description	Quantity	Units
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	1,384.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	1,384.000	LF
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	850.000	SQYD
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
8059901	MISC. SEED AND MULCH - COOL SEASON MIXTURES	1.000	LS
8061005	ROCK DITCH CHECK	165.000	LF
8061006	ALTERNATE DITCH CHECK	150.000	LF
8061016	SEDIMENT REMOVAL	24.000	CUYD
8061019	SILT FENCE	1,308.000	LF
8061050	TYPE C BERM	315.000	LF
6061060	MGS GUARDRAIL	275.000	LF
6061069	MGS BRIDGE APPROACH TRANSITION SECTION (REGULAR/NO CURB)	4.000	EA
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	4.000	EA
9031280	2.5 IN. PSST POST - 12 GA.	32.000	LF
9031281A	DRIVEN POST ANCHOR FOR 2.5 IN. PSST - 7 GA.	2.000	EA
2061000	CLASS 1 EXCAVATION	400.000	CUYD
2160500	REMOVAL OF BRIDGES	1.000	LS
5031011A	BRIDGE APPROACH SLAB (MINOR ROAD)	116.000	SQYD
7021212	GALVANIZED STRUCTURAL STEEL PILES (12 IN)	652.000	LF
7027000	PILE POINT REINFORCEMENT	34.000	EA
7032003	CLASS B CONCRETE (SUBSTRUCTURE)	154.200	CUYD
7034219A	TYPE D BARRIER	308.000	LF
7034221	SLAB ON CONCRETE NU-GIRDER	338.000	SQYD
7056022	NU 43, PRESTRESSED CONCRETE NU-GIRDER	402.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-D06

Item No.	Description	Quantity	Units
7061060	REINFORCING STEEL (BRIDGES)	7,540.000	LB
7123610	SLAB DRAIN	16.000	EA
7151001	VERTICAL DRAIN AT END BENTS	2.000	EA
7161000	PLAIN NEOPRENE BEARING PAD	8.000	EA

( ) Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
250221-F01		
FAF 100-1(92),	J6P3635, JSL0091, JSL0092	
J6P3635, JSL0091, JSL0092-ROUTE 100-ST LOUIS, FRANKLIN COUNTIES		
FAF-100-1 (92)	J6P3635	
Coldmill and resurface		
NHPP 5500690	JSL0091	
J-Turn		
FAF 100-1(95)	JSL0092	
Turn lanes		



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-F01

Contract ID: 250221-F01

Letting Date: February 21, 2025 11:00 AM

Projects: J6P3635  
JSL0091  
JSL0092

FAF-100-1 (92)  
NHPP 5500690  
FAF 100-1(95)

Counties: FRANKLIN, ST LOUIS

District: St. Louis

DBE Goal Percent: 9.00

Description: \*\*\*\*(1): Job J6P3635 Route 100 FRANKLIN, ST LOUIS County. Coldmill and resurface from Route OO in Franklin County to Westglen Farms Drive in St. Louis County, the total length of improvement being 9.522 miles.\*\*\*\*(2): Job JSL0091 Route 100 ST LOUIS County. J-Turn at Route T and at Pond Road in Wildwood, the total length of improvement being 2.07 miles. \*\*\*\*(3): Job JSL0092 Route 100 ST LOUIS County. Turn lanes at Booness Lane, Woodland Meadows Drive, Hencken Road and Windy Hollow Lane in Wildwood, the total length of improvement being 2.73 miles.

Contract Time: DT - 11/15/2025

Item No.	Description	Quantity	Units
1081000	SIGNET DBE REPORTING	1.000	LS
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2152000A	SHAPING SLOPES, CLASS II	854.000	100F
2159910	MISC. SHAPING SLOPES CLASS III - MODIFIED	3.000	100F
3101003	GRAVEL (A)	1,206.000	SQYD
4011209	BITUMINOUS PAVEMENT MIXTURE PG64-22, (BP-1)	19,927.200	TONS
4030103	ASPHALTIC CONCRETE MIXTURE PG 70-22 (SP125C MIX)	12,938.800	TONS
4030109	ASPHALTIC CONCRETE MIXTURE PG 70-22 (SP125CLP MIX)	28,103.900	TONS
4071007	TACK COAT - NON-TRACKING	26,938.000	GAL
4079912	MISC. MODIFIED BONDED ASPHALTIC CONCRETE PAVEMENT	40,942.000	GAL





Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-F01

Item No.	Description	Quantity	Units
6083003	3 IN. CONCRETE MEDIAN STRIP	30.400	SQYD
6083006	6 IN. CONCRETE MEDIAN STRIP	92.800	SQYD
6091052	CURB AND GUTTER TYPE B	84.000	LF
6093015	ASPHALT CURB (4 INCH)	208.000	LF
6123001	TRUCK MOUNTED ATTENUATOR (TMA)	1.000	LS
6131010	FURNISHING AND PLACING CONCRETE MATERIAL FOR FULL DEPTH PAVEMENT REPAIR	2,552.000	SQYD
6131012	SUBGRADE COMPACTION (6 IN. DEPTH) (PAVEMENT REPAIR)	255.000	SQYD
6131013	TYPE 1 OR 5 AGGREGATE FOR BASE (4 IN. THICK) (PAVEMENT REPAIR)	255.000	SQYD
6131014	FULL DEPTH PAVEMENT REPAIR SAW CUT (FOR PERIMETER AND INTERNAL SAW CUTS)	10,492.000	LF
6131015	DOWEL BAR (DRILLING, FURNISHING AND INSTALLATION) FOR FULL DEPTH PAVEMENT REPAIR	4,164.000	EA
6131017	DOWEL BAR (FURNISHING AND INSTALLATION WITH BASKETS) FOR FULL DEPTH PAVEMENT REPAIR	258.000	EA
6131018	TIE BAR (DRILLING, FURNISHING AND INSTALLATION) FOR FULL DEPTH PAVEMENT REPAIR (TYPE L JOINTS)	246.000	EA
6133018	FURNISHING AND PLACING BITUMINOUS MATERIAL FOR CLASS B PARTIAL DEPTH PAVEMENT REPAIR	26.300	TONS
6133019	REMOVAL FOR CLASS B PARTIAL DEPTH PAVEMENT REPAIR	119.000	SQYD
6161040	FLASHING ARROW PANEL	4.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	4.000	EA
6162000A	WORK ZONE TRAFFIC SIGNAL SYSTEM	1.000	EA
6169901	MISC. TEMPORARY TRAFFIC CONTROL	1.000	LS
6181000	MOBILIZATION	1.000	LS



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-F01

Item No.	Description	Quantity	Units
6181020	ADDITIONAL MOBILIZATION FOR SEEDING	1.000	EA
6200006	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 4 IN YELLOW	28.000	LF
6200009	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 6 IN. WHITE	93.000	LF
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	446.000	LF
6200018	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. YELLOW	825.000	LF
6200021	PREFORMED THERMOPLASTIC PAVEMENT MARKING, LEFT/RIGHT ARROW	56.000	EA
6200027	PREFORMED THERMOPLASTIC PAVEMENT MARKING, COMBINATION STR/LT/RT	3.000	EA
6200030	PREFORMED THERMOPLASTIC PAVEMENT MARKING, WORD (ONLY)	2.000	EA
6200036	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 30 IN WHITE MIDBLOCK	43.000	EA
6200042	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 12 IN WHITE, YIELD LINE TRIANGLES	32.000	EA
6205901A	4 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	58,917.000	LF
6205902A	6 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	110,778.000	LF
6205903A	6 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	37,257.000	LF
6205906A	12 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	1,560.000	LF
6209901	MISC. TEMPORARY PAVEMENT MARKING PAINT	1.000	LS
6221001	COLDMILLING BITUMINOUS PAVEMENT FOR REMOVAL OF SURFACING (3 IN. THICK OR LESS)	127,653.000	SQYD
6224010	MODIFIED COLDMILLING (DEPTH TRANSITIONS)	11,682.000	SQYD
6229905	MISC. TRANSVERSE TRANSITION MILLING	5,069.600	SQYD



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-F01

Item No.	Description	Quantity	Units
6261000A	BITUMINOUS SHOULDER RUMBLE STRIP	1,085.200	STA
6261001	BITUMINOUS CENTERLINE RUMBLE STRIP	169.200	STA
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
8025006	MULCHING	2.200	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	2.200	ACRE
6061060	MGS GUARDRAIL	38.000	LF
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	2.000	EA
6069902	MISC. MGS END ANCHOR ( COATED BLACK)	1.000	EA
6069902	MISC. TYPE A CRASHWORTHY END TERMINAL (COATED BLACK)	1.000	EA
6069903	MISC. MGS 8' POSTS GUARDRAIL (COATED BLACK)	1,429.000	LF
9031220	PIPE POSTS	1,340.000	LB
9031242	36 IN. SURFACE-MOUNT DELINEATOR POST	5.000	EA
9031270A	2 IN. PSST POST - 12 GA.	237.000	LF
9031271A	DRIVEN POST ANCHOR FOR 2 IN. PSST - 12 GA.	24.000	EA
9031280	2.5 IN. PSST POST - 12 GA.	25.000	LF
9031281A	DRIVEN POST ANCHOR FOR 2.5 IN. PSST - 7 GA.	2.000	EA
9035004A	SH-FLAT SHEET	454.000	SQFT
9035011A	ST-STRUCTURAL	782.000	SQFT
9035069A	SHF-FLAT SHEET FLUORESCENT	96.000	SQFT
9035071A	STF-STRUCTURAL FLUORESCENT	12.000	SQFT
2013000	CLEARING AND GRUBBING	2.000	ACRE
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2031000	CLASS A EXCAVATION	8,633.000	CUYD
2036000	COMPACTING EMBANKMENT	2,617.000	CUYD
2037075	COMPACTING IN CUT	11.200	STA



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-F01

Item No.	Description	Quantity	Units
2063000	CLASS 3 EXCAVATION	88.000	CUYD
2063500	CULVERT CLEANOUT	2.000	EA
3040506	TYPE 5 AGGREGATE FOR BASE (6 IN. THICK)	16,543.000	SQYD
5021310	CONCRETE PAVEMENT (10 IN. NON-REINFORCED 15 FT. JOINTS)	122.000	SQYD
6042010	ADJUSTING MANHOLE	1.000	EA
6042020	ADJUSTING BASIN OR INLET	5.000	EA
6044011	PIPE COLLAR, TYPE A	1.000	EA
6083003	3 IN. CONCRETE MEDIAN STRIP	226.700	SQYD
6083006	6 IN. CONCRETE MEDIAN STRIP	245.200	SQYD
6097000	ROCK LINING	10.000	CUYD
6113020	FURNISHING TYPE 2 ROCK BLANKET	1,127.000	CUYD
6113040	PLACING TYPE 2 ROCK BLANKET	1,127.000	CUYD
6161099	CHANGEABLE MESSAGE SIGN WITH COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	10.000	EA
6162002	TEMPORARY LONG-TERM RUMBLE STRIPS	7.000	EA
6169901	MISC. Lump Sum Temporary Traffic Control	1.000	LS
6181000	MOBILIZATION	1.000	LS
6181020	ADDITIONAL MOBILIZATION FOR SEEDING	2.000	EA
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	37.000	LF
6200021	PREFORMED THERMOPLASTIC PAVEMENT MARKING, LEFT/RIGHT ARROW	34.000	EA
6200030	PREFORMED THERMOPLASTIC PAVEMENT MARKING, WORD (ONLY)	5.000	EA
6200042	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 12 IN WHITE, YIELD LINE TRIANGLES	196.000	EA
6205301B	TEMPORARY REMOVABLE MARKING TAPE 4 IN., WHITE	30,811.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-F01

Item No.	Description	Quantity	Units
6205303B	TEMPORARY REMOVABLE MARKING TAPE 4 IN., YELLOW	31,182.000	LF
6205309	TEMPORARY REMOVABLE MARKING TAPE, 24 IN., WHITE	42.000	LF
6205440A	TEMPORARY NON-REMOVABLE MARKING TAPE LEFT/RIGHT ARROW	12.000	EA
6205901A	4 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	757.000	LF
6205902A	6 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	25,462.000	LF
6205903A	6 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	12,642.000	LF
6206124A	24 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	490.000	LF
6206125A	24 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	90.000	LF
6207001	PAVEMENT MARKING REMOVAL	39,025.000	LF
6207002	PAVEMENT MARKING REMOVAL (SYMBOLS)	23.000	EA
6209902	MISC. Merge Left Arrow	1.000	EA
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7250315A	15 IN. PIPE GROUP B	185.000	LF
7250318A	18 IN. PIPE GROUP B	205.000	LF
7311033	PRECAST CONCRETE DROP INLET 3 FT X 3 FT	4.000	FT
7320015A	15 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION	4.000	EA
7320018A	18 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION	5.000	EA
8025006	MULCHING	4.000	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	4.000	ACRE
8061003	SEDIMENT TRAP EXCAVATION	5.000	CUYD



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-F01

Item No.	Description	Quantity	Units
8061004	SEDIMENT TRAP ROCK	7.000	CUYD
8061006	ALTERNATE DITCH CHECK	636.000	LF
8061016	SEDIMENT REMOVAL	82.000	CUYD
8061017	TEMPORARY SEEDING	0.800	ACRE
8061019	SILT FENCE	4,830.000	LF
4039905	MISC. 11.5 IN. ASPHALTIC CONCRETE PAVEMENT, SP125CLP. SP125C, SP190C	16,421.200	SQYD
5021308	CONCRETE PAVEMENT (8 IN. NON-REINFORCED, 15 FT. JOINTS)	16,421.200	SQYD
9012230	BASE MOUNTED CONTROL STATION 240 VOLT - 4 CIRCUIT	2.000	EA
9013002	CONDUIT, 2 IN. RIGID, IN TRENCH	63.000	LF
9013003	CONDUIT, 3 IN. RIGID, IN TRENCH	33.000	LF
9014004	CONDUIT, 4 IN. RIGID, PUSHED	1,080.000	LF
9015010	TRENCHING TYPE I	7,003.000	LF
9015030	TRENCHING TYPE III	817.000	LF
9016110	PULL BOX, PREFORMED CLASS 1	28.000	EA
9017002	CABLE, 2 AWG 1 CONDUCTOR	610.000	LF
9017110	CABLE, 10 AWG 1 CONDUCTOR, POLE AND BRACKET	2,430.000	LF
9017404	CABLE-CONDUIT, 1 IN., 2 CONDUCTORS AND 1 BARE NEUTRAL, 6 AWG	4,620.000	LF
9017407	CABLE-CONDUIT, 1 IN., 2 CONDUCTORS AND 1 BARE NEUTRAL, 8 AWG	8,800.000	LF
9018245	POLE FOUNDATION (45 FT. OR 13.5 M MOUNTING HEIGHT)	27.000	EA
9018612	POWER SUPPLY ASSEMBLY, TYPE 2, 240/120 VOLT SERVICE, LIGHTING ONLY	2.000	EA
9019902	MISC. 45 Foot Roadway LED B Top Mounted Luminaire	27.000	EA
9019902	MISC. 45 Foot Roadway Top Mount Pole	27.000	EA



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-F01

Item No.	Description	Quantity	Units
9031010	CONCRETE FOOTINGS, EMBEDDED	0.900	CUYD
9031210	STRUCTURAL STEEL POSTS	660.000	LB
9031220	PIPE POSTS	120.000	LB
9031241	BREAKAWAY ASSEMBLY (PERFORATED SQUARE STEEL TUBE)	12.000	EA
9031270A	2 IN. PSST POST - 12 GA.	1,346.000	LF
9031271A	DRIVEN POST ANCHOR FOR 2 IN. PSST - 12 GA.	121.000	EA
9031272A	2.25 IN. PSST POST INSERT (6 FT.) - 12 GA.	2.000	EA
9031274	CONCRETE POST ANCHOR FOR 2 IN. PSST. - 7 GA.	7.000	EA
9031280	2.5 IN. PSST POST - 12 GA.	169.000	LF
9031281A	DRIVEN POST ANCHOR FOR 2.5 IN. PSST - 7 GA.	14.000	EA
9035004A	SH-FLAT SHEET	976.000	SQFT
9035069A	SHF-FLAT SHEET FLUORESCENT	65.000	SQFT
2013000	CLEARING AND GRUBBING	6.000	ACRE
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2031000	CLASS A EXCAVATION	6,994.000	CUYD
2036000	COMPACTING EMBANKMENT	4,541.000	CUYD
2037075	COMPACTING IN CUT	67.000	STA
2111000A	SUBGRADE SCARIFYING	67.000	100F
2142000	FURNISHING ROCK FILL	427.000	CUYD
2143000	PLACING ROCK FILL	427.000	CUYD
3040504	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK)	669.000	SQYD
3040506	TYPE 5 AGGREGATE FOR BASE (6 IN. THICK)	17,493.000	SQYD
4010150	TYPE A2 SHOULDER	11,572.000	SQYD
4011209	BITUMINOUS PAVEMENT MIXTURE PG64-22, (BP-1)	63.300	TONS
4013000	BITUMINOUS PAVEMENT MIXTURE PG64-22 (BASE)	144.200	TONS
4019905	MISC. OPTIONAL PAVEMENT	5,920.400	SQYD



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-F01

Item No.	Description	Quantity	Units
4071005	TACK COAT	33.000	GAL
6093010	ASPHALT CURB	139.000	LF
6096030A	FURNISHING TYPE 3 ROCK DITCH LINER	360.000	CUYD
6096043	PLACING TYPE 3 ROCK DITCH LINER	360.000	CUYD
6096050	BEDDING MATERIAL FOR ROCK DITCH LINER	131.000	CUYD
6123001	TRUCK MOUNTED ATTENUATOR (TMA)	1.000	LS
6131014	FULL DEPTH PAVEMENT REPAIR SAW CUT (FOR PERIMETER AND INTERNAL SAW CUTS)	13,160.000	LF
6169901	MISC. TEMPORARY TRAFFIC CONTROL	1.000	LS
6181000	MOBILIZATION	1.000	LS
6191000	PAVEMENT EDGE TREATMENT	12,881.000	LF
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7250424	24 IN. PIPE GROUP C	53.000	LF
7320824A	24 IN. OR ALLOWED SUBSTITUTE GROUP C FLARED END SECTION	2.000	EA
8025006	MULCHING	4.300	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	4.300	ACRE
8061005	ROCK DITCH CHECK	984.000	LF
8061019	SILT FENCE	8,818.000	LF
6061060	MGS GUARDRAIL	318.000	LF
6061061	MGS GUARDRAIL, 8 FT. POSTS, 6 FT. - 3 IN. SPACING	100.000	LF
6061080	MGS END ANCHOR	1.000	EA
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	2.000	EA
9031010	CONCRETE FOOTINGS, EMBEDDED	0.300	CUYD
9031210	STRUCTURAL STEEL POSTS	330.000	LB
9031220	PIPE POSTS	660.000	LB





Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-F01

Item No.	Description	Quantity	Units
9031270A	2 IN. PSST POST - 12 GA.	298.000	LF
9031271A	DRIVEN POST ANCHOR FOR 2 IN. PSST - 12 GA.	30.000	EA
9031280	2.5 IN. PSST POST - 12 GA.	51.000	LF
9031281A	DRIVEN POST ANCHOR FOR 2.5 IN. PSST - 7 GA.	4.000	EA
9035004A	SH-FLAT SHEET	312.000	SQFT
9035011A	ST-STRUCTURAL	56.000	SQFT

( ) Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
250221-F02		
IS 44-4(214)	JSL0206	
JSL0206-VARIOUS ROUTES - ST LOUIS, FRANKLIN COUNTY		
IS 44-4(214)	JSL0206	
Fixed Price Variable Scope pavement repair		



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-F02

Contract ID: 250221-F02

Letting Date: February 21, 2025 11:00 AM

Projects: JSL0206

IS 44-4(214)

Counties: FRANKLIN, ST LOUIS

District: St. Louis

DBE Goal Percent:

Description: \*\*\*\*(1): Job JSL0206 Route Various FRANKLIN, ST LOUIS County. Fixed Price Variable Scope pavement repair on I-55, I-255, Outer Road 44, Route 100 and Route 340 in St. Louis County and Route 47 in Franklin County, the total length of improvement being 14.276 miles.

Contract Time: DT - 10/1/2025

Item No.	Description	Quantity	Units
6123001	TRUCK MOUNTED ATTENUATOR (TMA)	1.000	LS
6139911	MISC. Removal, Furnishing, and Placing Hot Polymer Concrete Patching for Class A Partial Depth	439,139.000	LB
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	8.000	EA
6169901	MISC. Lump Sum Traffic Control	1.000	LS
6181000	MOBILIZATION	1.000	LS
9029902	MISC. 6'x15' LOOP DETECTOR	3.000	EA
9029902	MISC. 6'X30' LOOP DETECTOR	3.000	EA
9029902	MISC. 6'X6' LOOP DETECTOR	3.000	EA

( ) Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
250221-G04		
		JSRM0074, JSRM0075, JSUM0076
		JSRM0074, JSRM0075, JSUM0076 - VARIOUS ROUTES - VARIOUS COUNTIES
		JSRM0074
		Job Order Contract for signal and lighting repair
		JSRM0075
		Job Order Contract for signal and lighting repair
		JSUM0076
		Job Order Contract for signal and lighting repair



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-G04

Contract ID: 250221-G04

Letting Date: February 21, 2025 11:00 AM

Projects: JSRM0074  
JSRM0075  
JSUM0076

JSRM0074  
JSRM0075  
JSUM0076

Counties: VARIOUS

District: Southwest

DBE Goal Percent:

Description: \*\*\*\*(1): Job JSRM0074 Route Various VARIOUS County. Job Order Contract for signal and lighting repair in Barry, Barton, Dade, Jasper, Lawrence, McDonald and Newton Counties, the total length of improvement being 0 miles. \*\*\*\*(2): Job JSRM0075 Route Various VARIOUS County. Job Order Contract for signal and lighting repair in Bates, Benton, Cedar, Henry, Hickory, St. Clair and Vernon Counties, the total length of improvement being 0 miles. \*\*\*\*(3): Job JSUM0076 Route Various VARIOUS County. Job Order Contract for signal and lighting repair in Christian, Dallas, Greene, Polk, Stone, Taney and Webster Counties, the total length of improvement being 0 miles.

Contract Time: DT - 3/19/2026

Item No.	Description	Quantity	Units
6189916	MISC. ADJUSTMENT FACTOR	80,000.000	DLR
6189916	MISC. ADJUSTMENT FACTOR	14,000.000	DLR
6189916	MISC. ADJUSTMENT FACTOR	93,000.000	DLR

( ) Item will be bid as lump sum.



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-H01

Contract ID	Federal Project Number / State Project Number	Description
250221-H01	FAF 5-1(30),FAS S704(68),(73)	J9P3605,J9P3697,J9S3695
	J9P3605, J9P3697, J9S3695 - ROUTES 5, F - WRIGHT, DOUGLAS, LACLEDE COUNTIES	
	FAF 5-1(30)	J9P3605
	Resurface	
	FAS S704(68)	J9P3697
	Resurface	
	FAS S704(73)	J9S3695
	Resurface and bridge rehabilitation	



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-H01

Contract ID: 250221-H01

Letting Date: February 21, 2025 11:00 AM

Projects: J9P3605  
J9P3697  
J9S3695

FAF 5-1(30)  
FAS S704(68)  
FAS S704(73)

Counties: DOUGLAS, LACLEDE, WRIGHT

District: Southeast

DBE Goal Percent: 5.00

Description: \*\*\*\*(1): Job J9P3605 Route 5 DOUGLAS, WRIGHT County. Resurface from Route 60 to Route A in Douglas County, the total length of improvement being 17.798 miles.\*\*\*\*(2): Job J9P3697 Route 5 LACLEDE, WRIGHT County. Resurface from Route J in Laclede County to Route 60, the total length of improvement being 30.869 miles.\*\*\*\*(3): Job J9S3695 Route F WRIGHT County. Resurface and bridge rehabilitation from Route 5 to Route EE, the total length of improvement being 23.261 miles.

Contract Time: DT - 11/1/2026

Item No.	Description	Quantity	Units
1081000	SIGNET DBE REPORTING	1.000	LS
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2159903	MISC. Modified Shaping Slopes Class III	7,760.000	LF
3049910	MISC. PERMANENT AGGREGATE EDGE TREATMENT	3,216.600	TONS
3105002	GRAVEL (A) OR CRUSHED STONE (B)	111.000	TONS
4011209	BITUMINOUS PAVEMENT MIXTURE PG64-22, (BP-1)	19,656.400	TONS
4030101	ASPHALTIC CONCRETE MIXTURE PG 64-22 (SP125C MIX)	30,136.200	TONS
4071005	TACK COAT	32,445.000	GAL
6083003	3 IN. CONCRETE MEDIAN STRIP	18.600	SQYD
6161005	CONSTRUCTION SIGNS	1,984.000	SQFT
6161025	CHANNELIZER (TRIM LINE)	250.000	EA
6181000	MOBILIZATION	1.000	LS



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-H01

Item No.	Description	Quantity	Units
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	222.000	LF
6200018	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. YELLOW	326.000	LF
6200021	PREFORMED THERMOPLASTIC PAVEMENT MARKING, LEFT/RIGHT ARROW	15.000	EA
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	189,523.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	104,158.000	LF
6221001	COLDMILLING BITUMINOUS PAVEMENT FOR REMOVAL OF SURFACING (3 IN. THICK OR LESS)	3,734.000	SQYD
6224010	MODIFIED COLDMILLING (DEPTH TRANSITIONS)	7,293.000	SQYD
6261000A	BITUMINOUS SHOULDER RUMBLE STRIP	1,438.200	STA
6061060	MGS GUARDRAIL	31,075.000	LF
6061061	MGS GUARDRAIL, 8 FT. POSTS, 6 FT. - 3 IN. SPACING	9,500.000	LF
6061074	MGS HEIGHT AND BLOCK TRANSITION	4.000	EA
6061080	MGS END ANCHOR	19.000	EA
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	97.000	EA
9028500	CABLE, LOOP DETECTOR, IN DUCT	1,310.000	LF
9031010	CONCRETE FOOTINGS, EMBEDDED	0.700	CUYD
9031220	PIPE POSTS	350.000	LB
9035004A	SH-FLAT SHEET	277.000	SQFT
9035069A	SHF-FLAT SHEET FLUORESCENT	18.000	SQFT
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2159903	MISC. Modified Shaping Slopes Class III	800.000	LF
3049910	MISC. PERMANENT AGGREGATE EDGE TREATMENT	5,556.600	TONS
3105002	GRAVEL (A) OR CRUSHED STONE (B)	224.000	TONS





Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-H01

Item No.	Description	Quantity	Units
4011211	BITUMINOUS PAVEMENT MIXTURE PG64-22, (BP-2)	45,007.700	TONS
4071005	TACK COAT	35,823.000	GAL
6161005	CONSTRUCTION SIGNS	2,735.000	SQFT
6161025	CHANNELIZER (TRIM LINE)	250.000	EA
6181000	MOBILIZATION	1.000	LS
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	48.000	LF
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	317,360.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	274,794.000	LF
6221001	COLDMILLING BITUMINOUS PAVEMENT FOR REMOVAL OF SURFACING (3 IN. THICK OR LESS)	7,091.000	SQYD
6224010	MODIFIED COLDMILLING (DEPTH TRANSITIONS)	6,814.000	SQYD
6261000A	BITUMINOUS SHOULDER RUMBLE STRIP	2,083.200	STA
6061061	MGS GUARDRAIL, 8 FT. POSTS, 6 FT. - 3 IN. SPACING	588.000	LF
6061069	MGS BRIDGE APPROACH TRANSITION SECTION (REGULAR/NO CURB)	10.000	EA
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	10.000	EA
9035004A	SH-FLAT SHEET	201.000	SQFT
9035069A	SHF-FLAT SHEET FLUORESCENT	155.000	SQFT
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2159903	MISC. Modified Shaping Slopes Class III	1,520.000	LF
3049910	MISC. PERMANENT AGGREGATE EDGE TREATMENT	4,192.200	TONS
3105002	GRAVEL (A) OR CRUSHED STONE (B)	118.000	TONS
4020520	BITUMINOUS PAVEMENT MIXTURE PG64-22 (SURFACE LEVELING)	19,832.900	TONS
4071005	TACK COAT	27,903.000	GAL



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-H01

Item No.	Description	Quantity	Units
6122040	WORK ZONE CRASH CUSHION (NARROW)	6.000	EA
6122041	WORK ZONE CRASH CUSHION (NARROW) (RELOCATION)	6.000	EA
6161005	CONSTRUCTION SIGNS	2,659.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	6.000	EA
6161025	CHANNELIZER (TRIM LINE)	280.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	6.000	EA
6162000A	WORK ZONE TRAFFIC SIGNAL SYSTEM	3.000	EA
6162002	TEMPORARY LONG-TERM RUMBLE STRIPS	6.000	EA
6173600D	TEMPORARY TRAFFIC BARRIER, CONTRACTOR FURNISHED / RETAINED	972.000	LF
6175010A	RELOCATING TEMPORARY TRAFFIC BARRIER	972.000	LF
6181000	MOBILIZATION	1.000	LS
6205301B	TEMPORARY REMOVABLE MARKING TAPE 4 IN., WHITE	1,278.000	LF
6205303B	TEMPORARY REMOVABLE MARKING TAPE 4 IN., YELLOW	3,000.000	LF
6205309	TEMPORARY REMOVABLE MARKING TAPE, 24 IN., WHITE	60.000	LF
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	7,002.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	219,166.000	LF
6207001	PAVEMENT MARKING REMOVAL	2,622.000	LF
6221001	COLDMILLING BITUMINOUS PAVEMENT FOR REMOVAL OF SURFACING (3 IN. THICK OR LESS)	458.000	SQYD
6224010	MODIFIED COLDMILLING (DEPTH TRANSITIONS)	1,076.000	SQYD
6061061	MGS GUARDRAIL, 8 FT. POSTS, 6 FT. - 3 IN. SPACING	1,975.000	LF



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-H01

Item No.	Description	Quantity	Units
6061069	MGS BRIDGE APPROACH TRANSITION SECTION (REGULAR/NO CURB)	12.000	EA
6061074	MGS HEIGHT AND BLOCK TRANSITION	1.000	EA
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	19.000	EA
9031220	PIPE POSTS	30.000	LB
9031241	BREAKAWAY ASSEMBLY (PERFORATED SQUARE STEEL TUBE)	92.000	EA
9031250A	U-CHANNEL POST, 3 LB	66.000	LF
9031280	2.5 IN. PSST POST - 12 GA.	92.000	LF
9031285	CONCRETE POST ANCHOR FOR 2.5 IN. PSST. - 7 GA.	6.000	EA
9035004A	SH-FLAT SHEET	128.000	SQFT
9035069A	SHF-FLAT SHEET FLUORESCENT	470.000	SQFT
7034600	CURB BLOCKOUT	234.000	LF
7034600	CURB BLOCKOUT	270.000	LF
7039902	MISC. END POST MODIFICATION	4.000	EA

( ) Item will be bid as lump sum.



Contract ID	Federal Project Number / State Project Number	Description
250221-H02		
FAS S704(35)	J9S3744	
J9S3744 - ROUTE HH - SCOTT COUNTY		
FAS S704(35)	J9S3744	
Intersection turn lanes		



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-H02

**Contract ID:** 250221-H02

**Letting Date:** February 21, 2025 11:00 AM

**Projects:** J9S3744

FAS S704(35)

**Counties:** SCOTT

**District:** Southeast

**DBE Goal Percent:** 5.00

**Description:** \*\*\*\*(1): Job J9S3744 Route HH SCOTT County. Intersection turn lanes at Ingram Road, the total length of improvement being 0.363 miles.

**Contract Time:** DT - 11/14/2025

Item No.	Description	Quantity	Units
1081000	SIGNET DBE REPORTING	1.000	LS
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2031000	CLASS A EXCAVATION	3,709.000	CUYD
2036000	COMPACTING EMBANKMENT	2,967.000	CUYD
2063000	CLASS 3 EXCAVATION	17.000	CUYD
2101006A	SUBGRADE COMPACTION (6-INCH DEPTH)	12.900	100F
3040506	TYPE 5 AGGREGATE FOR BASE (6 IN. THICK)	2,603.000	SQYD
4011209	BITUMINOUS PAVEMENT MIXTURE PG64-22, (BP-1)	463.300	TONS
4019905	MISC. OPTIONAL PAVEMENT	2,603.100	SQYD
4071005	TACK COAT	489.000	GAL
6044011	PIPE COLLAR, TYPE A	2.000	EA
6083003	3 IN. CONCRETE MEDIAN STRIP	9.200	SQYD
6089902	MISC. MISC ISLAND TUBULAR MARKER	3.000	EA
6091041	CONCRETE GUTTER TYPE A	16.000	LF
6096020	FURNISHING TYPE 2 ROCK DITCH LINER	162.000	CUYD
6096042	PLACING TYPE 2 ROCK DITCH LINER	162.000	CUYD
6097000	ROCK LINING	6.000	CUYD
6123001	TRUCK MOUNTED ATTENUATOR (TMA)	1.000	LS



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-H02

Item No.	Description	Quantity	Units
6161005	CONSTRUCTION SIGNS	514.000	SQFT
6161008	ADVANCED WARNING RAIL SYSTEM	3.000	EA
6161025	CHANNELIZER (TRIM LINE)	120.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	2.000	EA
6181000	MOBILIZATION	1.000	LS
6181020	ADDITIONAL MOBILIZATION FOR SEEDING	4.000	EA
6191000	PAVEMENT EDGE TREATMENT	3,493.000	LF
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	13.000	LF
6200018	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. YELLOW	77.000	LF
6200021	PREFORMED THERMOPLASTIC PAVEMENT MARKING, LEFT/RIGHT ARROW	3.000	EA
6200027	PREFORMED THERMOPLASTIC PAVEMENT MARKING, COMBINATION STR/LT/RT	1.000	EA
6200042	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 12 IN WHITE, YIELD LINE TRIANGLES	9.000	EA
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	3,781.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	6,192.000	LF
6206108A	8 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	155.000	LF
6207001	PAVEMENT MARKING REMOVAL	21,132.000	LF
6208076	4 IN TEMPORARY PAVEMENT MARKING PAINT	16,763.000	LF
6221001	COLDMILLING BITUMINOUS PAVEMENT FOR REMOVAL OF SURFACING (3 IN. THICK OR LESS)	3,164.100	SQYD
6224010	MODIFIED COLDMILLING (DEPTH TRANSITIONS)	921.100	SQYD
6269909	MISC. OPTIONAL SHOULDER RUMBLE STRIPS	20.100	STA



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-H02

Item No.	Description	Quantity	Units
6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	LS
7261024	24 IN. PIPE GROUP A	31.000	LF
7320624A	24 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION	2.000	EA
8025006	MULCHING	1.600	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	1.200	ACRE
8061003	SEDIMENT TRAP EXCAVATION	15.000	CUYD
8061004	SEDIMENT TRAP ROCK	15.000	CUYD
8061006	ALTERNATE DITCH CHECK	132.000	LF
8061016	SEDIMENT REMOVAL	32.000	CUYD
8061017	TEMPORARY SEEDING	0.400	ACRE
8061019	SILT FENCE	1,484.000	LF
8064130	TYPE 3 TURF REINFORCEMENT MAT	484.000	SQYD
8064140	TYPE 3B EROSION CONTROL BLANKET	4,578.000	SQYD
9031241	BREAKAWAY ASSEMBLY (PERFORATED SQUARE STEEL TUBE)	1.000	EA
9031272A	2.25 IN. PSST POST INSERT (6 FT.) - 12 GA.	1.000	EA
9031280	2.5 IN. PSST POST - 12 GA.	48.000	LF
9031281A	DRIVEN POST ANCHOR FOR 2.5 IN. PSST - 7 GA.	3.000	EA
9035004A	SH-FLAT SHEET	35.000	SQFT

( ) Item will be bid as lump sum.



**Missouri Department of Transportation**

**Notice To Contractors - Contract ID 250221-H03**

<b>Contract ID</b>	<b>Federal Project Number / State Project Number</b>	<b>Description</b>
250221-H03		
FAS S705(89)	JSE0152	
JSE0152 - ROUTE B - ST FRANCOIS COUNTY		
FAS S705(89)	JSE0152	
Scrub seal and shoulders		





Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-H03

**Contract ID:** 250221-H03

**Letting Date:** February 21, 2025 11:00 AM

**Projects:** JSE0152

FAS S705(89)

**Counties:** ST FRANCOIS

**District:** Southeast

**DBE Goal Percent:** 6.00

**Description:** \*\*\*\*(1): Job JSE0152 Route B ST FRANCOIS County. Scrub seal and shoulders from Route 32 to Route 221 near Doe Run, the total length of improvement being 7.197 miles.

**Contract Time:** DT - 11/1/2026

Item No.	Description	Quantity	Units
1081000	SIGNET DBE REPORTING	1.000	LS
2022010	REMOVAL OF IMPROVEMENTS	1.000	LS
2129900	MISC. SHOULDER GRADING	695.000	100F
3049910	MISC. PERMANENT AGGREGATE EDGE TREATMENT	1,000.000	TONS
3105002	GRAVEL (A) OR CRUSHED STONE (B)	70.000	TONS
4011211	BITUMINOUS PAVEMENT MIXTURE PG64-22, (BP-2)	1,352.200	TONS
4013000	BITUMINOUS PAVEMENT MIXTURE PG64-22 (BASE)	3,653.700	TONS
4071005	TACK COAT	1,248.000	GAL
4139905	MISC. MINERAL AGGREGATE	99,792.000	SQYD
4139912	MISC. SCRUB SEAL EMULSION	24,948.000	GAL
6096020	FURNISHING TYPE 2 ROCK DITCH LINER	1,202.000	CUYD
6096042	PLACING TYPE 2 ROCK DITCH LINER	1,202.000	CUYD
6161005	CONSTRUCTION SIGNS	1,342.000	SQFT
6161025	CHANNELIZER (TRIM LINE)	82.000	EA
6161098A	CHANGEABLE MESSAGE SIGN WITHOUT COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	2.000	EA
6181000	MOBILIZATION	1.000	LS



Missouri Department of Transportation

Notice To Contractors - Contract ID 250221-H03

Item No.	Description	Quantity	Units
6181020	ADDITIONAL MOBILIZATION FOR SEEDING	3.000	EA
6200015	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	24.000	LF
6200033	PREFORMED THERMOPLASTIC PAVEMENT MARKING, R/R CROSSING MARKER	2.000	EA
6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	75,530.000	LF
6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	75,015.000	LF
6209901	MISC. TEMPORARY PAVEMENT MARKING PAINT	1.000	LS
6240103A	PERMANENT EROSION CONTROL GEOTEXTILE	3,605.000	SQYD
6261000A	BITUMINOUS SHOULDER RUMBLE STRIP	569.200	STA
8025006	MULCHING	24.100	ACRE
8051000A	SEEDING - COOL SEASON GRASSES	16.000	ACRE
8061003	SEDIMENT TRAP EXCAVATION	100.000	CUYD
8061004	SEDIMENT TRAP ROCK	200.000	CUYD
8061005	ROCK DITCH CHECK	1,200.000	LF
8061006	ALTERNATE DITCH CHECK	500.000	LF
8061016	SEDIMENT REMOVAL	215.000	CUYD
8061017	TEMPORARY SEEDING	8.100	ACRE
8061019	SILT FENCE	3,500.000	LF
6061060	MGS GUARDRAIL	300.000	LF
6061069	MGS BRIDGE APPROACH TRANSITION SECTION (REGULAR/NO CURB)	4.000	EA
6063014	TYPE A CRASHWORTHY END TERMINAL (MASH)	4.000	EA
9031260	WOOD POST, 4 IN. BY 4 IN.	420.000	LF
9031270A	2 IN. PSST POST - 12 GA.	1,030.000	LF
9031271A	DRIVEN POST ANCHOR FOR 2 IN. PSST - 12 GA.	110.000	EA
9031280	2.5 IN. PSST POST - 12 GA.	552.000	LF



**Missouri Department of Transportation**

**Notice To Contractors - Contract ID 250221-H03**

<b>Item No.</b>	<b>Description</b>	<b>Quantity</b>	<b>Units</b>
9031281A	DRIVEN POST ANCHOR FOR 2.5 IN. PSST - 7 GA.	42.000	EA
9035004A	SH-FLAT SHEET	27.000	SQFT
9035069A	SHF-FLAT SHEET FLUORESCENT	729.000	SQFT

**( ) Item will be bid as lump sum.**