

Job No.: J7P3477

Route: 82

County: St. Clair

JOB SPECIAL PROVISIONS TABLE OF CONTENTS (ROADWAY)

(Job Special Provisions shall prevail over General Special Provisions whenever in conflict therewith.)



REVISED

A.	General - Federal JSP-09-02H	1
B.	<b>Contract Liquidated Damages JSP-13-01B</b>	1
C.	Work Zone Traffic Management JSP-02-06M	2
D.	Boat Traffic Control Plan	4
E.	Emergency Provisions and Incident Management JSP-90-11A	5
F.	Project Contact for Contractor/Bidder Questions JSP-96-05	6
G.	Contractor Quality Control NJSP-15-42	7
H.	Removal and Delivery of Existing Signs JSP-12-01B	9
I.	Recycled Concrete Materials	9
J.	Slurry and Residue Produced During Surface Treatment of PCCP and Bridge Decks JSP-06-05	10
K.	Removal of Bridge Debris	10
L.	Restrictions for Migratory Birds NJSP-16-06A	11
M.	Adjusting Guardrail	12
N.	Liquidated Damages Specified JSP-93-28	14
O.	Supplemental Revisions JSP-18-01X	14
P.	Remove and Re-set Existing Sign on New PSST Post	32

Job No.: J7P3477

Route: 82

County: St. Clair

	<b>MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION</b> 105 W. CAPITOL AVE. JEFFERSON CITY, MO 65102 Phone 1-888-275-6636
	<b><i>Bartlett &amp; West, Inc.</i></b> <b><i>1719 Southridge Drive, Suite 100</i></b> <b><i>Jefferson City, MO 65109</i></b> Certificate of Authority: <b>000167-Eng.</b> Consultant Phone: <b>(573) 634-3181</b>
	If a seal is present on this sheet, JSP's have been electronically sealed and dated.
	JOB NUMBER: J3P3477 ST. CLAIR COUNTY, MO DATE PREPARED: 08/16/2022
	ADDENDUM DATE: <b><i>R001 5/12/2023</i></b>
Only the following items of the Job Special Provisions (Roadway) are authenticated by this seal: All	

JOB  
SPECIAL PROVISION

A. General - Federal JSP-09-02H

**1.0 Description.** The Federal Government is participating in the cost of construction of this project. All applicable Federal laws, and the regulations made pursuant to such laws, shall be observed by the contractor, and the work will be subject to the inspection of the appropriate Federal Agency in the same manner as provided in Sec 105.10 of the Missouri Standard Specifications for Highway Construction with all revisions applicable to this bid and contract.

**1.1** This contract requires payment of the prevailing hourly rate of wages for each craft or type of work required to execute the contract as determined by the Missouri Department of Labor and Industrial Relations and requires adherence to a schedule of minimum wages as determined by the United States Department of Labor. For work performed anywhere on this project, the contractor and the contractor's subcontractors shall pay the higher of these two applicable wage rates. State Wage Rates, Information on the Required Federal Aid Provisions, and the current Federal Wage Rates are available on the Missouri Department of Transportation web page at [www.modot.org](http://www.modot.org) under "Doing Business with MoDOT", "Contractor Resources". Effective Wage Rates will be posted 10 days prior to the applicable bid opening. These supplemental bidding documents have important legal consequences. It shall be conclusively presumed that they are in the bidder's possession, and they have been reviewed and used by the bidder in the preparation of any bid submitted on this project.

**1.2** The following documents are available on the Missouri Department of Transportation web page at [www.modot.org](http://www.modot.org) under "Doing Business with MoDOT"; "Standards and Specifications". The effective version shall be determined by the letting date of the project.

General Provisions & Supplemental Specifications

Supplemental Plans to July 2022 Missouri Standard Plans  
For Highway Construction

These supplemental bidding documents contain all current revisions to the published versions and have important legal consequences. It shall be conclusively presumed that they are in the bidder's possession, and they have been reviewed and used by the bidder in the preparation of any bid submitted on this project.



B. Contract Liquidated Damages JSP-13-01B

**1.0 Description.** Liquidated Damages for failure or delay in completing the work on time for this contract shall be in accordance with Sec 108.8. The liquidated damages include separate amounts for road user costs and contract administrative costs incurred by the Commission.

**2.0 Period of Performance.** Prosecution of work is expected to begin on the date specified below in accordance with Sec 108.2. Regardless of when the work is begun on this contract, all work shall be completed on or before the date specified below. Completion by this date shall be in accordance with the requirements of Sec 108.7.1.

Job No.: J7P3477

Route: 82

County: St. Clair

Notice to Proceed: July 10, 2023

Completion Date: ~~December 1, 2023~~

December 1, 2024

**2.1 Calendar Days.** The count of calendar days will begin on the date the contractor starts any construction operations on the project.

Job Number	Calendar Days	Daily Road User Cost
J7P3477	100	\$1,800

**3.0 Liquidated Damages for Contract Administrative Costs.** Should the contractor fail to complete the work on or before the completion date specified in Section 2.0, or within the number of calendar days specified in Section 2.1, whichever occurs first, the contractor will be charged contract administrative liquidated damages in accordance with Sec 108.8 in the amount of **\$750** per calendar day for each calendar day, or partial day thereof, that the work is not fully completed. For projects in combination, these damages will be charged in full for failure to complete one or more projects within the above specified completion date or calendar days.

**4.0 Liquidated Damages for Road User Costs.** Should the contractor fail to complete the work on or before the completion date specified in Section 2.0, or within the number of calendar days specified in Section 2.1, whichever occurs first, the contractor will be charged road user costs in accordance with Sec 108.8 in the amount specified in Section 2.1 for each calendar day, or partial day thereof, that the work is not fully completed. These damages are in addition to the contract administrative damages and any other damages as specified elsewhere in this contract.

C. Work Zone Traffic Management JSP-02-06M

**1.0 Description.** Work zone traffic management shall be in accordance with applicable portions of Division 100 and Division 600 of the Standard Specifications, and specifically as follows.

**1.1 Maintaining Work Zones and Work Zone Reviews.** The Work Zone Specialist (WZS) shall maintain work zones in accordance with Sec 616.3.3 and as further stated herein. The WZS shall coordinate and implement any changes approved by the engineer. The WZS shall ensure all traffic control devices are maintained in accordance with Sec 616, the work zone is operated within the hours specified by the engineer, and will not deviate from the specified hours without prior approval of the engineer. The WZS is responsible to manage work zone delay in accordance with these project provisions. When requested by the engineer, the WZS shall submit a weekly report that includes a review of work zone operations for the week. The report shall identify any problems encountered and corrective actions taken. Work zones are subject to unannounced inspections by the engineer and other departmental staff to corroborate the validity of the WZS's review and may require immediate corrective measures and/or additional work zone monitoring.

**1.2 Work Zone Deficiencies.** Failure to make corrections on time may result in the engineer suspending work. The suspension will be non-excusable and non-compensable regardless if road user costs are being charged for closures.

**2.0 Traffic Management Schedule.**

**2.1** Traffic management schedules shall be submitted to the engineer for review prior to the start of work and prior to any revisions to the traffic management schedule. The traffic management schedule shall include the proposed traffic control measures, the hours traffic control will be in place, and work hours.

**2.2** The traffic management schedule shall conform to the limitations specified in Sec 616 regarding lane closures, traffic shifts, road closures and other width, height and weight restrictions.

**2.3** The engineer shall be notified as soon as practical of any postponement due to weather, material or other circumstances.

**2.4** In order to ensure minimal traffic interference, the contractor shall schedule lane closures for the absolute minimum amount of time required to complete the work. Lanes shall not be closed until material is available for continuous construction and the contractor is prepared to diligently pursue the work until the closed lane is opened to traffic.

**2.5 Traffic Congestion.** The contractor shall, upon approval of the engineer, take proactive measures to reduce traffic congestion in the work zone. The contractor shall immediately implement appropriate mitigation strategies whenever traffic congestion reaches an excess of 10 minutes to prevent congestion from escalating to 15 minute or above threshold. If disruption of the traffic flow occurs and traffic is backed up in queues of 15 minute delays or longer, then the contractor shall immediately review the construction operations which contributed directly to disruption of the traffic flow and make adjustments to the operations to prevent the queues from reoccurring. Traffic delays may be monitored by physical presence on site or by utilizing real-time travel data through the work zone that generate text and/or email notifications where available. The engineer monitoring the work zone may also notify the contractor of delays that require prompt mitigation. The contractor may work with the engineer to determine what other alternative solutions or time periods would be acceptable.

#### **2.5.1 Traffic Safety.**

**2.5.1.1 Recurring Congestion.** Where traffic queues routinely extend to within 1000 feet of the ROAD WORK AHEAD, or similar, sign on a divided highway or to within 500 feet of the ROAD WORK AHEAD, or similar, sign on an undivided highway, the contractor shall extend the advance warning area, as approved by the engineer.

**2.5.1.2 Non-Recurring Congestion.** When traffic queues extend to within 1000 feet of the ROAD WORK AHEAD, or similar, sign on a divided highway or to within 500 feet of the ROAD WORK AHEAD, or similar, sign on an undivided highway infrequently, the contractor shall deploy a means of providing advance warning of the traffic congestion, as approved by the engineer. The warning location shall be no less than 1000 feet and no more than 0.5 mile in advance of the end of the traffic queue on divided highways and no less than 500 feet and no more than 0.5 mile in advance of the end of the traffic queue on undivided highways.

### **3.0 Work Hour Restrictions.**

**3.1** Except for emergency work, as determined by the engineer, and long term lane closures required by project phasing, all lanes shall be scheduled to be open to traffic during the five

major holiday periods shown below, from 12:00 noon on the last working day preceding the holiday until 6:00 a.m. on the first working day subsequent to the holiday unless otherwise approved by the engineer.

Memorial Day  
Labor Day  
Thanksgiving  
Christmas  
New Year's Day

**3.1.1 Independence Day.** The lane restrictions specified in Section 3.1 shall also apply to Independence Day, except that the restricted periods shall be as follows:

12:00 noon June 30, 2023 – 6:00 a.m. July 5, 2023

12:00 noon July 3, 2024 – 6:00 a.m. July 5, 2024

12:00 noon July 3, 2025 – 6:00 a.m. July 7, 2025

**3.2** The contractor shall not perform any construction operation on the roadway (*including the hauling of material within the project limits*), during restricted periods, holiday periods or other special events specified in the contract documents.

#### **4.0 Detours and Lane Closures.**

**4.1** When a changeable message sign (CMS) is provided, the contractor shall use the CMS to notify motorists of future traffic disruption and possible traffic delays one week before traffic is shifted to a detour or prior to lane closures. The CMS shall be installed at a location as approved or directed by the engineer. If a CMS with Communication Interface is required, then the CMS shall be capable of communication prior to installation on right of way. All messages planned for use in the work zone shall be approved and authorized by the engineer or its designee prior to deployment. When permanent dynamic message signs (DMS) owned and operated by MoDOT are located near the project, they may also be used to provide warning and information for the work zone. Permanent DMS shall be operated by the TMC, and any messages planned for use on DMS shall be approved and authorized by the TMC at least 72 hours in advance of the work.

**5.0 Basis of Payment.** No direct payment will be made to the contractor to recover the cost of equipment, labor, materials, or time required to fulfill the above provisions, unless specified elsewhere in the contract document. All authorized changes in the traffic control plan shall be provided for as specified in Sec 616.

#### **D. Boat Traffic Control Plan**

**1.0 Description.** This work shall consist of providing and maintaining a boat traffic control plan as shown on the drawings. The contractor is advised that special sign assemblies and buoys shall be required for the safety and control of boat traffic as well as safety to the contractor.

**2.0** The Sac River Arm of Truman Lake shall be closed to boat traffic for the proposed work at Bridge A39051 for a duration of no more than 80 days.

### **3.0 Construction.**

**3.1 Sign Requirements.** All special sign assemblies and buoys shall be anchored to the bottom of the lake or stream as shown on the Missouri Standard Plans for Highway Construction. Each special sign assembly shall be equipped with two (2) flashing light units with amber lens.

The Contractor will be required to furnish, place as shown on the plans, maintain and/or replace these signs and buoys throughout the period of this contract and to remove them when the project is completed. The Contractor shall be required to make any revisions requested by the Missouri State Water Patrol.

**3.2 Placement Requirements.** As part of the Contractor's work schedule submittal, a schedule for placement and removal of signs and buoys and an Application for Buoy Permit shall be submitted to the Missouri State Water Patrol. The placement and removal of these signs and buoys shall be subject to the approval of the Water Patrol and the Water Patrol shall be notified thirty (30) days prior to placement or removal of any signs or buoys. If the Contractor restricts boat traffic from more than one work area at a time, there shall be a minimum of 150 feet clear between restricted areas unless otherwise approved by the Water Patrol.

Any barge or working platform that may be used by the Contractor and is left in the work area during the hours of dusk to dawn shall be equipped with a flashing light unit with amber lens on each corner of each barge and/or working platform.

### **4.0 Water Patrol Contact.**

The address of the Water Patrol is:

Missouri State Water Patrol  
Attn: Capt. Matt Walz  
1510 East Elm Street  
Jefferson City, Missouri 65101  
Telephone: (573) 751-5071

### **5.0 Method of Measurement.**

Signs and buoys shall be measured per each according to the various pay items included in the contract.

### **6.0 Basis of Payment.**

All expenses incurred by the Contractor by reason of their compliance with this provision shall be considered completely covered by the unit prices for the various pay items included in the contract.

#### **E. Emergency Provisions and Incident Management JSP-90-11A**

**1.0** The contractor shall have communication equipment on the construction site or immediate access to other communication systems to request assistance from law enforcement or other

emergency agencies for incident management. In case of traffic accidents or the need for law enforcement to direct or restore traffic flow through the job site, the contractor shall notify law enforcement or other emergency agencies immediately as needed. The area engineer's office shall also be notified when the contractor requests emergency assistance.

**2.0** In addition to the 911 emergency telephone number for ambulance, fire or law enforcement services, the following agencies may also be notified for accident or emergency situation within the project limits.

Missouri Highway Patrol, Troop D	(417) 895-6868
Sac-Osage Fire Protection	(417) 646-2565
Sac-Osage Ambulance Service	(417) 646-8150
St. Clair County Sheriff	(417) 646-7704

**2.1** This list is not all inclusive. Notification of the need for wrecker or tow truck services will remain the responsibility of the appropriate law enforcement agency.

**2.2** The contractor shall notify law enforcement and emergency agencies before the start of construction to request their cooperation and to provide coordination of services when emergencies arise during the construction at the project site. When the contractor completes this notification with law enforcement and emergency agencies, a report shall be furnished to the engineer on the status of incident management.

**3.0** No direct pay will be made to the contractor to recover the cost of the communication equipment, labor, materials or time required to fulfill the above provisions.

F. Project Contact for Contractor/Bidder Questions JSP-96-05

All questions concerning this project during the bidding process shall be forwarded to the project contact listed below.

Shannon Kellner, Project Contact  
Southwest District  
3025 E Kearney St,  
Springfield, MO 65803

Telephone Number: 417-880-8046  
Email: [shannon.kellner@modot.mo.gov](mailto:shannon.kellner@modot.mo.gov)



All questions concerning the bid document preparation can be directed to the Central Office – Design at (573) 751-2876.

G. Contractor Quality Control NJSP-15-42

**1.0** The contractor shall perform Quality Control (QC) testing in accordance with the specifications and as specified herein. The contractor shall submit a Quality Control Plan (QC Plan) to the engineer for approval that includes all items listed in Section 2.0, prior to beginning work.

**2.0 Quality Control Plan.**

- (a) The name and contact information of the person in responsible charge of the QC testing.
- (b) A list of the QC technicians who will perform testing on the project, including the fields in which they are certified to perform testing.
- (c) A proposed independent third party testing firm for dispute resolution, including all contact information.
- (d) A list of Hold Points, when specified by the engineer.
- (e) The MoDOT Standard Inspection and Testing Plan (ITP). This shall be the version that is posted at the time of bid on the MoDOT website ([www.modot.org/quality](http://www.modot.org/quality)).

**3.0 Quality Control Testing and Reporting.** Testing shall be performed per the test method and frequency specified in the ITP. All personnel who perform sampling or testing shall be certified in the MoDOT Technician Certification Program for each test that they perform.

**3.1 Reporting of Test Results.** All QC test reports shall be submitted as soon as practical, but no later than the day following the test. Test data shall be immediately provided to the engineer upon request at any time, including prior to the submission of the test report. No payment will be made for the work performed until acceptable QC test results have been received by the engineer and confirmed by QA test results.

**3.1.1** Test results shall be reported on electronic forms provided by MoDOT. Forms and Contractor Reporting Excel2Oracle Reports (CRE2O) can be found on the MoDOT website. All required forms, reports and material certifications shall be uploaded to a Microsoft SharePoint® site provided by MoDOT, and organized in the file structure established by MoDOT.

**3.2 Non-Conformance Reporting.** A Non-Conformance Report (NCR) shall be submitted by the contractor when the contractor proposes to incorporate material into the work that does not meet the testing requirements or for any work that does not comply with the contract terms or specifications.

**3.2.1** Non-Conformance Reporting shall be submitted electronically on the Non-Conformance Report form provided on the MoDOT Website. The NCR shall be uploaded to the MoDOT SharePoint® site and an email notification sent to the engineer.

**3.2.2** The contractor shall propose a resolution to the non-conforming material or work. Acceptance of a resolution by the engineer is required before closure of the non-conformance report.

**4.0 Work Planning and Scheduling.**

**4.1 Two-week Schedule.** Each week, the contractor shall submit to the engineer a schedule that outlines the planned project activities for the following two-week period. The two-week schedule shall detail all work and traffic control events planned for that period and any Hold Points specified by the engineer.

**4.2 Weekly Meeting.** When work is active, the contractor shall hold a weekly project meeting with the engineer to review the planned activities for the following week and to resolve any outstanding issues. Attendees shall include the engineer, the contractor superintendent or project manager and any foreman leading major activities. This meeting may be waived when, in the opinion of the engineer, a meeting is not necessary. Attendees may join the meeting in person, by phone or video conference.

**4.3 Pre-Activity Meeting.** A pre-activity meeting is required in advance of the start of each new activity, except when waived by the engineer. The purpose of this meeting is to review construction details of the new activity. At a minimum, the discussion topics shall include: safety precautions, QC testing, traffic impacts, and any required Hold Points. Attendees shall include the engineer, the contractor superintendent and the foreman who will be leading the new activity. Pre-activity meetings may be held in conjunction with the weekly project meeting.

**4.4 Hold Points.** Hold Points are events that require approval by the engineer prior to continuation of work. Hold Points occur at definable stages of work when, in the opinion of the engineer, a review of the preceding work is necessary before continuation to the next stage.

**4.4.1** A list of typical Hold Point events is available on the MoDOT website. Use of the Hold Point process will only be required for the project-specific list of Hold Points, if any, that the engineer submits to the contractor in advance of the work. The engineer may make changes to the Hold Point list at any time.

**4.4.2** Prior to all Hold Point inspections, the contractor shall verify the work has been completed in accordance with the contract and specifications. If the engineer identifies any corrective actions needed during a Hold Point inspection, the corrections shall be completed prior to continuing work. The engineer may require a new Hold Point to be scheduled if the corrections require a follow-up inspection. Re-scheduling of Hold Points require a minimum 24-hour advance notification from the contractor unless otherwise allowed by the engineer.

**5.0 Quality Assurance Testing and Inspection.** MoDOT will perform quality assurance testing and inspection of the work, except as specified herein. The contractor shall utilize the inspection checklists provided in the ITP as a guide to minimize findings by MoDOT inspection staff. Submittal of completed checklists is not required, except as specified in 5.1.

**5.1** Inspection and testing required in the production of concrete for the project shall be the responsibility of the contractor. Submittal of the 501 Concrete Plant Checklist is required.

**6.0 Basis of Payment.** No direct payment will be made for compliance with this provision.

H. Removal and Delivery of Existing Signs JSP-12-01B

**1.0 Description.** All Commission-owned signs removed from the project shall remain the property of the Commission and shall be disassembled and delivered as specified herein.

**2.0 Disassembly and Delivery.** All Commission-owned signs, not to include abandoned billboard signs, designated for removal in the plans, and any other signs designated by the engineer, shall be removed by the contractor and delivered to the address below. The contractor shall call the phone number listed below 48 hours prior to delivery and make arrangements for delivery during normal business hours.

MoDOT-Osceola Maintenance  
5371 NE Bus. Hwy. 82  
Osceola, Mo 64776  
Phone: (417) 621-6525

**2.1** Signs shall be removed from sign supports and structures prior to delivery. Sign supports and structures shall become the property of the Contractor and removed from the project. Any oversized sign panels shall be disassembled or cut into widths of 8-feet or less with no restriction on length. Signs shall be stacked neatly in bins provided by MoDOT at the delivery site.

**3.0 Basis of Payment.** All costs associated with removing, disassembling, storing, and transporting of signs shall be considered as completely covered by the contract unit price for Item No. 202-20.10, "Removal of Improvements", per lump sum.

I. Recycled Concrete Materials

**1.0 Description.** The Contractor will have the option of placing concrete rubble from the existing bridge on top of the existing rock blanket. This work shall be in accordance with Sec 611.30 and any portion incorporated into the rock blanket shall conform to the plan dimensions for Type 2 rock blanket. All concrete pieces shall be free of exposed rebar. Any bridge deck rubble determined by the engineer to be excess shall become the property of the contractor and disposed of properly. Placement and specifications shall be as approved by the engineer.

**2.0 Restrictions.** The contractor shall not place rubblized bridge deck below elevation 742'. Any work below elevation 742' requires approval from USACE Regulatory Office, 573-634-2248 or email at [regulatory.missouristate@usace.army.mil](mailto:regulatory.missouristate@usace.army.mil).

**3.0 Basis of Payment.** Payment for this work will be made based on the plan quantities under Placing Rubblized Bridge Deck, 609-99.01, Lump Sum. No direct payment will be made to the contractor to recover the cost of equipment, labor, material or time required to crush concrete deck rubble to a size that satisfies Sec 611.30.

J. Slurry and Residue Produced During Surface Treatment of PCCP and Bridge Decks  
JSP-06-05

**1.0 Description.** This work covers the requirements for controlling residue or slurry produced by milling, grinding, planing, grooving or other methods of surface treatments on new or existing PCCP and bridge decks in addition to Section 622.

**2.0 Construction Requirements.** The following shall be considered the minimum requirements for performing this work within the project limits.

**2.1** The contractor shall submit to the Engineer for approval in writing prior to the pre-construction meeting, the best management practices (BMP's) to be used to protect the environment, including the method of disposal of the residue whether on right of way or off-site.

**2.2** Prior to starting work, slurry or residue "no discharge zones" will be identified by the Engineer with respect to the contractor's approved BMP and residue disposal plan.

**2.3** Operations may be suspended by the Engineer during periods of rainfall or during freezing temperatures.

**2.4** When slurry is dispersed on the right of way, BMP's shall be installed to keep slurry residue from entering drainage structures, from entering any waterways and from leaving the right of way.

**3.0 Basis of Payment.** No direct payment for slurry or residue control requirements for BMP's will be made. Compliance with this specification along with the cost of all materials, labor and equipment necessary for the surface treatment work shall be included in and completely covered by the unit price bid for each of the items of work for surface treatment included in contract.

K. Removal of Bridge Debris

**1.1 Description.** The contractor shall prevent any debris and materials from falling into the creek, stream, lake, or wetland below the bridge.

**1.1** The contractor shall make provisions to prevent debris and materials from falling below the bridge. If any debris or material from contractor operations falls into the river, stream, lake, or wetland it shall be removed as directed by the engineer at the contractor's expense.

**1.2** All material removed from the existing structure shall be disposed of by the contractor in accordance with Sec 202.

**1.3** Any damage sustained to the remaining structure as a result of the contractor's operations shall be repaired or the material replaced as determined by the engineer at the contractor's expense.

**2.0 Basis of Payment.** No direct payment will be made for any expense incurred by the contractor by reason of compliance with the specific requirements of this provision, including any delay, inconvenience, or extra work except for those items for which payment is included in the contract.

L. Restrictions for Migratory Birds NJSP-16-06A

**1.0 Description.** Swallows or other bird species protected by the Migratory Bird Treaty Act may be nesting under the bridge or bridges that will be repaired under this contract.

**2.0 Restrictions.** To comply with the Migratory Bird Treaty Act, nests of protected species cannot be disturbed when active (eggs or young are present). Generally, nests are active between April 1 and July 31, but active nests can be present outside of these dates.

**2.1 MoDOT to Maintain Prior to the Notice to Proceed.** The bridge, or bridges, associated with the work for this contract have been evaluated and any inactive nests found have been removed by MoDOT staff. MoDOT staff will maintain the structures to be free of nests until the Notice to Proceed date. At the notice to proceed, the contractor shall be responsible to maintain the structures to be free of nests until the work on the applicable bridge, or bridges, is complete.

**3.0 Avoidance Measures.** The contractor shall not disturb active nests or destroy adults, eggs or young birds. In an effort to comply with the Migratory Bird Treaty Act, the contractor operations will be limited to the options established in the following sections.

**3.1 Inactive or Partially Constructed Nests.** If nests are present and MoDOT determines that the nests are inactive or partially constructed, the contractor may remove the nests provided that the colony's inactive or partially constructed nests are completely removed by March 15 and the contractor maintains a nest free condition until the bridge work is complete. Dry removal methods shall be used when practicable. If dry removal is not practicable, hydro cleaning may be used if approved by the Engineer and only if water is free of blasting grit, chemicals, or detergents, and applied using pressure less than 5,000 PSI. Clean water such as that from municipal water treatment plants or wells shall be used. Use of source water from Waters of the State (i.e., streams or lakes), is allowable, if the appropriate methods to prevent the possible spread of invasive aquatic species are implemented.

**3.2 Water and Equipment Used for Hydro cleaning.** Aquatic invasives such as zebra mussels and some algae species have infested several bodies of water in the United States and can be transported by vessels (barges, boats, tugs, tankers, etc.) and equipment (tanks, tubing, pumps, etc.) that have been used in areas that contain these invasive species. If equipment is not properly inspected and treated to prevent the spread of invasives, these species can be introduced into areas not currently known to have a population. These invasive species are detrimental to existing ecosystems and can outcompete native species. To assist in preventing the introduction and spread of aquatic invasive species through MoDOT projects in Missouri streams and lakes, the following precautions shall be followed.

**3.2.1 Use of Water from Streams, Lakes or Ponds.** Contractors shall not use water for nest removal from streams, lakes or ponds, unless they have implemented appropriate methods to prevent the possible spread of invasive aquatic species. Water sources from municipal water treatment plants or wells may be used without following these measures provided the equipment to be used has not previously contained waters from streams, lakes or ponds. If the equipment has previously contained waters from other streams or lakes, the following measures must be implemented prior to use.

**3.2.1.1 Equipment Washing.** Prior to the use or re-use of equipment following any use with water from streams, lakes or ponds, all equipment shall be washed and rinsed thoroughly with hard spray (power wash) and hot (minimum 120° F) water, for at least one minute.

**3.2.1.2 Equipment Treating or Drying.** Equipment shall be treated or dried in one of the following manners.

**3.2.1.2.1** Equipment interior and/or other surfaces shall be treated with a 10% bleach solution to kill any aquatic nuisance species. This solution must also be run through all intake lines and hoses, to sterilize interior components. When chlorine treatment is used, all chlorine runoff from equipment washing must be collected and properly treated and/or disposed of in accordance with Sec 806.

**3.2.1.2.2** Equipment interior and/or other surfaces shall be treated with 140° F water for a minimum of 10 seconds contact on all surfaces. 140 ° F water must also be run through all intake lines and hoses, to purge any standing water.

**3.2.1.2.3** Equipment shall be flushed of all non-municipal water, and dried thoroughly, in the sun before using in or transporting between streams and lakes. Dry times will depend on the season the equipment is being used. Equipment must dry a minimum of 7 days for June-September, 18 days for March-May; 18 days for October-November, and 30 days for December-February. The drying method should be reserved as a last resort option.

**3.2.2** Prior to use of equipment, contractors shall provide the MoDOT inspector written documentation of the equipment's geographic origin (including the water body it was last used in), as well as defining the specified treatment method used to adequately ensure protection against invasive species. The written documentation will include a statement indicating the contractor is aware of these provisions and will also treat the equipment appropriately after completion of the project.

**3.3 Active Nests.** The contractor may work on the bridge if active nests are present, as long as the work does not impact or disturb the birds and/or nests. At a minimum, work shall not be performed within 10 feet of an active nest; however, the contractor is responsible for ensuring their activities do not impact the nests, eggs, or young.

**4.0 Additional Responsibilities.** If active bird nests remain after all reasonable avoidance measures have been taken, or if bird nests are observed during project construction, the contractor shall notify the Resident Engineer and contact the MoDOT Environmental Section (573-526-4778) to determine if there are other allowable options.

M. Adjusting Guardrail

**1.0 Description.** This work shall consist of all labor, equipment, and materials to remove, reuse, and reinstall guardrail, and any related appurtenances as shown on the plans or as approved by the engineer.

**1.1** The Contractor will be responsible for the proper storage of guardrail sections that have been removed. Any guardrail or related appurtenances that are damaged by the contractor will be replaced at the Contractor's expense.

**1.2** All work shall comply with Sections 202 and 606 except as herein modified.

**1.3 Alternative Methods.** The contractor may propose an alternate method for adjusting or retrofitting the guardrail height to the engineer for approval. Any proposed alternative guardrail retrofitting system or adjustment method must meet MASH requirements. The lifting of the guardrail posts to the proposed height will not be an allowed alternative.

**2.0 Materials.** All guardrail materials shall conform to Division 1000, Materials Details, and specifically Sec 1040.

**2.1** Replacement materials and components shall conform to the manufacturers latest approved design. All replacement components shall be from the original equipment manufacturer or an approved equal.

**3.0 Construction Requirements.** The plans specify locations where guardrail shall be removed and re-installed to meet the Standards in lieu of replacement. The contractor shall reuse and reinstall the guardrail as shown on the plans as approved by the engineer. All reused sections of guardrail shall be installed in accordance with the applicable portions of the Specifications and Standard Drawings. Existing guardrail shall be adjusted to 29 inches (+0 inches, -1 1/4 inches) measured from a horizontal line extended from the edge of shoulder to the top of the rail. Adjusted guardrail shall not be raised more than 3 inches from its original height. The minimum height of adjusted guardrail shall be 27 3/4 inches as measured to the top of rail.

**3.1** Sections of guardrail identified on the plans may be adjusted vertically up to a 3 inch maximum to conform to height standards. Existing posts shall be drilled or punched with a 13/16 inch hole in order to adjust the guardrail vertically to meet height requirements. The galvanized coating of field drilled or punched posts shall be repaired in accordance with Section 1081.

**3.2** Any non-standard blocks shall be replaced with new blocks. Existing blocks that meet MoDOT specifications and are in satisfactory condition may be reused as approved by the engineer.

#### **4.0 Basis of Payment.**

**4.1** The accepted quantities for adjusting guardrail, and/or transition sections, complete in place, will be paid for at the contract unit price for:

Item 606-99.03	Adjusting Guardrail	Linear Feet
----------------	---------------------	-------------

**4.1.1** No direct payment will be made for new guardrail delineators provided on existing guardrail.

**4.1.2** No direct payment will be made for new blocks on existing guardrail.

**4.2** Payment will be considered full compensation for all labor, equipment, and material necessary to adjust guardrail to meet Standard height requirements.

N. Liquidated Damages Specified JSP-93-28

**1.0 Description.** To ensure public safety during bridge construction, Sac River/Truman Lake traffic directly under Bridge A3905 will need to be restricted. The contractor will be allowed to close this area to river traffic for no more than 80 calendar days. If Sac River/Truman Lake directly under Bridge A3905 cannot be safely reopened to river traffic within 80 calendar days from its closure to traffic, the Commission, the traveling public, and state and local police and governmental authorities will be damaged in various ways, including but not limited to, increased construction administration cost, potential liability, traffic and traffic flow regulation cost, traffic congestion and motorist delay, with its resulting cost to the traveling public. These damages are not reasonably capable of being computed or quantified. Therefore, the contractor will be charged with liquidated damages specified in the amount of \$1,800 per day for each full day that Sac River/Truman Lake directly under Bridge A3905 is not safely reopened to river traffic in excess of the limitation as specified elsewhere in this special provision. It shall be the responsibility of the engineer to determine the quantity of excess closure time.

**1.1** The said liquidated damages specified will be assessed regardless of whether it would otherwise be charged as liquidated damages under the Missouri Standard Specification for Highway Construction, as amended elsewhere in this contract.

O. Supplemental Revisions JSP-18-01X

Compliance with [2 CFR 200.216 – Prohibition on Certain Telecommunications and Video Surveillance Services or Equipment](#).

The Missouri Highways and Transportation Commission shall not enter into a contract (or extend or renew a contract) using federal funds to procure or obtain equipment, services, or systems that uses covered telecommunications equipment or services as substantial or as critical technology as part of any system where the video surveillance and telecommunications equipment was produced by Huawei Technologies Company, ZTE Corporation, Hytera Communications Corporation, Hangzhou Hikvision Digital Technology Company, or Dahua Technology Company (or any subsidiary or affiliate of such entities).

Stormwater Compliance Requirements

**1.0 Description.** This provision requires the contractor to provide a Water Pollution Control Manager (WPCM) for any project that includes land disturbance on the project site and the total area of land disturbance, both on the project site, and all Off-site support areas, is one (1) acre or more. Regardless of the area of Off-site disturbance, if no land disturbance occurs on the project site, these provisions do not apply. When a WPCM is required, all sections within this provision shall be applicable, including assessment of specified Liquidated Damages for failure to correct Stormwater Deficiencies, as specified herein. This provision is in addition to any other stormwater, environmental, and land disturbance requirements specified elsewhere in the contract.



**1.1 Definitions.** The project site is defined as all areas designated on the plans, including temporary and permanent easements. The project site is equivalent to the “permitted site”, as defined in MoDOT’s State Operating Permit. An Off-site area is defined as any location off the project site the contractor utilizes for a dedicated project support function, such as, but not limited to, staging area, plant site, borrow area, or waste area.

**1.2 Reporting of Off-Site Land Disturbance.** If the project includes any planned land disturbance on the project site, prior to the start of work, the contractor shall submit a written report to the engineer that discloses all Off-site support areas where land disturbance is planned, the total acreage of anticipated land disturbance on those sites, and the land disturbance permit number(s). Upon request by the engineer, the contractor shall submit a copy of its land disturbance permit(s) for Off-site locations. Based on the total acreage of land disturbance, both on and Off-site, the engineer shall determine if these Stormwater Compliance Requirements shall apply. The Contractor shall immediately report any changes to the planned area of Off-site land disturbance. The Contractor is responsible for obtaining its own separate land disturbance permit for Off-site areas.

**2.0 Water Pollution Control Manager (WPCM).** The Contractor shall designate a competent person to serve as the Water Pollution Control Manager (WPCM) for projects meeting the description in Section 1.0. The Contractor shall ensure the WPCM completes all duties listed in Section 2.1.

**2.1 Duties of the WPCM:**

- (a) Be familiar with the stormwater requirements including the current MoDOT State Operating Permit for construction stormwater discharges/land disturbance activities; MoDOT’s statewide Stormwater Pollution Prevention Plan ( SWPPP); the Corps of Engineers Section 404 Permit, when applicable; the project specific SWPPP, the Project’s Erosion & Sediment Control Plan; all applicable special provisions, specifications, and standard drawings; and this provision;
- (b) Successfully complete the MoDOT Stormwater Training Course within the last 4 years. The MoDOT Stormwater Training is a free online course available at MoDOT.org;
- (c) Attend the Pre-Activity Meeting for Grading and Land Disturbance and all subsequent Weekly Meetings in which grading activities are discussed;
- (d) Oversee and ensure all work is performed in accordance with the Project-specific SWPPP and all updates thereto, or as designated by the Engineer;
- (e) Review the project site for compliance with the Project SWPPP, as needed, from the start of any grading operations until final stabilization is achieved, and take necessary actions to correct any known deficiencies to prevent pollution of the waters of the state or adjacent property owners prior to the engineer’s weekly inspections;
- (f) Review and acknowledge receipt of each MoDOT Inspection Report (Land Disturbance Inspection Record) for the Project within forty eight (48) hours of receiving the report and ensure that all Stormwater Deficiencies noted on the report are corrected as soon as possible, but no later than stated in Section 5.0.

**3.0 Pre-Activity Meeting for Grading/Land Disturbance and Required Hold Point.** A Pre-Activity meeting for grading/land disturbance shall be held prior to the start of any land disturbance operations. No land disturbance operations shall commence prior to the Pre-Activity meeting except work necessary to install perimeter controls and entrances. Discussion items at the pre-activity meeting shall include a review of the Project SWPPP, the planned order of grading operations, proposed areas of initial disturbance, identification of all necessary BMPs that shall be installed prior to commencement of grading operations, and any issues relating to compliance with the Stormwater requirements that could arise in the course of construction activity at the project.

**3.1 Hold Point.** Following the pre-activity meeting for grading/land disturbance and subsequent installation of the initial BMPs identified at the pre-activity meeting, a Hold Point shall occur prior to the start of any land disturbance operations to allow the engineer and WPCM the time needed to perform an on-site review of the installation of the BMPs to ensure compliance with the SWPPP is met. Land disturbance operations shall not begin until authorization is given by the engineer.

**4.0 Inspection Reports.** Weekly and post run-off inspections will be performed by the engineer and each Inspection Report (Land Disturbance Inspection Record) will be entered into a web-based Stormwater Compliance database. The WPCM will be granted access to this database and shall promptly review all reports, including any noted deficiencies, and shall acknowledge receipt of the report as required in Section 2.1 (f.).

**5.0 Stormwater Deficiency Corrections.** All stormwater deficiencies identified in the Inspection Report shall be corrected by the contractor within 7 days of the inspection date or any extended period granted by the engineer when weather or field conditions prohibit the corrective work. If the contractor does not initiate corrective measures within 5 calendar days of the inspection date or any extended period granted by the engineer, all work shall cease on the project except for work to correct these deficiencies, unless otherwise allowed by the engineer. All impact costs related to this halting of work, including, but not limited to stand-by time for equipment, shall be borne by the Contractor. Work shall not resume until the engineer approves the corrective work.

**5.1 Liquidated Damages.** If the Contractor fails to complete the correction of all Stormwater Deficiencies listed on the MoDOT Inspection Report within the specified time limit, the Commission will be damaged in various ways, including but not limited to, potential liability, required mitigation, environmental clean-up, fines and penalties. These damages are not reasonably capable of being computed or quantified. Therefore, the contractor will be charged with liquidated damages specified in the amount of \$2,000 per day for failure to correct one or more of the Stormwater Deficiencies listed on the Inspection Report within the specified time limit. In addition to the stipulated damages, the stoppage of work shall remain in effect until all corrections are complete.

**6.0 Basis of Payment.** No direct payment will be made for compliance with this provision.

#### Anti-Discrimination Against Israel Certification

By signing this contract, the Company certifies it is not currently engaged in and shall not, for the duration of the contract, engage in a boycott of goods or services from the State of Israel, companies doing business in or with Israel or authorized by, licensed by, or organized under the

laws of the State of Israel, or persons or entities doing business in the State of Israel as defined by Section 34.600 RSMo. This certification shall not apply to contracts with a total potential value of less than One Hundred Thousand Dollars (\$100,000) or to contractors with fewer than ten (10) employees.

## Ground Tire Rubber (GTR) Dry Process Modification of Bituminous Pavement Material

**1.0 Description.** This work shall consist of the dry process of adding ground tire rubber (GTR) to modify bituminous material to be used in highway construction. Existing GTR requirements in Section 1015 pertain to the wet process method of GTR modification that blends GTR with the asphalt binder (terminal blending or blending at HMA plant). The following requirements shall govern for dry process GTR modification. The dry process method adds GTR as a fine aggregate or mineral filler during mix production. All GTR modified asphalt mixtures shall be in accordance with Secs 401, 402, or 403 as specified in the contract; except as revised by this specification.

**2.0 Materials.** The contractor shall furnish a manufacturer's certification to the engineer for each shipment of GTR furnished stating the name of the manufacturer, the chemical composition, workability additives, and certifying that the GTR supplied is in accordance with this specification.

**2.1 Product Approval.** The GTR product shall contain a Trans-Polyoctenamer (TOR) added at 4.5 % of the weight of the crumb rubber or an engineered crumb rubber (ECR) workability additive that has proven performance in Missouri. Other GTR additives shall be demonstrated and proven prior to use such as a five-year field performance history in other states or performance on a federal or state-sanctioned accelerated loading facility.

**2.2 General.** GTR shall be produced from processing automobile or truck tires by ambient or cryogenic grinding methods. Heavy equipment tires, uncured or de-vulcanized rubber will not be permitted. GTR shall also meet the following material requirements:

Table 1 – GTR Material Properties		
Property	Test Method	Criteria
Specific Gravity	ASTM D1817	1.02 to 1.20
Metal Contaminates	ASTM D5603	≤ 0.01%
Fiber Content	ASTM D5603	≤ 0.5%
Moisture Content	ASTM D1509	≤ 1.0%*
Mineral Filler	AASHTO M17	≤ 4.0%

\*Moisture content of the GTR shall not cause foaming when combined with asphalt binder and aggregate during mix production

**2.3 Gradation.** The GTR material prior to TOR or ECR workability additives shall meet the following gradation and shall be tested in accordance with ASTM D5603 and ASTM D5644.

Table 2 – GTR Gradation	
Sieve	Percent Passing by Weight
No. 20	100
No. 30	98-100
No. 40	50-70
No. 100	5-15

**3.0 Delivery, Storage, and Handling.** The GTR shall be supplied in moisture-proof packaging or other appropriate bulk containers. GTR shall be stored in a dry location protected from rain before use. Each bag or container shall be properly labeled with the manufacturer's designation for the GTR and specific type, mesh size, weight and manufacturer's batch or Lot designation.

**4.0 Feeder System.** Dry Process GTR shall be controlled with a feeder system using a proportioning device that is accurate to within  $\pm 3$  percent of the amount required. The system shall automatically adjust the feed rate to always maintain the material within this tolerance and shall have a convenient and accurate means of calibration. The system shall provide in-process monitoring, consisting of either a digital display of output or a printout of feed rate, in pounds per minute, to verify feed rate. The supply system shall report the feed in 1-pound increments using load cells that will enable the user to monitor the depletion of the GTR. Monitoring the system volumetrically will not be allowed. The feeder shall interlock with the aggregate weight system and asphalt binder pump to maintain correct mixture proportions at all production rates.

Flow indicators or sensing devices for the system shall be interlocked with the plant controls to interrupt mixture production if GTR introduction rate is not within  $\pm 3$  percent. This interlock will immediately notify the operator if GTR introduction rate exceeds introduction tolerances. All plant production will cease if the introduction rate is not brought back within tolerance after 30 seconds. When the interlock system interrupts production and the plant has to be restarted, upon restarting operations; the modifier system shall run until a uniform feed can be observed on the output display. All mix produced prior to obtaining a uniform feed shall be rejected.

**4.1 Batch Plants.** GTR shall be added to aggregate in the weigh hopper. Mixing times shall be increased per GTR manufacturer recommendations

**4.2 Drum Plants.** The feeder system shall add GTR to aggregate and liquid binder during mixing and provide sufficient mixing time to produce a uniform mixture. The feeder system shall ensure GTR does not become entrained in the exhaust system of the drier or plant and is not exposed to the drier flame at any point after introduction.

**5.0 Testing During Mixture Production.** Testing of asphalt mixes containing GTR shall not begin until at least 30 minutes after production or per additive supplier's recommendation.

**6.0 Construction Requirements.** Mixes containing GTR shall have a target mixing temperature of 325 F or as directed by the GTR additive supplier. The additive supplier's recommendations shall be followed to allow for GTR binder absorption/reaction. This may include holding mix in the silo to allow time for binder to absorb into the GTR. Rolling operations may need to be modified.

**7.0 Mix Design Test Method Modification.** A formal mixing procedure from the additive supplier shall be provided to the contractor and engineer that details the proper sample preparation, including blending GTR with the binder or other additives. Samples shall be

prepared and fabricated in accordance with this procedure by the engineer and contractor throughout the duration of the project.

**8.0 Mix design Volumetrics.** Mix design volumetric equations shall be modified as follows:

**8.1** Additional virgin binder added to offset GTR absorption of binder shall be counted as part of the mix virgin binder

**8.2** GTR shall be included as part of the aggregate when calculating VMA of the mix.

**8.2.1** GTR SPG shall be 1.15

**8.3** VMA shall be calculated as follows:

$$VMA = 100 - G_{mb} \left( \frac{P_s}{G_{sb}} + \frac{P_{GTR}}{G_{GTR}} \right)$$

where:

$P_s$  = percent aggregate by total mixture weight

$P_{GTR}$  = percent GTR by total mixture weight

$G_{sb}$  = bulk specific gravity of the combined aggregate

$G_{GTR}$  = GTR specific gravity

**8.4**  $G_{se}$  shall be calculated as follows:

$$G_{se} = \frac{(100 - P_b - P_{GTR})}{\left( \frac{100}{G_{mm}} - \frac{P_b}{G_b} - \frac{P_{GTR}}{G_{GTR}} \right)}$$

**8.5**  $P_{be}$  shall be calculated as follows:

$$P_{be} = P_b - \frac{P_{ba}}{100} * (P_s + P_{GTR})$$

**9.0 Minimum GTR Amount.** The minimum dosage rate for GTR shall be 5 % by weight of total binder for an acceptable one bump grade or 10 % by weight of total binder for an acceptable two bump grade as detailed in the following table. Varying percentage blends of GTR and approved additives may be used as approved by the engineer with proven performance and meeting the specified requirements of the contract grade.

Contract Binder Grade	Percent Effective Virgin Binder Replacement Limits	Required Virgin Binder Grade	Minimum GTR Dosage Rate
PG 76-22	0 - 20	PG 70-22	5 %
		PG 64-22	10 %
PG 70-22	0 - 30	PG 64-22	5 %
		PG 58-28	10 %
PG 64-22	0 – 40*	PG 58-28	5 %
		PG 52-34	10 %
PG 58-28	0 – 40*	PG 52-34	5 %

		PG 46-34	10 %
--	--	----------	------

\* Reclaimed Asphalt Shingles (RAS) may be used when the contract grade is PG 64-22 or PG 58-28. RAS replacement shall follow the 2 x RAS criteria when calculating percent effective binder replacement in accordance Sec 401.

***Delete Sec 107 in its entirety and substitute the following:***

**107.1 Laws to be Observed** The contractor shall know, observe and comply with all federal and state laws, local laws, codes, ordinances, orders, decrees and regulations existing at the time of or enacted subsequent to the execution of the contract that in any manner affect the prosecution of the work, except as specified in the contract or as directed by the engineer. The Contractor shall also ensure that any subcontractor know, observe and comply with all federal and state laws, local laws, codes, ordinances, orders, decrees and regulations as outlined above. The contractor and surety shall indemnify and save harmless the State, the Commission, the Commission's agents, employees and assigns from any claim or liability arising from or based on the violation of any such law, code, ordinance, regulation, order or decree, except any local regulations, decrees, orders, codes or ordinances directed by the contract.

**107.1.1 Contract and Legal Inconsistency** The engineer shall be notified immediately in writing if any discrepancy or inconsistency is discovered between the contract and any law, ordinance, regulation, order or decree.

**107.1.2 Local Building and Zoning Codes or Ordinances** The projects of the Commission are not typically subject to local building or zoning codes or ordinances. Therefore, the contractor usually need not obtain a local building or zoning permit or variance for work done exclusively as the Commission's contractor on the Commission's project and the Commission's right of way. Other local codes or ordinances may not apply to the Commission, and thus to the contractor as well. If any questions arise concerning whether the contractor shall comply with a local code, ordinance, decree or order of any type, the contractor shall advise the engineer of the problem immediately, for resolution by the engineer. This provision will not exempt the contractor from the requirement of thoroughly researching and determining, before submitting a bid on the contract and from complying with, all federal, state or local laws, regulations, codes, ordinances, decrees or orders that may apply to the contract work. The Commission will not be responsible for the contractor's failure to be informed before bidding as to the federal, state and local laws, regulations, codes, ordinances, decrees or orders that may govern the contract work, or for the contractor's failure to determine before bidding which of these do not govern the contract work.

**107.1.3 Authentication of Certain Documents** If plans, plats, detailed drawings or specifications for falsework, cofferdams or any other work are required to be submitted to the engineer, the documents shall be signed, sealed and stamped in accordance with the laws relating to the practice of architecture and professional engineering in the State of Missouri (Chapter 327, RSMo).

**107.2 Permits, Licenses and Taxes** Except as otherwise provided in the contract, the contractor shall procure all permits and licenses, shall pay all charges, fees and taxes, and shall give all notices necessary and incidental to the due and lawful prosecution of the work. No direct payment will be made for the cost of complying with this requirement.

**107.3 Patented or Copyrighted Devices, Material and Processes.** If the contractor is required or desires to use any design, device, material or process covered by letters, patent, copyright, service or trademark, the contractor shall arrange and provide for such use by suitable agreement with the patentee or owner, and a copy of the agreement may be required by the Commission. The contractor and surety shall indemnify and save harmless the State, the Commission, the Commission's agents, employees and assigns from any suits, claims or damages arising from the infringement upon or use of any patented, copyrighted or registered design, device, material, process or mark.

**107.4 Safety and Sanitary Provisions** The contractor shall at all times take necessary precautions to protect the life and health of all persons employed on the project or, who at the direction of the contractor are present on the right of way. The contractor shall be familiar with the latest accepted accident prevention methods and shall provide necessary safety devices and safeguards accordingly. The Commission will refuse to provide inspection services at plants or work sites where adequate safety measures are not provided and maintained.

**107.4.1 Apparel.** All workers within highway right of way shall wear approved ANSI/ISEA 107 Performance Class 2 or 3 safety apparel and more specifically as follows:

**107.4.1.1** During daytime activities, flaggers shall wear a high visibility hard hat, safety glasses, a Performance Class 3 top OR a Performance Class 2 top, and safety footwear. Hard hats other than high visibility orange or green shall be covered with a high visibility covering.

**107.4.1.2** During daytime activities, workers shall wear a hard hat, safety glasses, a Performance Class 3 top OR a Performance Class 2 top, and safety footwear.

**107.4.1.3** During nighttime activities, flaggers shall wear a high visibility/reflective hard hat, safety glasses, a Performance Class 3 top AND Class E bottoms, OR Performance Class 2 top AND Class E bottoms, and safety footwear. Hard hats shall be reflective or covered with a high visibility covering.

**107.4.1.4** During nighttime activities, workers shall wear a hard hat, safety glasses, a Performance Class 3 top OR Performance Class 2 top AND Class E bottoms, and safety footwear.

**107.4.2** The contractor shall provide and maintain in a neat and sanitary condition, such accommodations for the use of employees as may be necessary to comply with the requirements and regulations of any agency having jurisdiction over public health and sanitation. The contractor shall permit no public or private nuisance.

**107.4.3** All sanitary facilities and safety devices shall be furnished free to employees and no direct payment will be made for such facilities or devices.

**107.5 Public Convenience and Safety** The contractor shall conduct the work in a manner that will ensure, as far as practical, the least obstruction to traffic and shall provide for the convenience and safety of the general public and residents along and adjacent to the highway in an adequate and satisfactory manner.

**107.5.1 Obstructions Prohibited** Fire hydrants on and adjacent to the highway shall be kept accessible to firefighting apparatus at all times, and no obstruction shall be placed within 15 feet of any such hydrant. Footways, gutters, sewers, outlets, inlets and portions of highways

adjoining the work under construction shall not be obstructed. Pavements over which hauling is performed shall be kept clean of spilled or tracked-on material at all times when in use by traffic.

**107.5.2 Objects Potentially Affecting Navigable Airspace.** The contractor shall comply with all federal regulations pertaining to constructing, erecting or installing any object, temporary or permanent, which could potentially affect navigable airspace.

**107.5.3 Material and Equipment.** During construction hours, equipment, material and vehicles utilized in construction of the project will only be permitted on shoulders, medians or pavements where the locations are closed to traffic, properly signed and occupied by ongoing construction operations, unless otherwise approved by the engineer. Except in cases of emergency, construction equipment, material and vehicles will not be permitted on pavements or shoulders being utilized by traffic. If the contract specifies time periods the contractor will not be permitted to perform work, construction equipment or vehicles shall not enter or leave the construction area via the pavements handling traffic nor be operated on the pavements handling traffic within the construction area during the restricted time periods. During non-construction hours, construction equipment, material and vehicles will not be permitted within 30 feet of the edge of the pavement or shoulders carrying traffic unless the equipment, material and vehicles are located in a properly protected area, an off-site storage area or as otherwise directed by the engineer.

**107.5.4 Distractions to the Traveling Public in Work Zones.** In order to avoid distracting operators of vehicles traveling on the roadway, the Contractor and its sub-contractors shall not bring or display any signs, flags, logos, emblems, advertising, or any other communicative device on construction equipment that is large enough to be legible from the main traveled way of the highway in the work zone or on highway right of way. This prohibition does not apply to any sign, logo or emblem placed on Contractor equipment identifying the owner or manufacturer of the equipment or to any official highway signs approved by the Commission pursuant to 227.220 RSMo.

**107.6 Bridges over Navigable Waters.** All work on navigable waters shall be conducted such that free navigation of the waterways will not be interfered with and that existing navigable depths will not be impaired except as allowed by permit issued by the USCG or the USACE.

**107.7 Use of Explosives.** All blasting operations shall be conducted under the direct supervision of a licensed blaster as required by the Missouri Blasting Safety Act. When explosives are used in the prosecution of the work, the contractor shall use the utmost care to prevent bodily injury and property damage. The contractor shall be responsible for damage resulting from the use of explosives. The engineer will have the authority to suspend any unsafe blasting operation. The contractor shall be familiar and comply with the rules and regulations of any city, county, state or federal agency or any other agency that may have jurisdiction in the handling, loading, transporting, storage and use of explosives. All places used for explosives storage shall be marked clearly "DANGEROUS EXPLOSIVES".

**107.7.1** Before beginning work, the contractor shall furnish the engineer letters of approval for the proposed operation from the appropriate regulating agencies. The contractor shall notify in writing the appropriate fire protection jurisdiction of the intent to store, transport or use explosives and shall provide proof of notice to the engineer. The contractor shall provide the engineer with copies of all permits, blasting logs and seismic monitoring data.



**107.7.2** The contractor shall notify in advance each property owner, tenant and public utility company having structures or facilities close to the work of any intention to use explosives.

**107.7.3** Removal of any item or material of any nature by blasting shall be done in such a manner and at such time as to avoid damage affecting the integrity of the design and to avoid damage to any new or existing structure, whether on Commission right of way or private property, included in or adjacent to the work. Unless the contract documents or the engineer restricts such operation, the contractor shall be responsible for determining a method of operation to ensure the desired results and the integrity of the completed work.

**107.7.4** The contractor and surety shall indemnify and save harmless the State, the Commission, the Commission's agents, employees and assigns from any claim related to the possession, transportation, storage or use of explosives.

#### **107.8 Preservation of Monuments and Artifacts.**

**107.8.1 Monuments.** The contractor shall not disturb or damage any land monument or property landmark unless authorized by the engineer.

**107.8.2 Human and Archaeological Remains.** The contractor shall report to the engineer the discovery of human remains, artifacts, fossils and other items of historical, archaeological or geological significance discovered within the right of way during construction. Such items will remain in the Commission's custody and shall not be removed from the site unless directed by the engineer. The preservation and handling of such items shall be in accordance with [Sec 203.4.8](#).

**107.9 Forest and Park Protection.** Environmental and sanitary laws and regulations regarding the performance of work within or adjacent to state or national forests or parks shall be obeyed. The contractor shall keep the project site in an orderly condition, dispose of all refuse, obtain permits for the construction and maintenance of all construction camps, stores, warehouses, residences, latrines, cesspools, septic tanks and other structures in accordance with the regulations and instructions issued by the forest or park supervisor. The contractor shall require employees and subcontractors, independently, and at the request of forest officials, to prevent and suppress forest fires, and to notify a forest official of the location and extent of any fire.

**107.10 Environmental Protection.** The contractor shall comply with all federal, state and local laws and regulations controlling pollution of the environment. Pollution of streams, lakes, ponds and reservoirs with fuels, oils, bitumens, chemicals or other harmful material and pollution of the atmosphere from particulate and gaseous matter shall be avoided.

**107.10.1** Fording of streams and fill for temporary work not specified on design plans will not be permitted unless the plan for such operation is authorized by the Corps of Engineers, meets the approval of the engineer, complies with the current MoDOT Pollution Plan and results in minimum siltation to the stream. Temporary stream crossings shall not be constructed unless specifically designated as a condition of the Corps of Engineers Section 404 permit or a permit is obtained, and the temporary stream crossing is in accordance with [Sec 806](#).

**107.10.2** When work areas or pits are located in or adjacent to streams, the areas shall be separated from the main stream by a dike or barrier to keep sediment from entering the stream.

Care shall be taken during the construction and removal of such barriers to minimize siltation of the stream.

**107.10.3** Disposal of Portland cement concrete residue and wash water, water from aggregate washing, or other operations producing sediment laden runoff shall be treated in accordance with Sec 806.

**107.10.4** Oil distributors or tanker trucks used for the transport or application of any petroleum-based products, and that have a capacity greater than 1,320 gallons, shall not be left unattended on MoDOT right of way within the project limits during non-construction hours unless secondary containment is deployed as per the Spill Prevention Control and Countermeasure rule. Parking of these vehicles on MoDOT right of way outside of the project limits, or on any MoDOT owned property, shall not be allowed without the aforementioned secondary containment and prior authorization from the engineer.

**107.11 Responsibility for Claims for Damage or Injury.** The contractor and insurance company shall indemnify and save harmless the State, the Commission, the Commission's agents, employees and assigns from all claims or suits made or brought for bodily injury, death or property damage, arising from performance of the work to the extent of:

(a) The negligent acts or omissions of the contractor, subcontractors, suppliers or their respective officers, agents or employees.

(b) The creation or maintenance of a dangerous condition of or on the Commission's property or right of way, which condition occurred due to the acts or omissions of the contractor, subcontractors, suppliers or their respective officers, agents or employees or for which the contractor had knowledge of or could have had knowledge of the condition in time to warn of or repair said condition.

(c) The failure of the contractor, subcontractors, suppliers or their respective officers, agents or employees, to perform the work in accordance with the plans and specifications.

**107.11.1** The contractor will not be required to defend, indemnify or hold harmless any other person, including the State, the Commission, or the Commission's agents, employees or assigns for any acts, omissions or negligence of other persons.

**107.11.2** Neither the Commission nor the contractor, by execution of a contract, shall intend to or create a new or enlarge an existing cause of action in any third party. This provision shall not be interpreted to create any new liability that does not exist under the law, or to waive or extinguish any defense that either party to this contract or their respective agents and employees may have to an action or suit by a third party.

**107.12 Contractor's Responsibility for Work** From the earlier of the date of commencement of the work or the effective date of the notice to proceed, and until any work is accepted by the engineer, the work shall be in the custody and under the charge and care of the contractor. Issuance of a payment estimate on any part of the work done will not be considered as final acceptance of any work completed up to that time.

**107.12.1** Damages to any portion of the work before the work is completed and accepted, caused by the action of the elements or from any other reason, shall be repaired or replaced at the contractor's expense. The contractor, at the contractor's option, may insure against any

such damages. The Commission may, in its discretion, make such a payment, determined in accordance with [Sec 109.4](#), for damage to the work due to unforeseeable causes beyond the control of, and without fault or negligence on the part of the contractor, unless the contractor has been reimbursed for such damages by the contractor's insurer. Prior to reimbursement, the contractor shall furnish documentary evidence of all efforts to recover such repair costs.

**107.12.2** The contractor shall immediately give written notice to the engineer of any pedestrian, worker and/or vehicular accident. The contractor may be directed by the engineer to repair permanent Commission facilities that have been damaged by events that are beyond the control of the contractor. Reimbursement will be provided by the Commission, determined in accordance with [Sec 109.4](#), for the actual direct cost of labor, equipment and material, exclusive of overhead, indirect or consequential costs of profit. The Commission may elect to make such repairs in lieu of the contractor.

**107.13 General Insurance Requirements.** The Contractor shall procure and maintain at the Contractor's expense until Final Acceptance of the project by the engineer, insurance for all damages and losses imposed by law and assumed under the contract, of the kinds and in the amounts specified in [Secs 107.13.1](#) through [107.13.8](#).

**107.13.1 Sovereign Immunity Limits for Missouri Public Entities.** The Contractor shall procure and maintain at least minimum insurance coverages to meet the sovereign immunity limits for Missouri public entities as calculated by the Missouri Department of Insurance and published annually in the Missouri Register pursuant to Section 537.610 RSMo., for [Secs 107.13.2](#) through [107.13.5](#), unless specified otherwise for each type of insurance coverage. Each policy shall provide additional insured status for the Missouri Highways and Transportation Commission (Commission), the Missouri Department of Transportation (MoDOT) and its employees up to Missouri's sovereign immunity limits.

**107.13.2 Commercial General Liability Insurance.** The Contractor shall procure, and maintain during the term of the project, commercial general liability insurance with coverage at least as broad as Insurance Services Office (ISO) policy form CG 00 01. The general aggregate limit shall, by endorsement or otherwise, provide a designated aggregate limit solely for this project using ISO form CG 25 03 05 09 or an equivalent form. General liability policies shall be endorsed to add the Commission, MoDOT, and its employees as additional insureds (the "Additional Insureds") using Insurance Services Office forms CG 20 10 or the equivalent under such policy. For construction contracts, an endorsement providing completed operations coverage to the Additional Insureds, ISO form CG 20 37 or the equivalent, is also required. This form, CG 20 37, shall be endorsed on each subsequent commercial general liability policy issued to the Contractor for three (3) years after final acceptance of the project. The contractor could provide extended completed operations for specific project needs. Discontinued operations coverage shall be provided for three (3) years when applicable. Coverage shall not be reduced by insured versus insured exclusions or by explosion, collapse and underground (XCU) exclusions.

**107.13.3 Commercial Automobile Liability Insurance.** The Contractor shall procure and maintain automobile liability coverage at least as broad as ISO policy form CA 00 01 covering owned, hired, and non-owned autos. The policy shall include as insureds anyone liable for the conduct of an insured as described by policy provision or by endorsement added to the policy.

**107.13.4 Contractor's Pollution Liability (CPL) Insurance.** The Contractor performing excavation, remediation, hazardous materials removal, or any other work involving potential

pollution arising from construction operations shall procure and maintain contractor's pollution liability insurance for liability arising out of sudden, accidental, and gradual pollution and remediation. The policy shall have minimum limits of \$1,000,000 and the Commission, MoDOT and its employees shall be endorsed as additional insureds under such policy. The policy shall provide coverage for the hauling of waste from the project site to the final disposal location, including non-owned disposal sites. Products/completed operations coverage for pollution liability insurance shall extend a minimum of three (3) years after final acceptance of the project. Coverage shall be included on behalf of the insured for covered claims arising out of the actions of independent contractors. If the insured is using subcontractors, the Policy must include work performed "by or on behalf" of the insured. Policy shall specifically provide for a duty to defend on the part of the insurer.

**107.13.5 Aircraft Liability Insurance.** If aircraft, including unmanned aircraft, will be used on the project, Contractor shall provide, or cause to be provided, aircraft liability insurance protecting against claims for damages resulting from such use in all cases where any aircraft that is owned, leased or chartered by any Contractor-Related Entity used on the Project. The policy shall have minimum limits of \$1,000,000 and the Commission, MoDOT and its employees shall be additional insureds on the policy by endorsement or policy provision. The use of any aircraft in performance of the Work, the aircraft crew, flight path and altitude, including landing of any aircraft on the Site or on any property owned by the Commission, MoDOT or other parties at interest, shall be subject to review and written acceptance by the Commission prior to any such usage. If any aircraft are leased or chartered with crew and/or pilot, evidence of non-owned aircraft liability insurance will be acceptable to meet these requirements but must be provided prior to use of the aircraft. For use of unmanned aircraft vehicles, the contractor may provide insurance either through an aircraft liability insurance policy, or by endorsement to the Contractor's commercial general liability insurance policy and excess liability policies. Use of unmanned aircraft must comply with all state and federal rules and regulations, including FAA requirements.

**107.13.6 Excess or Umbrella Liability Insurance.** The Contractor may satisfy the required limits for Secs 107.13.2 through 107.13.5 by use of excess or umbrella liability insurance policies in any combination that meets the contract limits requirements. Such policies shall include as insureds, the Missouri Highways and Transportation Commission (Commission), the Missouri Department of Transportation (MoDOT) and its employees.

**107.13.7 Workers' Compensation Insurance.** The Contractor shall provide evidence to the engineer that the Contractor has obtained workers' compensation insurance and employers liability insurance as required by the state or is exempt and provides proper documentation to the engineer. Coverage shall include all statutory workers' compensation benefits to Contractor employees who may sustain work-related injury, death or disease. If applicable, commensurate with the requirements of the U.S. Longshore and Harbor Workers' Compensation Act (USL&H) and the Jones Act, with a minimum limit of \$2,000,000 per occurrence and in the aggregate, or as may be specified by law, for each. The required insurance must be endorsed to include a waiver of subrogation in favor of the Commission, MoDOT and its employees.

**107.13.8 Railroad Protective Liability Insurance.** In addition to other forms of required insurance, the Contractor shall provide railroad protective liability insurance when any of the Contractor's work is to be performed within any railroad right of way and in some cases may be required when the project improvements are near a railroad right of way. The name or names of the railroad companies known to be in the vicinity of the contract improvements will be specified in each contract, but the contractor shall confirm the railroad companies impacted and the final

insurance needed with each railroad. The minimum limits of the insurance indicated by each railroad to the Commission will be included in the contract bid documents for informational purposes, but the contractor shall be bound by each individual railroad company requirements. Each railroad agency has final determination in the content and coverage limits of the policies required. No work will be permitted within any railroad's right of way until the railroad involved has reviewed and approved the insurance policy. Any day upon which the Contractor cannot perform work due to such a policy not being approved by the railroad will not be counted as a contract day under [Sec 108.7](#).

**107.13.9 Evidence of Insurance.** Required evidence of insurance providing confirmation of compliance with these requirements shall consist of a certificate of insurance, an endorsement to any workers compensation policy waiving the subrogation by the insurer, and any endorsements adding the Commission, MoDOT and its employees as additional insureds where specified. "Blanket" or "automatic" additional insured endorsements providing additional insured coverage "where required by contract," may be used, provided that such forms provide coverage at least as broad as provided by the specified endorsement forms required. The contractor and any subcontract work shall not commence under the contract until the contractor obtains the applicable insurance coverage required and receives approval for such insurance from the engineer. All evidence of insurance for the prime contractor, including certificates of insurance and required endorsements, and notices shall be submitted electronically by the insurance agent to [ContractorSupport@MoDOT.mo.gov](mailto:ContractorSupport@MoDOT.mo.gov). The Contractor shall promptly furnish the engineer with a complete copy of its policy upon request. Failure to furnish evidence of proper insurance, or complete insurance policies when requested, may result in the suspension of work as provided in [Sec 108](#), and may result in other claims or actions for breach of contract or otherwise, as may be recognized at law or in equity.

**107.13.9.1 Work Performed by Subcontract.** Prior to its commencement of the applicable work, the contractor shall cause each of its subcontractors to provide insurance that complies with the requirements for contractor-provided insurance. Contractor's determination of such insurance shall not be interpreted as relieving Contractor or its insurer of any liability otherwise imposed on Contractor or its insurers under these Contract Documents. The Contractor shall promptly furnish the engineer with a complete copy of its subcontractor policies upon request. Failure to furnish evidence of proper insurance, or complete insurance policies when requested, may result in the suspension of work as provided in [Sec 108](#), and may result in other claims or actions for breach of contract or otherwise, as may be recognized at law or in equity.

#### **107.13.10 Other Conditions and Requirements**

**107.13.10.1 Acceptability of Insurance Companies.** All insurers must be authorized to transact business under the laws of the State of Missouri and hold an AM Best rating of no less than A-: VI.

**107.13.10.2 Waiver of Right of Recovery.** All insurance coverage maintained or procured pursuant to this agreement shall be endorsed to waive subrogation against the Commission, MoDOT and its employees or shall specifically allow the Contractor, or others providing insurance evidence in compliance with these specifications, to waive their right of recovery prior to a loss. Contractor hereby waives its own right of recovery against the Commission, MoDOT and its employees.

**107.13.10.3 Enforcement of Contract Provisions (non estoppel).** Contractor acknowledges and agrees that any actual or alleged failure on the part of the Commission, MoDOT or its

employees to inform Contractor of non-compliance with any requirement imposes no additional obligations on the Commission, MoDOT or its employees, nor does it waive any rights hereunder.

**107.13.10.4 Primary and Non-contributory.** For any claims related to this contract, the Contractor's insurance coverage shall be primary insurance with respects to the Commission, MoDOT and its employees as the additional insureds. Any other insurance or self-insurance maintained by any of these parties shall be excess of the Contractor's insurance and shall not contribute with the Contractor's insurance.

**107.13.10.5 Specifications not Limiting.** Requirements of specific coverage features, or limits contained in this Section are not intended as a limitation on coverage, limits or other requirements, or a waiver of any coverage normally provided by any insurance. Specific reference to a given coverage feature is for purposes of clarification only as it pertains to a given issue and is not intended by any party or insured to be all inclusive, or to the exclusion of other coverage, or a waiver of any type.

**107.13.10.6 Notice of Cancellation and Change in Insurance Carrier.** Contractor agrees to oblige its insurance agent or broker, and insurers by endorsement to the policy, to provide to the engineer with thirty (30) days advance notice of cancellation, except for nonpayment for which ten (10) days' notice is required, or nonrenewal of coverage for each required coverage. If any policy is canceled or the insurance carrier is planned to change before the contract work is complete, a satisfactory replacement policy shall be obtained and in force, with notice and evidence of insurance submitted to the engineer, prior to the effective date of cancellation of the former policy.

**107.13.10.7 Self-insured Contractors and Self-insured Retentions.** A self-insured contractor will not be considered to comply with these specifications unless approved by the engineer prior to beginning work. A contractor with insurance policies arranged with self-insured retentions must be declared to and approved by the engineer prior to beginning work. The Commission reserves the right to require that self-insured retentions be eliminated, lowered, or replaced by a deductible or other policy type.

**107.13.10.8 Timely Notice of Claims.** Contractor shall give the engineer prompt and timely notice of claims made or suits instituted that arise out of or result from Contractor's performance under this Agreement, and that involve or may involve coverage under any of the required liability policies. The Commission and MoDOT will provide timely notice to the contractor of any claims or lawsuits that it receives. If the Commission demands that the contractor defend the suit and/or indemnify the Commission, the contractor or its insurance company shall acknowledge that demand within 20 days of receiving it and the contractor shall respond within a total of 45 days of the claim receipt the intent of the contractor to defend.

**107.13.10.9 Exhaustion of Policy Limits.** It shall be the contractor's responsibility to notify the engineer promptly when any provided insurance limits are not able to be maintained during the contract period or provide verification that additional coverage or excess coverage is also available.

**107.14 Cooperation in Defense.** The indemnified party shall cooperate with the indemnifying party in the defense of a third-party claim subject to the foregoing, (1) the indemnified party shall not have any obligation to participate in the defense of or to defend any third-party claim, and



(2) the indemnified party's defense of or its participation in the defense of any third-party claim shall not in any way diminish or lessen its right to indemnification as provided in this section.

**107.15 Third Party Liability.** Neither the State of Missouri, including the Commission, nor the contractor, by execution of the contract including these specifications, intend to create a right of action in a third-party beneficiary, except as specifically set out in these specifications and the contract. It is not intended by any required contractual liability in the contract or in these specifications that any third-party beneficiary has a cause of action arising out of the condition of the project when completed in accordance with the plans and accepted by the Commission.

**107.16 Personal Liability of Public Officials.** There shall be no personal liability upon the Chief Engineer, or any member, employee, or agent of the Commission in carrying out any of the provisions of the contract or in exercising any power or authority granted to the individual, it being understood that in such matters the individual acts as an agent and representative of the State, with official and public duty doctrine immunity. If any provision of the contract appears to impose a duty on such an individual, the duty will remain exclusively that of the Commission and will not be a personal duty or obligation of the individual.

**107.17 Contractors That Are Not Resident In Missouri.** Any contractor that is not a permanent resident of or domiciled in Missouri shall provide to the Commission proof of compliance with the Missouri "nonresident employers" financial assurance laws at Sections 285.230 to 285.234, RSMo, before the contractor performs any work on a project.

**107.17.1** A nonresident contractor that is a "transient employer" as that term is defined in Section 285.230.1, RSMo, and 12 CSR 10-2.017(1)(A), shall file with the Commission a photocopy of the contractor's current transient employer's certificate of registration issued by the Missouri Department of Revenue before performing any work on a project. A nonresident contractor that is not classified by the Missouri Department of Revenue as a "transient employer" because the nonresident contractor has properly registered with the Missouri Department of Revenue and the Missouri Division of Employment Security, and has filed and paid Missouri state income taxes for more than 24 consecutive months, shall file with the Commission a photocopy of the contractor's certificate of registration, issued by the Missouri Department of Revenue, that it is not a "transient employer" before performing any work on a project.

**107.17.2** The contractor shall require a nonresident subcontractor to file with the Commission a photocopy of the subcontractor's current transient employer's or alternate certificate of registration, as issued by the Missouri Department of Revenue, before that subcontractor performs any work on a project.

**107.17.3** Any nonresident contractor or subcontractor that fails to file the financial assurance forms with the Missouri Department of Revenue as required by Missouri law will be prohibited from contracting for or performing labor on any project for a period of one year.

**107.18 Basis of Payment.** No direct payment will be made for compliance with [Sec 107](#), except as provided by [Sec 618](#).

Buy America

In addition to Section 106.9 of the Missouri Standard Specifications for Highway Construction,

the following requirements will also be in effect for this project.

**1.0 Description.** The Bipartisan Infrastructure Law (BIL) was enacted on November 15, 2021. The BIL includes Build America, Buy America Act Publication L. No. 117-58. This provision expands the Buy America requirements beyond what is currently only required for steel and iron products. The steel and iron provisions have not changed with the new bill. Cement and cementitious materials; aggregates such as stone, sand, or gravel; or aggregate binding agents or additives are excluded from this requirement. All other materials and manufactured products permanently incorporated into the project will be subject to Buy America requirements. There are three categories requiring Buy America Certification:

- a) Iron and steel – no changes to the current specification requirements.
- b) Manufactured products – these are currently exempted under the 1983 waiver from FHWA.
- c) Construction materials consisting primarily of:
  - Non-ferrous metals;
  - Plastic and polymer-based products (including polyvinylchloride, composite build materials, and polymers used in fiber optic cables);
  - Glass (including optic glass);
  - Lumber; or
  - Drywall

**1.1** All products and or materials will only be classified under one of these categories and not under multiple categories. It is the prime contractor's responsibility to assure all submittals required for Buy America are submitted to the Engineer prior to the products and or materials being incorporated in the job. The implementation of this policy will be in effect for all projects awarded after November 10, 2022.

**1.2** New items designated as construction materials under this requirement will require the prime contractor to submit a material of origin form certification prior to incorporation into the project. The Certificate of Material origin form ([link to certificate form](#)) from the supplier and/or fabricator must show all steps of the manufacturing being completed in the United States. The Certificate of Material form shall be filed with the contract documents.

**1.3** Any minor miscellaneous construction material items that are not included in the materials specifications shall be certified by the prime contractor as being procured domestically. The certification shall read "I certify all materials permanently incorporated in this project covered under this provision have been to the best of my knowledge procured and all manufactured domestically." The certification shall be signed by an authorized representative of the prime contractor.

**1.4** The National Transportation Product Evaluation Program (NTPEP) compliance program verifies that some non-iron and steel products fabrication processes conform to 23 CFR 635.410 Buy America Requirements and an acceptable standard per 23 CFR 635.410(d). NTPEP compliant suppliers will not be required to submit step certification documentation with the shipment for some selected non-iron and steel materials. The NTPEP compliant supplier



shall maintain the step certification documentation on file and shall provide this documentation to the engineer upon request.

**2.0 Basis of Payment.** Any costs incurred by the contractor by reason of compliance with the above requirements shall be considered as included in and completely covered by the unit price bid for the various items of work included in the contract.

***Delete Sec 617.20.3 and substitute the following:***

**617.20.3 Certification.** Prior to use the contractor shall submit to the engineer a manufacture's certification of crashworthiness per NCHRP 350 or MASH 2016 for portable concrete barrier or other approved temporary barrier. Type F three-loop temporary concrete barrier is required to meet NCHRP 350 requirements regardless of manufacturing date and may be used until January 1, 2030. All other temporary barriers manufactured prior to January 1, 2023 may be used until January 1, 2030. All other temporary barriers manufactured after January 1, 2023 shall meet MASH 2016 crash test requirements.

***Delete Sec 1063.2 and substitute the following:***

**1063.2 General Requirements.** All temporary traffic control devices shall be manufactured as shown on the plans and as specified, in accordance with MUTCD requirements and shall be NCHRP 350 or MASH 2016 compliant. FHWA Category 1 temporary traffic control devices are not required to be crash tested unless modified. Non MASH 2016 FHWA Category 2 temporary traffic control devices and appurtenances manufactured prior to January 1, 2023 may be used until January 1, 2026. Non MASH 2016 FHWA Category 3 temporary traffic control devices and appurtenances manufactured prior to January 1, 2023 may be used until January 1, 2030. All other FHWA Category 2 and Category 3 temporary traffic control devices and appurtenances manufactured after January 1, 2023 shall meet MASH 2016 Test Level 3 crash test requirements. Type F three-loop temporary concrete barrier is required to meet NCHRP 350 requirements regardless of manufacturing date and may be used until January 1, 2030. MASH 2016 FHWA Category 4 temporary traffic control devices should be used when available. Nominal dimensions will be permitted for dimensional lumber where applicable. All temporary traffic control devices shall exhibit good workmanship and shall be free of objectionable marks or defects that affect appearance or serviceability. The brand name or model number shall be permanently identified on each traffic control device.

#### Alternate Weather Limitations for Plant Mix Bituminous Surface Leveling

**1.0 Description.** Weather limitations for Plant Mix Bituminous Surface Leveling mixtures shall be as specified in Sec 402.10.1 except as otherwise allowed herein.

**1.1** When all remedial actions listed in Section 2.0 have been implemented by the contractor, at no additional cost to the Commission, the alternate weather limitations in Section 1.2 shall apply in lieu of Sec 402.10.1

**1.2 Alternate Weather Limitations.** Bituminous mixtures shall not be placed (1) when either the air temperature or the temperature of the surface on which the mixture is to be placed is below 40 F, or (2) on any wet surface or frozen pavement. Temperatures shall be obtained in accordance with MoDOT Test Method TM 20.

## **2.0 Remedial Actions.**

- a) Reclaimed Asphalt Pavement (RAP) content in the mix does not exceed 20% asphalt binder replacement.
- b) No Reclaimed Asphalt Shingles (RAS) are added to the mix.
- c) A material transverse vehicle is utilized to transfer the mix from the haul trucks to the paver.
- d) Warm mix technology shall be incorporated into the mix (either by chemical additive or foaming), as approved by the engineer.

### **P. Remove and Re-set Existing Sign on New PSST Post**

**1.0 Description.** This item provides for relocating and mounting existing signs of various sizes to new posts at locations shown in the plans.

**2.0 Construction Requirements.** The contractor shall install new posts at the locations shown and then mount existing signs to the appropriate post type as summarized in the plans. All work shall be in accordance with the construction requirements of Section 903.

**3.0 Method of Measurement.** Measurement will be made per square foot for relocating and mounting existing signs to new Perforated Square Steel Tube (PSST) Posts. Measurement for any concrete footings, structural steel posts, pipe posts, perforated square steel tubes and anchor sleeves, and breakaway assemblies will be made in accordance with Section 903.

**4.0 Basis of Payment.** All cost incurred for relocating and mounting existing signs to new PSST posts at the locations shown, complete in place, will be paid for at the contract unit price for Pay Item 903-99.03 Remove and Re-set Sign Face, per square foot. Payment for all other labor, equipment, material, and incidental items will be made in accordance with Section 903 and paid for at the contract unit price for each of the pay items included in the contract.