

DESIGN DESIGNATION
A.A.D.T. - 2024 = 31,505
V = 70 M.P.H.

FUNCTIONAL CLASSIFICATION - INTERSTATE

NO RIGHT OF WAY IS ACQUIRED
ON THIS PROJECT


CONVENTIONAL SYMBOLS
(USED IN PLANS)

	EXISTING	NEW
BUILDINGS AND STRUCTURES		
GUARD RAIL		
GUARD CABLE		
CONCRETE RIGHT-OF-WAY MARKER		
STEEL RIGHT-OF-WAY MARKER		
LOCATION SURVEY MARKER		
UTILITIES		
FIBER OPTICS	-FO-	-FO-
OVERHEAD CABLE TV	-OTV-	-OTV-
UNDERGROUND CABLE TV	-UTV-	-UTV-
OVERHEAD TELEPHONE	-OT-	-OT-
UNDERGROUND TELEPHONE	-UT-	-UT-
OVERHEAD POWER	-OE-	-OE-
UNDERGROUND POWER	-UE-	-UE-
SANITARY SEWER	-S-	-S-
STORM SEWER	-SS-	-SS-
GAS	-G-	-G-
WATER	-W-	-W-
MANHOLE		
FIRE HYDRANT		
WATER VALVE		
WATER METER		
DROP INLET		
DITCH BLOCK		
GROUND MOUNTED SIGN		
LIGHT POLE		
H-FRAME POWER POLE		
TELEPHONE PEDESTAL		
FENCE		
CHAIN LINK		
WOVEN WIRE		
GATE POST		
BENCHMARK		


NOTE: DASHED OR OPEN SYMBOLS INDICATE
EXISTING FEATURES

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
PLANS FOR PROPOSED
STATE HIGHWAY

LAFAYETTE-SALINE COUNTIES




KEY MAP
LOCATION OF LAFAYETTE
AND SALINE COUNTIES



PROJECT LOCATION: RURAL ROUTE INTERSTATE 70
PROJECT DESCRIPTION: PAVEMENT MARKING PAINT ONLY

INDEX OF SHEETS

DESCRIPTION	SHEET NUMBER
TITLE SHEET -----	1
TYPICAL SECTIONS (TS) (0 SHEETS)---	N/A
QUANTITIES (QU) (08 SHEETS)-----	3
TRAFFIC CONTROL SHEETS (TC)-----	4-8



DATE PREPARED 9/26/2023	
ROUTE 70	STATE MO
DISTRICT KC	SHEET NO. 1
COUNTY LAFAYETTE / SALINE	
JOB NO. JKR0235	
CONTRACT ID.	

PROJECT NO.
BRIDGE NO.

DESCRIPTION	DATE

LENGTH OF PROJECT

<u>LAFAYETTE COUNTY - EASTBOUND</u>	
BEGINNING OF PROJECT	EB LOG MILE: 29.173
PROJECT AT COUNTY LINE	EB LOG MILE: 62.576
APPARENT LENGTH	33.403 LOG MILES
<u>SALINE COUNTY - EASTBOUND</u>	
PROJECT AT COUNTY LINE	EB LOG MILE: 62.576
END OF PROJECT	EB LOG MILE: 87.531
APPARENT LENGTH	24.955 LOG MILES

<u>SALINE COUNTY - WESTBOUND</u>	
BEGINNING OF PROJECT	WB LOG MILE: 162.465
PROJECT AT COUNTY LINE	WB LOG MILE: 187.432
APPARENT LENGTH	24.967 LOG MILES
<u>LAFAYETTE COUNTY - WESTBOUND</u>	
PROJECT AT COUNTY LINE	WB LOG MILE: 187.432
END OF PROJECT	WB LOG MILE: 220.817
APPARENT LENGTH	33.385 LOG MILES

NET LENGTH OF PROJECT (BASED ON EASTBOUND)	58.358 LOG MILES
STATE LENGTH	58.358 MILES
FOR INFORMATION ONLY ESTIMATED DISTURBED ACRES	00.00 ACRES



MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
TITLE SHEET

EASTBOUND PAVEMENT MARKING IN SALINE COUNTY							
BEGIN LOG MILE	END LOG MILE	LENGTH FT	HIGH BUILD PAINT TYPE L BEADS				REMARK
			6 IN. WHITE LIN FT	6 IN. WHITE INTERMITTENT OR DOTTED LIN FT	6 IN. YELLOW LIN FT	12 IN. WHITE LIN FT	
62.576	87.531	131,762		32,941	131,762		TOTAL EB SALINE COUNTY
62.576	62.727	797	797				COUNTY LINE TO GORE RTE Y RAMP D
						172	MAINLINE GORE RTE Y RAMP B
		315		79			RTE Y RAMP D ACCEL LANE
					735		RTE Y RAMP D
						122	GORE AT RTE Y RAMP D
			1,536				RTE Y RAMP D
62.886	66.532	19,251	19,611				RTE Y RAMP D TO RTE 127 INCLUDING SLIP RAMP
		640		160			RTE 127 SLIP RAMP DECEL LANE
						187	RTE 127 SLIP RAMP MAIN LINE GORE
						150	RTE 127 SLIP RAMP GORE
			215				RTE 127 SLIP RAMP
66.573	67.108	2,825	2,825				RTE 127 SLIP RAMP TO RAMP D
						180	RTE 127 RAMP D MAINLINE GORE
					630		RTE 127 RAMP D
						146	RTE 127 RAMP D GORE
			1,258				RTE 127 RAMP D
			169				RTE 127 RAMP D WB TRAFFIC CONNECTOR (BOTH SIDES)
67.258	71.176	20,687	20,687				RTE 127 RAMP D TO RTE K RAMP B
						200	RTE K RAMP B MAINLINE GORE
						140	RTE K RAMP B GORE
					640		RTE K RAMP B
			1,110				RTE K RAMP B
71.262	71.500	1,257	1,257				RTE K RAMP B TO RAMP D
						175	RTE K RAMP D MAINLINE GORE
		232		58			RTE K RAMP D ACCEL LANE
						130	RTE K RAMP D GORE
					630		RTE K RAMP D
			1,440				RTE K RAMP D
71.653	74.358	14,282	14,282				RTE K RAMP D TO RTE YY SLIP RAMP B
		284		71			RTE YY SLIP RAMP B DECEL LANE
						187	RTE YY SLIP RAMP B MAIN LINE GORE
						125	RTE YY SLIP RAMP B GORE
					320		RTE YY SLIP RAMP B
			1,033				RTE YY SLIP RAMP B (INCLUDES WB TRAFFIC CONNECTOR)
74.492	74.725	1,230	1,230				RTE YY SLIP RAMP B TO SLIP RAMP D
						175	RTE YY SLIP RAMP D MAIN LINE GORE
		210		53			RTE YY SLIP RAMP D ACCEL LANE
					590		RTE YY SLIP RAMP D
			1,408				RTE YY SLIP RAMP D (INCLUDES TRAFFIC CONNECTOR)
74.887	77.829	15,534	15,534				RTE YY SLIP RAMP D TO US 65 RAMP B
		200		50			US 65 RAMP B DECEL LANE
77.974	78.109	713	713				US 65 RAMP B TO US65 CLOVERLEAF RAMP
78.136	78.222	454	454				US 65 CLOVERLEAF RAMP TO US65 CLOVERLEAF RAMP
		550		138			US 65 ACCEL/DECEL LANE
78.270	78.458	993	993				US 65 CLOVERLEAF RAMP TO US65 RAMP D
		285		71			US 65 ACCEL LANE
78.627	84.360	30,270	30,270				US 65 RAMP D TO RTE J RAMP B
						220	MAINLINE GORE RTE J RAMP B
						211	GORE RTE J RAMP B
					700		RTE J RAMP B
			1,165				RTE J RAMP B AND ISLAND
84.475	84.718	1,283	1,283				RTE J RAMP B TO RAMP D
						175	MAINLINE GORE RTE J RAMP D
						160	GORE RTE J RAMP D
					530		RTE J RAMP D INCLUDES RADIUS AT THE BEGINNING OF RAMP
			1,492				RTE J RAMP D INCLUDES RADIUS AT THE BEGINNING OF RAMP
		200		50			RTE J ACCEL LANE
84.880	87.531	13,997	13,997				RTE J RAMP D TO COUNTY LINE
TOTAL EBL			168,430		136,537	2,855	

SEE SHEET 7 FOR PAY TOTALS

STATE OF MISSOURI

KARLEE A. COVINGTON

NUMBER
PE-2020000009

PROFESSIONAL ENGINEER

10/02/2023 9:50:06 AM

KARLEE A. COVINGTON - CIVIL

MO-PE-2020000009

DATE PREPARED
9/26/2023

ROUTE
70

DISTRICT
KC

STATE
MO

SHEET NO.
3

COUNTY
LAFAYETTE / SALINE

JOB NO.
JKR0235

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

MoDOT

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

WESTBOUND PAVEMENT MARKING IN SALINE COUNTY							
BEGIN	END	LENGTH	HIGH BUILD PAINT TYPE L BEADS				REMARK
			6 IN. WHITE	6 IN. WHITE INTERMITTENT OR DOTTED	6 IN. YELLOW	12 IN. WHITE	
LOG MILE	LOG MILE	FT	LIN FT	LIN FT	LIN FT	LIN FT	
162.465	187.432	131,826		32,957	131,826		TOTAL WB SALINE COUNTY
162.465	165.155	14,203	14,203				COUNTY LINE TO RTE J RAMP C
			1,096				RTE J RAMP C/ISLAND INCLUDES RADIUS AT THE BEGINNING OF RAMP
					591		RTE J RAMP C INCLUDES RADIUS AT THE BEGINNING OF RAMP
						185	GORE RTE J RAMP C
						200	MAINLINE GORE RTE J RAMP C
165.249	165.460	1,114	1,114				RTE J RAMP C TO RAMP A
					475		RTE J RAMP A
						211	GORE RTE J RAMP A
						220	MAINLINE GORE RTE J RAMP A
			1,446				RTE J RAMP A
165.639	171.348	30,144	30,144				RTE J RAMP A TO US 65 RAMP C
		300		75			US 65 DECEL LANE
171.518	171.743	1,188	1,188				US65 RAMP C TO US 65 CLOVERLEAF RAMP
		616		154			US 65 ACCEL/DECEL LANE
171.767	171.882	607	607				US 65 CLOVERLEAF RAMP TO US65 CLOVERLEAF RAMP
171.905	172.042	723	723				US65 CLOVERLEAF RAMP TO US 65 RAMP A
		166		42			US 65 RAMP A ACCEL LANE
172.190	175.186	15,819	15,819				US 65 RAMP A TO RTE YY RAMP C
			1,073				RTE YY RAMP C
					606		RTE YY RAMP C
						127	RTE YY RAMP C GORE
						188	RTE YY RAMP C MAIN LINE GORE
175.261	175.490	1,209	1,209				RTE YY RAMP C TO RAMP A
			1,280				RTE YY RAMP A
					520		RTE YY RAMP A
						150	RTE YY RAMP A GORE
						180	RTE YY RAMP A MAIN LINE GORE
		244		61			RTE YY RAMP A ACCEL LANE
175.645	178.437	14,742	14,742				RTE YY RAMP A TO RTE K RAMP C
						110	RTE EE RAMP C GORE
						170	RTE EE RAMP C MAINLINE GORE
			970				RTE EE RAMP C
					645		RTE EE RAMP C
178.500	178.717	1,146	1,146				RTE EE RAMP C TO RAMP A
			1,405				RTE EE RAMP A
					525		RTE EE RAMP A
						172	RTE EE RAMP A GORE
						226	RTE EE RAMP A MAINLINE GORE
		341		85			RTE EE RAMP A ACCEL LANE
178.875	182.903	21,268	21,268				RTE EE RAMP A TO RTE 127 RAMP C
			991				RTE 127 RAMP C
					580		RTE 127 RAMP C
						117	RTE 127 RAMP C GORE
						164	RTE 127 RAMP C MAINLINE GORE
182.987	183.239	1,331	1,331				RTE 127 SLIP RAMP TO RAMP D
					693		RTE 127 RAMP A INCLUDES RADIUS AT THE BEGINNING OF RAMP
						123	RTE 127 RAMP A GORE
						195	RTE 127 RAMP A MAIN LINE GORE
		238		60			RTE 127 RAMP A ACCEL LANE
			1,450				RTE 127 RAMP A
183.395	187.131	19,726	20,086				RTE 127 RAMP A TO RTE VV RAMP C
			1,508				RTE VV RAMP C
						160	GORE AT RTE Y RAMP D
					1,056		RTE VV RAMP C
						225	RTE VV RAMP C MAINLINE GORE
187.220	187.432	1,119	1,119				RTE VV RAMP C TO COUNTY LINE
	TOTAL WBL		169,352		137,517	3,123	

SEE SHEET 7 FOR PAY TOTALS

STATE OF MISSOURI

KARLEE A. COVINGTON

NUMBER

PE-2020000009

PROFESSIONAL ENGINEER

10/02/2023 9:30:40 AM

KARLEE A. COVINGTON - CIVIL

MO-PE-2020000009

DATE PREPARED

9/26/2023

ROUTE

70

STATE

MO

DISTRICT

KC

SHEET NO.

3

COUNTY

LAFAYETTE / SALINE

JOB NO.

JKR0235

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL

JEFFERSON CITY, MO 65102

1-888-ASK-MODOT (1-888-275-6636)

MoDOT

PAVEMENT MARKING IN SALINE COUNTY AT US 65 CLOVERLEAF			
LOCATION	HIGH BUILD PAINT TYPE L BEADS		
	6 IN. WHITE	6 IN. YELLOW	12 IN. WHITE
	LIN FT	LIN FT	LIN FT
NW RAMP AT 65	1935	1185	600
NW CLOVER RAMP AT 65	989	836	270
NE RAMP AT 65	2791	1919	620
NE CLOVER RAMP AT 65	1275	1160	411
SW RAMP AT 65	2416	1500	400
SW CLOVER RAMP AT 65	1346	1144	260
SE RAMP AT 65	2461	1455	320
SE CLOVER RAMP AT 65	1140	850	318
TOTALS	14,353	10,049	3,199

TOTAL PAVEMENT MARKING IN SALINE COUNTY			
LOCATIONS	HIGH BUILD PAINT TYPE L BEADS		
	6 IN. WHITE	6 IN. YELLOW	12 IN. WHITE
	LIN FT	LIN FT	LIN FT
TOTAL EBL	168,430	136,537	2,855
TOTAL WBL	169,352	137,517	3,123
TOTAL US 65 CLOVERLEAF	14,353	10,049	3,199
TOTAL SALINE COUNTY	352,135	284,103	9,177

TRUCK REST AND WEIGH STATION PAVEMENT MARKING PAINT IN LAFAYETTE COUNTY					
LOCATION	LENGTH FT	HIGH BUILD PAINT TYPE L BEADS			WATERBORNE PAINT TYPE P BEADS
		6 IN. WHITE	6 IN. WHITE INTER.	6 IN. YELLOW	24 IN. WHITE
		LIN FT	LIN FT	LIN FT	LIN FT
TRUCK REST PARKING EB	3265	3265		1235	
TRUCK REST PARKING WB	3263	2423		1175	
WEIGH STATION TRUCK PARKING EB	6230	6230	111	3410	
WEIGH STATION TRUCK PARKING EB MEDIAN	1975	3827			557
WEIGH STATION TRUCK PARKING WB	5650	5650	146	2900	
WEIGH STATION TRUCK PARKING WB MEDIAN	1265	2485			342
SUBTOTALS		23880	257	8720	899
TOTAL		24,137		8,720	899

NOTE THAT PAVEMENT MARKING AT THE REST STOPS (AROUND EB LM 57.4/WB LM 191.7) IS FOR THE BEGINNING OF THE RAMPS ONLY.
ALL OTHER MARKINGS AT THOSE REST STOPS AND PARKING AT ALL REST STOPS/WEIGH STATIONS ARE DONE BY OTHERS.

TOTAL PAVEMENT MARKING IN LAFAYETTE COUNTY				
LOCATIONS	HIGH BUILD PAINT TYPE L BEADS			WATERBORNE PAINT TYPE P BEADS
	6 IN. WHITE	6 IN. YELLOW	12 IN. WHITE	24 IN. WHITE
	LIN FT	LIN FT	LIN FT	LIN FT
TOTAL EBL	228,701	188,046	9,833	0
TOTAL WBL	204,993	187,374	8,634	0
TOTAL REST/WEIGH STATION	24,137	8,720	0	899
TOTAL LAFAYETTE COUNTY	457,831	384,140	18,467	899

TOTAL PAVEMENT MARKING IN PROJECT				
LOCATIONS	HIGH BUILD PAINT TYPE L BEADS			WATERBORNE PAINT TYPE P BEADS
	6 IN. WHITE	6 IN. YELLOW	12 IN. WHITE	24 IN. WHITE
	LIN FT	LIN FT	LIN FT	LIN FT
TOTAL LAFAYETTE COUNTY	457,831	384,140	18,467	899
TOTAL SALINE COUNTY	352,135	284,103	9,177	0
PROJECT PAY TOTAL	809,966	668,243	27,644	899

MOBILIZATION
1 LUMP SUM

STATE OF MISSOURI

KARLEE A. COVINGTON

NUMBER
PE-2020000009

PROFESSIONAL ENGINEER

10/02/2023 9:41:17 AM

KARLEE A. COVINGTON - CIVIL

MO-PE-2020000009

DATE PREPARED
9/26/2023

ROUTE
70

DISTRICT
KC

STATE
MO

SHEET NO.
3

COUNTY
LAFAYETTE / SALINE

JOB NO.
JKR0235

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION


DATE

MISSOURI HIGHWAYS AND TRANSPORTATION
COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102

1-888-ASK-MODOT (1-888-275-6636)

MoDOT



MULTI-LANE DIVIDED HIGHWAY
MOVING OPERATION ON HIGHWAY
OPEN TO TRAFFIC

FLASHING ARROW
PANEL -
ARROW MODES

WO20-6a
48" x 48"

GO22-1 (1)
21" x 15"

NOTES:

ALL SIGNS HAVE TYPE 3 FLUORESCENT ORANGE RETROFLECTIVE SHEETING.

UPON APPROVAL OF THE ENGINEER, THE CONTRACTOR MAY PROVIDE ADDITIONAL PROTECTIVE TRUCKS EQUIPPED WITH PROPER WARNING DEVICES.

PROTECTIVE TRUCK AND WORK VEHICLES SHALL DISPLAY HIGH-INTENSITY ROTATING, FLASHING, OSCILLATING OR STROBE LIGHTS.

VEHICLE HAZARD WARNING SIGNALS SHALL NOT BE USED INSTEAD OF THE VEHICLE'S HIGH -INTENSITY ROTATING FLASHING, FLASHING, OSCILLATING, OR STROBE LIGHTS.

(1). WET PAINT SIGNS ARE INSTALLED TO INDICATE THE SIDE IN WHICH THE PAVEMENT MARKING MATERIAL IS BEING APPLIED. AT THE CONTRACTOR'S OPTION, A FRONT FACING WET PAINT SIGN MAY BE INSTALLED ON THE LEFT SIDE OF THE PAVEMENT MARKING EQUIPMENT.

(2). ADVANCE WARNING TRUCK IS POSITIONED AT THE NO TRACK POINT OF THE PAVEMENT MARKING MATERIAL OR SPACING SHOWN, WHICHEVER IS GREATER.

FLASHING ARROW PANELS SHALL, AS A MINIMUM, BE TYPE B, WITH A SIZE OF 60 X 30 INCHES.

VEHICLE-MOUNTED SIGNS SHALL BE MOUNTED IN A MANNER SUCH THAT THEY ARE NOT OBSCURED BY EQUIPMENT OR SUPPLIES. SIGN LEGENDS ON VEHICLE-MOUNTED SIGNS SHALL BE COVERED OR TURNED FROM VIEW WHEN WORK IS NOT IN PROGRESS.

A FLASHING ARROW BOARD SHALL BE USED WHEN A FREEWAY LANE IS CLOSED. WHEN MORE THAN ONE LANE IS CLOSED, A SEPERATE FLASHING ARROW BOARD SHALL BE USED FOR EACH CLOSED LANE.

FLASHING ARROW
PANEL -
ARROW MODES

WO20-6a
48" x 48"

SPEED	SPACING LENGTH (ft.)
REGULATORY (MPH)	SPACING (T1)
0-35	245
40-45	540
50-55	660
60-70	840

SETUP TYPE 1


DATE PREPARED 9/26/2023	
ROUTE 70	STATE MO
DISTRICT KC	SHEET NO. 4
COUNTY LAFAYETTE / SALINE	
JOB NO. JKR0235	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	

DESCRIPTION	DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

TEMPORARY TRAFFIC CONTROL
SHEET 1 OF 5
MOVING OPERATION
OPEN TO TRAFFIC



SETUP TYPE 2

STATE OF MISSOURI
KARLEE A. COVINGTON
NUMBER
PE-2020000009
PROFESSIONAL ENGINEER

10/02/2023 9:00:30 AM
KARLEE A. COVINGTON - CIVIL
MO-PE-2020000009

DATE PREPARED
9/26/2023

ROUTE
70

STATE
MO

DISTRICT
KC

SHEET NO.
5

COUNTY
LAFAYETTE / SALINE

JOB NO.
JKR0235

CONTRACT ID.

PROJECT NO.

BRIDGE NO.


DESCRIPTION

DATE


MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

TEMPORARY TRAFFIC CONTROL
SHEET 2 OF 5
MOVING OPERATION
OPEN TO TRAFFIC



DISCLAIMER
THE PROFESSIONAL WHOSE SIGNATURE AND PERSONAL SEAL APPEAR HEREON ASSUMES RESPONSIBILITY ONLY FOR WHAT APPEARS ON THIS PAGE, AND DISCLAIMS (PURSUANT TO SECTION 327.411 RSMO) SPECIFICATION, ESTIMATES, REPORTS, OR OTHER DOCUMENTS OR INSTRUMENTS NOT SEALED BY THE UNDERSIGNED PROFESSIONAL RELATING TO OR INTENDED TO BE USED FOR ANY PART OR PARTS OF THE PROJECT TO WHICH THIS PAGE REFERS.



NOTES:

-

FOR SIGNALIZED INTERSECTIONS, ADJUSTMENTS MAY NEED TO BE MADE TO SIGNAL PHASING, TIMING, INDICATIONS OR DETECTOR SETTINGS.

FOR SHORT TERM OPERATION, WHERE IT IS NOT FEASIBLE TO MODIFY PAVEMENT MARKING, A 10-FOOT DEVICE SPACING IS USED WHERE TRAFFIC IS GUIDED ACROSS DOUBLE YELLOW LINES OR OTHER CONFLICTING PAVEMENT MARKING. ALL OTHER SPACING ARE ONE-HALF OF THE SPACING.

RIGHT LANE CLOSED AHEAD SIGN MAY BE OMITTED IN LOW SPEED URBAN AREAS WHERE THERE IS NOT SUFFICIENT SPACE FOR HTE FULL SIGN SERIES.

ANY EXISTING SIGNS THAT CONFLICT WITH THE TRAFFIC CONTROL PLAN SHALL BE COMPLETELY COVERED.

ALL SIGNS SHALL BE GROUND-MOUNTED.

ALL DISTANCES AND SPACING OF TRAFFIC CONTROL DEVICES ARE APPROXIMATE AND MAY BE REVISED AS DIRECTED BY THE ENGINEER TO FIT FIELD CONDITIONS.

TRAFFIC CONTROL LEGEND	
	SIGN (SINGLE SIDED)
	DIRECTIONAL INDICATOR BARRICADE
	CHANNELIZER (TRIM-LINE)
	WORK AREA
	FLASHING ARROW PANEL
	TYPE III BARRICADE

SPEED	SIGN SPACING (ft.)		TAPER LENGTH (ft.)		OPTIONAL BUFFER LENGTH (ft.) (B)	CHANNELIZER SPACING (ft.)	
	UN -DIVIDED (S)	DIVIDED (S)	SHOULDER (1) (T1)	LANE (2) (T2)		TAPERS	BUFFER/ WORK AREAS
0-35	-	200	70	245	280	35	40
40-45	-	500	150	540	400	40	80
50-55	-	1000	185	660	560	50	80
60-70	-	SA-1000 SB-1500 SC-2640	235	840	840	60	120

1 Shoulder taper length based on 10 ft. (standard shoulder width) offset.
2. Lane taper length based on 12 ft. (standard lane width) offset.

STATE OF MISSOURI

KARLEE A. COVINGTON

NUMBER

PE-2020000009

PROFESSIONAL ENGINEER

10/02/2023 9:48:25 AM

KARLEE A. COVINGTON - CIVIL

MO-PE-2020000009

DATE PREPARED

9/26/2023

ROUTE

70

STATE

MO

DISTRICT

KC

SHEET NO.

6

COUNTY

LAFAYETTE / SALINE

JOB NO.

JKR0235

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL

JEFFERSON CITY, MO 65102


1-888-ASK-MODOT (1-888-275-6636)

TEMPORARY TRAFFIC CONTROL

SHEET 3 OF 5


TEMPORARY FULL EXIT RAMP CLOSURE

SETUP TYPE 3




GO25-1 SHF-FLAT SHEET FLUORESCENT;
2.250" Radius, 0.875" Border, 0.525" Indent, Black on, Orange;
"SLOW", D 75% spacing; "VEHICLES", D 75% spacing;
Table of letter and object lefts

S	L	O	W
17.750	27.125	35.375	44.825
V	E	H	I
4.125	13.875	22.125	31.500
C	L	E	S
35.125	44.000	52.250	60.500



GO25-2 SHF-FLAT SHEET FLUORESCENT;
2.250" Radius, 0.875" Border, 0.525" Indent, Black on, Orange;
"RIGHT LANE", D 60% spacing; "CLOSED", D 60% spacing;
Table of letter and object lefts

R	I	G	H	T	L	A	N	E
4.750	12.125	14.750	22.000	29.125	40.125	45.875	54.500	61.750
C	L	O	S	E	D			
15.625	22.625	28.125	38.500	43.875	50.375			



GO25-2P (SIDE A) SHF-FLAT SHEET FLUORESCENT;
1.500" Radius, No border, Orange;
"CENTER" Black, C 50% spacing;
Table of letter and object lefts

C	E	N	T	E	R
2.000	7.625	12.875	18.625	23.875	29.125



GO25-2P (SIDE B) SHF-FLAT SHEET FLUORESCENT;
1.500" Radius, No border, Orange;
"LEFT" Black, D 60% spacing;
Table of letter and object lefts

L	E	F	T
5.625	12.125	18.625	24.875



DATE PREPARED
9/26/2023
ROUTE **70** STATE **MO**
DISTRICT **KC** SHEET NO. **8**

COUNTY
LAFAYETTE / SALINE
JOB NO.
JKR0235
CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION	DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION



105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

TEMPORARY TRAFFIC CONTROL
SHEET 5 OF 5
SPECIAL SIGNS DETAILS