


TABLE OF CONTENTS

- A. Construction Requirements
- B. Rapid Set Concrete Patching Material – Vertical and Overhead Repairs
- C. Rapid Set Concrete Patching Material – Horizontal Repairs
- D. Decorative Pedestrian Fence
- E. Deflection and Haunching
- F. Dynamic Pile Testing
- G. Form Liners
- H. Structural Steel Requirements
- I. Non-Destructive Testing

 <p>STATE OF MISSOURI TIMOTHY D. LEAF NUMBER PE-2012000778 PROFESSIONAL ENGINEER</p> <p><i>Timothy D. Leaf</i> 01/09/2024 11:52:16 AM TIMOTHY D. LEAF - CIVIL MO-PE-2012000778</p>	<p>MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION 105 W. CAPITOL AVE. JEFFERSON CITY, MO 65101 Phone (888) 275-6636</p>
	<p>If a seal is present on this sheet, JSP's has been electronically sealed and dated.</p>
	<p>JOB NO. J113330 Buchanan County, MO Date Prepared: 1/9/2024</p>
<p>Only the following items of the Job Special Provisions (Bridge) are authenticated by this seal: All</p>	

JOB SPECIAL PROVISIONS (BRIDGE)

A. CONSTRUCTION REQUIREMENTS

1.0 Description. This provision contains general construction requirements for this project.

2.0 Construction Requirements. The plans and the asbestos and lead inspection report for the existing structure(s) and the geotechnical report for the new structure(s) are included in the contract in the bridge electronic deliverables zip file for informational purposes only.

2.1 In order to assure the least traffic interference, the work shall be scheduled so that the bridge closure is for the absolute minimum amount of time required to complete the work. The bridge shall not be closed until material is available for continuous construction and the contractor is prepared to diligently pursue the work until the closed bridge is opened to traffic.

2.2 Bridge work by contractor forces, including erection, rehabilitation or demolition, shall not be allowed over traffic unless a bridge platform protection system is installed below the work area except for work performed above a deck that is intact. The protection system shall be capable of catching all falling objects such as tools, overhang brackets or materials. Lifting of objects that are heavier than the capacity of the bridge protection system shall not be permitted.

2.3 Qualified special mortar shall be a qualified rapid set concrete patching material in accordance with [Sec 704](#). A qualified rapid set concrete patching material will not be permitted for half-sole repair, deck repair with void tube replacement, full depth repair, modified deck repair and substructure repair (formed) unless a note on the bridge plans specifies that a qualified special mortar may be used.

2.4 The existing slab for the bridge(s) to be redecked was constructed as composite or non-composite as shown in the table below.

Bridge No.	Type of deck
A0700	Non-composite

2.5 The bridge substructure for the widened portion of stage one construction shall be constructed as near to completion as feasible before removing the adjacent portions of existing superstructure.

2.6 Provisions shall be made to prevent any debris and material from falling onto the roadway. If determined necessary by the engineer, any debris and material that falls below the bridge outside the previously specified limits shall be removed as approved by the engineer at the contractor's expense. Traffic under the bridge shall be maintained in accordance with the contract documents.

2.7 Any damage sustained to the remaining structure as a result of the contractor's operations shall be repaired or the material replaced as approved by the engineer at the contractor's expense.

2.8 Provisions shall be made to prevent damage to any existing utilities. Any damage sustained to the utilities as a result of the contractor's operations shall be the responsibility of the contractor. All costs of repair and disruption of service shall be as determined by the utility owners and as approved by the engineer.

JOB SPECIAL PROVISIONS (BRIDGE)

2.10 A washer shall be required under head and nut when any reaming is performed for bolt installation.

2.11 SSPC-SP2 and SSPC-SP3 surface preparation shall be in accordance with the environmental regulations in [Sec 1081](#) and collection of residue shall be in accordance with [Sec 1081](#) for collection of blast residue. SSPC-SP6, SSPC-SP10 and SSPC-SP11 surface preparation shall be in accordance with the approved blast media and environmental regulations in [Sec 1081](#) and collection of blast residue shall be in accordance with [Sec 1081](#).

3.0 Coating Information.

3.1 Straps Removal. Exposed portions of straps for stay-in-place forms shall be removed prior to surface preparation. Straps need not be removed in areas that are not being painted. Flame cutting will not be permitted. The contractor shall exercise care not to damage the existing structure during removal. Any damage sustained to the remaining structure as a result of the contractor's operations shall be repaired or the material replaced as approved by the engineer at the contractor's expense.

3.2 Slab Drains and Stay-In-Place Forms. The stay-in-place forms, slab drains and slab drain brackets shall not be recoated, overcoated or damaged during the painting operation. Any portion of the slab drain bracket that is blast cleaned shall be recoated with System G. Any damage sustained as a result of the contractor's operations shall be repaired or the material replaced as approved by the engineer at the contractor's expense.

3.3 Existing Bridge Information. The informational plans may be used by bidders in determining the amount of steel to be cleaned and painted/coated with the full understanding that the State accepts no responsibility for accuracy of the estimated tons of existing steel shown in the table below. The bidder's acceptance and use of the estimate shown below shall be no cause for claim for any final adjustment in the contract unit price for the work involved in repainting. Each bidder is expected to carefully examine the structure(s), investigate the condition of existing paint and prepare their own estimate of quantities involved before submitting a bid. Surface preparation and applying field coatings to the structural steel shall be based on the contract plan quantities. No final measurements will be made.

Bridge No.	Estimated Tons			Existing Paint System	Lead Based
	Coating System		Total		
	System G	Calcium Sulfonate			
A0700	65	0	65	S	Yes

3.4 Environmental Contact. Environmental Section may be contacted at the below address or phone number. The Missouri Department of Health may be contacted at (573) 751-6102.

MoDOT - Design Division - Environmental Section
 P.O. Box 270
 105 W. Capitol Ave., Jefferson City, MO 65102
 Telephone: (573) 526-4778

3.5 Approved Smelter and Hazardous Waste Treatment, Storage and Disposal Facility. The following is the approved smelter and hazardous waste treatment, storage and disposal facility:

JOB SPECIAL PROVISIONS (BRIDGE)

Doe Run Company - Resource Recycling Division - Buick Facility
Highway KK
Boss, MO 65440
Telephone: (573) 626-4813

4.0 Method of Measurement. No measurement will be made.

5.0 Basis of Payment. Payment for the above described work will be considered completely covered by the contract unit price for other items included in the contract.

B. RAPID SET CONCRETE PATCHING MATERIAL – VERTICAL AND OVERHEAD REPAIRS

1.0 Description. This specification covers cementitious concrete, polymer-modified concrete and polymer concrete that are suitable for repairing concrete surfaces on bridges or concrete structures, particularly under fast setting or special conditions. The repairs would involve vertical or overhead applications. The work shall consist of removing, furnishing, preparing, and placing materials at locations as shown on the plans or as directed by the engineer.

2.0 Material. All materials shall be in accordance with MoDOT specifications and as noted herein.

2.1 Aggregate. For Extending Commercial Mixture. Coarse and fine aggregates shall be in accordance with [Sec 1005](#), except the requirements for gradation and percent passing the No. 200 sieve shall not apply. Coarse aggregate meeting Gradation E requirements shall be used for repairs greater than one inch (25 mm) in depth. Fine aggregate will be allowed for repairs less than one inch (25 mm). Aggregate specified, bagged, labeled and furnished by the rapid set concrete patching material manufacturer may also be used for mortar extension.

2.2 Material Applications. The contractor shall select and use the product most suitable for the work and field conditions in accordance with these specifications.

2.3 Curing. Rapid set concrete patching material shall be cured until the minimum compressive strength 1500 psi is attained using standard curing specifications, unless otherwise specified by the manufacturer.

2.4 Qualification and Project Acceptance.

2.4.1 Inspection. All materials shall be subject to inspection and sampling by MoDOT at the source of manufacture, intermediate shipping terminal or destination. MoDOT will be allowed free access to all facilities and records as required to conduct inspection and sampling.

2.4.2 Qualification. Prior to use, rapid set concrete patching materials need to be qualified.

2.4.2.1 Requested Information. The manufacturer shall submit with samples of the materials, a written request to Construction and Materials with the following information:

- (a) New Products Evaluation Form
- (b) Brand name of the product.
- (c) Certification that the material meets this specification.

- (d) Certified test results from an independent laboratory showing compliance with this specification.
- (e) Specific preparation instructions of repair area.
- (f) Specific mixing, handling and curing instructions.
- (g) Application type (i.e., vertical or overhead).

2.4.2.2 Field Evaluation. Final approval will be granted when the following requirements are met:

- (a) MoDOT report documenting two years of field performance on MoDOT system. The report will contain the placement date, field observations (semi annual), description of field performance and photographs of in-place material.
- (b) A manufacturer's representative shall be present during placement of the material to provide technical expertise.

2.4.2.2.3 Disqualification. If during the two year observation period the repair area(s) fails the product will not be added to the qualified list.

2.5 Qualified List. The listing of qualified products are available from Construction and Materials or on MoDOT's web site. New certified test results and samples shall be submitted any time the manufacturing process or the material formulation is changed. The material will be subject to removal from the qualified list if there is evidence of unsatisfactory performance or a change in manufacturing process or formulation, or when random sampling and testing of material offered for use indicates nonconformity with any of the requirements herein specified.

2.6 Certification. The contractor shall supply a manufacturer's certification to the engineer for each lot of material furnished. The certification shall include the name of the manufacturer, a manufacturer certification statement that the material supplied is the same as that qualified and listing the date of qualification.

2.7 Acceptance. Acceptance of the material will be based on the use of a qualified product, the manufacturer's certification that the material supplied is the same as that approved and upon the results of such tests as may be performed by the engineer.

3.0 Mixture. Unless otherwise specified, rapid set concrete patching material shall be approved commercial mixtures meeting [Sections 3.1 – 3.1.3.](#) Rapid set concrete patching materials shall be specifically designed for the application needed.

3.1 Commercial Mixtures. Rapid set concrete patching material in its sacked form and mixtures when properly prepared in accordance with the manufacturer's specifications, shall meet the minimum test requirements given in Table 1. Mixtures may be supplied, as required, as a patching mortar or as a patching mortar with aggregate extension. If the material is to be supplied with extender aggregate, this shall also pass the required tests in Table 1 using the maximum allowed amount of extender aggregate.

3.1.1 Mixture Requirements. Rapid set concrete patching material shall be single packaged dry mix requiring the addition of water or other liquid component just prior to mixing. The

JOB SPECIAL PROVISIONS (BRIDGE)

material shall not contain soluble chlorides as an ingredient of manufacture. The material shall be placed in accordance to the manufacturer's recommendations.

Table 1 (English Unit)				
Physical Test Property	Specification	Requirement for cementitious concrete	Requirement for polymer-modified concrete	Requirement for polymer concrete
Bond Strength by Slant Shear	ASTM C882/C928 ²	min. 1000 psi @ 24hrs.& min. 1500 psi @ 7 days	n/a	min. 1000 psi @ 24hrs.& min. 1500 psi @ 7 days
Linear Coefficient of Thermal Expansion ¹ (for bagged mortar only, without extension aggregate)	ASTM C531	n/a	n/a	4 – 8 X 10 ⁻⁶ in/in/deg F
Resistance to Rapid Freezing & Thawing	AASHTO T161 or ASTM C666	80% min. using Procedure B ³ (300 Cycles)	80% min. using Procedure B ³ (300 Cycles)	n/a
Compressive Strength	AASHTO T22 or ASTM C39	1500 psi @ 3 hr & 3000 psi @ 24 hr	1500 psi @ 3 hr & 3000 psi @ 24 hr	n/a
Rapid Chloride Permeability	AASHTO T277 or ASTM C1202	1000 coulombs @ 28 days	1000 coulombs @ 28 days	1000 coulombs @ 28 days
Length Change	AASHTO T 160 or ASTM C157	In water Storage (+0.15) In air storage (-0.15)	In water storage (+0.15) In air storage (-0.15)	n/a
Color		gray	gray	gray

¹ Not required for extended mixtures if the mortar passes this requirement.

² ASTM C882 shall be performed on non-water based materials. ASTM C928 shall be performed on water-based materials.

³ Procedure A may be used in lieu of Procedure B

3.1.2 Construction Requirements. The manufacturer shall provide with the bagged mixture, specifications for the mixing procedure, amount and kind of liquid to be added, and the amount of aggregate extension allowed, if any. All mixing, handling and curing practices recommended by the manufacturer shall be followed and will be considered a part of these specifications.

3.1.3 Removal from Qualified List. All mixtures shall be approved before use. Reoccurring failures of any mixture for any reason will be cause for removal from the qualified list.

3.2 Vertical Repair. A qualified rapid set concrete patching material approved for vertical use may be used when specified on the plans and as approved by the engineer. The engineer will make field cylinders to verify the 1500 psi (10 MPa) minimum strength. The material shall adhere to the concrete surface without sagging.

JOB SPECIAL PROVISIONS (BRIDGE)

3.3 Overhead Repair. A qualified rapid set concrete patching material approved for overhead use may be used when specified on the plans and as approved by the engineer. The material shall be placeable in layers of at least 1 inch on overhead applications without the use of formwork or anchoring devices. The material shall adhere to the concrete surface without sagging. The engineer will make field cylinders to verify the 1500 psi (10 MPa) minimum strength.

4.0 Construction Requirements.

4.1 Mixing. Rapid set concrete patching material shall be mixed and finished according to the manufacturer's recommendation.

4.2 Preparation of Repair Area. Deteriorated, damaged or defective concrete as shown on the plans, required by the specifications or as directed by the engineer, shall be removed. All exposed reinforcement shall be thoroughly cleaned as shown on the plans, required by the specifications or as directed by the engineer. Unless otherwise specified by the commercial mixture manufacturer, the existing surface shall be damp and all free water shall be removed prior to placement of the required material.

4.3 Bonding Agent. A bonding agent may be used if recommended by the rapid set concrete patching material manufacturer.

5.0 Method of Measurement. No measurement will be made for rapid set concrete patching material.

6.0 Basis of Payment. Rapid set concrete patching material will be paid for at the contract unit price for other items and will be considered full compensation for all labor, equipment and material to complete the described work.

C. RAPID SET CONCRETE PATCHING MATERIAL – HORIZONTAL REPAIRS

1.0 Description. This specification covers cementitious concrete, polymer-modified concrete and polymer concrete that are suitable for repairing concrete surfaces on bridges or roadways, particularly under fast setting or special conditions. The repairs would involve horizontal applications. The work shall consist of removing, furnishing, preparing, and placing materials at locations as shown on the plans or as directed by the engineer.

2.0 Material. All materials shall be in accordance with MoDOT specifications and as noted herein.

2.1 Aggregate For Extending Commercial Mixture. Coarse and fine aggregates shall be in accordance with [Sec 1005](#), except the requirements for gradation and percent passing the No. 200 sieve shall not apply. Coarse aggregate meeting Gradation E requirements shall be used for repairs greater than one inch (25 mm) in depth. Fine aggregate will be allowed for repairs less than one inch (25 mm). Aggregate specified, bagged, labeled and furnished by the rapid set concrete patching material manufacturer may also be used for mortar extension.

2.2 Material Applications. The contractor shall select and use the product most suitable for the work and field conditions in accordance with these specifications.

JOB SPECIAL PROVISIONS (BRIDGE)

2.3 Curing. Rapid set concrete patching material shall be cured until the minimum compressive strength 3200 psi is attained using standard curing specifications, unless otherwise specified by the manufacturer.

2.4 Qualification and Project Acceptance.

2.4.1 Inspection. All materials shall be subject to inspection and sampling by MoDOT at the source of manufacture, intermediate shipping terminal or destination. MoDOT will be allowed free access to all facilities and records as required to conduct inspection and sampling.

2.4.2 Qualification. Prior to use, rapid set concrete patching material shall be qualified. In order to become qualified, a material shall have completed testing through AASHTO's National Transportation Product Evaluation Program (NTPEP). The manufacturer shall contact the AASHTO/NTPEP coordinator to obtain the testing location for the rapid setting concrete patching material.

2.4.2.1 Requested Information. The manufacturer shall submit with samples of the materials, a written request to Construction and Materials with the following information:

- (a) Brand name of the product.
- (b) Certification that the material meets this specification.
- (c) NTPEP test results showing compliance with this special provision.
- (d) Specific mixing, handling and curing instructions.
- (e) Application type (i.e., bridge or roadway).

2.4.2.2 Qualified List. Upon approval by the engineer, the brand name and manufacturer will be placed on a qualified list of rapid set concrete patching materials. The listing of qualified materials is available from Construction and Materials or on MoDOT's web site. New certified test results and samples shall be submitted any time the manufacturing process or the material formulation is changed. The material will be subject to removal from the qualified list if there is evidence of unsatisfactory performance or a change in manufacturing process or formulation, or when random sampling and testing of material offered for use indicates nonconformity with any of the requirements herein specified.

2.4.3 Provisional Approval. Provisional approval may be granted provided the following requirements have been met:

- (c) New Products Evaluation Form
- (d) Certified test results from an independent laboratory showing compliance with this special provision.
- (e) Documentation prepared by MoDOT covering two years of field performance on MoDOT's system. MoDOT will need to approve the location of the test site. Documentation will contain the placement date, field observations (semi annual), description of field performance and photographs of in-place material.

JOB SPECIAL PROVISIONS (BRIDGE)

(f) During placement the manufacturer’s representative shall be present on the project to provide technical expertise.

2.4.3.1 Disqualification. If during the two year observation period the repair area(s) fails provisional approval will not be granted. Repair area(s) experiencing any cracking, debonding or spalling will be considered a failure.

2.4.3.2 Length of Provisional Approval. Provisional approval will be granted for three years or until NTPEP testing is completed.

2.5 Certification. The contractor shall supply a manufacturer's certification to the engineer for each lot of material furnished. The certification shall include the name of the manufacturer, a manufacturer certification statement that the material supplied is the same as that qualified and listing the date of qualification.

2.6 Acceptance. Acceptance of the material will be based on the use of a qualified or provisionally approved material, the manufacturer's certification that the material supplied is the same as that approved and upon the results of such tests as may be performed by the engineer.

3.0 Mixture. Unless otherwise specified, rapid set concrete patching material shall be approved commercial mixtures meeting [Sections 3.1 – 3.1.3](#) or deck repair cementitious mortar meeting [Section 3.2](#). Rapid set concrete patching materials shall be specifically designed for the application needed.

3.1 Commercial Mixtures. Rapid set concrete patching material in its sacked form and mixtures when properly prepared in accordance with the manufacturer’s specifications, shall meet the minimum test requirements given in Table 1. Mixtures may be supplied, as required, as a patching mortar or as a patching mortar with aggregate extension. If the material is to be supplied with extender aggregate, this shall also pass the required tests in Table 1 using the maximum allowed amount of extender aggregate.

3.1.2 Mixture Requirements. Rapid set concrete patching material shall be single packaged dry mix requiring the addition of water or other liquid component just prior to mixing. The material shall be capable of ½ inch (13 mm) to full depth repair and require no bonding agent. The material shall not contain soluble chlorides as an ingredient of manufacture. The material shall be placed in accordance to the manufacturer's recommendations.

Table 1 (English Unit)				
Physical Test Property	Specification	Requirement for cementitious concrete	Requirement for polymer-modified concrete	Requirement for polymer concrete
Bond Strength by Slant Shear ¹	ASTM C882/C928 ³	min. 1000 psi @ 24hrs. & min. 1500 psi @ 7 days	n/a	min. 1000 psi @ 24hrs. & min. 1500 psi @ 7 days
Linear Coefficient of Thermal Expansion ^{1, 2} (for bagged mortar)	ASTM	n/a	n/a	4 – 8 X 10-6 in/in/deg F

JOB SPECIAL PROVISIONS (BRIDGE)

only, without extension aggregate)	C531			
Resistance to Rapid Freezing & Thawing ¹	AASHTO T161 or ASTM C666	80% min. using Procedure B ⁵ (300 Cycles)	80% min. using Procedure B ⁵ (300 Cycles)	n/a
Compressive Strength ¹	AASHTO T22 or ASTM C39	3200 psi @ 3 hr & 4000 psi @ 7 days	3200 psi @ 3 hr & 4000 psi @ 7 days	n/a
Rapid Chloride Permeability ¹	AASHTO T277 or ASTM C1202	<u>Bridge Decks</u> 1000 coulombs @ 28 days <u>Roadway</u> 2000 coulombs @ 28 days	<u>Bridge Deck</u> 1000 coulombs @ 28 days <u>Roadway</u> 2000 coulombs @ 28 days	<u>Bridge Deck</u> 1000 coulombs @ 28 days <u>Roadway</u> 2000 coulombs @ 28 days
Length Change ^{1, 4}	AASHTO T 160 or ASTM C157	In water Storage (+0.15) In air storage (-0.15)	In water storage (+0.15) In air storage (-0.15)	n/a
Color		gray	gray	gray

¹The commercial mix test values can be located in the AASHTO's National Transportation Product Evaluation Program (NTPEP) reports for Laboratory Evaluations of Rapid Set Concrete Patching Materials. Data for provisionally approved materials is located at the Construction and Materials Division.

²Not required for extended mixtures if the mortar passes this requirement.

³ ASTM C882 shall be performed on non-water based materials. ASTM C928 shall be performed on water-based materials.

⁴ As modified by ASTM C928.

⁵ Procedure A may be used in lieu of Procedure B

3.1.2 Construction Requirements. The manufacturer shall provide with the bagged mixture, specifications for the mixing procedure, amount and kind of liquid to be added, and the amount of aggregate extension allowed, if any. All mixing, handling and curing practices recommended by the manufacturer shall be followed and will be considered a part of these specifications.

3.1.3 Removal from Qualified List. All mixtures shall be approved before use. Reoccurring failures of any mixture for any reason will be cause for removal from the qualified list.

3.2 Deck Repair Concrete. A qualified rapid set concrete patching material indicated for horizontal use and intended for patching concrete bridge decks may be used when specified on the plans and as approved by the engineer. If this option is selected, the contractor shall provide a trial mix to determine the total cure time needed to achieve a compressive strength of 3200 psi (22 MPa). Compressive specimens shall be prepared in accordance with current MoDOT test methods and cured to simulate actual field conditions. Testing of compressive specimens shall be performed by methods and at facilities acceptable to the engineer. The repaired deck shall not be opened to traffic until at least 4 hours after the last placement of deck repair concrete, the established cure time has elapsed and until such concrete has achieved a compressive strength of 3200 psi (22 MPa). A new trial mix may be required if the engineer determines the field conditions vary substantially from trial mix conditions. The engineer will make field cylinders to verify the 3200 psi (22 MPa) minimum strength.

4.0 Construction Requirements.

4.1 Mixing. Rapid set concrete patching material shall be mixed and finished according to the manufacturer's recommendation.

4.2 Preparation of Repair Area. Deteriorated, damaged or defective concrete as shown on the plans, required by the specifications or as directed by the engineer, shall be removed. All exposed reinforcement shall be thoroughly cleaned as shown on the plans, required by the specifications or as directed by the engineer. Unless otherwise specified by the commercial mixture manufacturer, the existing surface shall be damp and all free water shall be removed prior to placement of the required material.

4.3 Bonding Agent. A bonding agent may be used if recommended by the rapid set concrete patching material manufacturer.

5.0 Method of Measurement. No measurement will be made for rapid set concrete patching material.

6.0 Basis of Payment. Rapid set concrete patching material will be paid for at the contract unit price for other items and will be considered full compensation for all labor, equipment and material to complete the described work.

D. DECORATIVE PEDESTRIAN FENCE

1.0 Description. This work shall consist of fabricating and installing a steel decorative pedestrian fence to provide a complete and properly functioning fence system as indicated on the plans and in this specification.

2.0 Performance Requirements.

2.0.1 The fence design shall allow for thermal movement of 1/4 inch per 30 feet of fence, minimum. The fence design shall account for the differential thermal expansion characteristics of the fence and concrete to which it is mounted.

2.0.2 Base plate shall be furnished for mounting posts to top of concrete. Base plate anchors shall be cast into the concrete.

2.1 Materials. Decorative fence system products shall meet or exceed the following requirements.

2.1.1 Acceptable Manufacturer Systems. The chosen decorative fence system shall be the same for all bridges in this project. Decorative fence system shall meet the performance requirements as stated in this special provision and shall consist of one of the approved decorative fence systems listed on the Bridge Pre-qualified Product Listing.

2.1.2 Visual Condition. Metal free from surface blemishes shall be provided where exposed to view in the finished unit. Exposed-to-view surfaces exhibiting pitting, seam marks, roller marks, stains, discolorations, or other imperfections on finished units are not acceptable.

2.1.3 Surface Coatings. The steel shall be hot-dip galvanized to meet the requirements of ASTM A 653 with a minimum zinc coating weight of 0.90 oz/sf, coating designation G-90. Surface preparation of galvanized surface for the aliphatic polyurethane finish coat shall be in

JOB SPECIAL PROVISIONS (BRIDGE)

accordance with the product specifications for the finish coat. The exterior of all fence components shall be coated with an aliphatic polyurethane finish coat to provide a total dry film thickness of 4 mils minimum and 6 mils maximum. The color of the finish coat shall be black (Federal Standard #17038).

2.2 Construction Requirements.

2.2.1 Delivery, storage, handling and installation methods shall be per fence manufacturer's recommendations.

2.2.2 Fence posts shall be spaced no greater than the maximum post spacing shown on the plans, plus one-half inch. For installations along sloping grades, the post spacing will be measured along the grade. Separation gaps shall be provided at a minimum of every six panels.

2.2.3 For field assembly, zinc-rich primer shall be applied to thoroughly cover field-cut or field-drilled edges. Two coats of manufacturer supplied finish paint shall be applied to match fence color.

2.3 Warranty. All structural fence components shall be warranted by the manufacturer for a period of ten (10) years from the date of final acceptance by the engineer. Warranty shall cover any defects in material finish, including cracking, peeling, chipping, blistering, or corrosion and necessary labor required to replace or restore such parts.

3.0 Method of Measurement. Measurement shall be made horizontally and to nearest linear foot of fence installed.

4.0 Basis of Payment. Payment for the work described above and on the contract plans, including all material, equipment, labor, and any other incidental work necessary, will be considered completely covered by the contract unit price for (72 in.) Decorative Pedestrian Fence (Structures) depending on the bidding alternate as outlined in the Roadway Job Special Provisions.

E. DEFLECTION AND HAUNCHING

1.0 Description. The contractor shall determine dead load deflections and haunching based on field measurements and/or existing bridge plans and these shall be adjusted based on the difference between the new and existing dead load weights.

2.0 Construction Requirements. In order to properly form the haunches for the new deck, the contractor shall survey top of deck elevations above each beam including centerline of roadway and along each beam line (top or bottom flange) prior to deck removal followed by surveying elevations of the beams (top or bottom flange) after deck removal.

3.0 Method of Measurement. No measurement will be made.

4.0 Basis of Payment. Payment for the above described work will be considered completely covered by the contract unit price for other items included in the contract.

F. DYNAMIC PILE TESTING

JOB SPECIAL PROVISIONS (BRIDGE)

1.0 General.

1.1 Scope of Work. Scope of work shall include furnishing all labor, equipment and analysis associated with dynamic testing of driven piles as specified in this special provision.

1.2 Performance and Design Requirements. Performance and design conditions for dynamic testing of driven piles shall be in accordance with [section 4.0](#) of this special provision.

1.3 Approved Manufacturers. For the following hardware and software components, only the listed manufacturer is recognized as providing the level of quality required. If the contractor wants to propose a non-listed manufacturer that is considered to provide an equivalent level of quality, this manufacturer shall be identified and supporting documentation provided. Acceptance of the manufacturer as a substitute will be at the discretion of the engineer.

Component	Product	Manufacturer
Pile Driving Modeling - Wave Equation Software	<u>GRLWEAP</u>	<u>Pile Dynamics, Inc.</u>
Pile Driving Monitoring - Hardware & Software	Pile Driving Analyzer - Model PAK	Pile Dynamics, Inc.
Pile Driving Analysis – Signal Matching Software	<u>CAPWAP</u>	<u>Pile Dynamics, Inc.</u>

1.4 Test Requirements. Dynamic pile testing shall be conducted in accordance with the standard test method indicated below.

Standard Test Method	Designation	Conducted By
High-Strain Dynamic Testing of Piles	ASTM D 4945	Contractor

1.5 Qualifications. The contractor shall perform dynamic pile testing utilizing the services of an independent dynamic pile testing consultant and qualified personnel. An engineer with a minimum of three years of dynamic pile testing and analysis experience or who has achieved Basic or better certification under the High-Strain Dynamic Pile Testing Examination and Certification process of the Pile Driving Contractors Association and Foundation QA shall perform pile driving monitoring. An engineer with a minimum of five years of dynamic pile testing and analysis experience or who has achieved Advanced or better certification under the High-Strain Dynamic Pile Testing Examination and Certification process of the Pile Driving Contractors Association and Foundation QA shall perform pile driving modeling and pile driving analyses.

2.0 Execution.

2.1 Pile Driving Modeling. The contractor shall perform preconstruction wave equation analyses and prepare a summary report of the results. The wave equation analyses shall be used to assess the ability of all proposed pile driving systems to install piles to the required capacity and the desired penetration depth within allowable driving stresses. The report shall include a drivability graph relating pile capacity, blow count and driving stresses to depth. The report shall include a bearing graph relating the pile capacity to the pile driving resistance. The bearing graph shall indicate blow count versus capacity and stroke. The report shall also contain a constant capacity analysis or inspectors chart to assist the engineer in determining the required driving resistance at other field observed strokes. The contractor shall perform wave equation analyses in accordance with [section 4.0](#) of this special provision. Acceptability of the wave equation report and the adequacy of analyses will be determined by the engineer.

2.1.1 Approval by the engineer of the proposed pile driving system will be based upon the wave equation analyses indicating that the proposed system can develop the specified pile capacity at a pile driving rate of 2 to 10 blows per inch at the end of driving, and within allowable driving stresses per *AASHTO LRFD Bridge Construction Specifications*, Section 4.4.1. The contractor shall provide preliminary pile driving criteria based on wave equation analyses and any anticipated capacity changes after driving, set-up or relaxation, subject to revision based upon dynamic pile testing field measurements.

2.1.2 If any changes or modifications are made to the approved pile driving system, additional wave equation analyses in accordance with [section 2.1](#) of this special provision shall be required.

2.2 High-Strain Dynamic Pile Testing.

2.2.1 The contractor shall perform dynamic pile testing at the locations and frequency required in accordance with [section 4.0](#) of this special provision.

2.2.2 Dynamic pile testing involves monitoring the response of a pile subjected to heavy impact applied by the pile hammer at the pile head. The testing shall provide information on the driving stresses, pile capacity, structural integrity and hammer efficiency.

2.2.3 The contractor shall engage an independent dynamic pile testing consultant and qualified personnel in accordance with [section 1.5](#) of this special provision. Prior to testing, the engineer will review and approve the proposed independent dynamic pile testing consultant, the experience and qualifications of assigned personnel, details of the method of testing, a list of equipment, and the method of analysis of test results. The contractor shall provide all available details of the subsurface conditions, pile dimensions and properties, and pile driving systems to the independent dynamic pile testing consultant.

2.2.4 All field testing and measurements shall be made in the presence of the engineer.

2.3 Field Testing.

2.3.1 Equipment. Dynamic pile testing field measurements shall be carried out using approved equipment, software and recording equipment. The data collected at the end of initial driving and the beginning of restrike shall be analyzed using approved signal matching techniques and software.

2.3.2 Monitoring During Driving. During pile driving, piles shall be instrumented and monitored with testing equipment satisfying the requirements of [section 1.3](#) of this special provision.

2.3.2.1 The contractor shall install two sets of strain transducers and accelerometers near the top of each pile to be tested and shall use a compatible measuring and recording system to record the data during driving.

2.3.2.2 The equipment required to be attached to the pile shall be appropriately positioned and fixed to the approval of the engineer.

2.3.2.3 The hammer and all site equipment used shall be capable of delivering an impact force sufficient to mobilize the specified pile capacity indicated in [section 4.0](#) of this special provision without damaging the pile.

2.3.2.4 The testing equipment shall monitor pile stresses during driving to prevent pile damage and ensure pile integrity and capacity. If the testing equipment indicates overstressing or damage to the pile, the contractor shall immediately discontinue driving and notify the engineer.

2.3.2.5 If the testing equipment determines that pile stresses during driving exceed acceptable levels, a new pile driving system, modifications to existing system or new pile installation procedures shall be proposed by the contractor. Approval by the engineer of any proposed changes to the pile driving system or pile installation procedures will be based upon the results of additional wave equation analyses in accordance with [section 2.1.2](#) of this special provision.

2.3.3 Preparation of the Pile Head. The preparation of the pile head for the application of dynamic test load shall involve, where appropriate, trimming the head, cleaning, and building up the pile using materials that shall, at the time of testing, safely withstand the impact stresses. The impact surface shall be flat and at right angles to the pile axis.

2.3.4 Dynamic Measurement and Analysis. Monitoring of pile driving shall begin when pile driving begins. The data shall be recorded and processed immediately in the field by the pile driving monitoring equipment and software. Unless monitoring indicates that additional driving will damage the pile, pile driving and monitoring shall continue until both the specified pile tip elevation and the specified pile capacity are reached. For each pile tested, pile driving analysis using signal matching techniques shall be performed for a selected blow at the end of driving to determine the relative capacities from end bearing and skin friction along the pile.

2.3.4.1 Restrike tests shall be performed at the frequency indicated in [section 4.0](#) of this special provision. The time interval between end of initial driving and beginning of restrike shall be in accordance with [section 4.0](#) of this special provision. During restrike, the pile shall be instrumented and monitored similar to during initial driving. For each restrike test, pile driving analysis using signal matching techniques shall be performed for a selected blow from the beginning of restrike to determine the relative capacities from end bearing and skin friction along the pile.

2.3.4.2 The restrike test shall be performed with a warmed-up hammer and shall consist of striking the pile for 20 blows or until the pile penetrates an additional 3 inches whichever occurs first unless testing equipment indicates overstressing or damage to the pile. If such overstressing or damage to the pile is indicated, the contractor shall immediately discontinue driving and notify the engineer. In the event initial restrike testing indicates a pile capacity below the specified capacity additional driving may be required as directed by the engineer.

2.3.4.3 The engineer may request use of pile driving monitoring equipment and software on additional piles if inconclusive results are obtained or unusual driving conditions are encountered.

2.3.4.4 Pile bearing capacity and integrity shall be evaluated based on the standard procedure used in practice.

2.3.4.5 Tabular records of the dynamic pile testing field measurements obtained at the end of initial driving and at the beginning of restrike shall be immediately provided to the engineer by the contractor.

2.3.5 Results.

2.3.5.1 Preliminary Reports. The contractor shall prepare a preliminary report for each pile tested for review by the engineer. Each report shall contain tabular as well as graphical presentation of the dynamic test results versus depth. Each report shall also indicate the pile driving criteria for the additional piles to be installed at the substructure unit of the pile tested. Each preliminary report shall include the following:

- (a) The maximum force applied to the pile head.
- (b) The maximum pile head velocity.
- (c) The maximum energy imparted to the pile.
- (d) The assumed soil damping factor and wave speed.
- (e) Static capacity estimate.
- (f) The maximum compressive and tensile forces in the pile.
- (g) Pile integrity.
- (h) Blows per inch.
- (i) Stroke.
- (j) Summary results of pile driving analysis from selected blow analyzed using signal matching techniques and software.

2.3.5.2 Summary Report. The contractor shall prepare a summary report of all piles tested for review by the engineer. The report shall include the results of hammer performance, pile driving stresses, and pile capacity during initial driving and restrike for all piles tested. The report shall also include the following:

- (a) Date of testing and date of pile installation.
- (b) Pile identification number and location.
- (c) All information given in preliminary reports as follows:
 - (1) Length of pile below commencing surface.
 - (2) Total length of pile, including projection above commencing surface at time of test.
 - (3) Length of pile from instrumentation position to tip.
- (d) Hammer type, drop and other relevant details.
- (e) Blow selected for signal matching analysis.

JOB SPECIAL PROVISIONS (BRIDGE)

- (f) Maximum compressive and tensile stresses, stroke, and capacity versus penetration depth.
- (g) Temporary compression.
- (h) Pile integrity and location of damage, if any.
- (i) Force/velocity versus time trace.
- (j) Force/velocity match curve.
- (k) Resistance distribution along the pile.
- (l) Detailed graphical and tabular results from blow analyzed using signal matching techniques and software.

3.0 Schedule of Contract Submittals.

Item Number	Submittal Item	Type	Calendar Days	Event/Date	Liquidated Damages Apply
1	Proposed independent dynamic pile testing consultant, and a listing of assigned personnel and their experience and qualifications.	DOCS	45 Before	Start of pile driving monitoring	No
2	Details of the components, method of testing, pile driving equipment and materials to be used, and the results of wave equations analyses.	DOCS	15 Before	Start of pile driving monitoring	No
3	Two copies of each Preliminary Report as defined in section 2.3.5.1 of this special provision	DOCS	3 After	Completion of each field test	No
4	Four copies of the Summary Report as defined in section 2.3.5.2 of this special provision	DOCS	7 After	Completion of all field tests	No

4.0 High-Strain Dynamic Pile Testing Specification.

Item	Requirement
Wave Equation Analysis	Minimum of one and sufficient additional analyses as needed to define performance for all combinations of piles, driving systems and subsurface conditions anticipated.

JOB SPECIAL PROVISIONS (BRIDGE)

Item	Requirement
Dynamic Testing Pile Capacity	Nominal Axial Pile Compressive Resistance or 2.25 times the Design Bearing shown on the plans or as required by engineer
End of Initial Driving Test Frequency	As shown in the contract plans
Restrike Test Frequency	As shown in the contract plans
Time Interval between End of Initial Driving and Restrike	Minimum of 7 days or as required by the engineer
Pile Driving Analyses using Signal Matching Techniques	For each End of Initial Driving Test and each Restrike Test

5.0 Method of Measurement. Dynamic pile testing and dynamic pile restrike testing will be measured per each.

6.0 Basis of Payment. Payment for the above described work, including all material, equipment, tools, labor and any other incidental work necessary to complete this item, will be considered completely covered by the contract unit price for Dynamic Pile Testing and Dynamic Pile Restrike Testing.

G. FORM LINERS

1.0 Description. This work item shall consist of constructing the form liner aesthetic treatment on cast-in-place concrete, mechanically stabilized earth (MSE) wall systems, and architectural elements as shown on the plans and described in this special provision.

2.0 Materials.

2.1 Shop Drawings. Contractor shall provide complete shop drawings of all aesthetic treatments.

2.2 Formwork. Formwork for aesthetic treatment of the cast-in-place concrete, concrete facing panels for the MSE wall systems, and architectural elements shall be a type that produces uniform results consistent in both, pattern and depth of relief with the project design aesthetics. The contractor shall be responsible to coordinate the aesthetic treatments of all components to meet the design aesthetic criteria described herein and as shown on plans. No mixing of pattern numbers or manufacturers will be permitted. The form liner pattern shall be one of the patterns listed on the plans or approved equal.

2.3 Form Ties. Wall form ties shall be placed in a uniform pattern. In surface areas receiving the aesthetic treatment form liner, all form ties shall be placed in the simulated stone surface. Form ties shall be fiberglass ties that shall hold the forms in the correct alignment. The color of the ties shall closely match the concrete wall color. Ties shall be ground flush with the surface of concrete prior to pressure washing.

2.4 Form Release Agent. Form release agents shall be the manufacturer's standard non-staining, non-petroleum based and compatible with surface sealer finish coating. Form release agents shall be applied to all surfaces of the form liner at the manufacturer's recommended rate.

2.5 Gaskets. Closed cell compressible neoprene of such thickness as is appropriate to assure leakage prevention shall be used to prevent joint leakage. One face shall be coated with an adhesive tape to assure proper positioning at the time of form closure. The neoprene shall be

sufficiently compressible as to assure virtual “zero” separation of the forms as a result of the use of this product.

2.6 Aggregates.

2.6.1 Aggregate Source. The aggregate incorporated into the concrete mix of all aesthetic concrete MSE Wall components shall be from the same source. The aggregate incorporated into the concrete mix of all aesthetic concrete bridge components shall be from the same source as the balance of the bridge concrete work. The purpose for this provision is to ensure uniformity of materials and color once areas are pressure washed and aggregates become exposed. Single-source shall be interpreted as one contiguous rock quarry, gravel pit or dredging location. This provision in no way alters the specification requirements for aggregate quality specified in other sections of the project specifications.

2.6.2 Aggregate Gradation. Concrete mixes supplied for the construction of the aesthetic treatments shall be in accordance with the following requirements. The concrete aggregate for the aesthetic treatment mix shall be Gradation E in accordance with [Sec 1005](#) for any areas where aesthetic treatment is formed monolithically with the structure. This requirement for aggregate size is necessary to permit concrete mixture to flow freely and fill completely into reveals and form liner proposed in the aesthetic treatment. Gradation E aggregate shall meet the aggregate source requirements.

2.7 Joint Materials. Bond breaker material shall be polyethylene tape, coated paper, metal foil or similar type materials. The backup material shall be compressible, non-shrink, non-reactive with the sealant and non-absorptive material type such as extruded butyl or polychloroprene foam rubber. The joint sealant shall be an elastomeric, multi-component sealant, in accordance with Federal Specification TT-S-227, Type II. The sealant color shall match the pressure washed concrete surface color.

3.0 Construction Requirements.

3.1 Reveals and Texture. All reveals and texture shall be continuous from element to element through construction joints and around corners. Techniques shall be utilized to ensure true continuous texture between separate elements. Sand blasting will not be permitted for cleaning concrete surface, as sand blasting will reduce the special surface texture specified. Pressure washing with water is the preferred method of removing laitance. Pressure washing cleaning shall provide a minimum pressure of 3000 psi at a rate of 3 to 4 gallons per minute (11.4 to 15.1 L/min) using a fan nozzle held perpendicular to the surface at a distance of 2 to 3 feet. The completed surface shall be free of blemishes, discolorations, surface voids and conspicuous form marks to the satisfaction of the engineer.

3.2 Sample Test Panels. Sample test panels shall be constructed to demonstrate the contractor’s workmanship for all form liner textures and patterns as shown on the plans. The sample test panels may also be used for demonstration special surface finish if approved by the engineer. The architectural surface treatment of the finished work shall achieve the same final effect as demonstrated on the approved sample test panels. The materials used in construction of the sample test panels shall be in accordance with all standards as listed in this specification and the plans. The concrete mix shall be consistent with the project specifications and criteria. The minimum size of the sample test panels shall be 6 x 6 feet x 8 inches. The form liner finish shall be demonstrated in a vertical strip covering one-half to three-quarters of the sample test panel(s).

JOB SPECIAL PROVISIONS (BRIDGE)

3.3 Patches. Holes and defects in concrete surface shall be filled within 48 hours of when the forms are removed. The same patching materials and techniques shall be used that were approved on sample test panels. The patches shall be made with a stiff mortar made with the same material sources as the concrete. The mortar mix proportions shall be adjusted so the dry patch matches the dry adjacent concrete. White cement shall be added to the mortar mix if necessary to lighten the mortar mix.

3.4 Joints. Joints shall be sealed when the sealant, air and concrete temperatures are above 40°F. Joints shall be primed and filled flush with joint sealant in accordance with the manufacturer's recommendation. All construction control and expansion joints shall occur within the vertical joints as shown in the elevation views on the plans. All vertical expansion joints shall be filled with preformed fiber expansion joint filler covered with bond break tape and sealed with elastomeric, multi-component sealant.

4.0 Method of Measurement. Final measurement will not be made except for authorized changes during construction or where significant errors are found in the contract quantity. The revision or correction will be computed and added to or deducted from the contract quantity.

4.1 Form Liners on MSE Wall Systems. No measurement of form liners on MSE wall systems shall be made.

4.2 Architectural Elements. Measurement will be made per each.

4.3 Form Liners for Cast-In-Place Concrete. Measurement of form liners will be made to the nearest square yard.

5.0 Basis of Payment.

5.1 Form Liners on MSE Wall Systems. Payment for the above described work, including all material, additional concrete, equipment, labor and any other incidental work necessary to complete this item, will be considered completely covered by the contract unit price for "MSE Wall Systems".

5.2 Architectural Elements. Payment for the above described work, including all material, equipment, labor and any other incidental work necessary to complete this item, will be considered completely covered by the contract unit price for "Architectural Element".

5.3 Form Liners for Cast-In-Place Concrete. Payment for form liners will be based on the contract plan quantities. Payment for the above described work, including all material, additional concrete, equipment, labor and any other incidental work necessary to complete this item, will be considered completely covered by the contract unit price for Form Liners depending on the bidding alternate as outlined in the Roadway Job Special Provisions. Any change in the contract plan quantities, based on approved change orders, will be paid for at the contract unit price.

H. STRUCTURAL STEEL REQUIREMENTS

1.0 Description. This provision contains general structural steel requirements for this project.

2.0 Material. All material shall be in accordance with Division 1000, Material Details, and specifically as shown below. The gray epoxy-mastic primer (non-aluminum) shall be compatible with concrete and produce a dry film thickness of no less than 3 mils (75 µm).

Item	Section
Structural Steel Construction	712
Gray Epoxy-Mastic Primer (non-aluminum)	1045
Structural Steel Fabrication	1080
Coating of Structural Steel	1081

3.0 Construction Requirements.

3.1 Before fabrication of new metalwork, the contractor shall make the necessary measurements in the field to verify dimensions of the existing structure where new members are affected. Any deviation of the dimensions shown on the plans shall be called to the engineer's attention. The contractor shall be responsible for developing all required dimensional adjustments and coordinating the implementation of the dimensional adjustments with all involved fabricators and subcontractors.

3.2 Prior to erection of the new structural steel, the steel that is to remain shall be carefully inspected for irregularities. If such irregularities are found, the irregularities shall be brought to the attention of the engineer.

3.3 Holes in the new diaphragm or cross frame connection plates and angles may be used as a template for drilling the holes in the existing material.

3.4 A minimum edge distance shall be maintained for all field drilled holes. The minimum edge distance for bolts shall be as shown in table below measured from the centerline of holes.

Bolt Diameter	Minimum Edge Distance
inch (mm)	inch (mm)
3/4 (19.0)	1-1/4 (32)
7/8 (22.2)	1-1/2 (38)
1 (25.4)	1-3/4 (45)

3.5 The surfaces of existing steel that will become faying surfaces for non-slip critical new connections, typically secondary members, shall be cleaned according to the manufacturer's recommendation and with a minimum of SSPC-SP-3 surface preparation and coated with one prime coat of Gray Epoxy-Mastic Primer (non-aluminum) in accordance with [Sec 1081](#). The surfaces of existing steel that will become faying surfaces for slip critical new connections, typically primary members, shall be in accordance with contact surfaces in [Sec 1081](#). Primary member connections include girder/beam splices, end diaphragms and intermediate diaphragms in curved structures.

3.6 Exposed girder/beam areas that are not faying surfaces or not covered by concrete that are scratched, damaged by the contractor or by field welding operations shall be touched up with Gray Epoxy-Mastic Primer (non-aluminum) in accordance with [Sec 1081](#). The areas shall receive the coating system as shown on the plans.

4.0 Method of Measurement. No measurement will be made.

5.0 Basis of Payment. Payment for the above described work will be considered completely covered by the contract unit price for the structural steel items included in the contract. No

JOB SPECIAL PROVISIONS (BRIDGE)

payments or adjustments will be made where new members are affected due to any deviation of the dimensions shown on plans or shop drawings.

I. NON-DESTRUCTIVE TESTING

1.0 Description. This work shall consist of performing non-destructive testing on the welds of all existing top flange cover plates.

2.0 Construction Requirements.

2.1 After the concrete deck is removed, the steel that is to remain will be inspected by the engineer. In addition to this inspection, the welds and adjacent base metal at the ends of the top cover plates shall have non-destructive (magnetic particle) testing performed. Non-destructive testing shall be performed by an acceptable testing agency. The contractor shall submit to the engineer and Bridge Division (Fabrication@modot.mo.gov) the following documentation for each individual performing non-destructive testing (NDT): their certifications, current eye exam and the NDT company written practice, including the Level III individual certification used for written practice. Personnel performing the tests shall be qualified for SNT-TC-1A Level II.

2.2 The length of weld to be tested and the base metal, one inch either side of the weld, shall be cleaned of all rust prior to the testing. On cover plates with square ends, the weld shall be tested one inch from each corner along the ends of the cover plate plus 6 inches back along the side from each corner of the plate. On cover plates with tapered ends, the weld shall be tested along the end of the cover plate, along tapered edges and 6 inches back along the cover plate from end of taper.

2.3 If fatigue cracks are found, the cracks are expected to be very small and may be located in the base metal at the toe of the welds. Any cracks discovered by testing, regardless of length, shall be marked and reported to the engineer. All repairs shall be made by a certified welder in accordance with [Sec 712.6](#). Any repair work and retesting of the repair work required, as a result of this inspection, will be paid for in accordance with [Sec 109](#). This shall not relieve the contractor from responsibility to repair any damage caused by this work at the contractor's expense. Any delay or inconvenience caused by this inspection requirement will be non-compensable and effect on time of performance non-excusable.

3.0 Method of Measurement. Measurement of non-destructive testing will be to the nearest linear foot. The extent of non-destructive testing may vary from the estimated quantities, but the contract unit price shall prevail regardless of the variation. Final measurements will not be made except for authorized changes during construction, or where appreciable errors are found in the contract quantity. The revision or correction will be computed and added to or deducted from the contract quantity.

4.0 Basis of Payment. Accepted quantities of non-destructive testing will be paid for at the contract unit price. Payment for the above described work, including all material, equipment, labor and any other incidental work necessary to complete this item, will be considered completely covered by the contract unit price for Non-Destructive Testing.