


DESIGN DESIGNATION		
RTE 22 W of 124		
A.A.D.T - 2024 =	4,715	
A.A.D.T - 2044 =	5,349	
D.H.V. =	7.42%	
T =	13.33%	
V =	40 m.p.h	
D =	49.7% / 50.3%	
FUNCTIONAL CLASS.	MINOR ARTERIAL	
RTE 22 E of 124		
A.A.D.T - 2024 =	4,622	
A.A.D.T - 2044 =	5,245	
D.H.V. =	7.44%	
T =	13.31%	
V =	40 m.p.h	
D =	47.4% / 52.6%	
FUNCTIONAL CLASS.	MINOR ARTERIAL	
RTE. 151		
A.A.D.T - 2024 =	1,253	
A.A.D.T - 2044 =	1,791	
D.H.V. =	8.76%	
T =	9.44%	
V =	45 M.P.H	
D =	48.5% / 51.5%	
FUNCTIONAL CLASS.	MAJOR COLLECTOR	
RTE. 124		
A.A.D.T - 2024 =	5,357	
A.A.D.T - 2044 =	5,758	
D.H.V. =	11.86%	
T =	9.61%	
V =	50 M.P.H	
D =	50.1% / 49.9%	
FUNCTIONAL CLASS.	MINOR ARTERIAL	

NO NEW RIGHT OF WAY REQUIRED		
------------------------------	--	--

CONVENTIONAL SYMBOLS (USED IN PLANS)		
BUILDINGS AND STRUCTURES GUARD RAIL GUARD CABLE CONCRETE RIGHT-OF-WAY MARKER STEEL RIGHT-OF-WAY MARKER LOCATION SURVEY MARKER UTILITIES FIBER OPTICS OVERHEAD CABLE TV UNDERGROUND CABLE TV OVERHEAD TELEPHONE UNDERGROUND TELEPHONE OVERHEAD POWER UNDERGROUND POWER SANITARY SEWER STORM SEWER GAS WATER MANHOLE FIRE HYDRANT WATER VALVE WATER METER DROP INLET DITCH BLOCK GROUND MOUNTED SIGN LIGHT POLE H-FRAME POWER POLE TELEPHONE PEDESTAL FENCE CHAIN LINK WOVEN WIRE GATE POST BENCHMARK	EXISTING	NEW

NOTE: DASHED OR OPEN SYMBOLS INDICATE EXISTING FEATURES



INDEX OF SHEETS			
DESCRIPTION	SHEET NUMBER		
TITLE SHEET	1		
TYPICAL SECTIONS (TS) (2 SHEETS)	2		
QUANTITIES (QU) (5 SHEETS)	3		
PLAN-PROFILE (PP)	4-22		
REFERENCE POINTS (RP)	23		
COORDINATE POINTS (CP)	24-25		
SPECIAL SHEETS (SS)	26-27		
TRAFFIC CONTROL SHEETS (TC)	28-36		
EROSION CONTROL SHEETS (EC)	37		
LIGHTING (LT)	38		
SIGNING (SN)	39-45		
PAVEMENT MARKING (PM)	46		
CROSS SECTIONS (XS)	1-61		

STATE OF MISSOURI
PATRICK J. HAKE
NUMBER
PE-2010000826
PROFESSIONAL ENGINEER

DATE PREPARED
2/27/2024

ROUTE
22

STATE
MO

DISTRICT
CD

SHEET NO.
1

COUNTY
BOONE

JOB NO.
JCD0030

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

TITLE SHEET

LENGTH OF PROJECT			
RTE 22			
BEGINNING	STA	243+00.15	
END	STA	248+36.50	
APPARENT LENGTH		536.35	FEET
EQUATIONS AND EXCEPTIONS			
NONE			
RTE 151			
BEGINNING	STA	81+77.95	
END	STA	84+04.06	
APPARENT LENGTH		226.11	FEET
EQUATIONS AND EXCEPTIONS			
NONE			
RTE 124			
BEGINNING	STA	84+04.06	
END	STA	86+55.80	
APPARENT LENGTH		251.74	FEET
EQUATIONS AND EXCEPTIONS			
NONE			
TOTAL CORRECTIONS		0.0	FEET
NET LENGTH OF PROJECT		1,014.2	FEET
STATE LENGTH		0.2	MILES



2" TYPE 1 AGG.—
4" AGGREGATE BASE





1 3/4" PLANT MIX BIT. PAVEMENT




10" NON-REINFORCED CONCRETE —


4" TYPE 5 AGGREGATE BASE




ROUNDABOUT PROPOSED TYPICAL SECTION
STA 0+00.00 TO STA 4+71.24




SPLITTER ISLAND CURB PROFILE
PINNED IN MONOLITHIC PAVEMENT



TRUCK APRON PROFILE



OPTIONAL TEMPORARY PAVEMENT DETAIL

MO-PE-2010000826
DATE PREPARED

DATE PREPARED
2/21/202

ROUTE	ST
33	1

22	M
DISTRICT	SHEP

CD

COUNTY

BOONE
JOB NO.

JCD0030

CONTRACT ID

PROJECT NO.

PROJECT NO. _____

BRIDGE NO.

DESCRIPTION

DATE _____

MISSOURI HIGHWAYS AND TRANSPORTATION
COMMISSION

TYPICAL SECTION SHEET
SHEET 2 OF 2

AGGREGATE FOR BASE					
STATION TO	STATION FROM	LOCATION	TYPE 5 AGG. FOR BASE (4 IN. THICK) (SY)	TYPE 5 AGG. FOR BASE (6 IN. THICK) (SY)	REMARK
STAGE 1 CONSTRUCTION					
241+85.77	244+18.13	RTE 22 EX CL	288		TEMP PAVT
246+48.04	248+48.00	RTE 22 EX CL	320		TEMP PAVT
STAGE 2 CONSTRUCTION					
2+07.42	3+61.38	RTE 151 EXIT LEG		333.8	
0+00.00	1+65.56	RTE 151 ENTRY LEG		391.7	
0+00.00	1+48.82	STG 2 RTE 22 TEMP BL	183		TEMP PAVT
0+00.00	2+21.44	RTE 22 W EXIT LEG	131.1	481.9	PAVEMENT AND TEMP PAVT
0+00.00	2+07.42	RTE 22 E ENTRY LEG	112.1	645.4	TRUCK APRON, PAVT, & TEMP PAVT
6+88.59	8+38.89	STG 2 RTE 22 TEMP BL	186.2		TEMP PAVT
4+64.23	2+52.54	CIRCLE		725.9	TRUCK APRON AND PAVEMENT
03+64.52	04+49.32	CIRCLE TEMP PAVT	387.6		TEMP PAVT
00+41.99	01+48.82	STG 2 RTE 124 TEMP BL	146		TEMP PAVT
STAGE 3 CONSTRUCTION					
3+46.64	4+64.23	CIRCLE		330.6	TRUCK APRON AND PAVEMENT
3+46.64	4+64.23	CIRCLE TEMP PAVT	152.4		TEMP PAVT
0+40.51	1+53.24	STG 3 RTE 124 TEMP BL	64		TEMP PAVT
0+00.00	2+23.39	RTE 124 ENTRY LEG	183	466.7	PAVEMENT AND TEMP PAVT
2+23.39	4+69.35	RTE 22 E EXIT LEG		482.7	
STAGE 4 CONSTRUCTION					
2+52.54	3+46.64	CIRCLE		261.3	TRUCK APRON AND PAVEMENT
0+00.00	1+92.37	RTE 22 W ENTRY		514.0	TRUCK APRON AND PAVEMENT
1+92.37	3+97.66	RTE 124 EXIT		651	
TOTAL			2153.4	5285	
USE			2,153.00	5,285.00	

GRAVEL (A), CRUSHED STONE (B)				
STATION TO	STATION FROM	LOCATION	GRAVEL (A) OR CRUSHED STONE (B) TONS	REMARKS
247+70.00		RTE 22 EX CL	5	P.E.
249+00.00		RTE 22 EX CL	5	P.E.
241+50.00	243+00.00	RTE 22 EX CL - Lt.	28.9	REPLACE AGG SHLDR
241+80.00	243+00.00	RTE 22 EX CL - Rt.	24.2	REPLACE AGG SHLDR
248+36.50	249+80.00	RTE 22 EX CL - Lt.	28.5	REPLACE AGG SHLDR
TOTAL			91.6	
USE			92	

CONCRETE CURB				
STATION FROM	STATION TO	LOCATION	CONCRETE CURB (OVER 6 IN. HEIGHT) TYPE S (LF)	REMARKS
		CIRCLE	248.9	CENTER ISLAND
TOTAL			249.0	

MOBILIZATION	ADDITIONAL MOBILIZATION FOR SEEDING
TOTAL = 1 LUMP SUM	TOTAL = 4 UNITS
	USE = 4 UNITS


CONTRACTOR FURNISHED SURVEYING AND STAKING
1 LUMP SUM

PAVEMENT						
STATION TO	STATION FROM	LOCATION	9 1/2 IN NON- REIN, 15' JOINTS (SY)	8 IN PCCP (SY)	OPTIONAL TEMP PAVT (SY)	REMARK
STAGE 1 CONSTRUCTION						
241+85.77	244+18.13	RTE 22 EX CL			288.0	TEMP PAVT
246+48.04	248+48.00	RTE 22 EX CL			320.0	TEMP PAVT
STAGE 2 CONSTRUCTION						
2+07.42	3+61.38	RTE 151 EXIT LEG	333.8			
0+00.00	1+65.56	RTE 151 ENTRY LEG	391.7			
0+00.00	1+48.82	STG 2 RTE 22 TEMP BL			183.0	TEMP PAVT
0+00.00	2+21.44	RTE 22 W EXIT LEG	481.9		131.1	PAVEMENT AND TEMP PAVT
0+00.00	2+07.42	RTE 22 E ENTRY LEG	599.4	46.0	112.1	TRUCK APRON, PAVT, & TEMP PAVT
6+88.59	8+38.89	STG 2 RTE 22 TEMP BL			186.2	TEMP PAVT
4+64.23	2+52.54	CIRCLE	456.8	269.1		TRUCK APRON AND PAVEMENT
03+64.52	04+49.32	CIRCLE TEMP PAVT			387.6	TEMP PAVT
00+41.99	01+48.82	STG 2 RTE 124 TEMP BL			146.0	TEMP PAVT
STAGE 3 CONSTRUCTION						
3+46.64	4+64.23	CIRCLE	208.0	122.6		TRUCK APRON AND PAVEMENT
3+46.64	4+64.23	CIRCLE TEMP PAVT			152.4	TEMP PAVT
0+40.51	1+53.24	STG 3 RTE 124 TEMP BL			64.0	TEMP PAVT
0+00.00	2+23.39	RTE 124 ENTRY LEG	466.7		183.0	PAVEMENT AND TEMP PAVT
2+23.39	4+69.35	RTE 22 E EXIT LEG	482.7			
STAGE 4 CONSTRUCTION						
2+52.54	3+46.64	CIRCLE	164.4	96.9		TRUCK APRON AND PAVEMENT
0+00.00	1+92.37	RTE 22 W ENTRY	473.7	40.3		TRUCK APRON AND PAVEMENT
1+92.37	3+97.66	RTE 124 EXIT	651.0			
STAGE 5 CONSTRUCTION						
2+62.00		RTE 22 W CON CL		109.9		RTE 22 W ISLAND
1+00.00		RTE 22 E CON CL		107.6		RTE 22 E ISLAND
0+97.00		RTE 151 CON CL		107.6		RTE 151 ISLAND
0+97.00		RTE 124 CON CL		109.7		RTE 124 ISLAND
TOTAL			4,710.1	1,009.7	2,153.4	
USE			4,710.0	1,010.0	2,153.0	

EROSION CONTROL				
STATION FROM	LOCATION	ROCK DITCH CHECK LF	SEDIMENT REMOVAL CUYD	REMARKS
241+90.00	RTE 22 EX CL Rt.	8	10	PLACE BEFORE ENTRANCE CULVERT
241+45.00	RTE 22 EX CL Lt.	8	10	PLACE APPROX. BEFORE STG 2 TEMP PAVT
243+00.00	RTE 22 EX CL Lt.	8	10	PLACE AT START OF PROJECT LIMITS
243+00.00	RTE 22 EX CL Rt.	8	10	PLACE AT START OF PROJECT LIMITS
244+45.00	RTE 22 EX CL Rt.	8	10	PLACE NEAR SOUTHWEST CORNER OF PROJECT
86+20.00	RTE 124 EX CL Rt.	8	10	PLACE DOWNSTREAM OF CULVERT
86+24.00	RTE 124 EX CL Lt.	16	20	2 RDC's, PLACE UPSTREAM OF CULVERT
246+12.00	RTE 22 EX CL Rt.	8	10	PLACE NEAR SOUTHEAST CORNER OF PRJECT
248+00.00	RTE 22 EX CL Lt.	8	10	PLACE DOWNSTREAM OF CULVERT
247+26.00	RTE EX CL Lt.	8	10	PLACE DOWNSTREAM OF CULVERT
82+20.00	RTE 151 EX CL Rt.	8	10	PLACE UPSTREAM OF CULVERT
81+87.00	RTE 151 EX CL Lt.	8	10	PLACE AT START OF PROJECT LIMITS
TOTAL		104	130	
USE		104	130	

SEEDING AND MULCHING					
STATION FROM	STATION TO	LOCATION	LENGTH FT	SEEDING & MULCHING MISC. LS	REMARKS
243+00.15	248+36.50	RTE 22 EX CL	536.35	1	PROJECT LIMITS
TOTAL				1	
USE				1	

SUMMARY OF QUANTITIES
SHEET 2 OF 5



DATE PREPARED
2/27/2024

ROUTE 22 STATE MO
DISTRICT CD SHEET NO. 3

COUNTY BOONE
JOB NO. JCD0030
CONTRACT ID.

PROJECT NO.

BRIDGE NO.


DESCRIPTION	DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

PAVEMENT MARKING											
STATION FROM	STATION TO	LOCATION	LENGTH (FT)	HIGH BUILD WATERBORNE PAV. MARK. PAINT, TYPE P BEADS		PREFORMED THERMOPLASTIC INTERSECTION MARKING			TEMPORARY REMOVABLE MARKING TAPE		REMARKS
				4" SOLID YELLOW (FT)	4" SOLID WHITE (FT)	24" SOLID YELLOW (FT)	24" SOLID WHITE (FT)	YEILD LINE TRIANGLES (EACH)	4 " WHITE (LF)	4" YELLOW (LF)	
241+60.00	248+90.00	RTE 22 EX CL							1,345	1,588	SEE TC SHEET #4
00+00.00	08+40.00	RTE 22 STG 2 BYPASS							1,507	1,681	SEE TC SHEET #5
00+60.00	02+15.00	RTE 151 CON CL							348	271	SEE TC SHEET #5
00+00.00	03+70.00	RTE 124 STG 2 BYPASS							797	764	SEE TC SHEET #5
00+00.00	03+80.00	RTE 124 STG 3 BYPASS							797	764	SEE TC SHEET #6
0+00.00	0+55.57	22 W ENTRY LEG	55.15	110.3							CENTERLINE
0+55.57	172+51.00	22 W ENTRY LEG	131.10	262.2		22					ISLAND/TAPER EDGE LINE
0+00.00	1+92.37	22 W ENTRY LEG	192.37		198.85						OUTSIDE EOP
1+73.00		22 W ENTRY LEG						9			
1+92.37	3+97.66	124 EXIT LEG	205.29		209.00		60				OUTSIDE EOP
2+10.00	3+34.00	124 EXIT LEG	124.00	136							ISLAND/TAPER EDGE LINE
0+00.00	0+67.18	124 ENTRY LEG	67.18	134.36							CENTERLINE
0+67.18	1+90.21	124 ENTRY LEG	123.03	131.22		22					ISLAND/TAPER EDGELINE
0+00.00	2+23.39	124 ENTRY LEG	223.39		223.62						OUTSIDE EOP
1+89.87		124 ENTRY LEG						9			
2+23.39	4+69.35	22 E EXIT LEG	245.96		246						OUTSIDE EOP
2+58.66	3+90.11	22 E EXIT LEG	131.45	135.82							ISLAND/TAPER EDGELINE
0+00.00	0+79.67	22 E ENTRY LEG	79.67	159.76							CENTERLINE
0+79.67	1+91.00	22 E ENTRY LEG	111.33	129.6		22					ISLAND/TAPER EDGELINE
0+00.00	2+07.42	22 E ENTRY LEG	207.42		216						OUTSIDE EOP
1+92.88		22 E ENTRY LEG						9			
2+07.42	3+61.38	151 EXIT LEG	153.96		160.8		69				OUTSIDE EOP
2+24.11	3+50.54	151 EXIT LEG	126.43	135.9							ISLAND/TAPER EDGELINE
0+00.00	0+11.19	151 ENTRY LEG	11.19	22.38							CENTERLINE
0+11.19	1+30.36	151 ENTRY LEG	119.17	129.5		22					ISLAND/TAPER EDGELINE
0+00.00	1+65.56	151 ENTRY LEG	165.56								OUTSIDE EOP
1+31.00		151 ENTRY LEG						9			
0+00.00	2+21.44	22 W EXIT LEG	221.44		221.76						OUTSIDE EOP
0+37.83	1+68.28	22 W EXIT LEG	130.45	136.32							ISLAND/TAPER EDGELINE
0+00.00	4+71.24	CIRCLE_BL	471.24	361.28							INSIDE EDGELINE
0+00.00	4+71.24	CIRCLE_BL	471.24		267.275						OUTSIDE EDGELINE
			TOTAL	1,984.6	1,743.3	88.0	129.0	36.0	4,794.0	5,068.0	
			USE	1,985	1,743	88	129	36	4,794	5,068	

LIGHTING																
STATION	LOCATION	FIXTURE #	CENTER TO CENTER DISTANCE FT	LIGHTING POLE 30 FT TYPE AT EA	POLE FOUNDATION (30 FT. MOUNT HEIGHT) EA	BRACKET ARM 15 FT. EA	LUMINAIRE LED-A EA	BASE MOUNTED CONTROL STATION 240 VOLT 4 CIRCUIT EA	PULL BOX PREFORMED CLASS 1 EA	CONDUIT 2 IN. RIGID IN TRENCH LF	CONDUIT 3 IN. RIGID IN TRENCH LF	CABLE-CONDUIT 1 IN. 2 CONDUCTORS 1 BARE NEUTRAL 2 AWG LF	CABLE-CONDUIT 1 IN. 2 CONDUCTORS 1 BARE NEUTRAL 8 AWG LF	CABLE 1 CONDUCTOR POLE & BRACKET 10 AWG LF	POWER SUPPLY ASSEMBLY TYPE 1 240/120 VOLT SERVICE EA	REMARKS
246+81.00	RTE 22 EX CL	9													1	
84+71.00	RTE 124 EX CL	10	89					1		89		105				
82+19.00	RTE 151 EX CL	16	46						1				57			
246+53.00	RTE 22 EX CL	7	109	1	1	1	1						117	90		
247+16.00	RTE 22 EX CL	8	81	1	1	1	1						91	90		
82+19.00	RTE 151 EX CL	16														
82+12.00	RTE 151 EX CL	15	45						1		45		51			
82+18.00	RTE 151 EX CL	6	6	1	1	1	1						14	90		
245+16.00	RTE 22 EX CL	5	141	1	1	1	1						151	90		
243+85.00	RTE 22 EX CL	14	148						1				156			
243+84.00	RTE 22 EX CL	13	43						1		43		49			
243+90.00	RTE 22 EX CL	4	6	1	1	1	1						14	90		
244+75.00	RTE 22 EX CL	3	91	1	1	1	1						101	90		
85+86.00	RTE 124 EX CL	12	106						1				114			
85+53.00	RTE 124 EX CL	11	47						1		47		53			
85+47.00	RTE 124 EX CL	2	6	1	1	1	1						14	90		
84+44.00	RTE 124 EX CL	1	110	1	1	1	1						120	90		
			TOTAL	8	8	8	8	1	6	89	135	105	1,102.00	720.00	1	
			USE	8	8	8	8	1	6	89	135	110	1100	720	1	



DATE PREPARED
2/27/2024
ROUTE 22 STATE MO
DISTRICT CD SHEET NO. 3

COUNTY
BOONE
JOB NO.
JCD0030
CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION	DATE								

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

TEMPORARY TRAFFIC CONTROL

BEGIN/ END PROJECT SIGNING

SIGN	SIZE IN.	AREA SF	QTY EA	TOTAL AREA SF	QTY RELOC EA	TOTAL RELOC SF	SIGN NUM.	DESCRIPTION	REMARK	ITEM NUMBER	TOTAL QTY	DESCRIPTION	REMARK
CONST-7	48X24	8.00	4	32			60	RATE OUR WORK ZONE		6161025	20	CHANNELIZER (TRIM LINE)	
CONST-8	48X36	12.00	4	48			33	WORK ZONE NO PHONE ZONE		6161099	4	CHANGEABLE MESSAGE SIGN WITH COMM. INTERFACE - CONTRACTOR FURNISHED/RETAINED	
CONST-5	48X36	12.00	4	48			61	POINT OF PRESENCE					
GO20-2	48X24	8.00	4	32			26	END ROAD WORK					
GO20-5aP	36X24	6.00	4	24			54	WORK ZONE (PLAQUE)					
R2-1	36X48	12.00	4	48			4	SPEED LIMIT XX					
SUBTOTAL (1)				232		0							

DETOUR/ ROAD CLOSURE SIGNING

SIGN	SIZE IN.	AREA SF	QTY EA	TOTAL AREA SF	QTY RELOC EA	TOTAL RELOC SF	SIGN NUM.	DESCRIPTION	REMARK	ITEM NUMBER	TOTAL QTY	DESCRIPTION	REMARK
R11-3a	60X30	12.50	1	12.5				ROAD CLOSED XX MILES AHEAD LOCAL TRAFFIC ONLY	REMOVE AFTER STG 2 CONSTR.	6161099	1	CHANGEABLE MESSAGE SIGN WITH COMM. INTERFACE - CONTRACTOR FURNISHED/RETAINED	REMOVE AFTER STG 2 CONSTR.
R11-4	60X30	12.50	1	12.5				ROAD CLOSED TO THRU TRAFFIC	REMOVE AFTER STG 2 CONSTR.				
SUBTOTAL (2)				25		0							

STAGE 1 CONSTRUCTION SIGNING

SIGN	SIZE IN.	AREA SF	QTY EA	TOTAL AREA SF	QTY RELOC EA	TOTAL RELOC SF	SIGN NUM.	DESCRIPTION	REMARK	ITEM NUMBER	TOTAL QTY	DESCRIPTION	REMARK
W05-5	48X48	16.00	1	16	1	16	34	NARROW LANES	RELOC FOR STG 6 CONSTR.	6161008	4	ADVANCED WARNING RAIL SYSTEM	RELOC FOR STG 2 CONSTR.
W020-1	48X48	16.00	4	64	4	64	2	ROAD/BRIDGE/RAMP WORK AHEAD	RELOC FOR STG 2 CONSTR.	6161025	45	CHANNELIZER (TRIM LINE)	RELOC FOR STG 2 CONSTR.
W021-5	48X48	16.00	2	32	2	32	21	SHOULDER WORK AHEAD	RELOC FOR STG 2 CONSTR.				
SUBTOTAL (3)				112		112							

STAGE 2 CONSTRUCTION SIGNING

SIGN	SIZE IN.	AREA SF	QTY EA	TOTAL AREA SF	QTY RELOC EA	TOTAL RELOC SF	SIGN NUM.	DESCRIPTION	REMARK	ITEM NUMBER	TOTAL QTY	DESCRIPTION	REMARK
W020-1	48X48	16.00			2	32	2	ROAD/BRIDGE/RAMP WORK AHEAD	RELOC TWO FOR STG 3 CONSTR.	6161008		ADVANCED WARNING RAIL SYSTEM	RELOC FOR STG 3 CONSTR.
W01-4L	48X48	16.00	2	32	2	32	15	REVERSE CURVE (SYMBOL LEFT ARROW)	RELOC FOR STG 3 CONSTR.	6161025	100	CHANNELIZER (TRIM LINE)	ADD, RELOC FOR STG 3 CONSTR.
W01-4R	48X48	16.00	2	32	2	32	15	REVERSE CURVE (SYMBOL RIGHT ARROW)	RELOC FOR STG 3 CONSTR.	6161030	5	TYPE III MOVEABLE BARRICADE	ADD FOR STG 2 CONSTR.
W013-1	30X30	6.25	2	12.5	2	12.5	44	ADVISORY SPEED (PLAQUE)	RELOC FOR STG 3 CONSTR.				
W020-3	48X48	16.00	2	32			20	ROAD CLOSED AHEAD					
W016-2	30X24	5.00	1	5				350 FEET (PLAQUE)					
R11-2	48X30	10.00	1	10			29	ROAD CLOSED					
R1-1	48X48	16.00	1	16	1	16	41	STOP	RELOC FOR STG 3 CONSTR.				
SUBTOTAL (4)				139.5		124.5							

STAGE 3 CONSTRUCTION SIGNING

SIGN	SIZE IN.	AREA SF	QTY EA	TOTAL AREA SF	QTY RELOC EA	TOTAL RELOC SF	SIGN NUM.	DESCRIPTION	REMARK	ITEM NUMBER	TOTAL QTY	DESCRIPTION	REMARK
W020-1	48X48	16.00			1	16	2	ROAD/BRIDGE/RAMP WORK AHEAD	RELOC FOR STG 4 CONSTR.	6161008		ADVANCED WARNING RAIL SYSTEM	RELOC FOR STG 4 CONSTR.
W01-4L	48X48	16.00	2	32			15	REVERSE CURVE (SYMBOL LEFT ARROW)	ADD ONE, USE FROM STG 2 CONSTR.	6161025		CHANNELIZER (TRIM LINE)	USE FROM STG 2 CONSTR.
W01-4R	48X48	16.00					15	REVERSE CURVE (SYMBOL RIGHT ARROW)	USE FROM STG 2 CONSTR.				
W013-1	30X30	6.25	1	6.25			44	ADVISORY SPEED (PLAQUE)	ADD ONE, USE FROM STG 2 CONSTR.				
R1-1	48X48	13.25	1	13.25	1	13.25	41	STOP	RELOC FOR STG 4 CONSTR.				
SUBTOTAL (5)				51.5		29.25							

STAGE 4 CONSTRUCTION SIGNING

SIGN	SIZE IN.	AREA SF	QTY EA	TOTAL AREA SF	QTY RELOC EA	TOTAL RELOC SF	SIGN NUM.	DESCRIPTION	REMARK	ITEM NUMBER	TOTAL QTY	DESCRIPTION	REMARK
W020-1	48X48	16.00					2	ROAD/BRIDGE/RAMP WORK AHEAD	USE FROM STG 3 CONSTR.	6161008		ADVANCED WARNING RAIL SYSTEM	USE FROM STG 3 CONSTR.
W01-4L	48X48	16.00					15	REVERSE CURVE (SYMBOL LEFT ARROW)	USE FROM STG 3 CONSTR.	6161025		CHANNELIZER (TRIM LINE)	USE FROM STG 3 CONSTR.
W01-4R	48X48	16.00	2	32			15	REVERSE CURVE (SYMBOL RIGHT ARROW)	ADD ONE, USE FROM STG 3 CONSTR.				
W013-1	30X30	6.25					44	ADVISORY SPEED (PLAQUE)	USE FROM STG 3 CONSTR.				
R1-1	48X48	13.25					41	STOP	USE FROM STG 3 CONSTR.				
SUBTOTAL (6)				32		0							

STAGE 5 CONSTRUCTION SIGNING

SIGN	SIZE IN.	AREA SF	QTY EA	TOTAL AREA SF	QTY RELOC EA	TOTAL RELOC SF	SIGN NUM.	DESCRIPTION	REMARK	ITEM NUMBER	TOTAL QTY	DESCRIPTION	REMARK
R1-2	48TRI.	6.93	4	27.72			13	YIELD		6161025		CHANNELIZER (TRIM LINE)	USE FROM PREV. STAGES
R4-7	24X30	5	4	20			99	KEEP RIGHT					
W05-5	48X48	16.00	3	48			34	NARROW LANES					
SUBTOTAL (7)				95.72		0							

STAGE 6 CONSTRUCTION SIGNING

SIGN	SIZE IN.	AREA SF	QTY EA	TOTAL AREA SF	QTY RELOC EA	TOTAL RELOC SF	SIGN NUM.	DESCRIPTION	REMARK	ITEM NUMBER	TOTAL QTY	DESCRIPTION	REMARK
W020-1	48X48	16.00					2	ROAD/BRIDGE/RAMP WORK AHEAD	USE FROM PREV. STAGES	6161008		ADVANCED WARNING RAIL SYSTEM	USE FROM PREV. STAGES
W021-5	48X48	16.00					21	SHOULDER WORK AHEAD	USE FROM PREV. STAGES	6161025		CHANNELIZER (TRIM LINE)	USE FROM PREV. STAGES
W05-5	48X48	16.00					34	NARROW LANES	USE FROM PREV. STAGES				
SUBTOTAL (8)				0		0							

STATE OF MISSOURI

PATRICK J. HAKE

NUMBER

PE-2010000826

PROFESSIONAL ENGINEER

DATE PREPARED

2/27/2024

ROUTE

22

DISTRICT

CD

STATE

MO

SHEET NO.

3

COUNTY

BOONE

JOB NO.

JCD0030

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL

JEFFERSON CITY, MO 65102

1-888-ASK-MODOT (1-888-275-6636)

SUMMARY OF QUANTITIES SHEET

SHEET 4 OF 5

SUMMARY OF QUANTITIES

SHEET 4 OF 5

TEMPORARY TRAFFIC CONTROL (CONTINUED)					
CONSTRUCTION SIGNS		RELOCATED SIGNS		CHANNELIZERS (TRIM LINE)	
SUBTOTAL (1)	232	SUBTOTAL (1)	0	CHANGEABLE MESSAGE SIGN WITH COMM.	
SUBTOTAL (2)	25	SUBTOTAL (2)	0	INTERFACE - CONTRACTOR FURNISHED/RETAINED	5
SUBTOTAL (3)	112	SUBTOTAL (3)	112	ADVANCED WARNING RAIL SYSTEM	4
SUBTOTAL (4)	139.5	SUBTOTAL (4)	124.5	TYPE III MOVEABLE BARRICADE	5
SUBTOTAL (5)	51.5	SUBTOTAL (5)	29.25		
SUBTOTAL (6)	32	SUBTOTAL (6)	0		
SUBTOTAL (7)	95.72	SUBTOTAL (7)	0		
SUBTOTAL (8)	0	SUBTOTAL (8)	0		
TOTAL	687.72	TOTAL	265.75		
USE	688	USE	266		



DATE PREPARED	
2/27/2024	
ROUTE	STATE
22	MO
DISTRICT	SHEET NO.
CD	3
COUNTY	
BOONE	
JOB NO.	
JCD0030	
CONTRACT ID.	



PROJECT NO.
BRIDGE NO.

DATE	DESCRIPTION

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION



105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)



DATE PREPARED
2/23/2024

ROUTE	STATE
22	MO

22	MO
DISTRICT	SHEET NO

CD	6
COUNTY	

BOONE

JCD0030

CONTRACT ID.

PROJECT NO.



BRIDGE NO.

[illegible]

MISSOURI HIGHWAYS AND TRANSPORTATION
COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102

PLAN SHEET
STAGE 3 CONSTR. REMOVALS
SHEET 3 OF 19



DATE PREPARED
2/23/2024

ROUTE 22 STATE MO

DISTRICT CD SHEET NO. 8

COUNTY BOONE

JOB NO. JCD0030

CONTRACT ID.

PROJECT NO.

BRIDGE NO.



DATE	DESCRIPTION

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

MoDOT

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

PLAN SHEET
STAGE 5 CONSTR. REMOVALS
SHEET 5 OF 19



DATE PREPARED
2/23/2024

ROUTE	STATE
22	MO
DISTRICT	SHEET NO.
CD	9

COUNTY
BOONE

JOB NO.
JCD0030

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DATE	DESCRIPTION


MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION



105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

PLAN SHEET
STAGE 6 CONSTR. REMOVALS
SHEET 6 OF 19

PLAN SHEET
STAGE 6 CONSTR. REMOVALS
SHEET 6 OF 19



SE4 OF NE4
S9,T51N,R11W

NOTE: FOR ALIGNMENT INFORMATION
SEE PP SHEET 11

WAECHTER BROS., LLC

80

SW4 OF NW4
S10,T51N,R11W

250

245

240

¼ SECTION LINE

PROJECT LIMITS:
STA 14+00.15 (CON. €)
OFFSET 0.00' RTE 22 €
STA 243+00.15 RTE 22 €

OFF 60.67' RTE 22 €
OFF 60.17' RTE 22 €
OFF 60.17' RTE 22 €

OFF 60.29' RTE 22 €
OFF 65.25' RTE 22 €
OFF 75' RTE 124 €

OFF 60.89' RTE 22 €
OFF 60.17' RTE 22 €
OFF 60.17' RTE 22 €

PROJECT LIMITS:
STA 248+00.04 (CON. €)
OFFSET 0.00' RTE 22 €
STA 248+30 RTE 22 €

OFF 60.03' RTE 22 €
OFF 60.17' RTE 22 €
OFF 60.17' RTE 22 €


COMMERCIAL SOWERS
FAMILY LLC

JIM BULTER
CHEVEROLET CENTRAL IA

NE4 OF SE4
S9,T51N,R11W

85

NW4 OF SW4
S9,T51N,R11W



DATE PREPARED
2/21/2024
ROUTE 22 STATE MO
DISTRICT CD SHEET NO. 10
COUNTY BOONE
JOB NO. JCD0030
CONTRACT ID.

PROJECT NO.
BRIDGE NO.

DATE	DESCRIPTION

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

PLAN SHEET
SHEET 7 OF 19

RTE 22 C CURVE DATA

22W_1
PI 250+50.85
PC 247+37.10
PT 253+62.10
Δ 12°30'16.6" (RT)
D 2°0'2.7"
L 625.00' (ARC)
T 313.75'
R 2,863.73'

151 CON B CURVE DATA

151_1
PI 0+78.04
PC 0+15.90
PT 1+38.44
Δ 23°24'12.3" (LT)
D 19°5'54.9"
L 122.54' (ARC)
T 62.14'
R 300.00'

151_2
PI 1+44.04
PC 1+38.44
PT 1+49.64
Δ 2°8'17.3" (RT)
D 19°5'54.9"
L 11.20' (ARC)
T 5.60'
R 300.00'

22 WEST CON B CURVE DATA

22W_1
PI 1+69.67
PC 1+31.28
PT 2+07.65
Δ 14°35'12.0" (LT)
D 19°5'54.9"
L 76.38' (ARC)
T 38.40'
R 300.00'

22W_2
PI 2+39.04
PC 2+07.65
PT 2+70.21
Δ 11°56'49.5" (RT)
D 19°5'54.9"
L 62.55' (ARC)
T 31.39'
R 300.00'

STA 3+58.32 (22 WEST CON B)=
STA 0+00.00 (22 EAST CON B)=
STA 0+00.00 (151 CON B)=
STA 0+00.00 (124 CON B)=

22 EAST CON B CURVE DATA

22E_1
PI 0+80.88
PC 0+21.47
PT 1+38.77
Δ 22°24'8.6" (LT)
D 19°5'54.9"
L 117.30' (ARC)
T 59.41'
R 300.00'

22E_2
PI 1+46.89
PC 1+38.77
PT 1+55.01
Δ 3°6'5.5" (RT)
D 19°5'54.9"
L 16.24' (ARC)
T 8.12'
R 300.00'

22E_3
PI 2+41.83
PC 1+83.64
PT 3+00.00
Δ 2°19'40.9" (RT)
D 2°0'2.7"
L 116.36' (ARC)
T 58.19'
R 2,863.73'

124 CON B CURVE DATA



124_1
PI 1+21.97
PC 0+91.96
PT 1+51.78
Δ 11°25'28.4" (LT)
D 19°5'54.9"
L 59.82' (ARC)
T 30.01'
R 300.00'

124_2
PI 1+91.94
PC 1+51.78
PT 2+31.63
Δ 15°14'59.0" (RT)
D 19°5'54.9"
L 79.85' (ARC)
T 40.16'
R 300.00'

124_3
PI 3+97.17
PC 3+39.35
PT 4+54.93
Δ 4°37'23.7" (RT)
D 4°0'0.0"
L 115.58' (ARC)
T 57.82'
R 1,432.39'

RTE 151/124 C CURVE DATA

124SP_1
PI 86+76.13
LS 150.00'
YS 2.62'
XS 149.96'
LT 100.01'
ST 50.01'



DATE PREPARED
2/23/2024

ROUTE	STATE
22	MO
DISTRICT	SHEET NO.
CD	11

COUNTY
BOONE

JOB NO.
JCD0030

CONTRACT ID.

PROJECT NO.




BRIDGE NO.

DATE	DESCRIPTION

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

PLAN SHEET
GEOMETRY DATA
SHEET 8 OF 19






DATE PREPARED 2/21/2024	
ROUTE 22	STATE MO
DISTRICT CD	SHEET NO. 12
COUNTY BOONE	
JOB NO. JCD0030	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	

DATE	DESCRIPTION

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION



105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)



DATE PREPARED
2/21/2024

ROUTE	STATE
22	MO

DISTRICT	SHEET NO.
CD	13

COUNTY
BOONE

JOB NO.
JCD0030

CONTRACT ID.




PROJECT NO.

BRIDGE NO.

DATE	DESCRIPTION

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)



DATE PREPARED
2/21/2024

ROUTE 22	STATE MO
DISTRICT CD	SHEET NO. 15

COUNTY
BOONE

JOB NO.
JCD0030

CONTRACT ID.

PROJECT NO.

BRIDGE NO.




DATE	DESCRIPTION

MISSOURI HIGHWAYS AND TRANSPORTATION
COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

PLAN SHEET
GEOMETRY DATA PROFILES
SHEET 12 OF 19





DATE PREPARED
2/21/2024

ROUTE 22 STATE MO

DISTRICT CD SHEET NO. 16

COUNTY BOONE

JOB NO. JCD0030

CONTRACT ID.

PROJECT NO.




BRIDGE NO.

DATE	DESCRIPTION

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

PLAN SHEET
GEOMETRY DATA PROFILES
SHEET 13 OF 19



DATE PREPARED
2/21/2024

ROUTE 22
STATE MO
DISTRICT CD
SHEET NO. 17

COUNTY
BOONE

JOB NO.
JCD0030

CONTRACT ID.

PROJECT NO.


BRIDGE NO.

DATE	DESCRIPTION

MISSOURI HIGHWAYS AND TRANSPORTATION
COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

PLAN SHEET
GEOMETRY DATA PROFILES
SHEET 14 OF 19



DATE PREPARED 2/21/2024	
ROUTE 22	STATE MO
DISTRICT CD	SHEET NO. 18
COUNTY BOONE	
JOB NO. JCD0030	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	



DESCRIPTION	DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION







105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

PLAN SHEET
STAGE 1 CONSTRUCTION
SHEET 15 OF 19



NOTE: SEE PLAN SHEET 5 FOR
RTE 22 C, RTE 124 C, & RTE 151 C
ALIGNMENT DATA

		DATE PREPARED 2/21/2024	
ROUTE 22		STATE MO	
DISTRICT CD		SHEET NO. 19	
COUNTY BOONE			
JOB NO. JCD0030			
CONTRACT ID.			
PROJECT NO.			
BRIDGE NO.			
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION		105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	
			
PLAN SHEET STAGE 2 CONSTRUCTION SHEET 16 OF 19			



CURVE 1
(STG 3 RTE 124 TEMP 6)

PI	0+41.53
PC	0+00.00
PT	0+83.03
Δ	3°18'51.1" (LT)
D	3°59'29.9"
L	83.03' (ARC)
T	41.53'
R	1,435.39'


```

CURVE 2
(STG 3 RTE 124 TEMP 6)
PI 2+26.39
PC 1+90.93
PT 2+61.54
Δ 13°21'9.3" (LT)
D 18°54'34.2"
L 70.61' (ARC)
T 35.47'
R 303.00'

```

CURVE 3
(STG 3 RTE 124 TEMP 6)


PI	3+03.41
PC	2+61.54
PT	3+44.75
Δ	15°53'32.3" (RT)
D	19°5'54.9"
L	83.21' (ARC)
T	41.87'
R	300.00'

[illegible]


MISSOURI HIGHWAYS AND TRANSPORTATION
COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)


PLAN SHEET
STAGE 3 CONSTRUCTION
SHEET 17 OF 19



STAGE 2 RTE 22 TEMP. PAVT



STAGE 2 RTE 124 TEMP. PAVT





DATE PREPARED
2/21/2024
ROUTE 22 STATE MO
DISTRICT CD SHEET NO. 21
COUNTY BOONE
JOB NO. JCD0030
CONTRACT ID.
PROJECT NO.
BRIDGE NO.

DATE	DESCRIPTION

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
MoDOT
105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

PROFILE SHEET
STAGE 2 TEMP PAVT PROFILES
SHEET 18 OF 19



&[Date] &[Time]
PATRICK J. HAKE - CIVIL
MO-PE-2010000826

DATE PREPARED
2/21/2024

ROUTE	STATE
22	MO

22	MO
DISTRICT	SHEET NO.
22	22

CD	22
COUNTY	

BOONE

JCD0030

CONTRACT ID.

PROJECT NO.






BRIDGE NO.

[illegible]

MISSOURI HIGHWAYS AND TRANSPORTATION
COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

PLAN SHEET
STAGE 3 RTE 124 TEMP 6 PROFILE
SHEET 19 OF 19



DATE PREPARED 2/21/2024	
ROUTE 22	STATE MO
DISTRICT CD	SHEET NO. 23
COUNTY BOONE	
JOB NO. JCD0030	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	


DESCRIPTION	DATE

MISSOURI HIGHWAYS AND TRANSPORTATION
COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

REFERENCE POINT SHEET
SHEET 1 OF 1

COORDINATE POINT LISTING							
SHEET NO.	STATION	LOCATION	OFFSET (USFT)	MODIFIED STATE PLANE (GROUND)			DESCRIPTION
				NORTHING (US SURVEY FT)	EASTING (US SURVEY FT)	ELEVATION (US SURVEY FT)	
PROJECT CONTROL POINTS							
12	249+11.69	Rt.	46.48	1,233,040.23	1,741,985.76	877.81	RB & CAP 46' S OF CL RT 22, 336' E OF JNCT 22 & 124
12	241+72.12	Rt.	55.96	1,232,904.46	1,741,261.74	877.65	RB & CAP 55' S OF CL RT 22, 407' W OF JNCT 22 & 124
12	87+25.73	Lt.	24.86	1,232,709.32	1,741,619.04	879.49	RB & CAP 24' E OF CL RT 124, 323' S OF JNCT 22 & 124
12	80+47.39	Rt.	24.42	1,233,387.36	1,741,681.75	876.32	RB & CAP 24' W OF CL RT 151, 357' N OF JNCT 22 & 124
ALIGNMENTS							
RTE 22 EXISTING CL							
	233+46.47			1,232,812.028	1,740,439.375		START
	247+37.10			1,233,060.448	1,741,807.640		PC
	250+50.85			1,233,116.495	1,742,116.340		HPI
				1,230,242.779	1,742,319.211		CC
	253+62.10			1,233,104.373	1,742,429.852		PT
	263+74.32			1,233,065.266	1,743,441.312		END
RTE 151/124 EXISTING CL							
	74+50.00			1,233,979.420	1,741,743.157		START
	76+89.96			1,233,739.536	1,741,737.125		PC
	78+84.94			1,233,544.618	1,741,732.223		HPI
				1,233,811.558	1,738,873.147		CC
	80+79.32			1,233,352.161	1,741,700.957		PT
	85+76.11			1,232,861.799	1,741,621.295		TS
	86+76.12			1,232,763.079	1,741,605.257		SPI
	87+26.11			1,232,714.201	1,741,594.664		SC
	89+61.40			1,232,484.251	1,741,544.832		HPI
				1,233,017.573	1,740,194.765		CC
	91+92.52			1,232,282.325	1,741,424.059		CS
	92+42.53			1,232,239.403	1,741,398.387		SPI
	93+42.52			1,232,156.374	1,741,342.628		ST
	97+00.00			1,231,859.606	1,741,143.329		END
22 WEST CON CL							
	0+00.00			1,232,964.501	1,741,279.176		START
	1+31.28			1,232,987.952	1,741,408.341		PC
	1+69.67			1,232,994.811	1,741,446.119		HPI
				1,233,283.126	1,741,354.750		CC
	2+07.65			1,233,010.963	1,741,480.952		PRC
	2+39.04			1,233,024.168	1,741,509.430		HPI
				1,232,738.799	1,741,607.154		CC
	2+70.21			1,233,031.192	1,741,540.026		PT
	3+58.32			1,233,050.908	1,741,625.902		END
124 CON CL							
	0+00.00			1,233,050.908	1,741,625.902		START
	0+91.96			1,232,959.392	1,741,616.845		PC
	1+21.97			1,232,929.529	1,741,613.889		HPI
				1,232,929.845	1,741,915.386		CC
	1+51.78			1,232,899.672	1,741,616.907		PRC
	1+91.94			1,232,859.715	1,741,620.947		HPI
				1,232,869.500	1,741,318.429		CC
	2+31.63			1,232,820.102	1,741,614.334		PT
	2+64.35			1,232,787.824	1,741,608.945		POT
	3+39.35			1,232,714.201	1,741,594.664		PC
	3+97.17			1,232,657.690	1,741,582.418		HPI
				1,233,017.573	1,740,194.765		CC
	4+54.93			1,232,602.351	1,741,565.657		PT/END
22 EAST CON CL							
	0+00.00			1,233,050.908	1,741,625.902		START
	0+21.47			1,233,047.545	1,741,647.108		PC
	0+80.88			1,233,038.241	1,741,705.782		HPI
				1,233,343.843	1,741,694.092		CC
	1+38.77			1,233,052.001	1,741,763.575		PRC
	1+46.89			1,233,053.882	1,741,771.476		HPI
				1,232,760.158	1,741,833.059		CC
	1+55.01			1,233,055.333	1,741,779.467		PT
	1+83.64			1,233,060.448	1,741,807.640		PC
	2+41.83			1,233,070.842	1,741,864.891		HPI
				1,230,242.779	1,742,319.211		CC
	3+00.00			1,233,078.903	1,741,922.518		PT/END
151 CON CL							
	0+00.00			1,233,050.908	1,741,625.902		START
	0+15.90			1,233,064.610	1,741,633.971		PC
	0+78.04			1,233,118.153	1,741,665.501		HPI
				1,233,216.839	1,741,375.463		CC
	1+38.44			1,233,179.814	1,741,673.170		PRC
	1+44.04			1,233,185.369	1,741,673.861		HPI
				1,233,142.789	1,741,970.876		CC
	1+49.64			1,233,190.895	1,741,674.758		PT
	2+92.34			1,233,331.753	1,741,697.642		END



DATE PREPARED	
2/23/2024	
ROUTE	STATE
22	MO
DISTRICT	SHEET NO.
CD	24
COUNTY	
BOONE	
JOB NO.	
JCD0030	
CONTRACT ID.	
PROJECT NO.	

BRIDGE NO.	
DESCRIPTION	
DATE	


MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

COORDINATE POINT LISTING							
SHEET NO.	STATION	LOCATION	OFFSET (USFT)	MODIFIED STATE PLANE (GROUND)			DESCRIPTION
				NORTHING (US SURVEY FT)	EASTING (US SURVEY FT)	ELEVATION (US SURVEY FT)	
ALIGNEMENTS CONTINUED							
22WENTRY_124EXIT CON BL							
	0+00.00			1,232,970.585	1,741,379.861		START
	0+31.12			1,232,976.145	1,741,410.485		PC
	0+43.36			1,232,978.330	1,741,422.520		HP I
				1,233,283.126	1,741,354.750		CC
	0+55.57			1,232,981.450	1,741,434.346		PCC
	0+84.05			1,232,986.185	1,741,462.429		HP I
				1,233,285.419	1,741,383.097		CC
	1+12.37			1,232,995.985	1,741,489.169		PRC
	1+87.79			1,233,021.936	1,741,559.981		HP I
				1,232,926.504	1,741,514.632		CC
	2+30.01			1,232,950.644	1,741,584.584		PCC
	3+15.81			1,232,869.542	1,741,612.573		HP I
				1,232,846.252	1,741,282.090		CC
	3+97.66			1,232,785.316	1,741,596.235		PT
124ENTRY_22EEXIT CON BL							
	0+00.00			1,232,780.746	1,741,619.796		START
	0+04.88			1,232,785.538	1,741,620.726		HP I
	0+37.92			1,232,818.126	1,741,626.170		PC
	0+52.56			1,232,832.568	1,741,628.583		HP I
				1,232,869.538	1,741,318.435		CC
	0+67.18			1,232,847.172	1,741,629.632		PCC
	0+94.11			1,232,873.753	1,741,633.967		HP I
				1,232,897.849	1,741,318.877		CC
	1+20.92			1,232,900.684	1,741,633.724		PRC
	1+87.35			1,232,967.119	1,741,633.126		HP I
				1,232,901.719	1,741,748.720		CC
	2+41.41			1,233,000.823	1,741,690.380		PCC
	3+01.12			1,233,031.113	1,741,741.834		HP I
				1,232,656.116	1,741,893.301		CC
	3+59.95			1,233,045.056	1,741,799.892		PT
	3+90.11			1,233,052.099	1,741,829.217		PC
	4+29.73			1,233,058.907	1,741,868.250		HP I
				1,230,242.784	1,742,319.233		CC
	4+69.35			1,233,064.629	1,741,907.458		PT
22ENTRY_151EXIT CON BL							
	0+00.00			1,233,088.377	1,741,903.993		PC
	0+39.84			1,233,082.625	1,741,864.570		HP I
				1,230,242.781	1,742,319.211		CC
	0+79.67			1,233,075.783	1,741,825.322		PT
	1+36.48			1,233,070.943	1,741,768.720		PC
	1+92.47			1,233,066.173	1,741,712.937		HP I
				1,233,134.710	1,741,763.267		CC
	2+28.48			1,233,120.826	1,741,700.792		PCC
	2+95.74			1,233,186.487	1,741,686.200		HP I
				1,233,196.755	1,742,042.456		CC
	3+61.38			1,233,252.879	1,741,696.985		PT
151ENTRY CON BL							
	0+00.00			1,233,256.728	1,741,673.296		START
	0+11.23			1,233,245.645	1,741,671.496		HP I
	0+57.63			1,233,200.757	1,741,659.740		PC
	1+14.98			1,233,145.275	1,741,645.210		HP I
				1,233,233.423	1,741,535.009		CC
	1+65.56			1,233,118.913	1,741,594.274		PT
22WEXIT CON BL							
	0+00.00			1,233,097.459	1,741,567.098		PC
	1+14.76			1,233,013.684	1,741,488.667		HP I
				1,233,331.107	1,741,317.528		CC
	2+21.44			1,232,994.199	1,741,375.574		PT

ALL PROJECT COORDINATES HAVE BEEN PROJECTED FROM THE MISSOURI STATE PLANE COORDINATE (SPC) SYSTEM OF 1983 USING AN AVERAGE PROJECT PROJECTION (GRID TO GROUND) FACTOR. TO GET BACK TO STATE PLANE COORDINATES MULTIPLY THE PROJECT COORDINATES BY THE AVERAGE GRID FACTOR AS SHOWN IN THE "REFERENCE CONTROL INFORMATION" PORTION OF THIS TABLE.

PROJECT COORDINATE INFORMATION		
COORDINATE SYSTEM	MODIFIED STATE PLANE	
HORIZONTAL DATUM	NAD83	
VERTICAL DATUM	NAVD88	
GEOID MODEL	G201BU7	
ELEVATIONS DETERMINED BY	DIFFERENTIAL LEVELING	
PROJECT PROJECTION FACTOR	1.0000946	
REFERENCE CONTROL INFORMATION		
COORDINATE SYSTEM	MODIFIED STATE PLANE	
CONTROL STATION		
DESIGNATION	MODOT COLUMBIA CORS ARP	
CORS_ID	MOCO	
PID	DN4500	
LATITUDE	385,932.0021	
LONGITUDE	921,704.8857	
NORTHING (M)	350,589.5150	
EASTING (M)	518,652.2980	
ZONE	2402 (MO-CENTRAL)	
PROJECT AVERAGE GRID FACTOR	0.9999054	
EXAMPLE OF PROJECT COORDINATE TO S.P.C.		
PROJECT NORTHING X AVERAGE GRID FACTOR = STATE PLANE NORTHING PROJECT EASTING X AVERAGE GRID FACTOR = STATE PLANE EASTING EXAMPLE: CONTROL POINT # 801 N 1,233,040.2285 X 0.9999054 = N 1,232,923.583 E 1,741,985.7634 X 0.9999054 = E 1,741,820.972		
LINEAR UNIT CONVERSION		
1 METER = 3.280833333 US SURVEY FEET (USFT)		



DATE PREPARED	
2/23/2024	
ROUTE	STATE
22	MO
DISTRICT	SHEET NO.
CD	25
COUNTY	
BOONE	
JOB NO.	
JCD0030	
CONTRACT ID.	


PROJECT NO.	
BRIDGE NO.	

DESCRIPTION	DATE						

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION



105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)



DATE PREPARED
2/21/2024

ROUTE
22

STATE
MO

DISTRICT
CD

SHEET NO.
26

COUNTY
BOONE

JOB NO.
JCD0030

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION


DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION


105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

MoDOT


SPECIAL SHEET
ISLAND DETAIL
SHEET 1 OF 2




RTE 22 WEST SIDE ISLAND DETAIL
STATIONING AND OFFSET BASED ON
RTE 22 EX C




RTE 22 WEST SIDE TRUCK APRON DETAIL
STATIONING AND OFFSET BASED ON
RTE 22 EX C




RTE 151 ISLAND DETAIL
STATIONING AND OFFSET BASED ON
RTE 151 EX C



RTE 22 EAST SIDE TRUCK APRON DETAIL
STATIONING AND OFFSET BASED ON
RTE 22 EX C



RTE 22 EAST SIDE ISLAND DETAIL
STATIONING AND OFFSET BASED ON
RTE 22 EX C



RTE 124 ISLAND DETAIL
STATIONING AND OFFSET BASED ON
RTE 124 EX C

NOT TO SCALE

245

85

SEE RTE 151
ISLAND DETAIL

SEE RTE 22 EAST SIDE
TRUCK APRON DETAIL

PC STA 247+37.10

SEE RTE 22 WEST
SIDE ISLAND DETAIL

SEE RTE 22 WEST SIDE
TRUCK APRON DETAIL

SEE RTE 22 EAST SIDE
ISLAND DETAIL



SEE RTE 124
ISLAND DETAIL

TS STA 85+76.11 R2

RTE 124 EX C

RTE 151 EX C

RTE 22 EX C



DATE PREPARED
2/21/2024

ROUTE	STATE
22	MO

DISTRICT	SHEET NO.
CD	37

CD	27
COUNTY	
ECONOMY	

BOONE
JOB NO.

JCD0030
CONTRACT ID.

PROJECT NO.

PROJECT NO. _____

BRIDGE NO.

[illegible]

NC	OL	02	6)
----	----	----	----

CAPITAL 651-663

PORTLAND, ME 04101-1000

NSP
6 WEST
CITY,
9898TRA
N

ND
SIO

Logo of the American Society of Human Genetics (ASHG), featuring a stylized 'A' and 'H' forming a circle.


 The logo for Sigma Xi, featuring a stylized Greek letter sigma (Σ) followed by a flame-like symbol.

2	✓

UT

YOU

LA 2

HEET
INT
OF 2

2020-2021



IAL ON ET

SECTION

SHRUBS

NSTN

8



DATE PREPARED
2/21/2024

ROUTE 22	STATE MO
DISTRICT CD	SHEET NO. 29

COUNTY
BOONE

JOB NO.
JCD0030

CONTRACT ID.

PROJECT NO.





BRIDGE NO.

DESCRIPTION	DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION


105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

TRAFFIC CONTROL SHEET
DETOUR / ROAD CLOSURE SIGNAGE
SHEET 2 OF 9





(1) RELOCATE FOR NEXT STAGE(S)

TRAFFIC CONTROL SHEET
STAGE 3 CONSTRUCTION
SHEET 5 OF 9



TRAFFIC CONTROL SHEET
STAGE 3 CONSTRUCTION SIGNING
SHEET 5 OF 9



&[Date] &[Time]
PATRICK J. HAKE - CIVIL
MO-PE-2010000826

DATE PREPARED
2/21/2024

ROUTE	STATE
22	MO

22	MO
DISTRICT	SHEET NO.

CD	33
COUNTY	


BOONE

JCD0030

CONTRACT ID.

PROJECT NO.



BRIDGE NO.

[illegible]


MISSOURI HIGHWAYS AND TRANSPORTATION
COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

TRAFFIC CONTROL SHEET
STAGE 4 CONSTRUCTION SIGNING
SHEET 6 OF 9



TRAFFIC CONTROL SHEET
STAGE 5 CONSTRUCTION
SHEET 7 OF 9




MOPE-201000026	
DATE PREPARED	
2/21/2024	
ROUTE	STATE
22	MO
DISTRICT	SHEET NO.
CD	34
COUNTY	
BOONE	
JOB NO.	
JCD0030	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	

[illegible]

MISSOURI HIGHWAYS AND TRANSPORTATION
COMMISSION

105 WEST CAPITAL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

TRAFFIC CONTROL SHEET
STAGE 5 CONSTRUCTION SIGNING
SHEET 7 OF 9



ROAD
WORK
AHEAD

WO20-1

2

SHOULDER
WORK
AHEAD

WO21-5

21

NARROW
LANES

WO5-5

34

DATE PREPARED
2/21/2024

ROUTE 22	STATE MO
DISTRICT CD	SHEET NO. 35

COUNTY
BOONE

JOB NO.
JCD0030

CONTRACT ID.

PROJECT NO.

BRIDGE NO.


DATE	DESCRIPTION

MISSOURI HIGHWAYS AND TRANSPORTATION
COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

TRAFFIC CONTROL SHEET
STAGE 6 CONSTRUCTION SIGNING
SHEET 8 OF 9

TRAFFIC CONTROL SHEET
STAGE 6 CONSTRUCTION
SHEET 8 OF 9



CENTERLINE/ EDGELINE STRIPING
TWO-LANE HIGHWAY


PAVEMENT MARKING EQUIPMENT

WARNING TRUCK WITH WORK SIGNS, FLASHING ARROW PANEL AND OPTIONAL TRUCK MOUNTED ATTENUATOR. (1)

ADVANCE WARNING TRUCK WITH WORK SIGNS, FLASHING ARROW PANEL AND TRUCK MOUNTED ATTENUATOR. (3)

NOTES:

- ALL SIGNS HAVE TYPE 3 FLUORESCENT ORANGE RETROFLECTIVE SHEETING.
- UPON APPROVAL OF THE ENGINEER, THE CONTRACTOR MAY PROVIDE ADDITIONAL PROTECTIVE TRUCKS EQUIPPED WITH PROPER WARNING DEVICES.
- PROTECTIVE TRUCK AND WORK VEHICLES SHALL DISPLAY HIGH-INTENSITY ROTATING, FLASHING, OSCILLATING OR STROBE LIGHTS.
- VEHICLE HAZARD WARNING SIGNALS SHALL NOT BE USED INSTEAD OF THE VEHICLE'S HIGH -INTENSITY ROTATING FLASHING, FLASHING, OSCILLATING, OR STROBE LIGHTS.
- (1). TRUCK IS OPTIONAL ON TWO-LANE UNDIVIDED HIGHWAYS IF SIGNING AND ARROW BOARD IS MOUNTED ON THE PAVEMENT MARKING EQUIPMENT.
- (2). WET PAINT SIGNS ARE INSTALLED TO INDICATE THE SIDE IN WHICH THE PAVEMENT MARKING MATERIAL IS BEING APPLIED. AT THE CONTRACTOR'S OPTION. A FRONT FACING WET PAINT SIGN MAY BE INSTALLED ON THE LEFT SIDE OF THE PAVEMENT MARKING EQUIPMENT.
- (3). ADVANCE WARNING TRUCK IS POSITIONED AT THE NO TRACK POINT OF THE PAVEMENT MARKING MATERIAL OR SPACING SHOWN, WHICHEVER IS GREATER.



DATE PREPARED
2/21/2024

ROUTE 22	STATE MO
DISTRICT CD	SHEET NO. 36

COUNTY
BOONE

JOB NO.
JCD0030

CONTRACT ID.

PROJECT NO.

BRIDGE NO.



DESCRIPTION	DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

MoDOT

	ALTERNATE DITCH CHECK
	CURB INLET CHECK
	ROCK DITCH CHECK
	SEDIMENT TRAP
	ENERGY DISSIPATOR
	TEMPORARY BERM TYPE B
	TEMPORARY BERM TYPE C
	SILT FENCE
	TEMPORARY SEDIMENT BASIN
	PERMANENT SEDIMENT BASIN



MO-PE-2010000826
DATE PREPARED

2/21/2024

2 / 21 / 2024	
ROUTE	STATE

ROUTE	STATE
22	MO

22	MO
DISTRICT	SHEET NO.

DISTRICT SHEET NO.
CD 37

CD	37
COUNTY	

BOONE

BOONE
JOB NO.

JCD0030

JCD0030

CONTRACT ID.

CONTRACT ID.

PROJECT NO.


PROJECT NO.

BRIDGE NO.

[illegible]MISSOURI HIGHWAYS AND TRANSPORTATION
COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

EROSION CONTROL SHEET
SHEET 1 OF 1



SIGNING SHEET
SIGN INSTALLATIONS
SHEET 2 OF 7

SIGNS

SIGN NO.

SIGN SIZE

STATION / LOG MILE

HORZ CLEAR IF NOT STD

LOCATION

SIGN DTL. SHT. NO.

CONCRETE FOOTINGS EMBEDDED

ITEM NO. 9031010

CY

STRUCTURAL STEEL POSTS *

POST DES NO.

POST NO. 1

POST NO. 2

POST NO. 3

LBS PER FT

TOTAL 9031210

IN.

LF

LF

LF

LBS

PIPE POST *

PIPE SIZE

POST NO. 1

POST NO. 2

PER FT

TOTAL 9031220

IN.

LF

LF

LF

LBS

BACKING BARS *

2" x 3/8" BARS @ 2.55 LBS PER LIN FT.

NO.

LGTH

TOTAL

TOTAL

IN.

LF

LF

LF

LBS

U CHANNEL POST

ITEM NO. 9031250A

LF

PERFORATED SQUARE STEEL TUBE POST

2 IN. POSTS

2.5 IN. POSTS

ANCHORS

POST NO. 1

POST NO. 2

TOTAL 9031270A

DRIVEN 12 GA. ITEM NO. 9031271A

DRIVEN 7 GA. ITEM NO. 9031273A

CONCRETE 7 GA. ITEM NO. 9031274

POST NO. 1

POST NO. 2

TOTAL 9031280

2.25" INSERT (6 FT) ITEM NO. 9031272A

ANCHORS

DRIVEN 7 GA. ITEM NO. 9031281A

CONCRETE 7 GA. ITEM NO. 9031285

BREAK - AWAY ASSEMBLY ITEM NO. 9031241

REMARKS & OTHER REQUIRED ITEMS

STATE OF MISSOURI

PATRICK J. HAKE

NUMBER

PE-2010000826

PROFESSIONAL ENGINEER

8/Date/4/Time/

PATRICK J. HAKE - CIVIL

MO-PE-2010000826

DATE PREPARED

2/27/2024

ROUTE

22

STATE

MO

DISTRICT

CD

SHEET NO.

41

COUNTY

BOONE

JOB NO.

JCD0030

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL

JEFFERSON CITY, MO 65102

1-888-ASK-MODOT (1-888-275-6636)

SIGNING SHEET

D-29

SHEET 3 OF 7

ROUND PIPE POST AND FOOTING DATA TABLE


NOM. SIZE	WEIGHT		STUB	FOOTING		CONCRETE
(IN.)	LBS/FT	LBS/IN	LENGTH	DIA.	DEPTH	C.Y.
2	5.79	0.48	4'-3" "	12"	4'-6"	0.13
3	7.58	0.63	4'-3" "	12"	4'-6"	0.13
4	10.79	0.90	5'-3" "	18"	5'-6"	0.36

POST AND FOOTING DATA TABLE

POST					FOOTING								
POST DES. NO.	NOM. SIZE	WEIGHT		STUB	DIA.	LEVEL GROUND		6:1 GRADE		4:1 GRADE		3:1 OR 2:1 GRADE	
		LBS/FT	LBS/IN	LENGTH		DEPTH	C.Y.	DEPTH	C.Y.	DEPTH	C.Y.	DEPTH	C.Y.
1	W6	9	0.75	3'-0"	15"	3'-0"	0.14	3'-2"	0.15	3'-3"	0.16	3'-6"	0.17
2	W6	15	1.25	4'-0"	24"	4'-0"	0.47	4'-2"	0.5	4'-3"	0.51	4'-6"	0.54
3	W6	18	1.5	4'-6"	28"	4'-6"	0.71	4'-8"	0.73	4'-9"	0.74	5'-0"	0.78
4	W10	22	1.83	5'-0"	36"	5'-0"	1.31	5'-2"	1.36	5'-3"	1.39	5'-6"	1.45
5	W10	26	2.17	5'-0"	36"	5'-0"	1.31	5-3"	1.37	5'-5"	1.43	5'-9"	1.52
6	W12	35	2.92	5'-6"	36"	5'-6"	1.44	5'-9"	1.52	5'-11"	1.56	6'-3"	1.65

STANDARD SIGN ASSEMBLIES																				SIGN SUMMARY							
SIGN NO.	STATION/ LOG MILE	LOCATION	SIGN																	STANDARD SIGN OR SPECIAL SIGN NUMBER	SIGN DETAIL SHEET NO.	NO. EACH	SIZE, TYPE, AND SQUARE FEET				
			36 x 36 (1N)	36 x 36 (1N)	24 x 24 (1N)	24 x 12 (1N)	24 x 24 (1N)	21 x 15 (1N)	24 x 12 (1N)	24 x 12 (1N)	30 x 24 (1N)	30 x 24 (1N)	21 x 15 (1N)	21 x 15 (1N)	36 x 36 (1N)	84 x 24 (1N)	24 x 30 (1N)	48 x 48 (1N)	36 x 12 (1N)				30 x 24 (1N)	36 x 12 (1N)			
			SIGN DESCRIPTION, SIZES, AND NUMBER OF EACH																								
																											
1	236+19	RTE 22 Rt.	1																	W3-5	STD.	1	36 x 36		9		
2	237+49	RTE 22 Rt.		1	1															1	W2-6	STD.	1	36 x 36		9	
3	238+79	RTE 22 Rt.				1	1	1	1	1	1	1	1								W13-1P	STD.	1	24 x 24		4	
4	241+00	RTE 22 Rt.												1							M3-2	STD.	1	24 x 12	2		
5	243+00	RTE 22 Rt.													1						M1-5	STD.	1	24 x 24	4		
6	244+09	RTE 22 Lt.														1					M6-3	STD.	1	21 x 15	2.1875		
7	244+79	RTE 22 Lt.														1					M3-1	STD.	1	24 x 12	2		
8	244+73	RTE 22 Rt.															1				M3-4	STD.	1	24 x 12	2		
9	245+27	RTE 22 Rt.																1	1		M1-5	STD.	1	30 x 24	5		
																					M5-3	STD.	1	21 x 15	2.1875		
																					M5-1R	STD.	1	21 x 15	2.1875		
																					W3-2	STD.	1	36 x 36		9	
																					D1-2a	STD.	1	84 x 24			14
																					R4-7	STD.	1	24 x 30	5		
																					R1-2	STD.	2	48 x 48	32		
																					R6-1R	STD.	1	36 x 12	3		
																					R6-4	STD.	1	30 x 24	5		
																					W16-17P	STD.	1	36 x 12		3	
												SUBTOTAL		1	72	34	14										

STANDARD SIGN ASSEMBLIES																				SIGN SUMMARY						
SIGN NO.	STATION/ LOG MILE	LOCATION	SIGN																	STANDARD SIGN OR SPECIAL SIGN NUMBER	SIGN DETAIL SHEET NO.	NO. EACH	SIZE, TYPE, AND SQUARE FEET			
			24 x 12 (1N)	30 x 24 (1N)	21 x 15 (1N)	21 x 15 (1N)	24 x 24 (1N)	30 x 24 (1N)	48 x 48 (1N)	24 x 24 (1N)	24 x 12 (1N)	30 x 24 (1N)	21 x 15 (1N)		24 x 12 (1N)	24 x 24 (1N)	21 x 15 (1N)	21 x 15 (1N)	48 x 48 (1N)				72 x 36 (1N)	36 x 12 (1N)		
			SIGN DESCRIPTION, SIZES, AND NUMBER OF EACH																							
																										
			M3-4	M1-5	M6-2R	M2-1	M1-5	M1-5	W2-6	W13-1P	M3-1	M1-5	M6-3		M3-2	M1-5	M5-3	M5-1R	W3-2				D1-2d	W16-17P		
10	84+70	RTE 124 Rt.	1	1	1																					
11	94+00	RTE 124 Lt.				1	1	1																		
12	92+00	RTE 124 Lt.							1	1									1							
13	90+50	RTE 124 Lt.	1								1	1	1		1	2	1	1								
14	87+68	RTE 124 Lt.																1								
15	86+38	RTE 124 Lt.																	1							



&[Date] &[Time]
PATRICK J. HAKE - CIVIL
MO-PE-2010000826

DATE PREPARED
2/27/2024

ROUTE	STATE
22	MO

22	MO
DISTRICT	SHEET NO.
22	12

CD	42
COUNTY	

BOONE

JCD0030

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

[illegible]

MISSOURI HIGHWAYS AND TRANSPORTATION
COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 63102
1-888-4ASK-MODOT (1-888-275-6636)

SIGNING SHEET
D-30
SHEET 4 OF 7

STANDARD SIGN ASSEMBLIES																					SIGN SUMMARY						
SIGN NO.	STATION/ LOG MILE	LOCATION	SIGN																		STANDARD SIGN OR SPECIAL SIGN NUMBER	SIGN DETAIL SHEET NO.	NO. EACH	SIZE, TYPE, AND SQUARE FEET			
			24 x 30	48 x 48	36 x 12	30 x 24	24 x 12	24 x 24	21 x 15	21 x 15	30 x 24	30 x 24	48 x 48	24 x 24	24 x 12	21 x 15	24 x 12	21 x 15	21 x 15	48 x 48				36 x 12			
			(IN)	(IN)	(IN)	(IN)	(IN)	(IN)	(IN)	(IN)	(IN)	(IN)	(IN)	(IN)	(IN)	(IN)	(IN)	(IN)	(IN)	(IN)				(IN)			
			SIGN DESCRIPTION, SIZES, AND NUMBER OF EACH																								
																											
R4-7	R1-2	R6-1R	R6-4	M3-2	M1-5	M6-2R	M2-1	M1-5	M1-5	W2-6	W13-1P	M3-4	M5-3	M3-1	M5-1R	M6-3	W3-2	W16-17P									
16	85+37	RTE 124 Rt.	1																		R4-7	STD.	1	24 x 30	5		
17	84+68	RTE 124 Rt.		1																	R1-2	STD.	2	48 x 48	32		
18	84+71	RTE 124 Lt.		1																	R6-1R	STD.	1	36 x 12	3		
19	84+14	RTE 124 Lt.			1	1															R6-4	STD.	1	30 x 24	5		
20	246+32	RTE 22 Rt.					1	1	1												M3-2	STD.	2	24 x 12	4		
21	247+96	RTE 22 Rt.					1	1													M1-5	STD.	3	24 x 24	12		
22	256+18	RTE 22 Lt.									1	1	1								M6-2R	STD.	1	21 x 15	2.1875		
23	254+18	RTE 22 Lt.												1	1						M2-1	STD.	1	21 x 15	2.1875		
24	252+18	RTE 22 Lt.						1				1	1			2	1	1	1	1	M1-5	STD.	2	30 x 24	10		
25	250+18	RTE 22 Lt.																	1		M1-5	STD.	2	30 x 24	10		
																					W2-6	STD.	1	48 x 48		16	
																					W13-1P	STD.	1	24 x 24		4	
																					M3-4	STD.	2	24 x 12	4		
																					M5-3	STD.	1	21 x 15	2.1875		
																					M3-1	STD.	1	24 x 12	2		
																					M5-1R	STD.	1	21 x 15	2.1875		
																					M6-3	STD.	1	21 x 15	2.1875		
																					W3-2	STD.	1	48 x 48		16	
																					W16-17P	STD.	1	36 x 12		3	
																		SUBTOTAL 3		3	98	39	0				

STANDARD SIGN ASSEMBLIES																					SIGN SUMMARY							
SIGN NO.	STATION/ LOG MILE	LOCATION	SIGN																			STANDARD SIGN OR SPECIAL SIGN NUMBER	SIGN DETAIL SHEET NO.	NO. EACH	SIZE, TYPE, AND SQUARE FEET			
			84 x 36	24 x 30	48 x 48	36 x 12	30 x 24	24 x 12	30 x 24	21 x 15	48 x 48	24 x 24	24 x 12	30 x 24	21 x 15	24 x 12	24 x 24	21 x 15	21 x 15	48 x 48	36 x 12							
			(1N)	(1N)	(1N)	(1N)	(1N)	(1N)	(1N)	(1N)	(1N)	(1N)	(1N)	(1N)	(1N)	(1N)	(1N)	(1N)	(1N)	(1N)	(1N)							
			SIGN DESCRIPTION, SIZES, AND NUMBER OF EACH																									
																												
D1-2d	R4-7	R1-2	R6-1R	R6-4	M3-1	M1-5	M6-2R	W2-6	W13-1P	M3-4	M1-5	M5-3	M3-2	M1-5	M5-1R	M6-3	W3-2	W16-17P										
26	248+18	RTE 22 Lt.	1																		D1-2d	STD.	1	84 x 36			21	
27	247+05	RTE 22		1																	R4-7	STD.	1	24 x 30	5			
28	246+33	RTE 22 Lt.			1																R1-2	STD.	2	48 x 48	32			
29	246+56	RTE 22 Lt.			1																R6-1R	STD.	1	36 x 12	3			
30	245+92	RTE 22 Lt.				1	1														R6-4	STD.	1	30 x 24	5			
31	83+13	RTE 151 Lt.						1	1	1											M3-1	STD.	1	24 x 12	2			
32	75+50	RTE 151 Rt.									1	1									M1-5	STD.	1	30 x 24	5			
33	77+50	RTE 151 Rt.											2	1	1	1	2	1	1		M6-2R	STD.	1	21 x 15	2.1875			
34	79+50	RTE 151 Rt.																	1		W2-6	STD.	1	48 x 48		16		
																					W13-1P	STD.	1	24 x 24		4		
																					M3-4	STD.	2	24 x 12	4			
																					M1-5	STD.	1	30 x 24	5			
																					M5-3	STD.	1	21 x 15	2.1875			
																					M3-2	STD.	1	24 x 12	2			
																					M1-5	STD.	2	24 x 24	8			
																					M5-1R	STD.	1	21 x 15	2.1875			
																					M6-3	STD.	1	21 x 15	2.1875			
																					W3-2	STD.	1	48 x 48		16		
																					W16-17P	STD.	1	36 x 12		3		
																		SUBTOTAL 4		4	80	39	21					



DATE PREPARED
2/27/2024

ROUTE **22** STATE **MO**

DISTRICT **CD** SHEET NO. **43**

COUNTY
BOONE

JOB NO.
JCD0030

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION	DATE								

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

STANDARD SIGN ASSEMBLIES																					SIGN SUMMARY													
SIGN NO.	STATION/ LOG MILE	LOCATION	SIGN																		STANDARD SIGN OR SPECIAL SIGN NUMBER	SIGN DETAIL SHEET NO.	NO. EACH	SIZE, TYPE, AND SQUARE FEET										
			84 x 48	24 x 30	48 x 48	36 x 12	30 x 24	x	x	21 x 15	x	x	x	x	x	x	x	x	x	x														
			(IN)	(IN)	(IN)	(IN)	(IN)	(IN)	(IN)	(IN)	(IN)	(IN)	(IN)	(IN)	(IN)	(IN)	(IN)	(IN)	(IN)	(IN)														
			SIGN DESCRIPTION, SIZES, AND NUMBER OF EACH																					SIZE (IN)	FLAT SHEET SH ITEM NO. 9035004A	FLAT SHEET FLOURESCENT SHF * ITEM NO. 9035069A	STRUCTURAL ST ITEM NO. 9035011A							
																																		
D1-3d	R4-7	R1-2	R6-1R	R6-4				M6-2R																										
35	81+50	RTE 151 Rt.	1																															
36	82+40	RTE 151		1																														
37	83+10	RTE 151 Rt.			1																													
38	82+96	RTE 151 Rt.			1																													
39	83+51	RTE 151 Rt.				1	1																											
40	244+77	RTE 22 Lt.						1																										
																		SUBTOTAL 5		47	0	28												
																		SUBTOTAL 4		80	39	21												
																		SUBTOTAL 3		98	39	0												
																		SUBTOTAL 2		46	39	18												
																		SUBTOTAL 1		72	34	14												
																		TOTAL		343	151	81												
																					* ORANGE, YELLOW, & YELLOW/GREEN													

STATE OF MISSOURI
PATRICK J. HAKE
NUMBER
PE-2010000826
PROFESSIONAL ENGINEER

DATE PREPARED
2/27/2024

ROUTE
22

DISTRICT
CD

STATE
MO

SHEET NO.
44

COUNTY
BOONE

JOB NO.
JCD0030

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION


DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION




105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

SIGNING SHEET
D-30
SHEET 6 OF 7




D1-2a ST-STRUCTURAL:
3,000" Radius, 1,000" Border, White on, Green;
Standard Arrow Custom 7,000" X 6,000" 90"; "Mexico", E Mod; "14", E Mod; "Hallsville", E Mod;
"8", E Mod; Standard Arrow Custom 9,000" X 6,000" 0";
Table of letter and object lefts

↑	M	e	x	l	c	o	l	4	
6,000	18,000	25,625	30,750	37,125	40,125	45,375	69,375	72,500	
H	a	l	l	s	v	l	l	e	8
6,000	12,875	19,000	22,375	25,125	30,125	36,375	39,750	43,125	46,125




D1-2d ST-STRUCTURAL:
3,000" Radius, 1,000" Border, White on, Green;
"US 63", E Mod; "10", E Mod; "Mexico", E Mod; "14", E Mod;
Standard Arrow Custom 9,000" X 6,000" 0";
Table of letter and object lefts

↑	U	S	6	3	l	o	
5,000	20,750	27,125	37,875	43,875	58,750	62,000	
M	e	x	l	c	o	l	4
5,000	12,625	17,750	24,125	27,125	32,250	44,000	47,000




D1-2d ST-STRUCTURAL:
3,000" Radius, 1,000" Border, White on, Green;
Standard Arrow Custom 9,000" X 6,000" 90"; "US 63", E Mod; "10", E Mod; "Hallsville", E Mod;
"8", E Mod;
Table of letter and object lefts

↑	U	S	6	3	l	o	
7,125	20,750	27,125	37,875	43,875	70,750	74,000	
↑	H	a	l	l	s	v	l
5,000	20,750	27,625	33,750	37,125	40,000	44,875	51,125



D1-3d ST-STRUCTURAL:
3,000" Radius, 1,000" Border, White on, Green;
Standard Arrow Custom 9,000" X 6,000" 90"; "Hallsville", E Mod; "8", E Mod; "Mexico", E Mod;
"14", E Mod; "US 63", E Mod; "10", E Mod; Standard Arrow Custom 9,000" X 6,000" 0";
Table of letter and object lefts

↑	H	a	l	l	s	v	l	l	l	e	8
7,125	20,750	27,625	33,750	37,125	40,000	44,875	51,125	54,500	57,875	60,875	74,250
↑	M	e	x	l	c	o	l	4			
5,000	20,750	28,375	33,500	39,875	42,875	48,125	70,500	73,500			



DATE PREPARED
2/21/2024
ROUTE 22 STATE MO
DISTRICT CD SHEET NO. 45
COUNTY BOONE
JOB NO. JCD0030
CONTRACT ID.

PROJECT NO.
BRIDGE NO.

DATE	DESCRIPTION

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
MODOT
105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

SIGNING SHEET
D-31
SHEET 7 OF 7

