

STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS					
LOG MILE	LOG MILE	LOCATION	4" WHITE (L.F.)	4" YELLOW (L.F.)	REMARKS
US 160 EB					
45.489	45.548	RT	311.5		RIGHT EDGELINE
45.489	45.548	LT	311.5		LEFT EDGELINE
45.489	45.548	CL		77.9	INTERMITTENT BETWEEN LANES
BU 65 SB					
3.109	3.207	RT	129.4		INTERMITTENT BETWEEN LANES
3.109	3.207	LT	129.4		INTERMITTENT BETWEEN LANES
3.109	3.207	CL RT		646.8	SOLID CENTERLINE & INTERMITTENT
3.109	3.207	CL LT		646.8	SOLID CENTERLINE & INTERMITTENT
BRANSON LANDING BLVD. SB					
1.710	1.871	RT	850.1		RIGHT EDGELINE
1.710	1.871	LT	850.1		LEFT EDGELINE
1.710	1.871	CL		1700.2	DOUBLE SOLID CENTERLINE
		TOTAL	2582.0	3071.7	
		USE	2582	3072	


PAVEMENT MARKING REMOVAL				
LOG MILE	LOG MILE	LOCATION	PAINT (L.F.)	REMARKS
I-49 SB				
178.724	178.821	RT	512.2	RIGHT EDGELINE
178.724	178.821	LT	512.2	LEFT EDGELINE
178.724	178.821	CL RT & LT	128.0	INTERMITTENT BETWEEN LANES
US 65 NB				
8.846	8.935	RT	469.9	RIGHT EDGELINE
8.846	8.935	LT	469.9	LEFT EDGELINE
8.846	8.935	CL	117.5	INTERMITTENT BETWEEN LANES
BU 65 SB				
3.109	3.207	RT	129.4	INTERMITTENT BETWEEN LANES
3.109	3.207	LT	129.4	INTERMITTENT BETWEEN LANES
3.109	3.207	CL RT	646.8	SOLID CENTERLINE & INTERMITTENT
3.109	3.207	CL LT	646.8	SOLID CENTERLINE & INTERMITTENT
BRANSON LANDING BLVD. SB				
1.710	1.871	RT	850.1	RIGHT EDGELINE
1.710	1.871	LT	850.1	LEFT EDGELINE
1.710	1.871	CL	1700.2	DOUBLE SOLID CENTERLINE
		TOTAL	7162.5	
		USE	7163	

SLAB JACKING MATERIAL HIGH DENSITY POLYURETHANE				
LOG MILE	LOG MILE	AREA (SY)	POLYURATHANE (LBS)	REMARKS
I-49 SB				
187.815	178.821	195	1800.0	APPROACH SLAB LIFT BENT 5
BU 65 SB				
3.129	3.134	190	1200.0	APPROACH SLAB LIFT BENT 1
3.197	3.202	190	1200.0	APPROACH SLAB LIFT BENT 5
TOTAL			4200.0	
USE			4200	

RELIEF JOINT			
LOG MILE	LENGTH (FT)	OPEN CELL FOAM JOINT SEAL (L.F.)	REMARKS
BU 65 SB			
3.129	95	95.0	BETWEEN APPROACH SLAB & APPROACH PAVEMENT
3.202	95	95.0	BETWEEN APPROACH SLAB & APPROACH PAVEMENT
TOTAL		190.0	
USE		190	

GUARDRAIL					
BEGIN LOG MILE	END LOG MILE	GUARDRAIL (LF)	BRIDGE APPROACH TRANSITION SECTION (EACH)	BRIDGE ANCHOR SECTION (EACH)	CWT (EACH)
US 160 EB					
LEFT SIDE					
45.479	45.506	50.0	1		1
45.526	45.552	50.0	1		1
RIGHT SIDE					
45.479	45.506	50.0	1	1	1
45.526	45.552	50.0	1	1	1
TOTAL		200.0	4	4	4
USE		200	4	4	4

2 REVIS
QUANTITY FOR THE BRIDGE ANCHOR SECTION IS INCLUDED IN THE BRIDGE APPROACH TRANSITION SECTION PAY ITEM.



DATE PREPARED
12/4/2024
ROUTE
VAR
DISTRICT
SW
COUNTY
VARIOUS
JOB NO.
JSR0053
CONTRACT ID.

PROJECT NO.
BRIDGE NO.

DESCRIPTION	DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

2 REVIS