
TABLE OF CONTENTS

- A. Construction Requirements
- B. Cleaning and Coating Existing Bearings



MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 W. CAPITOL AVE. JEFFERSON CITY, MO 65101 Phone (888) 275-6636

If a seal is present on this sheet, JSP's has been electronically sealed and dated.

JOB NO. JNE0123 Montgomery County, MO Date Prepared: 11/20/2024

Only the following items of the Job Special Provisions (Bridge) are authenticated by this seal: All

A. <u>CONSTRUCTION REQUIREMENTS</u>

- **1.0 Description.** This provision contains general construction requirements for this project.
- **2.0 Construction Requirements.** The plans and the asbestos and lead inspection report for the existing structure(s) are included in the contract in the bridge electronic deliverables zip file for informational purposes only.
- **2.1** In order to assure the least traffic interference, the work shall be scheduled so that the bridge closure is for the absolute minimum amount of time required to complete the work. The bridge shall not be closed until material is available for continuous construction and the contractor is prepared to diligently pursue the work until the closed bridge is opened to traffic.
- **2.2** Provisions shall be made to prevent any debris and material from falling into the waterway. If determined necessary by the engineer, any debris and material that falls below the bridge outside the previously specified limits shall be removed as approved by the engineer at the contractor's expense.
- **2.3** Any damage sustained to the remaining structure as a result of the contractor's operations shall be repaired or the material replaced as approved by the engineer at the contractor's expense.
- **2.4** Provisions shall be made to prevent damage to any existing utilities. Any damage sustained to the utilities as a result of the contractor's operations shall be the responsibility of the contractor. All costs of repair and disruption of service shall be as determined by the utility owners and as approved by the engineer.
- **2.5** SSPC-SP2 and SSPC-SP3 surface preparation shall be in accordance with the environmental regulations in Sec 1081 and collection of residue shall be in accordance with Sec 1081 for collection of blast residue. SSPC-SP6, SSPC-SP10 and SSPC-SP11 surface preparation shall be in accordance with the approved blast media and environmental regulations in Sec 1081 and collection of blast residue shall be in accordance with Sec 1081.
- 3.0 Method of Measurement. No measurement will be made.
- **4.0 Basis of Payment.** Payment for the above-described work will be considered completely covered by the contract unit price for other items included in the contract.

B. CLEANING AND COATING EXISTING BEARINGS

- **1.0 Description.** This work shall consist of cleaning and coating existing bearings as specified on the plans and as directed by the engineer.
- 2.0 Construction Requirements.
- **2.1 Cleaning and Coating.** Bearings shall be cleaned and coated in accordance with Sec 1081. Coating of bearings shall be as indicated for coating existing steel as specified in the contract documents.
- **3.0 Method of Measurement.** Measurement for cleaning and coating existing bearings will be made per each.

Job No JNE0123 Route RA Montgomery County

JOB SPECIAL PROVISIONS (BRIDGE)

4.0 Basis of Payment. Payment for the above described work, including all material, equipment, labor and any other incidental work necessary to complete this item, will be considered completely covered by the contract unit price for Cleaning and Coating Existing Bearings.