REMOVAL OF IMPROVEMENTS - 1 LUMP SUM

PLAN SHEET NO.	STATION	STATION	RDWY	LF	SF	EA	DESCRIPTION
4	146+70.2		141			1	FLARED END SECTION
4	147+79.82	149+51.08	141	750			GUARDRAIL
4-5	150+14.25	157+68.42	141	175			GUARDRAIL
4	145+60.65	157+00.00	141		7049		SHOULDER
4	148+46.87	157+00.00	141		3171.75		FULL DEPTH PAVEMENT
4	149+51.08	150+14.25	141	63.2			CONCRETE BARRIER
5	157+00.00	161+12.34	141		1564.4		FULL DEPTH PAVEMENT
5	157+00.00	159+73.23	141		5592		SHOULDER
9	4+25.03	9+05.00	EB RAMP		152.1		FULL DEPTH PAVEMENT
9	4+25.03	9+05.00	EB RAMP		4244.1		SHOULDER
10	9+05.00	9+60.00	EB RAMP		483		FULL DEPTH PAVEMENT
10	9+05.00	9+60.00	EB RAMP		516.3		SHOULDER
13	0+00	3+05	WB RAMP	320			GUARDRAIL
13	1+57.2	11+25.42	WB RAMP		4572		SHOULDER
13	508+85.00	510+10.00	N OUTER 40	125			GUARDRAIL
13	2+91.2		WB RIGHT TURN			1	SIGNAL POLE
13	2+39.07	2+72.63	WB RIGHT TURN			3	FLARED END SECTIONS
13	2+68.1	2+78.4	WB RIGHT TURN	12			48" PIPE
13	2+81.58		WB RIGHT TURN			1	MANHOLE
13	134+50.26	135+85.34	141		812		SHOULDER
16	143+01.17	144+51.65	141	150.5			CONCRETE BARRIER
69	145+93.00		141			1	YIELD SIGN
69	145+93.00		141			1	SIGN POST & FOOTING
69	147+35.00		141			1	SIGN POST & FOOTING
69	148+99.00		141			1	STRUCTURAL SIGN
69	148+99.00		141			1	TYPE C TUBULAR SUPPORT & BASE
69	145+48.00		141			1	YIELD SIGN
70	153+55.00		141			1	SPEED LIMIT SIGN
70	153+55.00		141			1	SIGN POST & FOOTING
71	157+69.00		141			1	ADOPT-A-HIGHWAY SIGN
71	157+69.00		141			1	SIGN POST
71	157+79.00	LT	141			1	ADOPT-A-HIGHWAY SIGN
71	157+79.00	RT	141			1	SIGN POST
72	165+69.00		141			2	STRUCTURAL SIGNS
72	165+69.00		141			1	OVERHEAD SIGN CATWALK/LIGHTING
73	6+70.00		EB RAMP			1	CCTV EQUIP.,POST, & FOOTING
73	7+03.00		EB RAMP			2	SIGN POSTS & FOOTINGS
73	7+54.00		EB RAMP			2	SIGN POSTS & FOOTINGS
73	8+05.00		EB RAMP			1	YIELD AHEAD SIGN
73	8+05.00		EB RAMP			1	SIGN POST & FOOTING
75	2+18.00		WB RAMP			1	STRUCTURAL SIGN
75	2+18.00	LT	WB RAMP			2	SIGN POSTS & FOOTINGS
75	2+18.00	RT	WB RAMP			1	ADOPT-A-HIGHWAY SIGN
75	2+18.00	RT	WB RAMP			1	SIGN POST
75	23+40.00		WB RAMP	ON-RAMP		1	ADOPT-A-HIGHWAY SIGN
75	23+40.00		WB RAMP	ON-RAMP		1	SIGN POST
			PAY TOTAL	1 LUMP SUM			

* ALL VERTICAL SAW CUTS SHALL BE CONSIDERED INCIDENTAL TO REMOVALS OF IMPROVEMENTS

SIGN RELOCATION

SHEET NO.	STATION	LOCATION	SIGN REMOVAL & RELOCATION EACH	REMARKS
68	147+35.00	141	2	M3-3 & M1-5 SIGNS
68	148+99.00	141	3	MoDOT GATEWAY GUIDE SIGNS
72	7+03.00	EB RAMP	1	STRUCTURAL SIGN
72	7+54.00	EB RAMP	1	LANE DIRECTION SIGN
		SUB TOTAL	7	
		PAY TOTAL	7	

MOBILIZATION - 1 LUMP SUM

ADDITIONAL MOBILIZATION FOR SEEDING - 1 LUMP SUM

CONTRACTOR FURNISHED SUREY & STAKING - 1 LUMP SUM

TRAFFIC SIGNAL MAINTENANCE AND PROGRAMMING - 1 LUMP SUM

1 ADDED

RAISED MEDIAN AND CONCRETE BARRIER

PLAN SHEET NO	RDWY	STA	STA	LOC	AREA S.F.	6 IN. CONC. MEDIAN STRIP S.Y.	TYPE C BARRIER L.F.	TYPE D BARRIER	REMARKS
15	141	143+01.17	144+51.65	51' RT	407.16	45.2			
4	141	148+90.84	149+51.08	58.7' RT			60.24		
4	141	149+51.08	150+14.25	51' RT				63.17	
					TOTALS	45.2	60.24	63.17	
					PAY TOTALS	45.2	61	64	

SEEDING

PLAN SHEET	LOCATION	AREA SF	TEMPORARY SEEDING ACRE	SEEDING WARM SEASON GRASSES ACRE	MULCHING ACRE	REMARKS
6	ROUTE 141	13068	0.3	0.3	0.6	
7	ROUTE 141	4356	0.1	0.1	0.2	
11	EB RAMP	4356	0.1	0.1	0.2	
12	EB RAMP	4356	0.1	0.1	0.2	
14	WB RAMP	13068	0.3	0.3	0.6	
		TOTAL	0.9	0.9	1.8	

SUMMARY OF QUANTITIES
SHEET 1 OF 6

STATE OF MISSOURI
STUART ROBINSON McNEIL
NUMBER PE-2006019687
PROFESSIONAL ENGINEER
01/07/2025 11:05:32 AM
STUART ROBINSON McNEIL - CIVIL
MO-PE-2006019687

DATE PREPARED 1/6/2025

ROUTE	STATE
141	MO
DISTRICT	SHEET NO.
SL	3

COUNTY ST. LOUIS

JOB NO. JSL0121

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION	DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

SUMMARY OF QUANTITIES