

CLEARING AND GRUBBING						
SHEET	FROM STATION	TO STATION	ROADWAY	LOCATION	CLEARING AND GRUBBING (ACRE)	REMARKS
10	7+25	9+97	RAMP 1	LT AND RT	0.1	
10	1+55	4+00	RAMP 3	LT AND RT	0.1	
10	70+68	73+00	ROUTE NN	LT AND RT	0.8	
11	4+00	13+46	RAMP 3	LT AND RT	0.1	
11	23+28	31+77	NORTH OUTER ROAD	LT AND RT	0.1	
12	34+00	40+64	NORTH OUTER ROAD	LT AND RT	0.1	
13	52+00	56+45	NORTH OUTER ROAD	LT AND RT	0.2	
15	20+25	21+90	NORTH OUTER ROAD	LT	0.1	
15	53+15	56+50	ROUTE A	LT	0.1	
16	73+00	86+50	ROUTE NN	LT AND RT	6.1	
17	86+50	94+25	ROUTE NN	LT AND RT	0.7	
17	12+33	16+67	EXISTING ROUTE NN	LT	0.1	
18	0+00	13+00	SOUTH OUTER ROAD	LT AND RT	3.8	
19	13+00	26+00	SOUTH OUTER ROAD	LT AND RT	4.3	
20	26+00	39+00	SOUTH OUTER ROAD	LT AND RT	2.2	
21	39+00	52+00	SOUTH OUTER ROAD	LT AND RT	1.5	
22	52+00	65+00	SOUTH OUTER ROAD	LT AND RT	1.5	
23	65+00	78+00	SOUTH OUTER ROAD	LT AND RT	0.7	
24	78+00	91+00	SOUTH OUTER ROAD	LT AND RT	1.3	
25	91+00	104+00	SOUTH OUTER ROAD	LT AND RT	3.6	
26	104+00	117+00	SOUTH OUTER ROAD	LT AND RT	1.6	
27	117+00	130+00	SOUTH OUTER ROAD	LT AND RT	0.3	
28	130+00	143+00	SOUTH OUTER ROAD	LT AND RT	0.3	
29	143+00	156+00	SOUTH OUTER ROAD	LT AND RT	0.6	
30	156+00	169+00	SOUTH OUTER ROAD	LT AND RT	0.4	
TOTALS					31	

EARTHWORK								
FROM STATION	TO STATION	BASELINE	CUT (CUYD)	FILL (CUYD)	UNCLASSIFIED EXCAVATION (CUYD)	COMPACTING EMBANKMENT (CUYD)	EMBANKMENT IN PLACE (CUYD)	REMARKS
0+00.00	42+71.66	EB US60	55,963	8,160				INCLUDES RAMP 2 AND RAMP 4 GORE
0+00.00	9+73.93	RAMP 1	182	64,018				
0+00.00	10+68.27	RAMP 2	2,586	42,776				
0+00.00	16+40.45	RAMP 3	7,606	93,385				
0+00.00	13+87.11	RAMP 4	12,848	55,066				
51+11.18	66+61.17	RTE A	1,155	148,521				NORTH OF US60
66+61.17	70+23.22	RTE A/NN	0	9,694				SOUTH OF US60/NORTH OF BNSF
70+23.22	93+12.73	RTE NN	494	449,819				SOUTH OF BNSF
10+47.96	17+53.70	EXISTING RTE NN	2,618	997				
10+11.24	14+81.00	NORTH OUTER ROAD	58	14,317				WEST OF RTE A
15+19.00	67+58.81	NORTH OUTER ROAD	52,138	40,055				EAST OF RTE A
0+00.00	26+05.89	SOUTH OUTER ROAD	14,991	104,625				RTE 2 TO BLUEBIRD
26+05.89	52+70.70	SOUTH OUTER ROAD	16,122	29,810				BLUEBIRD TO HUMMINGBIRD
52+70.70	79+99.07	SOUTH OUTER ROAD	8,380	15,366				HUMMINGBIRD TO TANDY
79+99.07	109+48.51	SOUTH OUTER ROAD	25,747	29,278				TANDY TO HONOR CAMP
109+48.51	140+51.69	SOUTH OUTER ROAD	15,052	118				HONOR CAMP TO GREENBRIAR
140+51.69	182+19.60	SOUTH OUTER ROAD	24,153	135,742				GREENBRIAR TO RTE NN
524+10.34	717+11.68	EXISTING US60	3,622	1,239				INCLUDES WB ACCEL/DECEL LANES
		RETAING WALLS	1,761					2' BELOW FOOTING
		UTILITY TRENCHING	222					
TOTALS			243,714	207,157			1,035,830	

DISCLAIMER
THE PROFESSIONAL WHOSE SIGNATURE AND PERSONAL SEAL APPEAR HEREON ASSUMES RESPONSIBILITY ONLY FOR WHAT APPEARS ON THIS PAGE, AND DISCLAIMS (PURSUANT TO SECTION 327.411 RSMO) SPECIFICATION, ESTIMATES, REPORTS, OR OTHER DOCUMENTS OR INSTRUMENTS NOT SEALED BY THE UNDERSIGNED PROFESSIONAL RELATING TO OR INTENDED TO BE USED FOR ANY PART OR PARTS OF THE PROJECT TO WHICH THIS PAGE REFERS.



THIS SHEET HAS BEEN SIGNED, SEALED AND DATED ELECTRONICALLY.

DATE PREPARED
1/9/2025
ROUTE 60 STATE MO
DISTRICT SW SHEET NO. 3

COUNTY
WEBSTER
JOB NO.
J7P3425C
CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION	DATE	REVISION NO.	1						
	1/10/25								

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
MoDOT
105 WEST CAPITOL JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

CMT
© Copyright CMT, Inc.
CRAWFORD, MURPHY & TILLY, INC.
6831 WEST ELDONDALE STREET
SPRINGFIELD, MO 65807 (417) 869-6009
ENGINEERING CORPORATION - 000631

ROCK BLANKET							
PLAN SHEET	FROM STATION	TO STATION	BASELINE	LOCATION	FURNISHING ROCK BLANKET (CUYD)	PLACING ROCK BLANKET (CUYD)	REMARKS
10	7+79.44	11+27.28	RAMP 2	LT	1533.9	1533.9	
10	7+32.14	11+38.56	RAMP 2	RT	1443.6	1443.6	
10	0+41.20	3+00.00	RAMP 4	RT	1220.4	1220.4	
11	3+00.00	13+87.11	RAMP 4	RT	2432.5	2432.5	
11	35+91.84	37+00.00	EB US60	RT	198.1	198.1	
12	37+00.00	42+71.66	EB US60	RT	584.2	584.2	
TOTALS					7,413	7,413	

ROCK FILL				
PLAN SHEET	LOCATION	FURNISHING ROCK FILL (CUYD)	PLACING ROCK FILL (CUYD)	REMARKS
10	A9351	425	425	
10	A9352	1059	1059	
10	A9354	1151	1151	
10	A9355	1155	1155	
TOTALS		3,790	3,790	

1 ADDED

COMPACTING IN CUT					
ROADWAY	LOCATION	FROM STATION	TO STATION	COMPACTING IN CUT (STA)	REMARKS
EB US60	CL	0+00	13+70	13.7	
EB US60	CL	25+30	42+70	17.4	
RAMP 2	CL	0+00	4+60	4.6	
RAMP 3	CL	9+90	13+50	3.6	
RAMP 4	CL	7+90	13+80	5.9	
RTE A	CL	51+10	54+10	3.0	
RTE NN	CL	92+50	92+80	0.3	
EXISTING RTE NN	CL	10+50	17+50	7.0	
NORTH OUTER ROAD	CL	10+10	11+10	1.0	
NORTH OUTER ROAD	CL	23+60	24+90	1.3	
NORTH OUTER ROAD	CL	25+50	55+70	30.2	
NORTH OUTER ROAD	CL	63+90	65+40	1.5	
SOUTH OUTER ROAD	CL	0+00	2+70	2.7	
SOUTH OUTER ROAD	CL	9+75	14+25	4.5	
SOUTH OUTER ROAD	CL	25+10	25+70	0.6	
SOUTH OUTER ROAD	CL	31+00	31+80	0.8	
SOUTH OUTER ROAD	CL	32+40	39+70	7.3	
SOUTH OUTER ROAD	CL	47+15	50+05	8.9	
SOUTH OUTER ROAD	CL	52+20	56+30	4.1	
SOUTH OUTER ROAD	CL	61+05	65+35	4.3	
SOUTH OUTER ROAD	CL	68+10	70+00	1.9	
SOUTH OUTER ROAD	CL	71+85	79+15	7.3	
SOUTH OUTER ROAD	CL	82+70	98+00	15.3	
SOUTH OUTER ROAD	CL	99+50	102+40	2.9	
SOUTH OUTER ROAD	CL	109+45	109+85	0.4	
SOUTH OUTER ROAD	CL	110+50	147+80	37.3	
SOUTH OUTER ROAD	CL	149+90	155+20	5.3	
SOUTH OUTER ROAD	CL	157+70	163+20	5.5	
SOUTH OUTER ROAD	CL	164+85	171+55	6.7	
				205.3	

1 ADDED

SUMMARY OF QUANTITIES
5 OF 26