PAVEMENT EDGE TREATMENT

STATION	LOCATION	STATION	LOCATION	QUANTITY LF	REMARK
SOUTH QUADRANT					
158.46	ROUTE 273 RT	141.72	TRACY DR RT	410	
WEST QUADRANT					
4+22.43	ROUTE 273 LT	5+25.07	RTE 371 RT	230	
EAST QUADRANT					
3+36.02	TRACY DR LT	7+64.61	RTE 273 RT	535	
NORTH QUADRANT					
1+49.03	ROUTE 371 LT	7+49.41	RTE 273 LT	750	
			SUBTOTAL	1515	
			PAY TOTAL	1515	

COMMUNICATION EQUIPMENT

STATION	LOCATION	SIDE	POST NO.	CELL PHONE NETWORK ROUTER EACH	CAMERA AND RADIO POLE RISER, 20 FT. EACH	TOP MOUNTED CCTV CAMERA ASSEMBLY EACH	REMARK
4+35.24	CONS'T ℄ RTE 273	LT	3	1	1	1	
			PAY TOTAL	1	1	1	

PAVEMENT MARKING REMOVAL

STATION	STATION	SIDE	LOCATION	REMOVAL LINES LF	REMOVAL SYMBOLS EACH	REMARK
SB RTE 273/SB TRACY DR - SOUTH QUAD.						
0+44	4+30	RT	CONS'T ℄ RTE 273	339		WHITE EDGE LINE
1+45	4+30	RT	CONS'T ℄ RTE 273	283		WHITE LINE, LT TURN LANE
0+46	1+46	CENTER	CONS'T ℄ RTE 273	202	2	DOUBLE YELLOW TAPER & HASH BARS
0+46	4+30	LT	CONS'T ℄ RTE 273	771		DOUBLE YELLOW
2+30	3+70	CENTER	CONS'T ℄ RTE 273		2	LT TURN ARROW
4+30		CENTER	CONS'T ℄ RTE 273		2	STOP BARS
0+47	2+43	RT	CONS'T ℄ TRACY DR	394	4	DOUBLE YELLOW & HASH BARS
NB TRACY DR/ SB RTE 273 - EAST QUAD.						
7+65	9+29	RT	CONS'T ℄ RTE 273	161		WHITE EDGE LINE
5+58		RT & LT	CONS'T ℄ RTE 273		2	STOP BARS
5+58	9+41	RT	CONS'T ℄ RTE 273	766		DOUBLE YELLOW
5+99	7+91	CENTER	CONS'T ℄ RTE 273		3	LT-TURN ARROWS
5+58	8+42	LT	CONS'T ℄ RTE 273	288		LT-TURN LANE LINE
0+47		LT	CONS'T ℄ TRACY DR		1	STOP BAR
0+47	2+43	LT	CONS'T ℄ TRACY DR	400	4	DOUBLE YELLOW MEDIAN BUBBLE & HASH BARS
2+43	6+51	CENTER	CONS'T ℄ TRACY DR	816		DOUBLE YELLOW
0+36	1+94	LT	CONS'T ℄ TRACY DR	186		WHITE LANE LINE
0+63	1+78	LT	CONS'T ℄ TRACY DR		6	LANE DESIGNATION ARROWS
SB RTE 371/ NB RTE 273 - WEST QUAD.						
4+15	4+30	RT	CONS'T ℄ RTE 273	15	1	EDGE LINE
2+52	4+30	RT	CONS'T ℄ RTE 273	188	1	LT-TURN LANE LINE & LT ARROW
4+30		RT & LT	CONS'T ℄ RTE 273		1	STOP BAR
2+93	4+30	LT	CONS'T ℄ RTE 273	274		DOUBLE YELLOW
2+73	3+65	LT	CONS'T ℄ RTE 273	95		EDGE LINE
-1+16	6+82	RT	CONS'T ℄ RTE 371	798		EDGE LINE
-0+56	6+82	RT	CONS'T ℄ RTE 371	1467		CENTERLINE
6+82		RT & LT	CONS'T ℄ RTE 371		1	STOP BAR
NB RTE 273/ NB RTE 371 - NORTH QUAD.						
1+49	3+18	LT	CONS'T ℄ RTE 371	169		WHITE EDGE LINE
5+58		RT & LT	CONS'T ℄ RTE 273		2	STOP BARS
5+58	10+93	RT	CONS'T ℄ RTE 273	1070		DOUBLE YELLOW
6+01	7+94	CENTER	CONS'T ℄ RTE 273		3	LT-TURN ARROWS
8+66	10+93	RT & LT	CONS'T ℄ RTE 273	457	4	DOUBLE YELLOW MEDIAN BUBBLE & HASH BARS
5+58	8+44	LT	CONS'T ℄ RTE 273	288		LT-TURN LANE LINE
7+49	10+92	LT	CONS'T ℄ RTE 273	3+43		WHITE EDGE LINE
9+15	10+65	RT & LT	CONS'T ℄ RTE 273		4	YELLOW HASH MARKS
			SUBTOTAL	9770	43	
			PAY TOTAL	9770	43	

SEEDING

STATION	LOCATION	STATION	LOCATION	COOL SEASON MIXTURE ACRE	REMARKS
SOUTH QUADRANT					
1+58.46	ROUTE 273 RT	1+41.72	TRACY DR RT	0.12	
WEST QUADRANT					
4+22.43	ROUTE 273 LT	5+25.07	RTE 371 RT	0.06	
EAST QUADRANT					
3+36.02	TRACY DR LT	7+64.61	RTE 273 RT	0.11	
NORTH QUADRANT					
1+49.03	ROUTE 371 LT	7+49.41	RTE 273 LT	0.19	
			SUBTOTAL	0.48	
			PAY TOTAL	0.5	

1 ADDED

TEMPORARY PAVEMENT MARKING
1 LUMP SUM

SEE TRAFFIC CONTROL SHEETS 6 TO 10 OF 10 FOR DETAILS.

1 ADDED

SUMMARY OF QUANTITIES
SHEET 5 OF 6

STATE OF MISSOURI
HEATHER R. BARROWS
NUMBER PE-2016040670
PROFESSIONAL ENGINEER
01/23/2025 3:55:53 PM
HEATHER R. BARROWS - CIVIL
MO-PE-2016040670

DATE PREPARED 1/23/2025
ROUTE 273 | STATE MO
DISTRICT KC | SHEET NO. 3
COUNTY PLATTE
JOB NO. JKU0009
CONTRACT ID.
PROJECT NO.
BRIDGE NO.

DESCRIPTION | DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)