TABLE OF CONTENTS

- A. Construction Requirements
- B. Deflection and Haunching

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 W. CAPITOL AVE. JEFFERSON CITY, MO 65101 Phone (888) 275-6636

Civil Design, Inc.

5220 Oakland Ave St. Louis, MO 63110 Certificate of Authority # 2002006804 Consultant Phone # (573) 859-0258

If a seal is present on this sheet, JSP's has been electronically sealed and dated.

JOB NO. J5P3537 Phelps County, MO Date Prepared: 12/30/2024

Only the following items of the Job Special Provisions (Bridge) are authenticated by this seal: A - B $\,$

A. CONSTRUCTION REQUIREMENTS

- **1.0 Description.** This provision contains general construction requirements for this project.
- **2.0 Construction Requirements.** The plans and the asbestos and lead inspection report for the existing structure are included in the contract in the bridge electronic deliverables zip file for informational purposes only.
- **2.1** In order to assure the least traffic interference, the work shall be scheduled so that a lane closure is for the absolute minimum amount of time required to complete the work. A lane shall not be closed until material is available for continuous construction and the contractor is prepared to diligently pursue the work until the closed lane is opened to traffic.
- **2.2** Qualified special mortar shall be a qualified rapid set concrete patching material in accordance with Sec 704. A qualified rapid set concrete patching material will not be permitted for half-sole repair, deck repair with void tube replacement, full depth repair, modified deck repair and substructure repair (formed) unless a note on the bridge plans specifies that a qualified special mortar may be used.
- **2.3** The existing slab for the bridge(s) to be redecked was constructed as composite or non-composite as indicated in the table below.

| Bridge No. | Type of deck |
|------------|--------------|
| J0115 | Composite |

- **2.4** Provisions shall be made to prevent any debris and material from falling into the waterway. If determined necessary by the engineer, any debris and material that falls below the bridge outside the previously specified limits shall be removed as approved by the engineer at the contractor's expense.
- **2.5** Any damage sustained to the remaining structure as a result of the contractor's operations shall be repaired or the material replaced as approved by the engineer at the contractor's expense.
- **2.6** Provisions shall be made to prevent damage to any existing utilities. Any damage sustained to the utilities as a result of the contractor's operations shall be the responsibility of the contractor. All costs of repair and disruption of service shall be as determined by the utility owners and as approved by the engineer.
- **2.7** SSPC-SP2 and SSPC-SP3 surface preparation shall be in accordance with the environmental regulations in Sec 1081, and collection of residue shall be in accordance with Sec 1081 for collection of blast residue. SSPC-SP6, SSPC-SP10 and SSPC-SP11 surface preparation shall be in accordance with the approved blast media and environmental regulations in Sec 1081, and collection of blast residue shall be in accordance with Sec 1081.

3.0 Coating Information.

3.1 Straps Removal. Exposed portions of straps for stay-in-place forms shall be removed prior to surface preparation. Straps need not be removed in areas that are not being painted. Flame cutting will not be permitted. The contractor shall exercise care not to damage the existing structure during removal. Any damage sustained to the remaining structure as a result of the

contractor's operations shall be repaired or the material replaced as approved by the engineer at the contractor's expense.

- **3.2 Slab Drains and Stay-In-Place Forms.** The stay-in-place forms, slab drains and slab drain brackets shall not be recoated, overcoated or damaged during the painting operation. Any portion of the slab drain bracket that is blast cleaned shall be recoated with System G. Any damage sustained as a result of the contractor's operations shall be repaired or the material replaced as approved by the engineer at the contractor's expense.
- **3.3 Environmental Contact.** Environmental Section may be contacted at the below address or phone number. The Missouri Department of Health may be contacted at (573) 751-6102.

MoDOT - Design Division - Environmental Section P.O. Box 270 105 W. Capitol Ave., Jefferson City, MO 65102 Telephone: (573) 526-4778

3.4 Approved Smelter and Hazardous Waste Treatment, Storage and Disposal Facility. The following is the approved smelter and hazardous waste treatment, storage and disposal facility:

Doe Run Company - Resource Recycling Division - Buick Facility Highway KK
Boss, MO 65440
Telephone: (573) 636 4813

Telephone: (573) 626-4813

- **4.0 Method of Measurement.** No measurement will be made.
- **5.0 Basis of Payment.** Payment for the above described work will be considered completely covered by the contract unit price for other items included in the contract.

B. DEFLECTION AND HAUNCHING

- 1.0 Description. The contractor shall determine haunching based on field measurements, existing bridge plans and/or adjusted dead load deflections based on the difference between the new and existing dead load weights. A spreadsheet showing adjusted girder or beam deflections due to the weight of the new deck and barriers is included in the contract in the bridge electronic deliverables zip file.
- 2.0 Construction Requirements. In order to properly form the haunches for the new deck, the contractor shall survey top of deck elevations above each girder or beam including centerline of roadway and along each girder or beam line (top or bottom flange) prior to deck removal followed by surveying elevations of the girders or beams (top or bottom flange) after deck removal.
- **3.0 Method of Measurement.** No measurement will be made.
- **4.0 Basis of Payment.** Payment for the above described work will be considered completely covered by the contract unit price for other items included in the contract.