

Job No.: JST0128
 Route: Y
 County: Audrain, Monroe

JOB SPECIAL PROVISIONS TABLE OF CONTENTS (ROADWAY)

(Job Special Provisions shall prevail over General Special Provisions whenever in conflict therewith.)

A.	General – State JSP-09-03K	1
B.	Contract Liquidated Damages JSP- 13-01D	1
C.	Work Zone Traffic Management JSP-02-06N	2
D.	Emergency Provisions and Incident Management JSP-90-11A	4
E.	Project Contact for Contractor/Bidder Questions JSP-96-05	5
F.	Supplemental Revisions JSP-18-01EE	5
G.	Lump Sum Temporary Traffic Control JSP-22-01A	12
H.	Bridge End Transitions	14
I.	Pavement Marking Log	14
J.	Additional Flaggers	14
K.	Paving Sequence	14
L.	Patching Cold Mix Routes	14
M.	The Kansas City Southern Railway Company Requirements	15

	MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION 105 W. CAPITOL AVE. JEFFERSON CITY, MO 65102 Phone 1-888-275-6636
	If a seal is present on this sheet, JSP's have been electronically sealed and dated.
	JOB NUMBER: JST0128 AUDRAIN, MONROE COUNTY, MO DATE PREPARED: 1/21/2025
	ADDENDUM DATE:
Only the following items of the Job Special Provisions (Roadway) are authenticated by this seal: All	

**JOB
SPECIAL PROVISION**

A. General – State JSP-09-03K

1.0 Description. The Federal Government is not participating in the cost of construction of this project.

1.1 This contract requires payment of the prevailing hourly rate of wages for each craft or type of worker required to execute the contract as determined by the Missouri Department of Labor and Industrial Relations. The current State Wage Rates can be found on the Missouri Department of Transportation web page at www.modot.org under "Doing Business with MoDOT", "Contractor Resources" for the applicable bid opening. This supplemental bidding document has important legal consequences. It shall be conclusively presumed that they are in the bidder's possession, and they have been reviewed and used by the bidder in the preparation of any bid submitted on this project.

State Wage Rates

1.2 The following documents are available on the Missouri Department of Transportation web page at www.modot.org under "Doing Business with MoDOT"; "Standards and Specifications". The effective version shall be determined by the letting date of the project.

General Provisions & Supplemental Specifications

Supplemental Plans to July 2024 Missouri Standard Plans
For Highway Construction

These supplemental bidding documents contain all current revisions to the published versions and have important legal consequences. It shall be conclusively presumed that they are in the bidder's possession, and they have been reviewed and used by the bidder in the preparation of any bid submitted on this project.

B. Contract Liquidated Damages JSP- 13-01D

1.0 Description. Liquidated Damages for failure or delay in completing the work on time for this contract shall be in accordance with Sec 108.8. The liquidated damages include separate amounts for road user costs and contract administrative costs incurred by the Commission.

2.0 Period of Performance. Prosecution of work is expected to begin on the date specified below in accordance with Sec 108.2. Regardless of when the work is begun on this contract, all work on all projects shall be completed on or before the date specified below. Completion by this date shall be in accordance with the requirements of Sec 108.7.1.

Notice to Proceed: May 5, 2025
Contract Completion Date: November 1, 2025

2.1 Calendar Days and Completion Dates. Completion of the project is required as specified herein. The count of calendar days will begin on the date the contractor starts any construction operations on the project.

Project	Calendar Days	Daily Road User Cost
JST0128	35	\$1,800

3.0 Liquidated Damages for Contract Administrative Costs. Should the contractor fail to complete the work on or before the contract completion date specified in Section 2.0, or within the number of calendar days specified in Section 2.1, whichever occurs first, the contractor will be charged contract administrative liquidated damages in accordance with Sec 108.8 in the amount of **\$750** per calendar day for each calendar day, or partial day thereof, that the work is not fully completed. For projects in combination, these damages will be charged in full for failure to complete one or more projects within the specified contract completion date or calendar days.

4.0 Liquidated Damages for Road User Costs. Should the contractor fail to complete the work on or before the contract completion date specified in Section 2.0, or within the number of calendar days specified in Section 2.1, whichever occurs first, the contractor will be charged road user costs in accordance with Sec 108.8 in the amount specified in Section 2.1 for each calendar day, or partial day thereof, that the work is not fully completed. These damages are in addition to the contract administrative damages and any other damages as specified elsewhere in this contract.

C. Work Zone Traffic Management JSP-02-06N

1.0 Description. Work zone traffic management shall be in accordance with applicable portions of Division 100 and Division 600 of the Standard Specifications, and specifically as follows.

1.1 Maintaining Work Zones and Work Zone Reviews. The Work Zone Specialist (WZS) shall maintain work zones in accordance with Sec 616.3.3 and as further stated herein. The WZS shall coordinate and implement any changes approved by the engineer. The WZS shall ensure all traffic control devices are maintained in accordance with Sec 616, the work zone is operated within the hours specified by the engineer, and will not deviate from the specified hours without prior approval of the engineer. The WZS is responsible to manage work zone delay in accordance with these project provisions. When requested by the engineer, the WZS shall submit a weekly report that includes a review of work zone operations for the week. The report shall identify any problems encountered and corrective actions taken. Work zones are subject to unannounced inspections by the engineer and other departmental staff to corroborate the validity of the WZS's review and may require immediate corrective measures and/or additional work zone monitoring.

1.2 Work Zone Deficiencies. Failure to make corrections on time may result in the engineer suspending work. The suspension will be non-excusable and non-compensable regardless if road user costs are being charged for closures.

2.0 Traffic Management Schedule.

2.1 Traffic management schedules shall be submitted to the engineer for review prior to the start of work and prior to any revisions to the traffic management schedule. The traffic management schedule shall include the proposed traffic control measures, the hours traffic control will be in place, and work hours.

2.2 The traffic management schedule shall conform to the limitations specified in Sec 616 regarding lane closures, traffic shifts, road closures and other width, height and weight restrictions.

2.3 The engineer shall be notified as soon as practical of any postponement due to weather, material or other circumstances.

2.4 In order to ensure minimal traffic interference, the contractor shall schedule lane closures for the absolute minimum amount of time required to complete the work. Lanes shall not be closed until material is available for continuous construction and the contractor is prepared to diligently pursue the work until the closed lane is opened to traffic.

2.5 Traffic Congestion. The contractor shall, upon approval of the engineer, take proactive measures to reduce traffic congestion in the work zone. The contractor shall immediately implement appropriate mitigation strategies whenever traffic congestion reaches an excess of 10 minutes to prevent congestion from escalating to 15 minute or above threshold. If disruption of the traffic flow occurs and traffic is backed up in queues of 15 minute delays or longer, then the contractor shall immediately review the construction operations which contributed directly to disruption of the traffic flow and make adjustments to the operations to prevent the queues from reoccurring. Traffic delays may be monitored by physical presence on site or by utilizing real-time travel data through the work zone that generate text and/or email notifications where available. The engineer monitoring the work zone may also notify the contractor of delays that require prompt mitigation. The contractor may work with the engineer to determine what other alternative solutions or time periods would be acceptable.

2.5.1 Traffic Safety.

2.5.1.1 Recurring Congestion. Where traffic queues routinely extend to within 1000 feet of the ROAD WORK AHEAD, or similar, sign on a divided highway or to within 500 feet of the ROAD WORK AHEAD, or similar, sign on an undivided highway, the contractor shall extend the advance warning area, as approved by the engineer.

2.5.1.2 Non-Recurring Congestion. When traffic queues extend to within 1000 feet of the ROAD WORK AHEAD, or similar, sign on a divided highway or to within 500 feet of the ROAD WORK AHEAD, or similar, sign on an undivided highway infrequently, the contractor shall deploy a means of providing advance warning of the traffic congestion, as approved by the engineer. The warning location shall be no less than 1000 feet and no more than 0.5 mile in advance of the end of the traffic queue on divided highways and no less than 500 feet and no more than 0.5 mile in advance of the end of the traffic queue on undivided highways.

3.0 Work Hour Restrictions.

3.1 Except for emergency work, as determined by the engineer, and long term lane closures required by project phasing, all lanes shall be scheduled to be open to traffic during the five major holiday periods shown below, from 12:00 noon on the last working day preceding the holiday until 6:00 a.m. on the first working day subsequent to the holiday unless otherwise approved by the engineer.

Memorial Day
Labor Day
Thanksgiving

Christmas
 New Year's Day

3.1.1 Independence Day. The lane restrictions specified in Section 3.1 shall also apply to Independence Day, except that the restricted periods shall be as follows:

When Independence Day falls on:	The Holiday is Observed on:	Halt Lane Closures beginning at:	Allow Lane Closures to resume at:
Sunday	Monday	Noon on Friday	6:00 a.m. on Tuesday
Monday	Monday	Noon on Friday	6:00 a.m. on Tuesday
Tuesday	Tuesday	Noon on Monday	6:00 a.m. on Wednesday
Wednesday	Wednesday	Noon on Tuesday	6:00 a.m. on Thursday
Thursday	Thursday	Noon on Wednesday	6:00 a.m. on Friday
Friday	Friday	Noon on Thursday	6:00 a.m. on Monday
Saturday	Friday	Noon on Thursday	6:00 a.m. on Monday

3.2 The contractor shall not perform any construction operation on the roadway, roadbed or active lanes, including the hauling of material within the project limits, during restricted periods, holiday periods or other special events specified in the contract documents.

4.0 Basis of Payment. No direct payment will be made to the contractor to recover the cost of equipment, labor, materials, or time required to fulfill the above provisions, unless specified elsewhere in the contract document. All authorized changes in the traffic control plan shall be provided for as specified in Sec 616.

D. Emergency Provisions and Incident Management JSP-90-11A

1.0 The contractor shall have communication equipment on the construction site or immediate access to other communication systems to request assistance from law enforcement or other emergency agencies for incident management. In case of traffic accidents or the need for law enforcement to direct or restore traffic flow through the job site, the contractor shall notify law enforcement or other emergency agencies immediately as needed. The area engineer's office shall also be notified when the contractor requests emergency assistance.

2.0 In addition to the 911 emergency telephone number for ambulance, fire or law enforcement services, the following agencies may also be notified for accident or emergency situation within the project limits.

Missouri Highway Patrol Troop B 660-385-2132
Missouri Highway Patrol Troop F 573-751-1000
Audrain County Sheriff 573-473-5800
Monroe County Sheriff 660-327-4060

2.1 This list is not all inclusive. Notification of the need for wrecker or tow truck services will remain the responsibility of the appropriate law enforcement agency.

2.2 The contractor shall notify law enforcement and emergency agencies before the start of construction to request their cooperation and to provide coordination of services when emergencies arise during the construction at the project site. When the contractor completes this notification with law enforcement and emergency agencies, a report shall be furnished to the engineer on the status of incident management.

3.0 No direct pay will be made to the contractor to recover the cost of the communication equipment, labor, materials or time required to fulfill the above provisions.

E. Project Contact for Contractor/Bidder Questions JSP-96-05

All questions concerning this project during the bidding process shall be forwarded to the project contact listed below.

Keith Killen, Project Contact
NE District, Macon regional Office
26826 N. Hwy 63
Macon, MO 63552

Telephone Number: 660-385-8222
Email: Keith.Killen@modot.mo.gov

All questions concerning the bid document preparation can be directed to the Central Office – Design at (573) 751-2876.

F. Supplemental Revisions JSP-18-01EE

- Compliance with [2 CFR 200.216 – Prohibition on Certain Telecommunications and Video Surveillance Services or Equipment](#).

The Missouri Highways and Transportation Commission shall not enter into a contract (or extend or renew a contract) using federal funds to procure or obtain equipment, services, or systems that uses covered telecommunications equipment or services as substantial or as critical technology as part of any system where the video surveillance and telecommunications equipment was produced by Huawei Technologies Company, ZTE Corporation, Hytera Communications Corporation, Hangzhou Hikvision Digital Technology Company, or Dahua Technology Company (or any subsidiary or affiliate of such entities).

- Stormwater Compliance Requirements

1.0 Description. This provision requires the contractor to provide a Water Pollution Control Manager (WPCM) for any project that includes land disturbance on the project site and the total area of land disturbance, both on the project site, and all Off-site support areas, is one (1) acre or more. Regardless of the area of Off-site disturbance, if no land disturbance occurs on the project site, these provisions do not apply. When a WPCM is required, all sections within this provision shall be applicable, including assessment of specified Liquidated Damages for failure to correct Stormwater Deficiencies, as specified herein. This provision is in addition to any other stormwater, environmental, and land disturbance requirements specified elsewhere in the contract.

1.1 Definitions. The project site is defined as all areas designated on the plans, including temporary and permanent easements. The project site is equivalent to the “permitted site”, as defined in MoDOT’s State Operating Permit. An Off-site area is defined as any location off the project site the contractor utilizes for a dedicated project support function, such as, but not limited to, staging area, plant site, borrow area, or waste area.

1.2 Reporting of Off-Site Land Disturbance. If the project includes any planned land disturbance on the project site, prior to the start of work, the contractor shall submit a written report to the engineer that discloses all Off-site support areas where land disturbance is planned, the total acreage of anticipated land disturbance on those sites, and the land disturbance permit number(s). Upon request by the engineer, the contractor shall submit a copy of its land disturbance permit(s) for Off-site locations. Based on the total acreage of land disturbance, both on and Off-site, the engineer shall determine if these Stormwater Compliance Requirements shall apply. The Contractor shall immediately report any changes to the planned area of Off-site land disturbance. The Contractor is responsible for obtaining its own separate land disturbance permit for Off-site areas.

2.0 Water Pollution Control Manager (WPCM). The Contractor shall designate a competent person to serve as the Water Pollution Control Manager (WPCM) for projects meeting the description in Section 1.0. The Contractor shall ensure the WPCM completes all duties listed in Section 2.1.

2.1 Duties of the WPCM:

- (a) Be familiar with the stormwater requirements including the current MoDOT State Operating Permit for construction stormwater discharges/land disturbance activities; MoDOT’s statewide Stormwater Pollution Prevention Plan (SWPPP); the Corps of Engineers Section 404 Permit, when applicable; the project specific SWPPP, the Project’s Erosion & Sediment Control Plan; all applicable special provisions, specifications, and standard drawings; and this provision;
- (b) Successfully complete the MoDOT Stormwater Training Course within the last 4 years. The MoDOT Stormwater Training is a free online course available at MoDOT.org;
- (c) Attend the Pre-Activity Meeting for Grading and Land Disturbance and all subsequent Weekly Meetings in which grading activities are discussed;
- (d) Oversee and ensure all work is performed in accordance with the Project-specific SWPPP and all updates thereto, or as designated by the engineer;
- (e) Review the project site for compliance with the Project SWPPP, as needed, from the start of any grading operations until final stabilization is achieved, and take necessary actions to correct any known deficiencies to prevent pollution of the waters of the state or adjacent property owners prior to the engineer’s weekly inspections;
- (f) Review and acknowledge receipt of each MoDOT Inspection Report (Land Disturbance Inspection Record) for the Project within forty eight (48) hours of receiving the report and ensure that all Stormwater Deficiencies noted on the report are corrected as soon as possible, but no later than stated in Section 5.0.

3.0 Pre-Activity Meeting for Grading/Land Disturbance and Required Hold Point. A Pre-Activity meeting for grading/land disturbance shall be held prior to the start of any land disturbance operations. No land disturbance operations shall commence prior to the Pre-Activity meeting except work necessary to install perimeter controls and entrances. Discussion items at the pre-activity meeting shall include a review of the Project SWPPP, the planned order of grading operations, proposed areas of initial disturbance, identification of all necessary BMPs that shall be installed prior to commencement of grading operations, and any issues relating to compliance with the Stormwater requirements that could arise in the course of construction activity at the project.

3.1 Hold Point. Following the pre-activity meeting for grading/land disturbance and subsequent installation of the initial BMPs identified at the pre-activity meeting, a Hold Point shall occur prior to the start of any land disturbance operations to allow the engineer and WPCM the time needed to perform an on-site review of the installation of the BMPs to ensure compliance with the SWPPP is met. Land disturbance operations shall not begin until authorization is given by the engineer.

4.0 Inspection Reports. Weekly and post run-off inspections will be performed by the engineer and each Inspection Report (Land Disturbance Inspection Record) will be entered into a web-based Stormwater Compliance database. The WPCM will be granted access to this database and shall promptly review all reports, including any noted deficiencies, and shall acknowledge receipt of the report as required in Section 2.1 (f.).

5.0 Stormwater Deficiency Corrections. All stormwater deficiencies identified in the Inspection Report shall be corrected by the contractor within 7 days of the inspection date or any extended period granted by the engineer when weather or field conditions prohibit the corrective work. If the contractor does not initiate corrective measures within 5 calendar days of the inspection date or any extended period granted by the engineer, all work shall cease on the project except for work to correct these deficiencies, unless otherwise allowed by the engineer. All impact costs related to this halting of work, including, but not limited to stand-by time for equipment, shall be borne by the Contractor. Work shall not resume until the engineer approves the corrective work.

5.1 Liquidated Damages. If the Contractor fails to complete the correction of all Stormwater Deficiencies listed on the MoDOT Inspection Report within the specified time limit, the Commission will be damaged in various ways, including but not limited to, potential liability, required mitigation, environmental clean-up, fines, and penalties. These damages are not reasonably capable of being computed or quantified. Therefore, the contractor will be charged with liquidated damages specified in the amount of \$2,000 per day for failure to correct one or more of the Stormwater Deficiencies listed on the Inspection Report within the specified time limit. In addition to the stipulated damages, the stoppage of work shall remain in effect until all corrections are complete.

6.0 Basis of Payment. No direct payment will be made for compliance with this provision.

- **Delete Sec 106.9 in its entirety and substitute the following:**

106.9 Buy America Requirements.

Buy America Requirements are waived if the total amount of Federal financial assistance applied to the project, through awards or subawards, is below \$500,000.

106.9.1 Buy America Requirements for Iron and Steel.

On all federal-aid projects, the contractor's attention is directed to Title 23 CFR 635.410 *Buy America Requirements*. Where steel or iron products are to be permanently incorporated into the contract work, steel and iron material shall be manufactured, from the initial melting stage through the application of coatings, in the USA except for "minimal use" as described herein. Furthermore, any coating process of the steel or iron shall be performed in the USA. Under a general waiver from FHWA the use of pig iron and processed, pelletized, and reduced iron ore manufactured outside of the USA will be permitted in the domestic manufacturing process for steel or iron material.

106.9.1.1 Buy America Requirements for Iron and Steel for Manufactured items.

A manufactured item will be considered iron and steel if it is "predominantly" iron or steel. Predominantly iron or steel means that the cost of iron or steel content of a product is more than 50 percent of the total cost of all its components.

106.9.2 Any sources other than the USA as defined will be considered foreign. The required domestic manufacturing process shall include formation of ingots and any subsequent process. Coatings shall include any surface finish that protects or adds value to the product.

106.9.3 "Minimal use" of foreign steel, iron or coating processes will be permitted, provided the cost of such products does not exceed 1/10 of one percent (0.1 percent) of the total contract cost or \$2,500.00, whichever is greater. If foreign steel, iron, or coating processes are used, invoices to document the cost of the foreign portion, as delivered to the project, shall be provided and the engineer's written approval obtained prior to placing the material in any work.

106.9.4 Buy America requirements include a step certification for all fabrication processes of all steel or iron materials that are accepted per Sec 1000. The AASHTO Product Evaluation and Audit Solutions compliance program verifies that all steel and iron products fabrication processes conform to 23 CFR 635.410 Buy America Requirements and is an acceptable standard per 23 CFR 635.410(d). AASHTO Product Evaluation and Audit Solutions compliant suppliers will not be required to submit step certification documentation with the shipment for some selected steel and iron materials. The AASHTO Product Evaluation and Audit Solutions compliant supplier shall maintain the step certification documentation on file and shall provide this documentation to the engineer upon request.

106.9.4.1 Items designated as Category 1 will consist of steel girders, piling, and reinforcing steel installed on site. Category 1 items require supporting documentation prior to incorporation into the project showing all steps of manufacturing, including coating, as being completed in the United States and in accordance with CFR Title 23 Section 635.410 Buy America Requirements. This includes the Mill Test Report from the original producing steel mill and certifications documenting the manufacturing process for all subsequent fabrication, including coatings. The certification shall include language that certifies the following. That all steel and iron materials permanently incorporated in this project was procured and processed domestically and all manufacturing processes, including coating, as being completed in the United States and in accordance with CFR Title 23 Section 635.410.

106.9.4.2 Items designated as Category 2 will include all other steel or iron products not in Category 1 and permanently incorporated in the project. Category 2 items shall consist of, but not be limited to items such as fencing, guardrail, signing, lighting and signal supports. The prime contractor is required to submit a material of origin form certification prior to incorporation into the project from the fabricator for each item that the product is domestic. The Certificate of Materials Origin form ([link to certificate form](#)) from the fabricator must show all steps of manufacturing,

including coating, as being completed in the United States and in accordance with CFR Title 23 Section 635.410 Buy America Requirements and be signed by a fabricator representative. The engineer reserves the right to request additional information and documentation to verify that all Buy America requirements have been satisfied. These documents shall be submitted upon request by the engineer and retained for a period of 3 years after the last reimbursement of the material.

106.9.4.3 Any minor miscellaneous steel or iron items that are not included in the materials specifications shall be certified by the prime contractor as being procured domestically. Examples of these items would be bolts for sign posts, anchorage inserts, etc. The certification shall read "I certify that all steel and iron materials permanently incorporated in this project during all manufacturing processes, including coating, as being completed in the United States and in accordance with CFR Title 23 Section 635.410 Buy America Requirements procured and processed domestically in accordance with CFR Title 23 Section 635.410 Buy America Requirements. Any foreign steel used was submitted and accepted under minor usage". The certification shall be signed by an authorized representative of the prime contractor.

106.9.5 When permitted in the contract, alternate bids may be submitted for foreign steel and iron products. The award of the contract when alternate bids are permitted will be based on the lowest total bid of the contract based on furnishing domestic steel or iron products or 125 percent of the lowest total bid based on furnishing foreign steel or iron products. If foreign steel or iron products are awarded in the contract, domestic steel or iron products may be used; however, payment will be at the contract unit price for foreign steel or iron products.

106.9.6 Buy America Requirements for Construction Materials other than iron and steel materials. Construction materials means articles, materials, or supplies that consist of only one of the items listed. Minor additions of articles, materials, supplies, or binding agents to a construction material do not change the categorization of the construction material. Upon request by the engineer, the contractor shall submit a domestic certification for all construction materials listed that are incorporated into the project.

- (a) Non-ferrous metals
- (b) Plastic and Polymer-based products (including polyvinylchloride, composite building materials, and polymers used in fiber optic cables)
- (c) Glass (including optic glass)
- (d) Fiber optic cable (including drop cable)
- (e) Optical fiber
- (f) Lumber
- (g) Engineered wood
- (h) Drywall

106.9.6.1 Minimal Use allowance for Construction Materials other than iron or steel.

"The total value of the non-compliant products is no more than the lesser of \$1,000,000 or 5% of total applicable costs for the project." The contractor shall submit to the engineer any non-domestic materials and their total material cost to the engineer. The contractor and the engineer will both track these totals to assure that the minimal usage allowance is not exceeded.

106.9.7 Buy America Requirements for Manufactured Products.

Manufactured products means:

- (a) Articles, materials, or supplies that have been:

- (i) Processed into a specific form and shape; or
 - (ii) Combined with other articles, materials, or supplies to create a product with different properties than the individual articles, materials, or supplies.
- (b) If an item is classified as an iron or steel product, a construction material, or a section 70917(c) material under § 184.4(e) and the definitions set forth in this section, then it is not a manufactured product. However, an article, material, or supply classified as a manufactured product under § 184.4(e) and paragraph (1) of this definition may include components that are construction materials, iron or steel products, or section 70917(c) materials.

106.9.7.1 Manufactured products are exempt from Buy America requirements. To qualify as a manufactured product, items that consist of two or more of the listed construction materials that have been combined together through a manufacturing process, and items that include at least one of the listed materials combined with a material that is not listed through a manufacturing process, should be treated as manufactured products, rather than as construction materials.

106.9.7.2 Manufactured items are covered under a general waiver to exclude them from Buy America Requirements. To qualify for the exemption the components must comprise of 55% of the value of materials in the item. The final assembly must also be performed domestically.

- Pavement Marking Paint Requirements for Standard Waterborne and Temporary

1.0 Description. High Build acrylic waterborne pavement marking paint shall be used in lieu of standard acrylic waterborne pavement marking paint for all Standard Waterborne Pavement Marking Paint items and all Temporary Pavement Marking Paint items. Paint thickness, bead type, bead application rate, retroreflectivity requirements, and all other specifications shall remain as stated in the Missouri Standard Specifications for Highway Construction, except as otherwise amended in the contract documents.

2.0 Material Requirements. Material requirements for Sec 620.20.2.5 Standard Waterborne Paint, and Sec 620.10.2 Temporary Pavement Marking Paint shall be per Sec 1048.20.1.2 High Build Acrylic Waterborne Pavement Marking Paint.

- ***Delete paragraph 15.0 of the General Provision Disadvantaged Business Enterprise (DBE) Program Requirements and substitute the following:***

15.0 Data Collection from Bidders for DBE and Non-DBE Subcontractors, Suppliers, Manufacturers and/or Brokering used and not used in bids during the reporting period. MoDOT is a recipient of federal funds and is required by 49 CFR 26.11, to provide data about its DBE program. The information shall consist of all subcontractor quoting received for actual use and of consideration by the prime bidder. MoDOT will be requesting this information from bidding prime contractors and will provide prime bidders a form to submit the data by the last day of each month for the current letting. The information shall only include the names of both DBE and non-DBE companies that the prime bidders received quotes. MoDOT will then contact the DBEs and non-DBE subcontractors and request additional information from DBE and non-DBE subcontractors including current year of gross receipts and number of years in business. The information provided by the prime bidders shall not include any bid quote pricing regardless if it was used or not. This information will aid MoDOT in the determination of the availability of DBEs and will be used in subsequent availability studies.

- Third-Party Test Waiver for Concrete Aggregate

1.0 Description. Third party tests may be allowed for determining the durability factor for concrete pavement and concrete masonry aggregate.

2.0 Material. All aggregate for concrete shall be in accordance with Sec 1005.

2.1 MoDOT personnel shall be present at the time of sampling at the quarry. The aggregate sample shall be placed in an approved tamper-evident container (provided by the quarry) for shipment to the third-party testing facility.

2.2 AASHTO T 161 Method B Resistance of Concrete to Rapid Freezing and Thawing, shall be used to determine the aggregate durability factor. All concrete beams for testing shall be 3-inch wide by 4-inch deep by 16-inch long or 3.5-inch wide by 4.5-inch deep by 16-inch long. All beams for testing shall receive a 35-day wet cure fully immersed in saturated lime water prior to initiating the testing process.

2.3 Concrete test beams shall be made using a MoDOT approved concrete pavement mix design.

3.0 Testing Facility Requirements. All third-party test facilities shall meet the requirements outlined in this provision.

3.1 The testing facility shall be AASHTO accredited.

3.1.1 For tests ran after January 1, 2025, accreditation documentation shall be on file with the Construction and Materials Division prior to any tests being performed.

3.1.2 Construction and Materials Division may consider tests completed prior to January 1, 2025, to be acceptable if all sections of this provision are met, with the exception of 3.1.1. Accreditation documentation shall be provided with the test results for tests completed prior to January 1, 2025. No tests completed prior to September 1, 2024, will be accepted.

3.2 The testing facility shall provide their testing process, list of equipment, equipment calibration documentation, and testing certifications or qualifications of technicians performing the AASHTO T 161 Procedure B tests. The testing facility shall provide details on their freezing and thawing apparatus including the time and temperature profile of their freeze-thaw chamber. The profile shall include the temperature set points throughout the entirety of the freeze-thaw cycle. The profile shall show the cycle time at which the apparatus drains/fills with water and the cycle time at which the apparatus begins cooling the specimens.

3.3 Results, no more than five years old, from the third-party test facility shall compare within ± 2.0 percent of an independent test from another AASHTO accredited test facility or with MoDOT test records, in order to be approved for use (e.g. test facility results in a durability factor of 79, MoDOT's recent durability test factor is 81; this compared within +2 percent). The independent testing facility shall be in accordance with this provision. The comparison test can be from a different sample of the same ledge combination.

3.4 When there is a dispute between the third party durability test results and MoDOT durability test results, the MoDOT durability test result shall govern.

3.5 Test results shall be submitted to MoDOT's Construction and Materials division electronically for final approval. Test results shall include raw data for all measurements of relative modulus of elasticity and percent length change for each individual concrete specimen. Raw data shall include initial measurements made at zero cycles and every subsequent measurement of concrete specimens. Raw data shall include the cycle count and date each measurement was taken. Test results shall also include properties of the concrete mixture as required by AASHTO T 161. This shall include the gradation of the coarse aggregate sample. If AASHTO T 152 is used to measure fresh air content, then the aggregate correction factor for the mix determined in accordance with AASHTO T 152 shall also be included.

4.0 Method of Measurement. There is no method of measurement for this provision. The testing requirements and number of specimens shall be in accordance with AASHTO T 161 Procedure B.

5.0 Basis of Payment. No direct payment will be made to the contractor or quarry to recover the cost of aggregate samples, sample shipments, testing equipment, labor to prepare samples or test samples, or developing the durability report.

G. Lump Sum Temporary Traffic Control JSP-22-01A

1.0 Delete Sec 616.11 and insert the following:

616.11 Method of Measurement. Measurement for relocation of post-mounted signs will be made to the nearest square foot of sign area only for the signs designated for payment on the plans. All other sign relocations shall be incidental. Measurement for construction signs will be made to the nearest square foot of sign area. Measurement will be made per each for each of the temporary traffic control items provided in the contract.

616.11.1 Lump Sum Temporary Traffic Control. No measurement will be made for temporary traffic control items grouped and designated to be paid per lump sum. The list of lump sum items provided in the plans or contract is considered an approximation and may be subject to change based on field conditions. This is not a complete list and may exclude quantities for duplicate work zone packages used in simultaneous operations. The contractor shall provide all traffic control devices required to execute the provided traffic control plans for each applicable operation, stage, or phase. No measurement will be made for any additional signs or devices needed except for changes in the traffic control plan directed by the engineer.

2.0 Delete Sec 616.12 and insert the following:

616.12 Basis of Payment. All temporary traffic control devices authorized for installation by the engineer will be paid for at the contract unit price for each of the pay items included in the contract. Whether the devices are paid individually, or per lump sum, no direct payment will be made for the following:

- (a) Incidental items necessary to complete the work, unless specifically provided as a pay item in the contract.
- (b) Installing, operating, maintaining, cleaning, repairing, removing, or replacing traffic control devices.

- (c) Covering and uncovering existing signs and other traffic control devices.
- (d) Relocating temporary traffic control devices, including permanent traffic control devices temporarily relocated, unless specifically included as a pay item in the contract.
- (e) Worker apparel.
- (f) Flaggers, AFADs, PFDs, pilot vehicles, and appurtenances at flagging stations.
- (g) Furnishing, installing, operating, maintaining, and removing construction-related vehicle and equipment lighting.
- (h) Construction and removal of temporary equipment crossovers, including restoring pre-existing crossovers.
- (i) Provide and maintaining work zone lighting and work area lighting.

616.12.1 Lump Sum Temporary Traffic Control. Traffic control items grouped together in the contract or plans for lump sum payment shall be paid incrementally per Sec 616.12.1.1. Alternately, upon request from the contractor, the engineer will consider a modified payment schedule that more accurately reflects completion of traffic control work. No payment will be made for any additional signs or devices needed except for changes in the traffic control plan directed by the engineer. Additional items directed by the engineer will be paid for in accordance with Sec 109.4. No adjustment to the price will be made for overruns or underruns of other work or for added work that is completed within existing work zones.

616.12.1.1 Partial payments. For purposes of determining partial payments, the original contract amount will be the total dollar value of all original contract line items less the price for Lump Sum Temporary Traffic Control (LSTTC). If the contract includes multiple projects, this determination will be made for each project. Partial payments will be made as follows:

- (a) The first payment will be made when five percent of the original contract amount is earned. The payment will be 50 percent of the price for LSTTC, or five percent of the original contract amount, whichever is less.
- (b) The second payment will be made when 50 percent of the original contract amount is earned. The payment will be 25 percent of the price for LSTTC, or 2.5 percent of the original contract amount, whichever is less.
- (c) The third payment will be made when 75 percent of the original contract amount is earned. The payment will be 20 percent of the price for LSTTC, or two percent of the original contract amount, whichever is less.
- (d) Payment for the remaining balance due for LSTTC will be made when the contract has been accepted for maintenance or earlier as approved by the engineer.

616.12.1.2 Temporary traffic control will be paid for at the contract lump sum price for Item:

Item No.	Unit	Description
616-99.01	Lump Sum	Misc. Lump Sum Temporary Traffic Control

H. Bridge End Transitions

1.0 At all bridge exceptions, the engineer will determine in the field the ending point of the transition. This point will not necessarily be at the bridge end, but will be located at a point which provides the smoothest transition and approach to the bridge. Where bridges are to be resurfaced, the surfacing shall be from curb to curb.

I. Pavement Marking Log

1.0 Description. The contractor shall log the locations of existing pavement marking prior to any construction operations that may affect the existing pavement marking. The log shall contain all existing pavement marking and shall include center stripes, no passing stripes, lane lines, turn arrows, hash bars, cross walks, and stop bars. The contractor shall provide a copy of the existing pavement marking log to the engineer. The contractor shall place the new pavement marking at the same locations as the existing pavement marking, unless otherwise directed by the engineer or shown on the plans.

2.0 Basis of Payment. No direct payment will be made for logging of existing pavement marking.

J. Additional Flaggers

1.0 Additional flagger(s) and appropriate construction signs shall be provided at each of the specified locations when work zone extends through the following intersections and/or approaches:

- a) All State Route Intersections
- b) All City Street Intersections

2.0 Basis of Payment. There will be no direct pay for all labor and equipment necessary to provide additional flaggers. All cost shall be considered completely covered under the pay items provided in the contract.

K. Paving Sequence

1.0 Description. The pavement shall be laid in lanes approximately one half the full width of the completed pavement, and the full width shall be completed as soon as practical. Unless otherwise permitted, a single lane shall not be constructed to a length that cannot be completed to full width of the pavement the succeeding operating day.

2.0 Basis of Payment. No additional payment will be made for compliance with this provision.

L. Patching Cold Mix Routes

1.0 Description. This project will resurface routes primarily composed of cold mix material. Due to increased truck traffic during construction, it is anticipated sections of these routes may

experience severe distress and loss of surface integrity, to the point of becoming impassable to passenger vehicles.

1.1 It shall be the contractor's responsibility to repair all damaged pavement areas from the time paving begins to final acceptance of each route. Locations to be repaired shall be determined by the engineer.

1.2 Quantities included in the contract are estimated and may be completely underrun or overrun.

2.0 Construction Requirements. Removal of damaged pavement shall be by cold milling, skid steer or other means approved by the engineer. All loose material shall be removed or swept from damaged areas prior to placement of new material.

3.0 Material. The contractor may use a surface leveling mix or other material as approved by the engineer to repair the damaged pavement areas.

4.0 Method of Measurement. Measurement of Misc. Removal of Damaged Pavement will be computed to the nearest square yard. Measurement of Misc. Replacement of Damaged Pavement will be computed to the nearest 0.1 ton.

5.0 Basis of Payment. All costs including labor, equipment, and materials to comply with this provision will be completely covered under pay items 622-99.05 Misc. Removal of Damaged Pavement, per Square Yard and 402-99.10 Misc. Replacement of Damaged Pavement, per Ton.

M. The Kansas City Southern Railway Company Requirements

To report an emergency on The Kansas City Southern Railway Company right-of-way call: (800) 527-9464. This Project is located on Route Y on the Mexico Subdivision, MP 348.66, designated as DOT # 293378R northwest of Sturgeon, MO.

1.0 Authority of Railroad Engineer and State Engineer.

1.1 The authorized representative of The Kansas City Southern Railway Company, herein called "Railroad Engineer", shall have final authority in all matters affecting the safety of employees of The Kansas City Southern Railway Company, herein called "Railroad", the public, and the safe maintenance and operation of railroad traffic including the adequacy of the foundations and structures supporting the railroad tracks. The Railroad designates the following individual as the Railroad Engineer for this project. Except as otherwise provided in this document, herein called "Railroad Requirements", the Missouri Highway and Transportation Commission's Contractor, herein called "Contractor", shall address all notices to the Railroad concerning this Project to the following person:

Mr. Justin Meyer
Senior Vice President, Engineering and Mechanical
The Kansas City Southern Railway Company
427 West 12th Street
Kansas City, MO 64105
c/o Mr. Bentley Tomlin
Office: 816-983-1605
E-mail: bentley.tomlin@cpkcr.com

1.2 The authorized representative, herein called "Engineer", of the Missouri Highways and Transportation Commission, herein called "Commission", shall have authority over all other matters as prescribed herein and in the project plans and specifications.

1.3 The Railroad's right of way (hereinafter, "Railroad ROW") is located within this Project, which requires the Contractor to perform work on Railroad ROW. Therefore, the Contractor shall coordinate its work activities with the activities of the Railroad as required in this document.

1.4 Indemnification of Railroad by Contractor.

1.4.a. The term Contractor as used herein includes any and all subcontractors.

1.4.b. The Contractor agrees to defend, indemnify and hold harmless Railroad, its directors, officers, employees, agents, successors and assigns from and against any injury or death of persons whomsoever or from any loss or damage to the Railroad's property, right of way, tracks and other facilities, herein called "Railroad's property," and from the Railroad's liability or loss incurred for damage to any other property in Railroad's care, custody or control in or upon Railroad's property, caused by acts or omissions of the Contractor in performing work on this Project, whether on, over, under or in the vicinity of the Railroad's property.

1.4.c. In the event the Contractor shall fail to restore the Railroad's property immediately to a condition acceptable to the Railroad when any such loss or damage to the Railroad's property is called to the Contractor's attention by the Railroad, then the Railroad may perform such corrective work at the cost of the Contractor. The term "loss or damage" as used herein shall include, but not be limited to, the erosion and silting of, water damage to, and the accidental or intentional placing or dropping of objects on the Railroad's property.

2.0 Right of Entry. At least forty-five (45) days in advance of the date the contractor proposes to begin work on the Railroad's Property, the contractor shall enter into a Right of Entry Agreement with Railroad prior to working on Railroad property. Request application for Right of Entry Agreement from:

Denise Case – Permit Manager
JLL – Rail Practice Group
4200 Buckingham Road, Suite 110
Fort Worth, TX 76155
Phone: (817) 230-2614
Email: denise.case@am.ill.com

Online Permit Application: https://jllrpg.360works.com/fmi/webd/rpo_web_kcs.fmp12

2.1 Processing Fee. A One Thousand Dollar (\$1,000) non-refundable processing fee must accompany the application, made payable to JLL, or the application will be returned.

2.2 Permit Fee. A one-time permit fee of \$1,000 will be required once the Right of Entry Agreement is returned to the contractor.

3.0 Construction Requirements. The Contractor's work on the Railroad's ROW shall be performed in accordance with these Railroad Requirements. The Contractor shall supply adequate equipment, labor and materials to perform the proposed work at the job site. The Contractor shall take special precaution and care to prevent any debris or material from falling on the Railroad's right of way. The safe operation of the Railroad shall take precedence over all work

and nothing shall be done by the Contractor that will endanger the Railroad's operations. The Contractor shall protect the Railroad property from any damage resulting from the Contractor's acts or omissions during the highway Project.

4.0 Contractor Plans and Procedures. Before performing any excavation, demolition, blasting, lifting of structural members or construction of falsework on or over Railroad's ROW or adjacent to the Railroad's ROW that may interfere with the safe operation of the trains, the Contractor shall submit its excavation, shoring, demolition, blasting, lifting of structural members and falsework plans and relevant procedures to the Engineer for review, and to the Railroad Engineer for review and approval. These plans and procedures shall be signed and sealed by a Professional engineer licensed in the State of Missouri. However, such approval shall not relieve the Contractor from any liability relating to this Project. During the course of the Project, the Contractor shall submit any proposed changes to the approved plans or procedures to the Engineer for review and to the Railroad Engineer for review and approval. Any clearing and grubbing to increase the sight distance for a safer construction operation, or erection of temporary structures within the Railroad property shall not be done prior to the approval of the Railroad. The Railroad Engineer shall make a decision within 30 days. Should the Railroad Engineer deny the plans and requires a resubmittal, the Railroad Engineer shall provide approval or denial and requirement for resubmittal within 30 days after receipt of the revised plans.

4.1 The Contractor shall be required to take special precautions and care in connection with excavating and shoring. Excavations for construction of footings, piers, columns, walls or other facilities that require shoring shall comply with requirements of OSHA, AREMA and Section IV, Design and Construction of Shoring Adjacent to and on Railroad Right-Of-Way contained within the "KCS Guidelines for the Design and Construction of Railroad Overpasses and Underpasses".

4.2 The Contractor shall abide by the following minimum temporary clearances during the course of construction:

- (a) 14 feet horizontal from centerline of track
- (b) 22 feet vertical above top of rail.

4.3 The Contractor shall comply with the Railroad's rules and regulations concerning protection of persons and property and the Contractor shall consult with the Railroad Engineer concerning the Railroad's rules and regulations. Any questions arising about coordination of work between the Contractor and the Railroad Engineer or between the Contractor and others shall be taken up with the Engineer and the Contractor, Railroad Engineer and Engineer shall agree upon a method of coordination before commencing the work.

4.4 Prior to commencing any work upon, over or under the Railroad's ROW, the Contractor shall furnish to the Railroad Engineer evidence that the Contractor's insurance is in compliance with Section 6 of this special provision.

4.5 The Contractor shall be required to maintain all ditches and drainage structures free of silt or other obstructions which may result from Contractor's operations; to promptly repair eroded areas within Railroad's ROW and to repair any other damage to the property of the Railroad or its tenants which may result from Contractor's operations. All such maintenance and repair of damages due to the Contractor's operations shall be done at the Contractor's expense. If the Contractor's method of erosion control differs from the approved plans, the Contractor shall submit a proposed method of erosion control and have the method reviewed by the Railroad and

Commission prior to beginning any grading work on the Project site. Erosion control methods must comply with all applicable local, state and federal regulations.

4.6 The Contractor shall, reasonably throughout each work day and at the end of each work day when performing work near the Railroad's tracks, inspect the track area and clean up any debris that may have been dropped on or within ten (10) feet of Railroad's tracks. Upon completion of the Project, the Contractor shall return the Railroad ROW and all other Railroad property to a condition equal to or better than existed prior to commencement of the work. Contractor shall remove all waste, excess materials, false work and other temporary structures, and equipment, leaving the location of the work cleaned to the reasonable satisfaction of Railroad. The Contractor shall repair to the reasonable satisfaction of Railroad Engineer, and at the Contractor's sole cost and expense, any and all damages to the Railroad's property caused during construction of the Project.

5.0 Site Inspections By Railroad's Designated Representative.

5.1 In addition to the office review of construction submittals, site inspections may be performed by Railroad's Designated Representative at milestone events during construction, including but not limited to the following:

- (a) Preconstruction meetings.
- (b) Excavations, shoring placement/removal, pile driving, drilling of caissons or drilledshafts adjacent to tracks.
- (c) Reinforcement and concrete placement for near track piers.
- (d) Erection of precast concrete or steel overpass bridge superstructure.
- (e) Reinforcement and concrete placement of overpass bridge decks.
- (f) Completion of the bridge structure.

5.2 The Railroad Designated Representative can either be an employee of the Railroad or a hired outside consultant. Site inspection is not limited to the milestone events listed above. Site visits to check progress of the work may be performed at any time throughout the construction as deemed necessary by the Railroad.

5.3 In addition to the project schedule required by the Commission, the Contractor shall provide to the Engineer a detailed construction schedule for its work on Railroad ROW, including the proposed temporary horizontal and vertical clearances and construction sequence for all work to be performed on Railroad ROW. The Contractor shall submit a copy of this detailed construction schedule to Railroad's Designated Representative for review prior to the start of the work. This schedule shall also include the anticipated dates when the milestone events listed in subsection 5.1 will occur. The Contractor shall update the schedule for these milestone events as necessary, but at least monthly, and shall provide a copy of all updates to the Railroad so that site visits may be scheduled. The Commission shall reimburse the Railroad all costs associated with Site Inspection work by the Railroad.

6.0 Safety and Railroad Flagging.

6.1 The safe operation of the Railroad shall take precedence over Commission’s work on, under and above the Railroad ROW. Contractor shall not, without Railroad’s prior consent, come within 25 feet of Railroad’s tracks. All work of the Contractor to be performed on, above, below or adjacent to the Railroad ROW shall be coordinated with Railroad so as to avoid, to the greatest extent possible, interference with railroad operations and to assure, at a minimum, sufficient advance notice to Railroad to ensure operational safety. Contractor shall be solely responsible with complying with any applicable laws, rules and regulations, including but not limited to OSHA regulations governing multi-employer work sites.

6.2 While on the Railroad’s ROW, Contractor shall comply with Railroad’s rules and regulations concerning protection of persons and property. Railroad shall make its applicable rules available to the Contractor for review and copying.

6.3 Except as authorized by Railroad the Contractor shall not work within the “Minimum Clearance Zone” of any track. The “Minimum Clearance Zone” is defined as an area measured 25 feet, horizontally, on either side of the centerline of track with unlimited vertical distance within the horizontal limits. Additionally, Contractor will locate all equipment, devices, and materials at a sufficient distance from any track to ensure that no apparatus or part of any equipment, device, or material, such as the boom of a crane or a dragline, could under any circumstances encroach on the “Minimum Clearance Zone” of any track. A railroad flagger will also be required when any equipment or its attachment or booms, even though stationed outside the above-mentioned 25 feet of the nearest rail but within the railroad ROW, has a potential to come within the 25 feet of the nearest rail.

6.4 Flagging services provided by a Railroad-qualified flagging contractor will be required whenever agents, employees or equipment of the Contractor or any of its contractors or subcontractors on this Project shall be within twenty-five feet (25’) of the nearest rail or if conditions as noted in item 6.3 above arise, unless specifically waived in writing by the Railroad.

6.5 Contractor shall notify the Railroad concerning any flagging services that will be required during the course of the Project, but the Contractor shall make all arrangements for flagging protection directly with a Railroad-qualified flagging contractor. Railroad’s designation of a flagging contractor as a “Railroad-qualified” flagging contractor shall be construed solely as Railroad’s willingness to allow that flagging contractor to provide flagging services on Railroad’s property without further proof of qualification, and shall not be construed as an endorsement or other verification of the abilities or qualifications of that flagging contractor. Under these Railroad Requirements, all flagging contractors utilized on the Project shall be treated solely as independent contractors of the Contractor for all purposes under these Railroad Requirements.

6.6 The Contractor shall contract directly with any of the Railroad-qualified flagging contractors and pay them directly. The Contractor shall provide at least one month’s notice prior to the first use of flaggers. Current Railroad-qualified flagging contractors are:

Railpros Field Services

Joel Ashcraft 417-362-9007 joel.ashcraft@railpros.com

Bottom Line On-Track Safety Services

Jeff Yarbrough	972-824-3348	jeff.yarbrough@alliedtrack.com
Nick Loar	214-394-5237	nick.loar@alliedtrack.com

6.7 Contractor may also obtain a list of Railroad-qualified flagging contractors together with their address and telephone numbers for flagging purposes at the proposed site by written request, sent at least 30 (thirty) days in advance, by U.S. mail or by e-mail addressed to:

Mr. Justin Meyer
Senior Vice President, Engineering and Mechanical
The Kansas City Southern Railway Company
427 West 12th Street
Kansas City, MO 64105
c/o Mr. Bentley Tomlin
Office: 816-983-1605
E-mail: bentley.tomlin@cpkcr.com

6.8 Contractor shall clear the tracks when directed to do so by the flagger. The presence of the flagger will not relieve Contractor of its duty to keep all of its agents, employees and contractors clear of the tracks when trains are in dangerous proximity to the area where construction is occurring.

6.9 All railroad tracks within and adjacent to the Project site are active, and rail traffic over these facilities shall be maintained throughout the Project. Railroad signal facilities within the project limits shall be protected at all times. KCS shall be notified if any of its facilities are in conflict with the planned work. Activities may include both through moves and switching moves to local customers. Railroad traffic and operations will occur continuously throughout the day and night on the tracks. The Contractor shall coordinate and schedule the work so that construction activities do not interfere with railroad operations. Any and all costs associated with delays caused to the train traffic by the Contractor shall be reimbursed by the Contractor. The Commission or the Contractor may audit these costs.

6.10 The Contractor shall notify Railroad of the completion of work on Railroad ROW within 30 days after the completion of work on Railroad ROW. Railroad shall inspect Railroad's property within 30 days after the Contractor has given this notice, to verify the Contractor's compliance with these Railroad Requirements. Railroad shall notify the Engineer of any outstanding issues to be addressed on Railroad ROW. Engineer will notify the Contractor of work to be completed.

7.0 Insurance Requirements. The amount of work to be performed upon, over or under Railroad's right of way is estimated to be one percent of the Contractor's total bid for the Project. In addition to any other forms of insurance or bonds required under the terms of the contract and specifications, the Contractor shall be required to carry insurance of the following kinds:

(a) Commercial General Liability Insurance, including contractual liability and products completed/operations, against claims arising out of bodily injury, illness and death and from damage to or destruction of property of others, including loss of use thereof, with minimum limits for bodily injury and property damage of \$2,000,000 for each occurrence, with an aggregate of \$6,000,000.

1. The definition of "insured contract" shall be amended to remove any exclusion or other limitation for any work being done within 50 feet of railroad property.
2. No other endorsement limiting the coverage required by paragraph (a) of section 7.0 of these Railroad Requirements shall be included on the policy with regard to

the work being performed under the contract between the contractor and the Commission.

(b) Business Automobile Policy Insurance, including owned, non-owned, and hired vehicles with minimum limits for bodily injury and property damage of \$1,000,000 per occurrence, on all vehicles used on Railroad's property during the term of the contract between the contractor and the Commission.

(c) Worker's Compensation Insurance or coverage as required under the Worker's Compensation Act of the State of Missouri. The policy shall include occupational disease to required statutory limits, employer's liability of \$1,000,000 to include FELA, if appropriate, and an "all states" endorsement.

(d) A Railroad Protective Liability policy issued in the name of the Railroad with limits of \$2,000,000 for bodily injury and property damage per occurrence, with an aggregate of \$6,000,000. The policy shall remain in force during the construction phase of the Project and shall be provided prior to start of work. The following provisions apply to the endorsements to this policy:

1. The policy shall be endorsed to include the Pollution Exclusion Amendment (ISO form CG 28 31 10 93).
2. The policy shall be endorsed to include the Limited Seepage and Pollution Endorsement.
3. The policy shall be endorsed to remove any exclusion for punitive damages.
4. The policy shall be endorsed to include Evacuation Expense Coverage Endorsement.
5. No other endorsements restricting coverage shall be added to the policy, except as authorized by paragraph 7.1.2 of these Railroad Requirements.
6. The Contractor shall provide the original policy to the Railroad before performing any work or services under the contract between the Contractor and the Commission.

7.1 Evidence of Insurance. The Declarations shall include the description of operations matching the Project description in the Contractor's contract with the Commission and shall include the appropriate Commission project and contract identification numbers. The job number and Project location shall appear on the Declarations and shall include the city, state and appropriate highway designation as follows:

Route Y Audrain County, Northwest of Sturgeon, MO
Job No. JST0128
Mexico Subdivision, MP 348.66, DOT# 293378R

7.1.1 The name and address of the Contractor shall appear on the Declarations. The name and address of the Commission shall be identified on the Declarations as the "Involved Governmental Authority or Other Contracting Party".

7.1.2 Other endorsements/forms that will be accepted are:

- (a) Broad Form Nuclear Exclusion – Form IL 00 21.
- (b) 30-day Advance Notice of Non-renewal or cancellation.
- (c) Required State Cancellation Endorsement.
- (d) Quick Reference or Index Form CL/IL 240.

7.1.3 Endorsements/forms that will NOT be acceptable are:

- (a) Any Pollution Exclusion Endorsement except CG 28 31.
- (b) Any Punitive or Exemplary Damages Exclusion.
- (c) Known injury or Damage Exclusion form CG 00 59.
- (d) Any Common Policy Conditions form.
- (e) Any other endorsement/form not specifically authorized in this special provision.

7.1.4 If any part of the work is sublet, similar insurance and evidence thereof as specified above, shall be provided by or on behalf of the subcontractor to cover the subcontractor's operations on the Railroad ROW, including such operations by any Railroad-qualified flagging contractor.

7.1.5 Prior to entry on the Railroad's ROW, the Contractor shall submit the original Railroad Protective Liability Insurance Policy to the Commission and to the Railroad at the addresses below, for review by the Commission and approval by the Railroad. In addition, the Contractor shall submit certificates of insurance evidencing the Contractor's and any subcontractor's Commercial General Liability Insurance to the Railroad and the Commission at the addresses below, for review by the Commission and approval by the Railroad. The certificates of insurance shall state that the insurance coverage shall not be suspended, voided, canceled or reduced in coverage or limits without 30 days advance written notice to the Railroad and the Commission. No work shall be permitted on the Railroad's right-of-way until the Railroad has reviewed and approved the evidence of insurance required herein.

Railroad

Mr. Bentley Tomlin
CPKC Limited
427 West 12th Street
Kansas City, MO 64079
P.O. Box 219335
Kansas City, MO 64121-9335

Commission

Mr. Brandi Baldwin
State Construction & Material Engineer
MoDOT
P.O. Box 270
Jefferson City, MO 65102

8.0 Failure to Comply. If the Contractor violates or fails to comply with any of these Railroad Requirements, then the provisions in paragraphs (a) and (b) of this section shall apply, and shall remain in effect until the Contractor has remedied the situation to the satisfaction of the Railroad Engineer and the Engineer.

Job No.: JST0128
Route: Y
County: Audrain, Monroe

(a) The Railroad Engineer may require that the Contractor shall vacate the Railroad's property.

(b) The Engineer may withhold all monies due to the Contractor until the Contractor has remedied the situation to the satisfaction of the Railroad Engineer and the Engineer.

9.0 Payment for Cost of Compliance. No separate payment will be made for any extra cost incurred by the Contractor on account of compliance with these Railroad Requirements. The Contractor shall include all such costs in its contract unit price for other items included in its contract with the Commission.