

FULL DEPTH PAVEMENT REPAIR												
LOG MILE	LANES		LENGTH FT	WIDTH FT	FURNISHING & PLACING CONC. SQYD	SUBGRADE COMPACTION SQYD	TYPE 5 AGGR. FOR BASE SQYD	SAW CUT LF	DOWEL BARS EA	DOWEL BARS w/ BASKET EA	TIE TIE BAR EA	REMARKS
	EB	WB										
68.535	1		12	12	16.00	1.60	1.60	48	20			
68.525	1		80	12	106.67	10.67	10.67	184	20	40	32	
68.503/ 152.837	1	1	6	24	16.00	1.60	1.60	54	20			
68.473	1		6	12	8.00	0.80	0.80	30	20			
68.463	1		6	12	8.00	0.80	0.80	30	20			
68.444	1		6	12	8.00	0.80	0.80	30	20			
68.241	1		6	12	8.00	0.80	0.80	30	20			
68.233/ 153.107	1	1	6	24	16.00	1.60	1.60	54	20			
68.221	1		6	12	8.00	0.80	0.80	30	20			
68.107/ 153.414	1	1	6	24	16.00	1.60	1.60	54	20			
67.926/ 153.414	1	1	6	24	16.00	1.60	1.60	54	20			
69.907	1		6	12	8.00	0.80	0.80	30	20			
67.882/ 153.477	1	1	6	24	16.00	1.60	1.60	54	20			
67.748/ 153.611	1	1	6	24	16.00	1.60	1.60	54	20			
67.460/ 153.899	1	1	6	24	16.00	1.60	1.60	54	20			
66.990/ 154.369	1	1	6	24	16.00	1.60	1.60	54	20			
66.772/ 154.587	1	1	6	24	16.00	1.60	1.60	54	20			
56.714	1		12	12	16.00	1.60	1.60	48	20			
56.106/ 165.253	1	1	8	24	21.33	2.13	2.13	56	20			
55.277/ 166.082	1	1	6	24	16.00	1.60	1.60	54	20			
51.159/ 170.200	1	1	6	24	16.00	1.60	1.60	54	20			
TOTAL					384.00	38.40	38.40	1110.00	420.00	40.00	32.00	
FINAL PAY TOTAL					384.00	38.00	38.00	1110.00	420.00	40.00	32.00	


DOWEL BARS	
EA	
20	
20	
40	
20	
20	
20	
40	
20	
40	
40	
20	
40	
40	
40	
20	
40	
40	
40	
660.00	
660.00	

1 REVISED

CONCRETE SIDEWALK & CURB RAMP							
BEG. STA.	END STA.	LENGTH L.F.	LINEAR GRADING STA.	5' CONCRETE, 4" SIDEWALK & LANDINGS S.Y.	CONC. CURB RAMP S.Y.	TRUNCATED DOMES S.F.	REMARKS
1041+66.58	1042+17.12	50.54	0.51	28.08			5' CONC. SIDEWALK AND LANDINGS
1041+66.58	1041+71.65	6.15	0.06		3.42	20.0	CONC. RAMP TO SANTE FE ELEM. SCHOOL PARKING LOT
1042+12.07	1042+17.10	9.15	0.09		5.08	20.0	CONC. RAMP TO US24 WB
1042+12.07	1042+17.04	5.00	0.05	2.78		20.0	5' CONC. LANDING ON US24 EB
FINAL TOTAL				0.66	30.86	8.50	60.00
FINAL PAY TOTAL				1.00	30.90	8.50	60.00

OBJECT MARKER								
NO	LOG MILE	OBJECT MARKER		SIGN SIZE	TYPE III OBJECT MARKER EA	2" PSST POST 12 GA LF	POST ANCHOR FOR 2" PSST - 12 GA LF	LOCATION
		WB	EB					
A	54.287	1	1	12"X36"	2	2	12	1697' EAST OF SLUSHER SCHOOL RD. - ROUTE 24(OM3-L/R)
B	54.661	1	1	12"X36"	2	2	12	832' EAST OF NORTHROP RD. - ROUTE 24(OM3-L/R)
C	59.005	1	1	12"X36"	2	2	12	3900' EAST OF MILL ST - ROUTE 24(OM3-L/R)
D	59.345	1	1	12"X36"	2	2	12	5377' EAST OF MILL ST. - ROUTE 24(OM3-L/R)
E	64.257	1	1	12"X36"	2	2	12	290' EAST OF BALTIMORE BENT RD. - ROUTE 24(OM3-L/R)
F	66.945	1	1	12"X36"	2	2	12	620' EAST OF OLD STANTA FE TRAIL - ROUTE 24(OM3-L/R)
FINAL PAY TOTAL					12.00	*12.00	*72.00	* REFER SIGN SHEET 20(D-29)

RELOCATE EXISTING SIGN ASSEMBLIES							
EX. SIGN STATION	EX. SIGN OFFSET FT	RELOCATE STATION	RELOCATE OFFSET FT	LOCATIONS	RELOCATE SIGNS EA	RELOCATE SIGNS SQFT	REMARKS
1041+80.88	29.09 LT.	1042+19.12	18.42 LT.	RELOCATE EX. SIGN TO NEW LOCATION w/ POST & ASSEMBLIES	1.00	9.00	RELOCATE SCHOOL CROSSING SIGN - S1-1
1041+80.88	29.09 LT.	1042+19.12	18.42 LT.	RELOCATE EX. SIGN TO NEW LOCATION		2.00	RELOCATE DIAGONAL ARROW SIGN - W16-7P_L
1040+67.84	24.62 RT.	1042+10.08	17.37 RT.	RELOCATE EX. SIGN TO NEW LOCATION	1.00	2.00	RELOCATE DIAGONAL ARROW SIGN - W16-7P_L
FINAL PAY TOTAL					2.00	*13.00	* FOR IMFORMATION ONLY



DATE PREPARED
2/7/2025

ROUTE 24 STATE MO
DISTRICT KC SHEET NO. 3

COUNTY LAFAYETTE
JOB NO. J3P3158
CONTRACT ID.

PROJECT NO.
BRIDGE NO.

DESCRIPTION	
DATE	

