

DRAINAGE STRUCTURES											
PLAN SHEET NO.	FROM STRUCTURE	FROM STATION	TO STRUCTURE	TO STATION	ROUTE	LOCATION	PIPE COLLAR, TYPE C	18 IN. PIPE GROUP C	18 IN. GROUP C FLARED END SECTIONS	18 IN. FLAP GATES	CLASS 3 EXCAVATION
							EACH	LF	EACH	EACH	CY
13	1-1 FES	313+02	1-2 F	313+98	ROUTE 0	RT		94	1	1	11
13	2-1 FES	313+54	2-2 F	313+98	ROUTE 0	LT		43	1	1	3
13	3-1 FES	315+25	3-2 F	314+43	ROUTE 0	LT		80	1	1	40
13	PIPE COLLAR	315+31	PIPE COLLAR	314+94	ROUTE 0	RT	1	37			20
14	PIPE COLLAR	314+94	4-1 F	314+45	ROUTE 0	RT	1	50		1	36
SUBTOTAL =							2	304	3	4	110
PAY TOTAL =							2	304	3	4	110

EROSION CONTROL - TEMPORARY								
PLAN SHEET NO.	STATION	STATION	ROUTE	LOCATION	SEDIMENT TRAP	SILT FENCE	SEDIMENT REMOVAL	REMARKS
					CY	LF	CY	
9	312+90	314+05	ROUTE 0	RT		118	2	
9	314+42	315+39	ROUTE 0	RT		98	1	
9	315+69	316+30	ROUTE 0	RT		62	1	
9	312+90	314+14	ROUTE 0	LT		133	2	
9	314+32	314+84	ROUTE 0	LT		53	1	
9	315+04	316+30	ROUTE 0	LT		127	2	
9	313+02		ROUTE 0	RT	1		10	FES 1-1
9	313+54		ROUTE 0	LT	1		10	FES 2-1
9	314+77		ROUTE 0	LT	1		10	EXISTING 18" CMP
9	315+25		ROUTE 0	LT	1		10	FES 3-1
9	315+29		ROUTE 0	RT	1		10	EXISTING 18" CMP
9	315+75		ROUTE 0	RT	1		10	EXISTING 18" CMP
SUBTOTAL =					6	591	69	
PAY TOTAL =					6	709	69	20% CONTINGENCY ADDED TO SILT FENCE

PERMANENT PAVEMENT MARKINGS - LINEAR						
PLAN SHEET NO.	STATION	STATION	ROUTE	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	REMARKS
				LF	LF	
10	308+00	320+00	ROUTE 0	1200		SOLID EDGE LINE LEFT
10	308+00	320+00	ROUTE 0	1200		SOLID EDGE LINE RIGHT
10	308+00	320+00	ROUTE 0		2400	DOUBLE YELLOW CENTER LANE
SUBTOTAL =				2400	2400	
PAY TOTAL =				2400	2400	

ROADSIDE DEVELOPMENT						
PLAN SHEET NO.	STATION	STATION	ROUTE	LOCATION	SEEDING - COOL SEASON MIXTURES	MULCHING
					AC	AC
4	313+00	314+04	ROUTE 0	LT / RT	0.08	0.08
4	314+42	316+20	ROUTE 0	LT / RT	0.08	0.08
SUBTOTAL =					0.16	0.16
PAY TOTAL =					1.0	1.0


NOTE: NO FINAL MEASUREMENT WILL BE PERFORMED.

BITUMINOUS RUMBLE STRIPS						
PLAN SHEET NO.	STATION	STATION	ROUTE	LOCATION	CENTERLINE RUMBLE STRIPS	REMARKS
					STA	
12	310+00	313+69	ROUTE 0	CENTER	3.7	CENTERLINE
12	314+72	320+00	ROUTE 0	CENTER	5.3	CENTERLINE
SUBTOTAL =					9.0	
PAY TOTAL =					9.0	

GUARDRAIL					
PLAN SHEET NO.	STATION	ROUTE	LOCATION	TYPE C CRASHWORTHY END TERMINAL (MASH) *	REMARKS
				EACH	
4	313+82	ROUTE 0	LEFT	1	NORTHWEST BRIDGE END - A9401
4	313+82	ROUTE 0	RIGHT	1	SOUTHWEST BRIDGE END - A9401
4	314+59	ROUTE 0	LEFT	1	NORTHEAST BRIDGE END - A9401
4	314+59	ROUTE 0	RIGHT	1	SOUTHEAST BRIDGE END - A9401
SUBTOTAL =				4	
PAY TOTAL =				4	

* ALL ITEMS ASSOCIATED WITH INSTALLATION OF TYPE C CRASHWORTHY END TERMINAL (MASH) SHALL BE CONSIDERED COMPLETELY COVERED BY THE PAY ITEM - TYPE C CRASHWORTHY END TERMINAL (MASH).

1 ADDED



DATE PREPARED
2/24/2025

ROUTE 0 STATE MO
DISTRICT SE SHEET NO. 3

COUNTY
STODDARD

JOB NO.
JSE0116

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DATE	DESCRIPTION
2/24/25	001 - ADD GUARDRAIL

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

MoDOT

105 WEST CAPITOL JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

HR GREEN, INC.
520 MARYVILLE CENTRE DRIVE, SUITE 100
ST. LOUIS, MISSOURI 63141
PHONE: (636) 519-0990
CORPORATE LICENSE #2002006608

