REMOVAL OF IMPROVEMENTS	1 LUMP SUM
MOBILIZATION	1 LUMP SUM
CONTRACTOR FURNISHED SURVEYING AND STAKING	1 LUMP SUM

	SIGN REMOVAL — FOR INFORMATION ONLY										
PLAN SHEET NO.	STATION	ROUTE	LOCATION	ITEM TO BE REMOVED							
10	550+62	ROUTE 102	LT	OBJECT MARKER							
10	550+83	ROUTE 102	LT	OBJECT MARKER							
10	552+52	ROUTE 102	LT	OBJECT MARKER							
10	552+70	ROUTE 102	LT	OBJECT MARKER							
10	550+61	ROUTE 102	RT	OBJECT MARKER							
10	550+82	ROUTE 102	RT	OBJECT MARKER							
10	552+51	ROUTE 102	RT	OBJECT MARKER							
10	552+71	ROUTE 102	RT	OBJECT MARKER							

NOTE: NO DIRECT PAY WILL BE MADE FOR SIGN REMOVAL. SIGN REMOVAL IS INCLUDED IN THE LUMP SUM COST FOR REMOVAL OF IMPROVEMENTS.

	SAWCUT - FOR INFORMATION ONLY							
PLAN SHEET NO:	STATION	ROUTE	SIDE	SAWCUT				
4	549+46	ROUTE 102	TRANSVERSE	20				
4	552+95	ROUTE 102	TRANSVERSE	20				
			SUBTOTAL =	40				

NOTE: NO DIRECT PAY WILL BE MADE FOR SAWCUT, SAWCUT IS INCLUDED IN THE LUMP SUM COST FOR REMOVAL OF IMPROVEMENTS.

CLEARING AND GRUBBING								
STATION	STATION	ROUTE	LOCATION	CLEARING AND GRUBBING AC				
550+45	552+95	ROUTE 102	LT / RT	0.1				
	•		SUBTOTAL =	0.1				
			PAY TOTAL =	1.0				

PAVE	PAVEMENT REMOVAL - FOR INFORMATION ONLY							
PLAN SHEET NO.	STATION	STATION	ROUTE	PAVEMENT REMOVAL				
				SY				
4	4 550+45 552+95 ROUTE 102							
	SUBTOTAL = 666.7							

NOTE: NO DIRECT PAY WILL BE MADE FOR PAVEMENT REMOVAL. PAVEMENT REMOVAL IS INCLUDED IN THE LUMP SUM COST FOR REMOVAL OF IMPROVEMENTS.

	EARTHWORK									
STATION	STATION	ROUTE	CLASS A EXCAVATION	REQUIRED FILL (FOR INFO ONLY)	COMPACTING EMBANKMENT	EMBANKMENT IN PLACE				
			CY	CY	CY	CY				
550+45	552+95	ROUTE 102	139	1,515	139	1,376				
	SUBTOTAL = 139 1,515 139 1,376									
		PAY TOTAL =	139	0	139	1,376				

NOTES: NO SHRINK OR SWELL FACTORS APPLIED TO EARTHWORK QUANTITY. INCLUDES REMOVAL AND DISPOSAL OF EXISTING ASPHALT.

	PAVEMENT									
PLAN SHEET NO:	STATION	STATION	ROUTE	LOCATION	TYPE 1 AGGREGATE FOR BASE (6 IN. THICK) SY	OPTIONAL PAVEMENT SY				
4	550+45	552+95	ROUTE 102	LT / RT	722.3	666.7				
	•			PAY TOTAL =	722.3	666.7				

	ROCK									
PLAN SHEET NO:	STATION	STATION	ROUTE	LOCATION	FURNISHING TYPE 1 ROCK BLANKET	PLACING TYPE 1 ROCK BLANKET	FURNISHING TYPE 2 ROCK BLANKET	PLACING TYPE 2 ROCK BLANKET	PERMANENT EROSION CONTROL GEOTEXTILE	
					CY		CY	CY	SY	
9	551+38	551+83	ROUTE 102	LT / RT	12	12	115	115	1555	
				PAY TOTAL =	12	12	115	115	<u> 1555</u> l	

	PERMANENT PAVEMENT MARKINGS - LINEAR										
PLAN SHEET NO:	STATION	STATION	ROUTE	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	REMARKS					
				LF	LF						
10	550+45	552+95	ROUTE 102	250		SOLID EDGE LINE LEFT					
10	550+45	552+95	ROUTE 102	250		SOLID EDGE LINE RIGHT					
10	550+45	552+95	ROUTE 102		500	DOUBLE YELLOW CENTER LANE					
	<u> </u>		PAY TOTAL =	500	500						

	BITUMINOUS RUMBLE STRIPS										
PLAN SHEET NO.	STATION	STATION	ROUTE	LOCATION	SHOULDER RUMBLE STRIPS	CENTERLINE RUMBLE STRIPS	REMARKS				
					STA	STA					
10	550+45	552+95	ROUTE 102	CENTER		2.5	CENTERLINE				
10	550+45	552+95	ROUTE 102	LT	2.5		LEFT SHOULDER				
10	550+45	552+95	ROUTE 102	RT	2.5		RIGHT SHOULDER				
	•	•		SUBTOTAL =	5.0	2.5					
				PAY TOTAL =	5.0	2.5					

NOTE: SEE PAVEMENT MARKING SHEET FOR DETAILS

ROADSIDE DEVELOPMENT									
PLAN SHEET NO.	STATION	STATION	ROUTE	LOCATION	SEEDING - COOL SEASON MIXTURES	MUL CH I NG			
4	550+45	552+95	ROUTE 102	LT / RT	0.12	0.12			
	SUBTOTAL = 0.12 0.12								
				PAY TOTAL =	1.0	1.0			

NOTE: NO FINAL MEASUREMENT WILL BE PERFORMED.

	EROSION CONTROL - TEMPORARY										
PLAN SHEET NO:	STATION	STATION	ROUTE	LOCATION	SEDIMENT TRAP	SILT FENCE	ALTERNATE DITCH CHECK	SEDIMENT REMOVAL			
					СҮ	LF	LF	CY			
9	550+35	551+30	ROUTE 102	LT		104		1			
9	551+96	553+05	ROUTE 102	LT		127		2			
9	550+35	551+25	ROUTE 102	RT		99		1			
9	551+99	578+55	ROUTE 102	RT		125		2			
9	550+52	551+41	ROUTE 102	LT			60				
9	551+41		ROUTE 102	LT	1			10			
				SUBTOTAL =	1	455	60	16			
				PAY TOTAL =	1	546	60	16			

NOTE: 20% CONTINGENCY ADDED TO SILT FENCE

SUMMARY OF QUANTITIES
SHEET 1 OF 2

DATE PREPARED

3/6/2025

ROUTE STATE

102 MO

DISTRICT SHEET NO.

SE 3

COUNTY

MISSISSIPPI

JOB NO.
J9S3680
CONTRACT ID.

PROJECT NO.

BRIDGE NO.

191

DATE DESCRIPTION
/6/25 R002 - ROCK QUANTITIES

ISSOURI HIGHWAYS AND TRANSPORTATION
COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102

HR GREEN, INC.
20 MARYVILLE CENTRE DRIVE,
SUITE 100
ST. LOUIS, MISSOURI 63141
PHONE: (636) 519.0990
RPORATE LICENSE #2002006608



REMOVAL OF IMPROVEMENTS	1 LUMP SUM
MOBILIZATION	1 LUMP SUM
CONTRACTOR FURNISHED SURVEYING AND STAKING	1 LUMP SUM

	SIGN REM	MOVAL - FOR	INFORMATIO	IN ONLY				
PLAN SHEET NO.	STATION	ROUTE	LOCATION	ITEM TO BE REMOVED				
10	313+51	ROUTE O	LT	OBJECT MARKER				
10	313+72	ROUTE O	LT	OBJECT MARKER				
10	313+92	ROUTE O	LT	OBJECT MARKER				
10	314+59	ROUTE O	LT	OBJECT MARKER				
10	314+69	ROUTE O	LT	OBJECT MARKER				
10	316+74	ROUTE O	LT	YIELD				
10	311+70	ROUTE O	RT	YIELD				
10	313+52	ROUTE O	RT	OBJECT MARKER				
10	313+71	ROUTE O	RT	OBJECT MARKER				
10	313+92	ROUTE O	RT	OBJECT MARKER				
10	313+95	ROUTE O	RT	STRUCTURE NUMBER				
10	314+60	ROUTE O	RT	OBJECT MARKER				

NOTE: NO DIRECT PAY WILL BE MADE FOR SIGN REMOVAL, SIGN REMOVAL IS INCLUDED IN THE LUMP SUM COST FOR REMOVAL OF IMPROVEMENTS.

PAVEMENT REMOVAL - FOR INFORMATION ONLY						
PLAN SHEET NO.	STATION	STATION	ROUTE	PAVEMENT REMOVAL		
				SY		
4	313+00	313+69	ROUTE O	184.0		
4	314+72	316+20	ROUTE O	394.7		
			SUBTOTAL =	578.7		

NOTE: NO DIRECT PAY WILL BE MADE FOR PAVEMENT REMOVAL.
PAVEMENT REMOVAL IS INCLUDED IN THE LUMP SUM COST FOR REMOVAL OF IMPROVEMENTS.

SAWCUT - FOR INFORMATION ONLY						
PLAN SHEET NO:	STATION	ROUTE	LOCATION	SAWCUT		
4	313+00	ROUTE O	TRANSVERSE	20		
4	316+20	ROUTE O	TRANSVERSE	20		
			SUBTOTAL =	40		

NOTE: NO DIRECT PAY WILL BE MADE FOR SAWCUT, SAWCUT IS INCLUDED IN THE LUMP SUM COST FOR REMOVAL OF

	PAVEMENT							
PLAN SHEET NO:	STATION	STATION	ROUTE	LOCATION	TYPE 1 AGGREGATE FOR BASE (6 IN. THICK)	GRAVEL (A)	OPTIONAL PAVEMENT	
					SY	SY	SY	
4	313+00.00	313+69.28	ROUTE O	LT / RT	184.7		184.7	
4	314+71.78	316+20.00	ROUTE O	LT / RT	395.2		395.2	
4	314+81.78	315+18.42	ROUTE O	LT		52.7		
4	315+28.58	315+80.77	ROUTE O	RT		46.9		
	•	•		SUBTOTAL =	579.9	99.6	579.9	
				PAY TOTAL =	580	100	579.9	

ROCK							
PLAN SHEET NO.	STATION	STATION	ROUTE	LOCATION	FURNISHING TYPE 2 ROCK BLANKET CY	PLACING TYPE 2 ROCK BLANKET CY	PERMANENT EROSION CONTROL GEOTEXTILE
6	313+82	314+04	ROUTE O	LT / RT	258	258	129
6	314+42	314+59	ROUTE O	LT / RT	183	183	91
	•			SUBTOTAL =	441	441	220
				PAY TOTAL =	441	441	220

EARTHWORK						
STATION	STATION	ROUTE	CLASS A EXCAVATION	COMPACTING EMBANKMENT		
			CY	CY		
313+00.00	316+20.00	ROUTE O	345	223		
	SI	345	223			
	PA	345	223			

NOTES: NO SHRINK OR SWELL FACTORS APPLIED TO EARTHWORK QUANTITY. INCLUDES REMOVAL AND DISPOSAL OF EXISTING ASPHALT.

CLEARING AND GRUBBING						
STATION	STATION	ROUTE	LOCATION	CLEARING AND GRUBBING AC		
313+00	316+20	ROUTE O	LT / RT	0.1		
			SUBTOTAL =	0.1		
			PAY TOTAL =	1.0		

		DAT	E DI	DED A	RED		
) 2 5		
O MO							
	S	Ε			-	T NO 3).
COUNTY STODDARD							
JOB NO. JSE0116							
CONTRACT ID.							
PROJECT NO.							
BRIDGE NO.							
	TIES						

PORTATION	DATE 3/6/25	DATE DESCRIPTION 3/6/25 R002 - ROCK QUANTII
Y, MO 65102		
38-275-6636)		



HR GREEN. INC.
520 MARYVILLE CENTRE DRIVE.
SUITE 100
ST. LOUIS. MISSOURI 63141
PHONE: (636) 519.0990
CORPORATE LICENSE #2002006608



86 61

147

147

147

REMOVAL OF IMPROVEMENTS	1 LUMP SUM
NOD II. I ZA TIONI	4 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
MOBILIZATION	1 LUMP SUM
CONTRACTOR FURNISHED SURVEYING AND STAKING	1 LUMP SUM

	SIGN REMOVAL - FOR INFORMATION ONLY								
PLAN SHEET NO:	STATION	ROUTE	LOCATION	ITEM TO BE REMOVED					
10	574+35	ROUTE E	LT	OBJECT MARKER					
10	575+35	ROUTE E	LT	OBJECT MARKER					
10	576+19	ROUTE E	LT	OBJECT MARKER					
10	577+24	ROUTE E	LT	OBJECT MARKER					
10	577+24	ROUTE E	LT	OBJECT MARKER					
10	577+24	ROUTE E	LT	OBJECT MARKER					
10	574+14	ROUTE E	RT	OBJECT MARKER					
10	574+36	ROUTE E	RT	OBJECT MARKER					
10	574+54	ROUTE E	RT	OBJECT MARKER					
10	575+04	ROUTE E	RT	OBJECT MARKER					
10	577+24	ROUTE E	RT	OBJECT MARKER					
10	577+24	ROUTE E	RT	OBJECT MARKER					
10	578+13	ROUTE E	LT	SPEED LIMIT SIGN					

NOTE: NO DIRECT PAY WILL BE MADE FOR SIGN REMOVAL, SIGN REMOVAL IS INCLUDED IN THE LUMP SUM COST FOR REMOVAL OF

L	PAVEMENT REMOVAL - FOR INFORMATION ONLY						
	PLAN SHEET NO.	STATION	STATION	ROUTE	PAVEMENT REMOVAL SY		
	4	574+25	576+05	ROUTE E	475.9		
	4	577+30	578+45	ROUTE E	307.8		
	SUBTOTAL = 783.7						

NOTE: NO DIRECT PAY WILL BE MADE FOR PAVEMENT REMOVAL. PAVEMENT REMOVAL IS INCLUDED IN THE LUMP SUM COST FOR REMOVAL OF IMPROVEMENTS.

SAWCUT - FOR INFORMATION ONLY							
PLAN SHEET NO:	STATION	ROUTE	LOCATION	FULL DEPTH PAVEMENT REPAIR SAW CUT LF			
4	574+25	ROUTE E	TRANSVERSE	20			
4	578+45	ROUTE E	TRANSVERSE	20			
			SUBTOTAL =	40			

NOTE: NO DIRECT PAY WILL BE MADE FOR SAWCUT, SAWCUT IS INCLUDED IN THE LUMP SUM COST FOR REMOVAL OF IMPROVEMENTS.

PAVEMENT								
PLAN SHEET NO.	STATION	STATION	ROUTE	LOCATION	TYPE 1 AGGREGATE FOR BASE (6 IN. THICK)	GRAVEL (A)	OPTIONAL PAVEMENT	REMARKS
					SY	SY	SY	
4	574+25	576+05	ROUTE E	LT / RT	533		475.9	MAIN LINE
4	577+30	578+45	ROUTE E	LT / RT	330		307.8	MAIN LINE
4	577+31	577+59	ROUTE E	LT		25		FIELD ENTRANCE
4	575+84	576+11	ROUTE E	RT		23		FIELD ENTRANCE
4	577+28	577+55	ROUTE E	RT		24		FIELD ENTRANCE
SUBTOTAL					863	71	783.7	
			РА	Y TOTAL =	863	71	783.7	

	ROCK								
PLAN SHEET NO.	STATION	STATION	ROUTE	LOCATION	FURNISHING TYPE 2 ROCK BLANKET	PLACING TYPE 2 ROCK BLANKET CY	PERMANENT EROSION CONTROL GEOTEXTILE	REMARKS	
6	575+85	576+35	ROUTE E	LT / RT	176	176	88	AROUND BRIDGE ABUTMENT	
6	576+99	577+30	ROUTE E	LT / RT	178	178	89	AROUND BRIDGE ABUTMENT	
SUBTOTAL =					354	354	177		
PAY TOTAL =					354	354	<u> 177</u>		

	EARTHWORK							
STATION	STATION	ROUTE	CLASS A EXCAVATION	REQUIRED FILL (FOR INFO ONLY)	COMPACTING EMBANKMENT	EMBANKMENT IN PLACE		
			CY	CY	CY	CY		
574+25	578+45	ROUTE E	346	353	346	7		
SUBTOTAL =			346	353	346	7		
	РА	Y TOTAL =	346	0	346	7		

NOTES: NO SHRINK OR SWELL FACTORS APPLIED TO EARTHWORK QUANTITY. INCLUDES REMOVAL AND DISPOSAL OF EXISTING ASPHALT.

	56	56	84
/ 2 \	65	65	97
	121	121	181

121

121

181



DATE PREPARED 3 / 6 / 2025

NEW MADRID

JOB NO.

JSE0127

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

SHEET NO.

ROUTE

DISTRICT