



DAVIS BLVD SHOULDER WIDTH				
LEFT		RIGHT		REMARKS
STA.	WIDTH FEET	STA.	WIDTH FEET	
94+65.00	1.00	94+65.00	1.00	
95+15.00	6.00	95+15.00	6.00	
97+64.75	6.00	97+64.75	6.00	
98+14.75	4.00	98+14.75	4.00	
103+66.00	4.00	103+68.00	4.00	END SHLDR LT.
		104+21.02	8.00	
		106+63.08	8.00	
		107+32.39	2.50	END SHLDR RT.



TYPICAL SECTION SHEET
DAVIS BOULEVARD
SHEET 1 OF 14



DATE PREPARED 2/28/2025	
ROUTE FF	STATE MO
DISTRICT SW	SHEET NO. 2
COUNTY JASPER	
JOB NO. J7S3059B	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	

DESCRIPTION	DATE



MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

MoDOT


105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

Bartlett & West

601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 572-634-3161
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM



TYPICAL SECTION SHEET
DAVIS BOULEVARD
SHEET 2 OF 14



DATE PREPARED 2/28/2025	
ROUTE FF	STATE MO
DISTRICT SW	SHEET NO. 2
COUNTY JASPER	
JOB NO. J7S3059B	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	

DESCRIPTION	DATE



MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

MoDOT


105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

Bartlett & West

601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 572-634-3161
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM



TYPICAL SECTION SHEET
DAVIS BOULEVARD
SHEET 4 OF 14



DATE PREPARED
2/28/2025

ROUTE	STATE
FF	MO

DISTRICT	SHEET NO.
SW	2

COUNTY
JASPER

JOB NO.
J7S3059B

CONTRACT ID.

PROJECT NO.

BRIDGE NO.



[illegible]

MISSOURI HIGHWAYS AND TRANSPORTATION
COMMISSION




Bartlett & West

601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 573-634-3181
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM



TYPICAL SECTION SHEET
ROUTE FF
SHEET 5 OF 14



DATE PREPARED
2/28/2025

ROUTE FF	STATE MO
DISTRICT SW	SHEET NO. 2

COUNTY
JASPER

JOB NO.
J7S3059B

CONTRACT ID.

PROJECT NO.

BRIDGE NO.


[illegible]

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION



Bartlett & West

501 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 573-634-3181
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM




OPTIONAL PAVEMENT DESIGN				
LOCATION	BASE TYPE	ASPHALT OPTION ⁽²⁾	CONCRETE ⁽²⁾ OPTION	SHOULDER ⁽³⁾
STEPHENS BLVD	6" TYPE 5 AGGREGATE BASE	10.5" HMA 2" SP125 W/ PG 70-22 OVER 2" SP125 W/ PG 70-22 OVER 6.5" SP250 W/ PG 64-22	9" PCCP 15 FT. JOINT SPACING AND 1¼" DOWELS	FULL DEPTH SHOULDER

(2) DESIGNED PAVEMENT THICKNESSES BASED ON FULL DEPTH PAVEMENT WIDTH EXTENDED A MINIMUM OF 24" BEYOND THE STRIPED EDGE LINE LOCATION

(3) SHOULDER 4' OR LESS IN WIDTH MAY BE CONSTRUCTED AS FULL DEPTH PAVEMENT AS PART OF TRAVEL WAY

TYPICAL SECTION SHEET
STEPHENS BOULEVARD
SHEET 6 OF 14



DATE PREPARED 2/28/2025	
ROUTE FF	STATE MO
DISTRICT SW	SHEET NO. 2
COUNTY JASPER	
JOB NO. J7S3059B	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	

DESCRIPTION	DATE





MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

Bartlett & West

601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 872-634-3161
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM

1. CONCRETE SIDEWALK, CURB RAMP AND DETECTABLE WARNING DEVICE (TRUNCATED DOMES) DETAILS SHALL CONFORM TO ADA REQUIREMENTS UNLESS NOTED OTHERWISE IN THESE PLANS. FOR SIDEWALK JOINT AND CURB DETAILS, SEE STANDARD PLAN 609.00.
2. TINTED CONCRETE SHALL NOT BE USED. TRUNCATED DOMES SHALL BE OF A COLOR CONTRASTING WITH UNTINTED CONCRETE AND APPROVED BY THE ENGINEER. TRUNCATED DOMES ARE REQ'D. AT STREET INTERSECTIONS AND COMMERCIAL ENTRANCES WITH TRAFFIC CONTROL ONLY. (STOP/YIELD SIGNS OR SIGNALS)
3. CONCRETE SHALL BE IN ACCORDANCE WITH SEC. 608 & SEC. 609. CURING COMPOUND SHALL BE TRANSPARENT.
4. ALL CONCRETE SIDEWALK AND CURB RAMP/TRANSITION/LANDING AREAS SHALL BE 4" THICK, WITH THE EXCEPTION OF THE BOTTOM TRANSITION WHICH TIES INTO THE EXISTING PAVED APPROACH AND ROADWAY. THIS TRANSITION, OR LANDING AREA, MUST BE 8" THICK IF IT FALLS WITHIN THE RADIUS OF THE APPROACH AND SITS AT THE BACK OF CURB OF THE ROADWAY. ALL CONCRETE SIDEWALK AND CURB RAMP/TRANSITION/LANDING AREAS SHALL BE ON 4" TYPE 1 AGGREGATE BASE.
5. AGGREGATE BASE DENSITY - CONTRACTOR SHALL EXERCISE GOOD COMPACTIVE EFFORT AS APPROVED BY THE ENGINEER. DENSITY REQUIREMENTS BY NUCLEAR METHOD WILL NOT BE REQUIRED DUE TO WORK AREA CONSTRAINTS.
6. CONCRETE CURB RAMP - WIDTH = 5' MIN. LENGTH = 5' MIN. TO 15' PREFERRED MAX. (16' MAX.)
RUNNING SLOPE = >5% (MIN.) TO 8.33% (MAX.) UNIFORMLY DOWN THE LENGTH OF THE RAMP.
- CONCRETE LANDING - WIDTH = TO MATCH PROPOSED CURB RAMP AND SIDEWALK WIDTH LENGTH = 5' MIN.
SLOPE IN ALL DIRECTIONS = 1% PREFERRED (2% MAX.) UNLESS TIED TO ROADWAY EXCEPTION.
7. ALL EXISTING UTILITIES SHALL BE USED IN PLACE UNLESS OTHERWISE NOTED. ALL MANHOLE OR VALVE COVER, ETC. ELEVATIONS SHALL BE ADJUSTED AS REQUIRED IF THEY ARE LOCATED WITHIN THE IMPROVEMENT AREA.
8. "PREFORMED FIBER JOINT" SHALL BE IN ACCORDANCE WITH SEC. 1057 FOR PREFORMED FIBER JOINT EXPANSION JOINT FILLER.
9. REINFORCING STEEL TIE BARS SHALL BE IN ACCORDANCE WITH SECTION 706. ALL REINFORCING STEEL SHALL BE EPOXY COATED AND USED AS APPROVED BY THE ENGINEER. WHERE TIE BARS ARE USED, THE CONCRETE SHALL BE 8" THICK (NO DIRECT PAY).
10. CONSTRUCTION AND LENGTH OF EACH CURB RAMP INCLUDING LANDINGS AND TRANSITION AREAS SHALL BE AS SHOWN ON THE PLANS UNLESS DIFFERING FIELD CONDITIONS ARE FOUND OR AS APPROVED BY THE ENGINEER. CURB RAMP CROSS SLOPES SHALL BE 1% PREFERRED (2% MAX.) TOWARD THE STREET. CURB RAMPS ARE TO BE FORMED UP AND HAVE A TRUE AND STRAIGHT LINE.
11. SIDEWALK AND CONCRETE CURB SHALL BE POURED MONOLITHICALLY. THE CONTRACTOR SHALL MATCH EXISTING GROUND SLOPES ADJACENT TO THE CURB RAMPS OR USE AN ALTERNATE METHOD APPROVED BY THE ENGINEER.
12. S-CURB 12"-30" HIGH (MODIFIED S-CURB) WILL REQUIRE #4 REINFORC. BARS ON MAX. 12" CENTERS - SEE DETAIL (NO DIRECT PAY)
13. SODDED SLOPES AT EDGES OF SIDEWALK OR S-CURB SHOULD BE GRADED TO BE 6:1 MIN.



1/4" VERTICAL MAX.

EXIST.

1/4" - 1/2" GRIND TO 2:1

EXIST.



1/2" - 3/4" GRIND TO 8.33%

EXIST.

OVER 3/4" REPLACE PANEL(S)

JOINT GRINDING

TRIP HAZARDS 622-99.03



STATE OF MISSOURI

MICHAEL WAYNE DUSEBERG

NUMBER 5-38546

PROFESSIONAL ENGINEER

THIS SHEET HAS BEEN SIGNED, SEALED AND DATED ELECTRONICALLY.

DATE PREPARED 2/28/2025

ROUTE FF STATE MO

DISTRICT SW SHEET NO. 2

COUNTY JASPER

JOB NO. J753059B

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

MoDOT

105 WEST CAPITAL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)

Bartlett & West

601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101


PHONE 572-634-3161

CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING


WWW.BARTLETTWEST.COM

REV. IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.


PERPENDICULAR - TYPE 1											
TYPE 1-A											
LENGTH (LF)	8			12			16			REMARKS	
	4	5	6	4	5	6	4	5	6		
TRUNCATED DOMES SF	-	10.0	12.0	-	10.0	12.0	-	10.0	12.0		
CURB RAMP SY	-	8.2	12.8	-	10.8	12.7	-	13.5	15.8		
CONC. SIDEWALK SY	-	5.6	6.4	-	5.6	6.4	-	4.9	6.4		
TYPE 1 AGGREGATE SY	-	13.8	16.0	-	16.4	19.1	-	18.3	22.2		
ADA LINEAR GRADING LF	-	22.0	22.0	-	27.5	27.5	-	30.0	30.5		
SODDING SY	-	5.8	5.7	-	6.8	6.9	-	7.5	7.9		
TYPE 1-B											
LENGTH (LF)	8			12			16			REMARKS	
	4	5	6	4	5	6	4	5	6		
TRUNCATED DOMES SF	-	22.0	24.0	-	22.0	24.0	-	22.0	24.0		
CURB RAMP SY	-	10.9	13.1	-	13.6	16.3	-	16.2	19.3		
CONC. SIDEWALK SY	-	5.6	6.3	-	5.6	6.4	-	4.9	5.7		
TYPE 1 AGGREGATE SY	-	16.5	19.4	-	19.2	22.7	-	21.1	25.0		
ADA LINEAR GRADING LF	-	28.0	28.0	-	34.5	34.5	-	38.0	38.0		
SODDING SY	-	7.4	7.8	-	8.4	8.7	-	9.1	9.5		
TYPE 1-C											
LENGTH (LF)	8			12			16			REMARKS	
	4	5	6	4	5	6	4	5	6		
TRUNCATED DOMES SF	-	10.0	12.0	-	10.0	12.0	-	10.0	12.0		
CURB RAMP SY	-	8.8	10.3	-	11.5	13.4	-	14.1	16.5		
CONC. SIDEWALK SY	-	5.6	6.4	-	5.6	6.4	-	4.9	5.7		
TYPE 1 AGGREGATE SY	-	14.4	16.7	-	17.1	19.8	-	19.0	22.1		
ADA LINEAR GRADING LF	-	22.0	22.0	-	26.5	26.5	-	30.0	30.0		
SODDING SY	-	11.5	11.7	-	13.5	13.5	-	15.0	15.2		
TYPE 1-D											
LENGTH (LF)	8			12			16			REMARKS	
	4	5	6	4	5	6	4	5	6		
TRUNCATED DOMES SF	-	18.0	24.0	-	18.0	24.0	-	18.0	24.0		
CURB RAMP SY	-	18.6	22.8	-	24.0	29.0	-	29.3	35.3		
CONC. SIDEWALK SY	-	11.2	12.8	-	11.2	12.8	-	9.8	11.4		
TYPE 1 AGGREGATE SY	-	29.8	35.6	-	35.2	41.8	-	39.1	46.7		
ADA LINEAR GRADING LF	-	42.0	50.0	-	57.0	61.0	-	67.0	72.0		
SODDING SY	-	11.0	11.3	-	13.0	13.3	-	14.5	14.9		
TYPE 1-E											
LENGTH (LF)	8			12			16			REMARKS	
	4	5	6	4	5	6	4	5	6		
TRUNCATED DOMES SF	-	18.0	24.0	-	18.0	24.0	-	18.0	24.0		
CURB RAMP SY	-	14.8	19.0	-	20.1	25.2	-	25.5	31.4		
CONC. SIDEWALK SY	-	11.2	12.8	-	11.2	12.8	-	9.8	11.4		
TYPE 1 AGGREGATE SY	-	26.0	31.8	-	31.3	38.0	-	35.3	42.8		
ADA LINEAR GRADING LF	-	43.0	46.0	-	52.0	55.0	-	59.0	62.0		
SODDING SY	-	13.3	13.6	-	16.0	16.9	-	18.6	19.3		
TYPE 1-F											
LENGTH (LF)	8			12			16			REMARKS	
	4	5	6	4	5	6	4	5	6		
TRUNCATED DOMES SF	-	14.0	16.0	-	14.0	16.0	-	14.0	16.0		
CURB RAMP SY	-	15.5	19.0	-	20.8	25.2	-	26.2	31.4		
CONC. SIDEWALK SY	-	11.2	12.8	-	11.2	12.8	-	9.8	11.4		
TYPE 1 AGGREGATE SY	-	26.7	31.8	-	32.0	38.0	-	36.0	42.8		
ADA LINEAR GRADING LF	-	43.0	46.0	-	52.0	55.0	-	59.0	62.0		
SODDING SY	-	18.4	18.8	-	22.4	22.8	-	25.6	25.9		



TYPE 1-A



ISOMETRIC VIEW
TYPE 1-B



TYPE 1-B

T'- IS TO BE 8" THICK
AT ALL PAVED APPROACHES
AND STREETS IF WITHIN THE
RADIUS. PAID FOR AS
CONCRETE CURB RAMP

T - TRANSITION TO EXISTING SW
OR PAVED APPROACH (LANDING
PREFERRED AT PAVED APPROACH
IF CONDITIONS ALLOW)

- IS STILL NEEDED EVEN IF THE
EXISTING SIDEWALK IS THE SAME
WIDTH AS THE NEW SIDEWALK. (IT
WILL BLEND THE EXIST XSLOPE
INTO THE NEW LANDING XSLOPE)

- LANDING

- RAMP


- CURB RAMP PAY LIMITS

- SOD SLOPE 6:1 MIN.


- TRUNCATED DOME LOCATION,
IF DIST. IS 5' OR 5'

TRUNCATED DOMES ARE USED ONLY
AT STREETS & ENTRANCES UTILIZING
YIELD / STOP SIGNS OR SIGNALS

NOTE:
QUANTITIES ARE CALCULATED BY AREA AND
MAY NOT MATCH EXACT FIELD CONDITIONS.



TYPE 1-C



TYPE 1-F


ADA LIBRARY TYPICAL

TYPE 1

PERPENDICULAR
CURB RAMPS

TYPICAL SHEET
8 OF 14

REVISED: 2022-05-18



DATE PREPARED
2/28/2025

ROUTE FF STATE MO

DISTRICT SW SHEET NO. 2

COUNTY JASPER

JOB NO. J7S3059B

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITAL

JEFFERSON CITY, MO 65102

1-888-ASK-MODOT (1-888-275-6636)

MoDOT

Bartlett & West

601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101

PHONE 572-634-3161

CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING

WWW.BARTLETTWEST.COM

PARALLEL - TYPE 2										
TYPE 2-A										
LENGTH (LF)	8			12			16			REMARKS
	4	5	6	4	5	6	4	5	6	
TRUNCATED DOMES	SF	-	10.0	10.0	-	10.0	10.0	-	10.0	10.0
CURB RAMP	SY	-	9.1	10.6	-	11.8	13.7	-	14.4	16.8
CONC. SIDEWALK	SY	-	5.6	6.4	-	4.9	5.7	-	4.9	5.7
TYPE 1 AGGREGATE	SY	-	14.7	17.0	-	16.7	19.4	-	19.3	22.5
ADA LINEAR GRADING	LF	-	26.0	26.0	-	29.0	29.0	-	33.0	33.0
SODDING	SY	-	8.0	8.3	-	8.6	8.8	-	9.6	9.8

TYPE 2-B										
LENGTH (LF)	8			12			16			REMARKS
	4	5	6	4	5	6	4	5	6	
TRUNCATED DOMES	SF	-	10.0	10.0	-	10.0	10.0	-	10.0	10.0
CURB RAMP	SY	-	11.8	13.3	-	14.5	16.4	-	17.2	19.5
CONC. SIDEWALK	SY	-	5.6	6.4	-	4.9	5.7	-	4.9	5.7
TYPE 1 AGGREGATE	SY	-	17.4	19.7	-	19.4	22.1	-	22.1	25.2
ADA LINEAR GRADING	LF	-	26.0	26.0	-	29.0	29.0	-	33.0	33.0
SODDING	SY	-	13.8	14.1	-	15.1	15.5	-	17.1	17.5


TYPE 2-C										
LENGTH (LF)	8			12			16			REMARKS
	4	5	6	4	5	6	4	5	6	
TRUNCATED DOMES	SF	-	10.0	10.0	-	10.0	10.0	-	10.0	10.0
CURB RAMP	SY	-	16.4	18.7	-	21.7	24.9	-	27.0	31.2
CONC. SIDEWALK	SY	-	11.2	12.8	-	9.8	11.4	-	9.8	11.4
TYPE 1 AGGREGATE	SY	-	27.6	31.5	-	31.5	36.3	-	36.8	42.6
ADA LINEAR GRADING	LF	-	41.0	41.0	-	47.0	47.0	-	55.0	55.0
SODDING	SY	-	12.3	12.5	-	13.6	13.9	-	15.6	15.9

TYPE 2-D										
LENGTH (LF)	8			12			16			REMARKS
	4	5	6	4	5	6	4	5	6	
TRUNCATED DOMES	SF	-	10.0	10.0	-	10.0	10.0	-	10.0	10.0
CURB RAMP	SY	-	16.8	19.2	-	22.2	25.4	-	27.5	31.6
CONC. SIDEWALK	SY	-	11.2	12.8	-	9.8	11.4	-	9.8	11.4
TYPE 1 AGGREGATE	SY	-	28.0	32.0	-	32.0	36.8	-	37.3	43.0
ADA LINEAR GRADING	LF	-	41.0	41.0	-	47.0	47.0	-	55.0	55.0
SODDING	SY	-	20.2	20.3	-	22.4	23.2	-	26.4	27.2


TYPE 2-E										
LENGTH (LF)	8			12			16			REMARKS
	4	5	6	4	5	6	4	5	6	
TRUNCATED DOMES	SF	-	10.0	10.0	-	10.0	10.0	-	10.0	10.0
CURB RAMP	SY	-	10.8	11.5	-	13.2	14.4	-	15.7	17.3
CONC. SIDEWALK	SY	-	5.6	6.7	-	5.0	6.0	-	5.0	6.0
TYPE 1 AGGREGATE	SY	-	16.4	18.2	-	18.2	20.4	-	20.7	23.3
ADA LINEAR GRADING	LF	-	22.5	22.5	-	26.5	26.5	-	30.5	30.5
SODDING	SY	-	-	-	-	-	-	-	-	-
HANDRAIL	LF	-	-	-	-	-	-	-	-	SEE STANDARDS FOR LENGTH

TYPE 2-F										
LENGTH (LF)	8			12			16			REMARKS
	4	5	6	4	5	6	4	5	6	
TRUNCATED DOMES	SF	-	10.0	10.0	-	10.0	10.0	-	10.0	10.0
CURB RAMP	SY	-	15.5	17.1	-	20.4	23.1	-	25.5	28.9
CONC. SIDEWALK	SY	-	11.2	13.4	-	10.0	12.0	-	10.0	12.0
TYPE 1 AGGREGATE	SY	-	26.7	30.5	-	30.4	35.1	-	35.5	40.9
ADA LINEAR GRADING	LF	-	39.0	39.0	-	47.0	47.0	-	55.0	55.0
SODDING	SY	-	-	-	-	-	-	-	-	-
HANDRAIL	LF	-	-	-	-	-	-	-	-	SEE STANDARDS FOR LENGTH


NOTE:
QUANTITIES ARE CALCULATED BY AREA AND
MAY NOT MATCH EXACT FIELD CONDITIONS.




TYPE 2-A



TYPE 2-B



ISOMETRIC VIEW
TYPE 2-E



TYPE 2-E

USE ONLY WHEN TYPE 2-F IS UNABLE TO BE CONSTRUCTED DUE TO AN
EXIST. D.I. OR OTHER OBSTACLE
SEE STANDARDS FOR HANDRAIL SPECS

*** 3.5' LANDING EXTENSION REQ'D.
FOR INSTALLATION OF FUTURE OR NEW
PED.PUSH BUTTON

NOTE: SEE STANDARDS FOR ALL PED.
PUSH BUTTON LOCATIONS

----- TRUNCATED DOME

TRUNCATED DOMES ARE USED ONLY
AT STREETS & ENTRANCES UTILIZING
YIELD / STOP SIGNS OR SIGNALS


T - TRANSITION TO EXISTING SW
* - T IS STILL NEEDED EVEN IF THE
EXISTING SIDEWALK IS THE SAME
WIDTH AS THE NEW SIDEWALK.(IT
WILL BLEND THE EXIST XSLOPE
INTO THE NEW LANDING XSLOPE)

L - LANDING

R - RAMP


----- SOD SLOPE 6:1 MIN.

----- CURB RAMP PAY LIMITS




ISOMETRIC VIEW
TYPE 2-C

TYPE 2-C




ISOMETRIC VIEW
TYPE 2-F




TYPE 2-F

SEE STANDARDS FOR HANDRAIL SPECS



TYPE 2-D



DATE PREPARED
2/28/2025

ROUTE
FF

STATE
MO

DISTRICT
SW

SHEET NO.
2

COUNTY
JASPER

JOB NO.
J7S3059B

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION
COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102

1-888-ASK-MODOT (1-888-275-6636)

MoDOT

Bartlett & West

601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101

PHONE 572-634-3161

CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING

WWW.BARTLETTWEST.COM

REV.

PARALLEL - TYPE 2 (cont'd.)											
TYPE 2-G											
LENGTH (LF)	WIDTH (LF)	8			12			16			REMARKS
		4	5	6	4	5	6	4	5	6	
TRUNCATED DOMES	SF	-	12.0	12.0	-	10.0	10.0	-	10.0	10.0	
CURB RAMP	SY	-	15.7	18.0	-	20.8	23.7	-	25.8	30.2	
CONC. SIDEWALK	SY	-	21.4	25.0	-	17.6	20.3	-	15.2	17.5	
TYPE 1 AGGREGATE	SY	-	37.1	43.0	-	38.4	44.0	-	41.0	47.7	
ADA LINEAR GRADING	LF	-	52.0	52.0	-	54.0	54.0	-	58.0	58.0	
SODDING	SY	-	13.6	13.6	-	13.7	13.5	-	14.5	14.9	

TYPE 2-H											
LENGTH (LF)	WIDTH (LF)	8			12			16			REMARKS
		4	5	6	4	5	6	4	5	6	
TRUNCATED DOMES	SF	-	12.0	12.0	-	10.0	10.0	-	10.0	10.0	
CURB RAMP	SY	-	15.7	18.0	-	21.0	24.5	-	26.9	31.4	
CONC. SIDEWALK	SY	-	13.2	16.0	-	12.0	14.2	-	12.0	14.4	
TYPE 1 AGGREGATE	SY	-	28.9	34.0	-	33.0	38.6	-	38.9	45.8	
ADA LINEAR GRADING	LF	-	42.0	42.0	-	49.0	49.0	-	55.0	55.0	
SODDING	SY	-	11.1	11.2	-	12.5	12.5	-	14.5	14.9	

T* - IS STILL NEEDED EVEN IF THE EXISTING SIDEWALK IS THE SAME WIDTH AS THE NEW SIDEWALK. (IT WILL BLEND THE EXIST XSLOPE INTO THE NEW LANDING XSLOPE)

T - TRANSITION TO EXISTING SW
L - LANDING
R - RAMP

↓ ↓ - SOD SLOPE 6:1 MIN.






----- - TRUNCATED DOME LOCATION, IF DIST. IS <5' OR > 5'

TRUNCATED DOMES ARE USED ONLY AT STREETS & ENTRANCES UTILIZING YIELD / STOP SIGNS OR SIGNALS

▨ - CURB RAMP PAY LIMITS

..... - INCLUDED IN 4" CONC. SIDEWALK PAY LIMIT

NOTE:
QUANTITIES ARE CALCULATED BY AREA AND MAY NOT MATCH EXACT FIELD CONDITIONS.



DATE PREPARED 2/28/2025	
ROUTE FF	STATE MO
DISTRICT SW	SHEET NO. 2
COUNTY JASPER	
JOB NO. J7S3059B	
CONTRACT ID.	

PROJECT NO.
BRIDGE NO.

DESCRIPTION	DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)



MoDOT

Bartlett & West

601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 572-634-3161
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM

ADA LIBRARY TYPICAL
TYPE 2 PARALLEL CURB RAMPS
TYPICAL SHEET 10 OF 14

DIAGONAL - TYPE 3												
TYPE 3-A												
LENGTH (LF)	8			12			16			REMARKS		
	4	5	6	4	5	6	4	5	6			
TRUNCATED DOMES	SF	-	24.0	28.0	-	20.6	25.0	-	20.6	25.0		
CURB RAMP	SY	-	24.4	27.0	-	26.9	31.2	-	32.2	37.4		
CONC. SIDEWALK	SY	-	11.2	12.8	-	9.8	11.4	-	9.8	11.4		
TYPE 1 AGGREGATE	SY	-	35.6	39.8	-	36.7	42.6	-	42.0	48.8		
ADA LINEAR GRADING	LF	-	51.0	51.0	-	59.0	59.0	-	67.0	67.0		
SODDING	SY	-	11.6	11.4	-	12.9	12.9	-	14.9	14.9		
8"SW OR MED STRIP	SY	-	3.0	2.2	-	3.0	2.2	-	3.0	2.2		
TYPE 3-B												
LENGTH (LF)	8			12			16			REMARKS		
	4	5	6	4	5	6	4	5	6			
TRUNCATED DOMES	SF	-	24.0	28.0	-	20.6	25.0	-	20.6	25.0		
CURB RAMP	SY	-	22.0	26.3	-	25.9	31.2	-	31.2	37.4		
CONC. SIDEWALK	SY	-	11.2	12.8	-	9.8	11.4	-	9.8	11.4		
TYPE 1 AGGREGATE	SY	-	33.2	39.1	-	35.7	42.6	-	41.0	48.8		
ADA LINEAR GRADING	LF	-	51.0	51.0	-	59.0	59.0	-	67.0	67.0		
SODDING	SY	-	15.2	15.3	-	17.1	17.5	-	20.1	20.5		
8"SW OR MED STRIP	SY	-	1.5	1.5	-	1.5	1.5	-	1.5	1.5		
TYPE 3-C												
LENGTH (LF)	8			12			16			REMARKS		
	4	5	6	4	5	6	4	5	6			
TRUNCATED DOMES	SF	-	20.0	24.0	-	20.0	24.0	-	20.0	24.0		
CURB RAMP	SY	-	20.7	26.8	-	25.1	31.5	-	30.4	37.7		
CONC. SIDEWALK	SY	-	11.2	12.8	-	9.8	11.4	-	9.8	11.4		
TYPE 1 AGGREGATE	SY	-	31.9	39.6	-	34.9	42.9	-	40.2	49.1		
ADA LINEAR GRADING	LF	-	51.0	51.0	-	58.0	58.0	-	67.0	67.0		
SODDING	SY	-	18.8	19.3	-	21.3	22.1	-	25.3	26.1		
8"SW OR MED STRIP	SY	-	1.0	1.6	-	1.0	1.6	-	1.0	1.6		
TYPE 3-D												
LENGTH (LF)	8			12			16			REMARKS		
	4	5	6	4	5	6	4	5	6			
TRUNCATED DOMES	SF	-	24.0	28.0	-	22.4	26.5	-	22.4	26.5		
CURB RAMP	SY	-	15.9	19.1	-	17.7	21.4	-	20.4	24.5		
CONC. SIDEWALK	SY	-	5.6	6.4	-	4.9	5.7	-	4.9	5.7		
TYPE 1 AGGREGATE	SY	-	21.5	25.5	-	22.6	27.1	-	25.3	30.2		
ADA LINEAR GRADING	LF	-	31.0	31.0	-	34.0	34.0	-	38.0	38.0		
SODDING	SY	-	12.6	12.9	-	13.5	14.0	-	15.5	16.0		
8"SW OR MED STRIP	SY	-	1.0	0.8	-	1.0	0.8	-	1.0	0.8		
TYPE 3-E												
LENGTH (LF)	8			12			16			REMARKS		
	4	5	6	4	5	6	4	5	6			
TRUNCATED DOMES	SF	-	20.0	24.0	-	20.0	24.0	-	20.0	24.0		
CURB RAMP	SY	-	17.2	19.8	-	17.7	21.4	-	20.4	24.5		
CONC. SIDEWALK	SY	-	8.4	10.7	-	7.3	9.4	-	7.3	9.4		
TYPE 1 AGGREGATE	SY	-	25.6	30.5	-	25.0	30.8	-	27.7	33.9		
ADA LINEAR GRADING	LF	-	30.0	30.0	-	35.5	35.5	-	39.5	39.5		
SODDING	SY	-	12.4	12.4	-	12.9	13.3	-	14.9	15.3		
8"SW OR MED STRIP	SY	-	1.6	1.6	-	1.6	1.6	-	1.6	1.6		



TYPE 3-A

T' - IS TO BE 8" THICK AT ALL PAVED APPROACHES AND STREETS IF WITHIN THE RADIUS. PAID FOR AS CONCRETE CURB RAMP

NOTE: QUANTITIES ARE CALCULATED BY AREA AND MAY NOT MATCH EXACT FIELD CONDITIONS.

T - TRANSITION TO EXISTING SW OR PAVED APPROACH (LANDING PREFERRED IF CONDITIONS ALLOW)

T* - IS STILL NEEDED EVEN IF THE EXISTING SIDEWALK IS THE SAME WIDTH AS THE NEW SIDEWALK. (IT WILL BLEND THE EXIST XSLOPE WITH THE NEW LANDING XSLOPE)

L - LANDING


R - RAMP

- CURB RAMP PAY LIMITS


- SOD SLOPE 6:1 MIN.

- TRUNCATED DOME LOCATION, IF DIST. IS <5' OR >5'


TRUNCATED DOMES ARE USED ONLY AT STREETS & ENTRANCES UTILIZING YIELD / STOP SIGNS OR SIGNALS




TYPE 3-B



TYPE 3-C



TYPE 3-D



TYPE 3-E

ADA LIBRARY TYPICAL

TYPE 3
DIAGONAL
CURB RAMPS

TYPICAL SHEET
11 OF 14

REVISED: 2022-05-18

STATE OF MISSOURI

MICHAEL WAYNE DUSEBERG

NUMBER 0-05646

PROFESSIONAL ENGINEER

THE SHEET HAS BEEN SIGNED, SEALED AND DATED ELECTRONICALLY.

DATE PREPARED

2/28/2025

ROUTE

FF

STATE

MO

DISTRICT

SW

SHEET NO.

2

COUNTY

JASPER

JOB NO.

J7S3059B

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

MoDOT

105 WEST CAPITAL

JEFFERSON CITY, MO 65102

1-888-ASK-MODOT (1-888-275-6636)

Bartlett & West

601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101

PHONE 572-634-3161

CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING

WWW.BARTLETTWEST.COM

pw://bartwest-pw.bentley.com:bartwest-pw-04/Documents/19000/19421.G40 - Jasper FF - Davis Boulevard/OpenRoads Designer/plan_sheets/3_Final Plans/002_TS_11_of_14_J7S3059B_T5_ADA_TYPE3_DIAGONAL.dgn 1:04:51 PM 2/28/2025


NOTES FOR MODIFIED SIDEWALK:

1. REMOVE EXIST. CURB & RAISED ISLAND WITHIN LIMITS SHOWN.
2. AREA INSIDE FINAL CURB TO BE REPAIRED OR REPLACED WITH EXISTING SURFACE MATERIAL. GRADE TO DRAIN.
3. CONSTRUCT 8" THICK CONC. SIDEWALK FLUSH WITH EXIST. CONC. PAVED APPROACH.
4. CONSTRUCT CURB ADJACENT TO MODIFIED SIDEWALK.
5. MODIFIED SIDEWALK PAID FOR AS 8" SIDEWALK.
6. 6' MINIMUM WIDTH.
7. NO DIRECT PAY FOR SAW CUTS AND TIE BARS (ON 12" CENTERS MAX.)
8. TRUNCATED DOMES ARE USED ONLY AT STREETS & ENTRANCES UTILIZING STOP SIGNS OR SIGNALS.
9. X-SLOPE 1% PREFERRED (2% MAX.)
10. USE S-CURB IF CONSTRUCTING CURB ON R/W LINE.


* INTEGRAL CURB IS PAID FOR WITH THE 8" CONC. SIDEWALK PAY ITEM.
INTEGRAL CURB IS PAID AS 1' ADDITIONAL SIDEWALK WIDTH (EX. 6' SIDEWALK PAID AS 7') (0.11 SY/LF OF CURB)

TYPICAL
MODIFIED SIDEWALK
8" THICK


** TRUNCATED DOMES ARE USED ONLY AT STREETS & ENTRANCES UTILIZING STOP/YIELD SIGNS OR SIGNALS.



SECTION A-A
WITH S-CURB OR MODIFIED S-CURB



SECTION A-A
WITH INTEGRAL CURB




NOT TO SCALE

NOTES FOR CUT-THRU SIDEWALK:


1. REMOVE EXIST. CURB & RAISED ISLAND WITHIN LIMITS SHOWN.
2. AREA INSIDE FINAL CURB TO BE REPAIRED OR REPLACED WITH EXISTING SURFACE MATERIAL. GRADE TO DRAIN.
3. CONSTRUCT 4" THICK CONC. SIDEWALK FLUSH WITH EXIST. CONC. PAVED APPROACH.
4. CONSTRUCT CURB ON BOTH SIDES ADJACENT TO SIDEWALK.
5. CUT-THRU SIDEWALK PAID FOR AS 4" SIDEWALK.
6. 6' PREFERRED WIDTH (5' MIN.)
7. SAW CUTS (NO DIRECT PAY).
8. TRUNCATED DOMES ARE USED ONLY AT STREETS & ENTRANCES UTILIZING STOP SIGNS OR SIGNALS.
9. X-SLOPE 1% PREFERRED (2% MAX.)
10. USE S-CURB IF CONSTRUCTING CURB ON R/W LINE.

* INTEGRAL CURB IS PAID FOR AS 4" CONC. SIDEWALK PAY ITEM. S-CURB IS PAID FOR AS ITS OWN PAY ITEM. (ALWAYS USE S-CURB IF AT R/W LINE.)
INTEGRAL CURB IS PAID AS 1' ADDITIONAL SIDEWALK WIDTH (EX. 6' SIDEWALK PAID AS 7') (0.11 SY/LF OF CURB)

TYPICAL
CUT-THRU SIDEWALK




SECTION C-C
WITH S-CURB OR INTEGRAL



NOT TO SCALE

TYPICAL
ISLAND CUT-THRU SIDEWALK
X-SLOPE 2% MAX. CONSTRUCT TO DRAIN




■ SMALL QTY. HAS BEEN INCLUDED FOR 8" THICK SIDEWALK TO ADDRESS ANY UNFORSEEN PVMNT. REPAIRS OR DIFFERENCES IN ELEVATION. (UNDERRUN IF FIELD CONDITIONS DO NOT WARRANT)

** NO INTEGRAL CURB, AGGR. OR LIN. GRADING REQUIRED IF THE ISLAND IS 'PINNED-ON'


SECTION B-B

ISLAND CUT-THRU SIDEWALK
FOR EXISTING 'PINNED-ON' ISLAND



SECTION B-B

ISLAND CUT-THRU SIDEWALK




* INTEGRAL CURB IS PAID FOR WITH THE 4" CONC. SIDEWALK PAY ITEM. INTEGRAL CURB IS PAID AS 1' ADDITIONAL SIDEWALK WIDTH (EX. 6' SIDEWALK PAID AS 7') (0.11 SY/LF OF CURB)

ADA LIBRARY TYPICAL

MODIFIED SIDEWALK
AND
SIDEWALK CUT-THRUS

TYPICAL SHEET
12 OF 14



DATE PREPARED
2/28/2025

ROUTE
FF

STATE
MO

DISTRICT
SW

SHEET NO.
2

COUNTY
JASPER

JOB NO.
J753059B

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

1-888-ASK-MODOT (1-888-275-6636)

105 WEST CAPITOL

JEFFERSON CITY, MO 65102

1-888-ASK-MODOT (1-888-275-6636)

1-888-ASK-MODOT (1-888-275-6636)

1-888-ASK-MODOT (1-888-275-6636)

1-888-ASK-MODOT (1-888-275-6636)

1-888-ASK-MODOT (1-888-275-6636)

1-888-ASK-MODOT (1-888-275-6636)

1-888-ASK-MODOT (1-888-275-6636)

1-888-ASK-MODOT (1-888-275-6636)

1-888-ASK-MODOT (1-888-275-6636)

1-888-ASK-MODOT (1-888-275-6636)

1-888-ASK-MODOT (1-888-275-6636)

1-888-ASK-MODOT (1-888-275-6636)

1-888-ASK-MODOT (1-888-275-6636)

1-888-ASK-MODOT (1-888-275-6636)

1-888-ASK-MODOT (1-888-275-6636)

1-888-ASK-MODOT (1-888-275-6636)

1-888-ASK-MODOT (1-888-275-6636)

1-888-ASK-MODOT (1-888-275-6636)

1-888-ASK-MODOT (1-888-275-6636)

1-888-ASK-MODOT (1-888-275-6636)

1-888-ASK-MODOT (1-888-275-6636)

1-888-ASK-MODOT (1-888-275-6636)

1-888-ASK-MODOT (1-888-275-6636)

1-888-ASK-MODOT (1-888-275-6636)

1-888-ASK-MODOT (1-888-275-6636)

1-888-ASK-MODOT (1-888-275-6636)


1-888-ASK-MODOT (1-888-275-6636)

1-888-ASK-MODOT (1-888-275-6636)


1-888-ASK-MODOT (1-888-275-6636)

* ROUND TO 3/4" RADIUS
** ROUND TO 1/4" RADIUS
H = 2'-6" MAX. (30")
D = BURY DEPTH (FORMING NOT REQUIRED)
THIS SHALL BE 18 INCHES OR "H" WHICHEVER IS GREATER.
VERTICAL REINFORCING LENGTHS VARY AS NEEDED.
DEPTH MAY BE REDUCED IF KEYED 6" IN ROCK

MODIFIED S-CURB
> 12" TALL (2'-6" MAX.)



NOT TO SCALE



MODIFIED S-CURB
> 12" TALL (3'-0" MAX.)
POURED CONCRETE SIDEWALK WALL


NOT TO SCALE

ADA LIBRARY TYPICAL

MODIFIED S-CURB

TYPICAL SHEET
14 OF 14

CREATED: 2023-11-16
REVISED: 2024-02-13



DATE PREPARED
2/28/2025

ROUTE FF STATE MO
DISTRICT SW SHEET NO. 2

COUNTY JASPER
JOB NO. J7S3059B
CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION	DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

MoDOT

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

Bartlett & West

601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 572-634-3161
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM

REMOVAL OF IMPROVEMENTS							
ROUTE	STA.	STA.	LOCATION	DESCRIPTION	AMOUNT	UNIT	REMARKS
DAVIS	94+65.00	99+71.00	EXISTING DAVIS BLVD	PAVEMENT REMOVAL	1,883.7	SY	
DAVIS	98+96.00	99+71.00	RT	CURB & GUTTER	101.7	LF	
DAVIS	99+21.00	99+71.00	LT	CURB & GUTTER	70.0	LF	
DAVIS	94+65.00	-	CENTERLINE	SAW CUT	25.00	LF	
DAVIS	95+55.30	-	RT	SAW CUT	58	LF	
DAVIS	95+55.30	-	RT	PCCP ENTRANCE	212.2	SY	
EX. STEPHENS	0+27.78	8+00.00	CENTERLINE	PAVEMENT REMOVAL	3,284.2	SY	
RTE. FF	33+42.00	39+28.96	LT	SAW CUT	570.00	LF	
EX. STEPHENS	8+00.00	-	CENTERLINE	SAW CUT	25.00	LF	
RTE. FF	35+14.00	-	LT	INLET	1	EA	
RTE. FF	36+93.00	-	LT	INLET	1	EA	
RTE. FF	37+42.00	-	LT	INLET	1	EA	
STEPHENS	106+00.00	-	RT	PCCP ENTRANCE	73.4	SY	
STEPHENS BLVD	-	-	BOTH	SIGNS, POSTS AND BASE CONCRETE	12	EA	
EX DAVIS BLVD	-	-	BOTH	SIGNS, POSTS AND BASE CONCRETE	3	EA	
EX DAVIS BLVD	-	-	BOTH	INLETS	2	EA	
EX DAVIS BLVD	-	-	BOTH	12" PIPES	25	LF	
TOTALS					1	LS	

CONTRACTOR FURNISHED
SURVEYING AND STAKING
TOTAL = 1 LUMP SUM

MOBILIZATION
TOTAL = 1 LUMP SUM

ADDITIONAL MOBILIZATION FOR SEEDING
TOTAL = 2 EA

CLEARING AND GRUBBING					
ROUTE	STA.	STA.	LOCATION	ACRE	REMARKS
DAVIS BLVD	96+50.00	97+25.00	CL	0.20	
DAVIS BLVD	97+65.00	102+30.00	CL	0.53	
DAVIS BLVD	316+01.94	316+36.94	RT	2.24	
TOTALS				3.0	
USE				3.0	

CURB & GUTTER								
SHEET	ROUTE	STA.	STA.	LOCATION	C&G TYPE A 3' WIDE	C&G CITY OF JOPLIN 2.5' WIDE	4" TYPE 5 AGGREGATE BASE 4" THICK	REMARKS
					LF	LF	SY	
4	DAVIS BLVD	105+44.45	105+83.40	LT		292.4	81.2	
4	DAVIS BLVD	107+54.44	108+32.39	LT	116.7		32.4	
4	DAVIS BLVD	107+32.40	108+44.94	RT	157.6		43.8	
6	RTE FF	35+22.91	39+31.60	LT	409.2		113.7	
6	RTE FF	33+42.24	33+99.70	RT	57.5		16.0	
7	STEPHENS BLVD	5+06.84	9+74.84	RT		505.4	140.4	
TOTALS					741.0	797.8	427.5	
USE					741	798	428	

OPTIONAL PAVEMENT						
SHEET	ROUTE	STA.	STA.	OPTIONAL PAVEMENT	AGGR. BASE TYPE 5 6" THICKNESS	REMARKS
				SY	SY	
4	STEPHEN BLVD	5+15.74	9+74.84	1667.1	1667.1	INCLUDES FULL DEPTH SHOULDER
TOTALS				1667.1	1667.1	
USE				1667.1	1667	

ENTRANCES							
SHEET	ROUTE	STA.	LOCATION	PAVED APPROACH 8" THICK	4" TYPE 5 AGGREGATE BASE	LINEAR GRADING CLASS 1	REMARKS
				SY	SY	STA.	
4	DAVIS BLVD	95+68.00	RT	212.2	212.2	0.3	
4	DAVIS BLVD	104+00.56	RT	244.6	244.6	0.6	
4	DAVIS BLVD	105+61.95	LT	88.8	88.8	0.2	
4	STEPHENS BLVD	7+97.48	LT	141.1	141.1	0.3	
6	RTE FF	34+43.89	RT	206.2	206.2	0.3	
TOTALS				892.9	892.9	1.7	
USE				893	893	1.7	

CONCRETE PAVEMENT						
SHEET	ROUTE	STA.	STA.	CONCRETE PAVEMENT 9" NON-REINFORCED 15' JOINTS	AGGR. BASE TYPE 5 6" THICKNESS	REMARKS
				SY	SY	
4	DAVIS BLVD	94+65.00	107+44.40	5454.5	5454.5	INCLUDES FULL DEPTH SHOULDER
6	ROUTE FF	35+11.93	39+13.52	428.9	428.9	RIGHT TURN LANE
TOTALS				5883.4	5883.4	
USE				5883.4	5883	

TRUNCATED DOMES, CURB RAMP, SIDEWALK, TYPE 1 AGGREGATE, ADA LINEAR GRADING, TURF TYPE TALL FESCUE SODDING, CURBS																								
SHEET	STATION	STATION	LOCATION	LT RT	TRUNC. DOMES	CURB RAMP				SIDEWALK								4" TYPE 1 AGGR.	ADA LINEAR GRADING	SOD	S-CURB			REMARKS
										S.W. WIDTH	* PAY WIDTH	4" SDWLK.	4" CUT THRU	4" BUS STOP	4" PASS AREA	8" SDWLK.	8" MODIFD. SDWLK.				INTEGRAL CURB	LESS/EQ 6" (1" - 6")	OVER 6" (6" - 12")	
						SF	LENGTH	WIDTH	TYPE	SY	LF	LF	SY	SY	SY	SY	SY	SY	* LF	SY	LF	SY	LF	
4	33+93.00	34+14.76	RTE FF	RT	27.0	7	6	N/A	13.8	6	6	33.6						47.4	33.8	8.9		35.6		
4	34+78.06	35+11.59	RTE FF	RT	19.4	7	6	N/A	11.2	6	6	12.2						23.4	45.6	10.9		94.1		
4	35+11.59	35+29.09	RTE FF	RT	9.6	7	6	N/A	9.8	6	6	6.0						15.8	29.5	8.2		17.5		
4	106+22.56	108+29.29	DAVIS BLVD	RT	9.6	5	5	N/A	10.2	5	5	165.1						175.3	216.8	39.4				
4	9+54.37	9+74.84	STEPHENS	RT							5	11.0						11.0	20.5	3.5				
TOTAL					65.6	--	--	--	45.0	--	--	227.9					*	272.9	346.2	70.9		147.2		
USE					66	--	--	--	45.0	--	--		227.9				*	273	347	71		148		
QTY IS INCLUDED IN 8" SW FOR PINNED-ON ISLANDS, IF NEED PVMNT REPAIR UNDERNEATH. * PAY WIDTH INCLUDES INTEGRAL CURB CONC. WIDTH/HEIGHT. SEE TYPICAL SHEET 1 FOR ALL PAY ITEM LIMITS. SOD IS ESTIMATED AT 2.25' FOR CURB RAMP AREAS AND AT 1.5' FOR LONG SIDEWALK RUNS.																								

SUMMARY OF QUANTITES
SHEET 1 OF 5

STATE OF MISSOURI

MICHAEL WAYNE DUSENBERG

NUMBER F-28646

PROFESSIONAL ENGINEER

THIS SHEET HAS BEEN SIGNED, SEALED AND DATED ELECTRONICALLY.

DATE PREPARED

2/28/2025

ROUTE

FF

STATE

MO

DISTRICT

SW

SHEET NO.

3

COUNTY

JASPER

JOB NO.

J7S3059B

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

MoDOT

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

Bartlett & West

601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 572-663-3161
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

GENERAL NOTES

1. RIGHT OF WAY LIMITS FOR THIS PROJECT EXTEND FROM STA. 94+65.00 TO STA. 108+71.92 ALONG RELOCATED DAVIS BLVD., A DISTANCE OF 0.266 MILES, AND FROM STA. 33+42.00 TO STA. 39+31.60 ALONG ROUTE FF, A DISTANCE OF 0.112 MILES.
2. ANY WORK INDICATED ON THE PLANS THAT EXTENDS BEYOND THE PROJECT LIMITS IS CONSIDERED INCIDENTAL TO AND A PART OF THE CONSTRUCTION OF THIS PROJECT.
3. ALL UTILITIES SHALL NOT BE DISTURBED DURING CONSTRUCTION UNLESS OTHERWISE NOTED ON THE PLANS.
4. ALL BEARINGS ARE BASED ON STATE PLANE BEARINGS, WEST ZONE.
5. SEE SHEETS 7-9 FOR R/W INFORMATION.

TESORO INVESTMENTS
NO ACQUISITION

BUILD BRIDGE #A9696
3(11'x 7') CONCRETE BOX CULVERT
STA. 102+90.63 TO STA. 103+34.17
SKEW 36° LA
SQUARE END SECTION
CL. 4 EXC.=368 CY
ROCK LINING=233 CY

IMPROVEMENTS BEGIN AT
STA. 94+65.00 @ DAVIS BLVD.
AT POINT LOCATED 608.54' NORTH
AND 2835.09' WEST OF THE CORNER
OF SECTION 18, T27N R32W

CURVE DATA LABELS ARE LOCATED
ON THE CIVIL GEOMETRY PLAN SHEET
SHEET 1 OF 1

ENTRANCES

- (A) - STA. 95+68.00 RT
CONSTRUCT 213 SY ENTRANCE
57.85' WIDE PAVED SURFACE
- (B) - STA. 104+00.56 RT
CONSTRUCT 245 SY ENTRANCE
35' WIDE PAVED SURFACE
- (C) - STA. 105+61.95 LT
CONSTRUCT 89 SY ENTRANCE
24' WIDE PAVED SURFACE
- (D) - STA. 7+97.37 LT-STEPHENS BLVD
CONSTRUCT 141 SY ENTRANCE
24' WIDE PAVED SURFACE
- (E) - STA. 34+43.89 RT-RTE FF
CONSTRUCT 206 SY PAVED APPROACH
88' WIDE PAVED SURFACE

TEMP. CONST.
ESMT.

DEFAM-THREE
SEE SHEET 8 FOR R/W INFO.

STA. 102+36.52 TO STA.
103+27.88 RELOC. DAVIS BLVD.
TYPE 2 ROCK BLANKET

BRIDGE #A9696
TIE STATION
103+12.09
AT CENTERLINE
OF BOX CULVERT


PERM. ESM'T
(DRAINAGE)

GENERAL MILLS OPERATIONS INC.
SEE SHEET 8 FOR R/W INFO.

IMPROVEMENTS END AT
STA. 108+71.92 @ DAVIS BLVD.
AT POINT LOCATED 48.69' NORTH
AND 1880.97' WEST OF THE CORNER
OF SECTION 18, T27N R32W

STA. 34+34.90 @ ROUTE FF =
STA. 108+71.92 @ DAVIS BOULEVARD

PLAN SHEET
SHEET 1 OF 3



DATE PREPARED
3/24/2025

ROUTE FF STATE MO

DISTRICT SW SHEET NO. 4

COUNTY JASPER

JOB NO. J753059B

CONTRACT ID.


PROJECT NO.

BRIDGE NO.



DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION
COMMISSION



Bartlett & West
601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 572-634-3161
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM



PLAN SHEET
SHEET 2 OF 3

STATE OF MISSOURI

MICHAEL WAYNE DUSEMBERG

NUMBER 5-28566

PROFESSIONAL ENGINEER

THIS SHEET HAS BEEN SIGNED, SEALED, AND DATED ELECTRONICALLY.

DATE PREPARED
2/28/2025

ROUTE
FF

DISTRICT
SW

STATE
MO

SHEET NO.
5

COUNTY
JASPER

JOB NO.
J7S3059B

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION


MoDOT

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

Bartlett & West

601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 572-634-3161
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.



STATE OF MISSOURI
MICHAEL WAYNE
DUSENBERG
NUMBER
F-26546
PROFESSIONAL ENGINEER

THE SHEET HAS BEEN
SIGNED, SEALED AND DATED
ELECTRONICALLY.

DATE PREPARED
3/25/2025

ROUTE
FF

STATE
MO

DISTRICT
SW

SHEET NO.
6

COUNTY
JASPER

JOB NO.
J753059B

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION
COMMISSION

MoDOT


105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)


Bartlett & West

601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 572-634-3161
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

REV.





STATE OF MISSOURI

MICHAEL WAYNE DUSENBERG

NUMBER F-28546

PROFESSIONAL ENGINEER

THE SHEET HAS BEEN SIGNED, SEALED AND DATED ELECTRONICALLY.

DATE PREPARED
2/28/2025

ROUTE
FF

STATE
MO

DISTRICT
SW

SHEET NO.
8

COUNTY
JASPER

JOB NO.
J753059B

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

MoDOT

105 WEST CAPITAL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)



Bartlett & West

601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 572-634-3161
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM


SCALE
0 20 40 60

RIGHT OF WAY PLAN
SHEET 2 OF 3

pw://bartwest-pw.bentley.com:bartwest-pw-04/Documents/19000/19421.G40 - Jasper FF - Davis Boulevard/OpenRoads Designer/plan_sheets/3_Final Plans/008_RW_02_OF_03_1753059B_120.dgn 1:08:35 PM 2/28/2025



RIGHT OF WAY PLAN
SHEET 3 OF 3



DATE PREPARED 3/24/2025	
ROUTE FF	STATE MO
DISTRICT SW	SHEET NO. 9
COUNTY JASPER	
JOB NO. J7S3059B	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	

DATE	DESCRIPTION

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

Bartlett & West

601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 572-634-3161
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

ALL PROJECT COORDINATES HAVE BEEN PROJECTED FROM THE MISSOURI STATE PLANE COORDINATE (SPC) SYSTEM OF 1983 USING AN AVERAGE PROJECT PROJECTION (GRID TO GROUND) FACTOR. TO GET BACK TO STATE PLANE COORDINATES, MULTIPLY THE PROJECT COORDINATES BY THE AVERAGE GRID FACTOR AS SHOWN IN THE "REFERENCE CONTROL INFORMATION" PORTION OF THIS TABLE.

PROJECT COORDINATE INFORMATION

COORDINATE SYSTEM	MODIFIED STATE PLANE
HORIZONTAL DATUM	NAD83
VERTICAL DATUM	NAVD88
GEOID MODEL	CON_US_NGS2018
ELEVATIONS DETERMINED BY	MODOT GNSS

PROJECT PROJECTION FACTOR	1.0001028
---------------------------	-----------

REFERENCE CONTROL INFORMATION

COORDINATE SYSTEM	MODIFIED STATE PLANE
CONTROL STATION	SEE COORDINATE POINT LISTING TABLE
DESIGNATION	MODOT CARTHAGE CORS ARP
CORS_ID	MOCA
PID	DL6014
LATITUDE	N37_10_39.16612
LONGITUDE	W094_21_27.2430
NORTHING (M)	112181.729
EASTING (M)	862647.874
ZONE	MISSOURI WEST

PROJECT AVERAGE GRID FACTOR	0.9998972
-----------------------------	-----------

EXAMPLE OF PROJECT COORDINATE TO S.P.C.


```
PROJECT NORTHING X AVERAGE GRID FACTOR
= STATE PLANE NORTHING
PROJECT EASTING X AVERAGE GRID FACTOR
= STATE PLANE EASTING
```

```
EXAMPLE: CONTROL POINT #100
N 323433.8930 X 0.9998972 = N 323400.644
E 2799908.6370 X 0.9998972 = E 2799620.806
```


LINEAR UNIT CONVERSION

1 METER = 3.28033333 US SURVEY FEET (USFT)

COORDINATE POINT LISTING


[illegible]

CONTROL POINT #100
N: 323433.893
E: 2799908.637
EL: 1058.077
STA. 45+99.34 OFF. 45.0032' ROUTE FF
60D NAIL PREVIOUSLY SET BY MODOT
RM1: SHINER IN 12 IN. MAPLE TREE
RM2: MAG NAIL IN EAST DRIVE EDGE
RM3: WEST PC OF WEST CURB AT DRIVE
RM4: NW CORNER OF STORM GRATE @ CURB
RM5: CENTER OF DROP INLET MANHOLE



CONTROL POINT #51
N: 323522.082
E: 2796605.907
EL: 1056.776
STA. 12+95.44 OFF. 47.5646' ROUTE FF
5/8" I-B. W/ ALUMINUM CAP
RM1: CHISELED SQUARE IN LIGHT POLE BASE
RM2: CENTER OF MANHOLE LID
RM3: FACE OF STEEL LIGHT POLE
RM4: PERPENDICULAR TO CURB EAST
RM5: PERPENDICULAR TO CURB SOUTH

CONTROL / REFERENCE
POINT SHEET
1 OF 1



DATE PREPARED
2/28/2025

ROUTE	STATE
EE	MO

FT	MO
DISTRICT	SHEET NO.

SW	10
COUNTY	

JASPER

JOB NO.
J7S3059B

CONTRACT ID.

PROJECT NO.

[illegible]

MISSOURI HIGHWAYS AND TRANSPORTATION
COMMISSION




Bartlett & West

501 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 573-634-3181
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM



PI 96+79.36
PC 95+20.99
PT 97+64.75
Δ 93°6'39.9" (LT)
D 38°11'49.9"
L 243.76' (ARC)
T 158.37'
R 150.00'

START STA 94+65.00
PC STA 95+20.99
PT STA 97+64.75



ROUTE FF
S88°30'54"E

DAVIS BLVD
N88°46'49"E

PI 5+79.95
PC 5+00.00
PT 6+56.26
Δ 29°50'35.6" (RT)
D 19°5'54.9"
L 156.26' (ARC)
T 79.95'
R 300.00'

PC STA 104+20.06
PT STA 106+63.08
STA 5+00.00 STEPHENS BLVD =
STA 104+25.00 DAVIS BLVD

PI 105+77.65
PC 104+20.06
PT 106+63.08
Δ 92°49'30.1" (RT)
D 38°11'49.9"
L 243.02' (ARC)
T 157.58'
R 150.00'

PI 9+01.38
PC 8+24.72
PT 9+74.84
Δ 28°40'16.0" (LT)
D 19°5'54.9"
L 150.12' (ARC)
T 76.67'
R 300.00'


PC STA 8+24.72
PT STA 6+56.26
STEPHENS BLVD
EXIST. STEPHENS BLVD
N30°30'34"E

105

PT STA 106+63.08

35

SPECIAL SHEET
CIVIL GEOMETRY PLAN
SHEET 1 OF 2



DATE PREPARED 2/28/2025	
ROUTE FF	STATE MO
DISTRICT SW	SHEET NO. 11
COUNTY JASPER	
JOB NO. J7S3059B	
CONTRACT ID.	

PROJECT NO.
BRIDGE NO.


DESCRIPTION	DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

Bartlett & West

601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 572-634-3161
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM



STATE OF MISSOURI

MICHAEL WAYNE DUSENBERG

NUMBER F-28546

PROFESSIONAL ENGINEER

THIS SHEET HAS BEEN SIGNED, SEALED AND DATED ELECTRONICALLY.

DATE PREPARED

3/24/2025

ROUTE

FF

STATE

MO

DISTRICT

SW

SHEET NO.

12

COUNTY

JASPER

JOB NO.

J7S3059B

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION






MoDOT

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)


Bartlett & West

601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 572-634-3161
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM

pw://bartwest-pw.bentley.com:bartwest-pw-04/Documents/19000/19421.G40 - Jasper FF - Davis Boulevard/OpenRoads Designer/plan_sheets/3_Final Plans/012_SS_02_OF_02_17S3059B_140.dgn 3:03:26 PM 3/24/2025



SPECIAL SHEET
DRIVE PROFILES
SHEET 1 OF 1



DATE PREPARED
2/28/2025

ROUTE FF	STATE MO
DISTRICT SW	SHEET NO. 13
COUNTY JASPER	
JOB NO. J7S3059B	
CONTRACT ID.	

PROJECT NO.
BRIDGE NO.

DATE	DESCRIPTION

MISSOURI HIGHWAYS AND TRANSPORTATION
COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

Bartlett & West

601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 572-634-3161
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM

NOTES:

TYPE D SHALL BE USED ONLY AT LOCATIONS SHOWN ON PLANS.

FOR CONCRETE TRAFFIC BARRIER DELINEATION DETAILS SEE STD PLAN 903.03.

ALL REINFORCEMENT SHALL BE GRADE 60 EPOXY COATED.


NO DIRECT PAYMENT WILL BE MADE FOR REINFORCING STEEL.

MINIMUM CLEARANCE TO REINFORCING STEEL SHALL BE 1½" UNLESS OTHERWISE SHOWN.


* TILT TRANSVERSE PAVEMENT REINFORCEMENT HOOKS FROM VERTICAL ALIGNMENT TO MAINTAIN 1½" MINIMUM CLEARANCE.

** SEE ROADWAY PAVEMENT DESIGN.


*** R1 AND R2 MAY BE REPLACED WITH ALTERNATE (3'-3") R1 AND R2 OR R5 ONLY FOR USE WITH OPTIONAL STIRRUP.




PLAN



ELEVATION
BARRIER HEIGHT TRANSITION




PART SECTION THROUGH BARRIER



TYPE D TRAFFIC BARRIER - MOMENT SLAB**

TABLE A TRANSVERSE PAVEMENT REINFORCEMENT	
PAVEMENT THICKNESS	BAR SIZE & SPACING
** 8"	#5 @ 4"*
9"	#5 @ 5"*
10"	#5 @ 6"
11"	#5 @ 7"
12"	#6 @ 12"
≥ 13"	#6 @ 12"

SPECIAL SHEET
TYPE D BARRIER
SHEET 1 OF 1



DATE PREPARED
2/28/2025

ROUTE
FF

STATE
MO

DISTRICT
SW

SHEET NO.
14

COUNTY
JASPER

JOB NO.
J7S3059B

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION	DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)




Bartlett & West
601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 872-64-3181
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM

TRAFFIC CONTROL LEGEND


- SIGN (SINGLE SIDED)
- BARRICADE
- CHANGEABLE MESSAGE BOARD

TRAFFIC CONTROL PHASE 1:

- 1. CONSTRUCT DAVIS BLVD., STEPHENS BLVD. CONNECTION AND ROUTE FF RIGHT TURN LANE WITHOUT IMPACTING EXISTING TRAFFIC.
- 2. A LANE DROP WILL BE REQUIRED ON ROUTE FF FOR RIGHT TURN LANE CONSTRUCTION. ROUTE FF TRAFFIC WILL UTILIZE THE EXISTING CENTER TURN LANE TO MAINTAIN TWO LANES OF TRAFFIC IN BOTH DIRECTIONS.
- 3. TRAFFIC WILL CONTINUE TO USE EXISTING DAVIS BLVD., STEPHENS BLVD., AND ROUTE FF.



TRAFFIC CONTROL
PHASE 1
SHEET 1 OF 7



DATE PREPARED 2/28/2025	
ROUTE FF	STATE MO
DISTRICT SW	SHEET NO. 16
COUNTY JASPER	
JOB NO. J753059B	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	


DATE	DESCRIPTION

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

Bartlett & West

601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 572-634-3161
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM



STATE OF MISSOURI

MICHAEL WAYNE DUSENBERG

NUMBER F-28546

PROFESSIONAL ENGINEER

THIS SHEET HAS BEEN SIGNED, SEALED AND DATED ELECTRONICALLY.

DATE PREPARED
2/28/2025

ROUTE
FF

STATE
MO

DISTRICT
SW

SHEET NO.
17

COUNTY
JASPER

JOB NO.
J7S3059B

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION	DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

MoDOT

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

Bartlett & West

601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 572-634-3161
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM

TRAFFIC CONTROL
PHASE 1
SHEET 2 OF 7



pw://bartwest-pw.bentley.com:bartwest-pw-04/Documents/19000/19421.G40 - Jasper FF - Davis Boulevard/OpenRoads Designer/plan_sheets/3_Final Plans/017_TTC_02 OF 07_J7S3059B_I100.dgn 1:10:31 PM 2/28/2025

TRAFFIC CONTROL LEGEND


- SIGN (SINGLE SIDED)
- BARRICADE
- CHANGEABLE MESSAGE BOARD

TRAFFIC CONTROL PHASE 3:

1. COMPLETE CONSTRUCTION OF TIE-IN FROM NEW DAVIS BLVD. TO EXISTING STEPHENS BLVD. AND ROUTE FF INTERSECTION.
2. COMPLETE RIGHT TURN LANE FROM ROUTE FF TO NEW DAVIS BLVD. AND SIGNAL AND ADA IMPROVEMENTS AT ROUTE FF/DAVIS BLVD. INTERSECTION.
3. REMOVE EXISTING DAVIS BLVD. AND STEPHENS BLVD. PAVEMENT AND COMPLETE DRAINAGE CONSTRUCTION.
4. TRAFFIC CONTINUES TO UTILIZE RANGELINE RD AND 20TH STREET DETOUR TO ACCESS NEW DAVIS BLVD. AND STEPHENS BLVD. UNTIL ALL CONSTRUCTION IS COMPLETE.



TRAFFIC CONTROL
PHASE 3
SHEET 4 OF 7



DATE PREPARED 2/28/2025	
ROUTE FF	STATE MO
DISTRICT SW	SHEET NO. 19
COUNTY JASPER	
JOB NO. J7S3059B	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	


DESCRIPTION	DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

Bartlett & West

601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 572-634-3161
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM




THE FLAGGER SHALL FOLLOW THE PROCEDURES
PROVIDED IN EPG 616.5.07 AND 616.05.08

DAYLIGHT FLAGGING OPERATIONS ONLY.

NO DIRECT PAYMENT WILL BE MADE FOR DRUM-LIKE,
OR TRIM-LINE CHANNELIZERS. OR FOR THE RELOCATION
OF CHANNELIZERS AS SHOWN ON THE PLANS.

Bartlett & West
601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 572-534-3181
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.



NOTES:

ALL SIGNS HAVE TYPE 3 FLUORESCENT ORANGE RETROREFLECTIVE SHEETING.


- (1) WET PAINT SIGNS ARE INSTALLED TO INDICATE THE SIDE IN WHICH THE PAVEMENT MARKING MATERIAL IS BEING APPLIED. AT THE CONTRACTOR'S OPTION, A FRONT FACING WET PAINT SIGN MAY BE INSTALLED ON THE LEFT SIDE OF THE PAVEMENT MARKING EQUIPMENT.
- (2) ADVANCE WARNING TRUCK IS POSITIONED AT THE NO TRACK POINT OF THE PAVEMENT MARKING MATERIAL OR SPACING SHOWN. WHICHEVER IS GREATER.

PROTECTIVE TRUCK AND WORK VEHICLES SHALL DISPLAY HIGH-INTENSITY ROTATING, FLASHING, OSCILLATING, OR STROBE LIGHTS.



VEHICLE HAZARD WARNING SIGNALS SHALL NOT BE USED INSTEAD OF THE VEHICLE'S HIGH-INTENSITY, ROTATING, FLASHING, OSCILLATING, OR STROBE LIGHTS.

FLASHING ARROW PANELS SHALL, AS A MINIMUM, BE TYPE B, WITH A SIZE OF 60 X 30 INCHES.

THE STRIPING OPERATION SHALL BE COMPLETED UNDER A LANE CLOSURE.



LANE CLOSURE - NON-DIVIDED HIGHWAY ROUTE FF



GENERAL NOTES:

- ANY EXISTING SIGNING THAT CONFLICTS WITH THE TRAFFIC CONTROL SIGNING SHALL BE COMPLETELY COVERED OR REMOVED.
- QUANTITIES FOR TRAFFIC CONTROL ASSUMES TWO LANE DROPS FOR TWO BLOCK WORK AREA.
- DISTANCE MAY BE ADJUSTED ACCORDING TO FIELD CONDITIONS AND AS APPROVED BY THE ENGINEER. WHERE TRAFFIC BACKUPS ARE EXPECTED BEYOND THE ADVANCE WARNING AREA, ADDITIONAL SIGNING MAY BE NEEDED.
- ALL SIGNS SHALL BE PORTABLE UNLESS OTHERWISE NOTED.
- TWO CHANGEABLE MESSAGE SIGNS TO BE LOCATED AS APPROVED BY THE ENGINEER.
- LAYOUT IS SHOWN FOR EAST BOUND LANE BUT SHOULD BE MIRRORED FOR WEST BOUND LANE.
- ALL REDUCTION IN LANES SHALL BE DURING NIGHT TIME HOURS ONLY.
- ROAD WORK AHEAD SIGNS TO BE PLACED ON EACH SIDE ROAD WITHIN THE WORK ZONE.

NOTES:

SIGN ① NOT NEEDED IF LOCATED WITHIN LIMITS OF AN ACTIVITY AREA WHERE ANOTHER SIGN ① IS ALREADY USED.

NOT TO SCALE

TRAFFIC CONTROL LEGEND

- SIGN (SINGLE SIDED)
- CHANNELIZER
- WORK ZONE
- DIRECTIONAL INDICATOR BARRICADE
- BARRICADE
- ARROW PANEL

LONGITUDINAL BUFFER SPACE	
POSTED SPEED PRIOR TO CONSTRUCTION, MPH	LENGTH, FT.
UP TO 35	280
40-45	400
50-55	560
60-70	840

SPEED MPH (S) ¹	TAPER LENGTHS (L) FOR LATERAL SHIFTS (W) FT ²		CHANNELIZER SPACING ³ , FT	
	SHOULDER ⁴ (T1)	LANE ⁵ (T2)	TAPERS	BUFFER/ WORK AREA
UP TO 35	70	245	35 ⁶	40 ⁶
40-45	150	540	40 ⁶	80 ⁶
50-55	185	660	50 ⁷	80 ⁷
60-70	235	840	60 ⁷	120 ⁷


- SPEED LIMIT IS BASED ON POSTED SPEED LIMIT.
- TAPER LENGTHS MAY BE ADJUSTED TO ACCOMMODATE CROSSROADS, CURVES, INTERSECTIONS, RAMPS OR OTHER GEOMETRIC FEATURES.
- CHANNELIZER SPACING MAY BE REDUCED TO DISCOURAGE TRAFFIC ENCROACHMENT.
- BASED ON 10 FT. SHOULDER WIDTH.
- BASED ON 12 FT. LANE WIDTH.
- SPACING REDUCED TO 1/2 AT INTERSECTIONS.
- SPACING MAY BE REDUCED TO 1/2 AT INTERSECTIONS.

SIGN SPACING FOR ADVANCE SIGN SERIES ^{8,9}

POSTED SPEED MPH (P)	NON-DIVIDED HIGHWAYS (S)	DIVIDED HIGHWAYS (S)
0-35	200 FT	200 FT
40-45	350 FT	500 FT
50-55	500 FT	1000 FT
60-70	SA - 1000 FT, SB - 1500 FT AND SC - 2640 FT	


- SPACING BETWEEN SIGNS AND SPACING BETWEEN LAST SIGN AND FLAGGER, BEGINNING OF TAPER, OR SIGNED CONDITION.
- SPACING MAY BE ADJUSTED AS NECESSARY TO MEET FIELD CONDITIONS.

TAPER LENGTH (L)
L = W X P FOR 40 MPH OR MORE
L = $\frac{WP^9}{60}$ FOR 35 MPH OR LESS
L = TAPER LENGTH IN FEET
W = LATERAL SHIFT IN FEET
P = POSTED SPEED PRIOR TO ROAD WORK IN MPH



FOUR CHANGEABLE MESSAGE SIGNS INCLUDED IN CONTRACT. LOCATION TO BE DETERMINED BY THE ENGINEER.

TRAFFIC CONTROL PLAN
SHEET 7 OF 7



DATE PREPARED
2/28/2025
ROUTE FF STATE MO
DISTRICT SW SHEET NO. 22
COUNTY JASPER
JOB NO. J7S3059B
CONTRACT ID.

PROJECT NO.
BRIDGE NO.

DESCRIPTION	DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

Bartlett & West
601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 872-63-3161
CERTIFICATE OF AUTHORITY NO. 000107 - ENGINEERING
WWW.BARTLETTWEST.COM

TEMPORARY EROSION CONTROL LEGEND

- A


ALTERNATE DITCH CHECK
- C

CURB INLET CHECK
- R

ROCK DITCH CHECK
- S

SEDIMENT TRAP
- SILT FENCE
- TYPE 2 REINFORCEMENT MAT

NOTE: PROJECT DRAINAGE OUTLETS IN SILVER CREEK



STATE OF MISSOURI

MICHAEL WAYNE DUSENBERG

NUMBER E-26546

PROFESSIONAL ENGINEER

THE SHEET HAS BEEN SIGNED, SEALED AND DATED ELECTRONICALLY.

DATE PREPARED

3/24/2025

ROUTE

FF

STATE

MO

DISTRICT

SW

SHEET NO.

23

COUNTY

JASPER

JOB NO.

J7S3059B

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

MoDOT

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

Bartlett & West

601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 572-634-3161
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM

pw://bartwest-pw.bentley.com:bartwest-pw-04/Documents/19000/19421.G40 - Jasper FF - Davis Boulevard/OpenRoads Designer/plan_sheets/3_Final Plans/023_EC_01_01_J7S3059B_150.dgn 3:03:38 PM 3/24/2025

SUMMARY OF LIGHTING QUANTITIES

SUMMARY OF LIGHTING QUANTITIES					
PAY ITEM	DESCRIPTION	UNIT	QUAN	ROUTE FF/32ND ST.	
				AT HAMMONS BLVD.	AT DAVIS BLVD.
901.10-30	LIGHTING POLE, 30 FT., TYPE AT	EA	1		1
901.11-15	BRACKET ARM, 15 FT.	EA	1		1
901.13-11	LUMINAIRE, LED-A	EA	1		1
901.22-30	BASE MOUNTED CONTROL STATION 240 VOLT - 4 CIRCUIT	EA	1		1
901.30-02	CONDUIT, 2 IN. RIGID, IN TRENCH	LF	20		20
901.30-03	CONDUIT, 3 IN. RIGID, IN TRENCH	LF	40		40
901.40-03	CONDUIT, 3 IN. RIGID, PUSHED	LF	80		80
901.61-20	PULL BOX, CONCRETE, STANDARD	EA	2		2
901.70-01	CABLE, 1 AWG 1 CONDUCTOR	LF	60		60
901.71-10	CABLE, 10 AWG 1 CONDUCTOR, POLE AND BRACKET	LF	90		90
901.74-07	CABLE-CONDUIT, 1 IN., 2 CONDUCTORS AND 1 BARE NEUTRAL, 8 AWG	LF	120		120
901.82-30	POLE FOUNDATION, 30 FT MOUNTING HEIGHT	EA	1		1
901.86-13	POWERSUPPLY ASSEMBLY, TYPE 2, 240/120V, LIGHTING AND SIGNALS	EA	1		1

SUMMARY OF LIGHTING EQUIPMENT LOCATIONS

SUMMARY OF LIGHTING EQUIPMENT LOCATIONS				
PULL BOX	POLE	STA.	OFFSET	NOTES
11		35+18.65	37.23 RT.	
12		35+20.30	46.41 LT.	
	(L1)	35+13.28	46.76 LT.	TYPE IV DISTRIBUTION
	(3)	SEE SIGNAL PLANS		TYPE IV DISTRIBUTION

SUMMARY OF LIGHTING QUANTITIES
LIGHTING SHEET 1 OF 2



DATE PREPARED
3/25/2025

ROUTE	STATE
FF	MO

DISTRICT	SHEET NO.
SW	24

COUNTY
JASPER

JOB NO.
J7S3059B

CONTRACT ID.

PROJECT NO.

BRIDGE NO. _____

[illegible]

MISSOURI HIGHWAYS AND TRANSPORTATION
COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

Bartlett & West
601 MONROE ST., SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 573-634-3181
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

1. SEE ROADWAY PLANS FOR DETAILS OF EXISTING EASEMENTS.
2. SEE SIGNAL PLANS FOR DETAILS OF SIGNAL EQUIPMENT.

GENERAL NOTE (LIGHTING SHEETS)

1. SEE ROADWAY PLANS FOR DETAILS OF EXISTING EASEMENTS.
2. SEE SIGNAL PLANS FOR DETAILS OF SIGNAL EQUIPMENT.
3. SEE ITS PLANS FOR DETAILS OF ITS EQUIPMENT.

SCALE

0 10 20 30

DAVIS BLVD.

EXIST. R/W

PROP. R/W

EXIST. UTILITY ESM'T

CIRCUIT 1
2" CONDUIT
1" CABLE CONDUIT
2c#8 AND 1 BARE NEUTRAL

SIGNAL CONDUIT
1c#1
(QUANTIFIED ON
SIGNAL SHEETS)

10c#10 (POLE & BRACKET)
(QUANTIFIED ON SIGNAL
SHEETS)

INSTALL NEW LED-A
30' MOUNTING HEIGHT
15' BRACKET ARM
TYPE IV DISTRIBUTION
(QUANTIFIED ON
SIGNAL SHEETS)

FF/32ND ST.

ROUTE FF/32ND ST.

CONTRACTOR TO
PROVIDE CONNECTION
TO POWER SOURCE.
INCLUDED IN COST OF
POWER SUPPLY.

CIRCUIT 1
3" CONDUIT
1" CABLE CONDUIT
2c#8 AND 1 BARE NEUTRAL

SIGNAL CONDUIT
1c#1
(QUANTIFIED ON
SIGNAL SHEETS)

CIRCUIT 1
2" CONDUIT
1" CABLE CONDUIT
2c#8 AND 1 BARE NEUTRAL

PROPOSED ITS CABINET

PROPOSED SIGNAL CABINET

PROPOSED LIGHTING CABINET

2" CONDUIT
3-1c#1 AWG

ROUTE FF AT DAVIS BLVD
LIGHTING SHEET 2 OF 2

LIGHTING LEGEND


- CONTROLLER, LIGHTING
- CONTROLLER, LIGHTING (EXISTING)
- WOOD POST
- POWER SUPPLY
- JUNCTION BOX
- PULL BOX CONCRETE TYPE 1
- PULL BOX PREFORMED TYPE 1
- CONDUIT, RIGID (TRENCH)
- CONDUIT, RIGID (MEDIAN)
- CONDUIT, RIGID (EXISTING)

LIGHTING LEGEND (CONT'D)

- LED-A LUMINAIRE
- LED-B LUMINAIRE
- LED-C LUMINAIRE
- P.S. POWER SOURCE
- PULL BOX (EXISTING)
- PULL BOX CONCRETE TYPE 2
- PULL BOX PREFORMED TYPE 2
- CONDUIT, RIGID (PUSHED)
- CONDUIT, RIGID (BRIDGE)
- CABLE-CONDUIT (EXISTING)
- CABLE-CONDUIT

	CONTROLLER, LIGHTING
	CONTROLLER, LIGHTING (EXISTING)
	WOOD POST
	POWER SUPPLY
JCT	JUNCTION BOX
	PULL BOX CONCRETE TYPE 1
	PULL BOX PREFORMED TYPE 1
	CONDUIT, RIGID (TRENCH)
	CONDUIT, RIGID (MEDIAN)
	CONDUIT, RIGID (EXISTING)

	LED-A LUMINAIRE
	LED-B LUMINAIRE
	LED-C LUMINAIRE
P.S.	POWER SOURCE
	PULL BOX (EXISTING)
	PULL BOX CONCRETE TYPE 2
	PULL BOX PREFORMED TYPE 2
	CONDUIT, RIGID (PUSHED)
	CONDUIT, RIGID (BRIDGE)
	CABLE-CONDUIT (EXISTING)
	CABLE-CONDUIT


[illegible]

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

Bartlett & West
601 MONROE ST., SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 573-634-3181
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM

SUMMARY OF SIGNAL QUANTITIES			
PAY ITEM	DESCRIPTION	UNIT	QUAN
902.02-13	SIGNAL HEAD, TYPE 3S	EA	2
902.02-14	SIGNAL HEAD, TYPE 4S	EA	1
902.05-13	SIGNAL HEAD, TYPE 3B	EA	8
902.05-14	SIGNAL HEAD, TYPE 4B	EA	3
902.08-11	SIGNAL HEAD, TYPE 1S, PEDESTRIAN	EA	4
902.08-33	SH-FLAT SHEET - SIGNAL SIGN	SF	68
902.08-34	SIGNAL SIGN, MOUNTING HARDWARE	EA	8
902.26-51	LUMINAIRE, LED-A	EA	1
902.27-08	POST, SIGNAL 8 FT.	EA	3
902.27-15	POST, SIGNAL 15 FT.	EA	1
902.31-40	POST, TYPE CL, 40 FT. ARM	EA	1
902.32-35	POST, TYPE C, 35 FT. ARM	EA	2
902.32-55	POST, TYPE C, 55 FT. ARM	EA	1
902.49-21	ACCESSIBLE PEDESTRIAN SIGNAL	EA	4
902.52-00	CONDUIT, 2 IN., TRENCH WITH TRACER WIRE	LF	30
902.53-00	CONDUIT, 3 IN., TRENCH WITH TRACER WIRE	LF	103
902.54-00	CONDUIT, 4 IN., TRENCH WITH TRACER WIRE	LF	98
902.74-00	CONDUIT, 4 IN., PUSHED WITH TRACER WIRE	LF	368
902.81-00	CABLE, 10 AWG 1 CONDUCTOR, POLE AND BRACKET	LF	100
902.82-01	CABLE, 1 AWG 1 CONDUCTOR, POWER	LF	140
902.83-02	CABLE, 12 AWG 2 CONDUCTOR	LF	270
902.83-08	CABLE, 16 AWG 2 CONDUCTOR	LF	410
902.83-10	CABLE, 16 AWG 5 CONDUCTOR	LF	410
902.83-11	CABLE, 16 AWG 7 CONDUCTOR	LF	2,140
902.88-20	PULL BOX, CONCRETE, STANDARD	EA	3
902.88-21	PULL BOX, CONCRETE, DOUBLE TYPE A	EA	1
902.91-00	BASE, CONCRETE	CUYD	15.6
902.99-01	MISC. {SIGNAL COMMUNICATION}	LS	1
902.99-01{1}	MISC. {RADAR DETECTION SYSTEM, CONTRACTOR FURNISHED, CONTRACTOR INSTALLED}	LS	1
902.99-02	MISC. {SIGNAL CONTROLLER AND CABINET, TYPE 2070}	EA	1
902.99-02{1}	MISC. {UNINTERRUPTABLE POWER SUPPLY (UPS)}	EA	1

* SIGNAL QUANTITIES SHOWN ON THIS SHEET ARE FOR INFORMATIONAL PURPOSES ONLY. SEE D37 SHEETS FOR OFFICIAL QUANTITIES.



DATE PREPARED
4/7/2025

ROUTE	STATE
FF	MO

DISTRICT	SHEET NO.
SW	26

COUNTY
JASPER

JOB NO.
J7S3059B

CONTRACT ID.

PROJECT NO. _____

BRIDGE NO. _____

[illegible]

MISSOURI HIGHWAYS AND TRANSPORTATION
COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)


Bartlett & West
601 MONROE ST., SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 572-634-3181
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

SUMMARY OF SIGNAL QUANTITIES
SIGNAL SHEET 1 OF 7

GENERAL: USE 4" CONDUIT

1. TRAFFIC FLOW ARROWS SHOWN FOR DIAGRAM PURPOSES ONLY. DO NOT INSTALL PAVEMENT MARKING ARROWS UNLESS SPECIFIED IN THE PLANS.
2. SEE ROADWAY PLANS FOR DETAILS OF EXISTING EASEMENTS.
3. SEE LIGHTING PLANS FOR DETAILS OF STAND-ALONE LIGHTING EQUIPMENT.
4. SEE ITS PLANS FOR DETAILS OF ITS EQUIPMENT.
5. RADAR DEVICE LOCATIONS AND CABLES SHOWN FOR INFORMATIONAL PURPOSES ONLY. CONTRACTOR SHALL INSTALL ACCORDING TO MANUFACTURER SPECIFICATIONS.



ROUTE FF AT DAVIS BLVD
SIGNAL SHEET 2 OF 7



STATE OF MISSOURI

JASON MICHAEL
SOMMER

NUMBER
PE-2008002211

PROFESSIONAL ENGINEER

THIS SHEET HAS BEEN
SIGNED, SEALED, AND DATED
ELECTRONICALLY.

DATE PREPARED
3/25/2025

ROUTE FF	STATE MO
DISTRICT SW	SHEET NO. 27

COUNTY
JASPER

J7S3059B

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

[illegible]TOL
5102
636)

-275-

05 WEEK
CITY
1-884

ERSON
DOT

JEFF
ASK-M

888-888-8888

MI

et

es
IO 6510
EERING

W
CITY,
- ENG
M

S&P
PERSONAL
4-3181
. 00016
EST.CO

01 - JEFF
573-6
RITY N
TLETT


et
SUITE
PHONE
AUTHC
WWW.BAA

PRO STATE OF

01 MO
CERTIF

6 PM 3/25/2025

EFFECTIVE: 10-01-2015																					
* FOR INFORMATION ONLY, PAID UNDER CONTRACTOR FURNISHED, CONTRACTOR INSTALLED RADAR DETECTION SYSTEM																					
** SEE LIGHTING PLANS FOR DETAILS OF STAND-ALONE LIGHTING POLE																					
*** SEE COMMUNICATIONS/ITS PLANS FOR DETAILS OF CCTV AND RADIO CABLES																					
PS = POWER SOURCE Ø = POWER SUPPLY																					
CONDUIT (WITH #14 TRACER WIRE)																					
CABLE																					
FROM	TO	CENTER TO CENTER DISTANCE	LOOP DET.	TRENCH				PUSHED			MEDIAN			ON STRUCTURE			REMARKS	FROM	TO		
				1"	2"	3"	4"	2"	3"	4"	2"	3"	4"	2"	3"						
				1"	2"	3"	4"	2"	3"	4"	2"	3"	4"	2"	3"						
PS	Ø	16															INCLUDED IN COST OF POWER SUPPLY	PS	Ø		
Ø	⊞	20		30														Ø	⊞		
LT CABINET	1	11			14													DAVIS BOULEVARD			
⊞	1	12				32											TWO RUNS	⊞	1		
1	1	6				9												⊞	1		
1	P1	23			24													⊞	V		
1	P2	27			28													⊞	V		
1	2	96								94								⊞	V		
1	5	72								70								⊞	V		
																		⊞	R4		
2	2	20				23												⊞	P1		
2	P3	7			8													⊞	V		
2	3	94								92								⊞	24		
																		⊞	P2		
5	4	6				9												⊞	V		
5	P4	28			29													⊞	V		
5	4	114								112								⊞	83		
																		SOUTHWEST CORNER			
																		⊞	2		
																		⊞	2		
																		⊞	V		
																		⊞	V		
																		⊞	V		
																		⊞	R1		
																		⊞	P3		
																		⊞	V		
																		⊞	84		
																		NORTHWEST CORNER			
																		⊞	3		
																		⊞	4		
																		⊞	3		
																		⊞	V		
																		⊞	V		
																		⊞	V		
																		⊞	V		
																		⊞	R3		
																		ITS CABINET	229		
																		ITS CABINET	229		
																		3	⊞		
																		NORTHEAST CORNER			
																		⊞	5		
																		⊞	4		
																		⊞	V		
																		⊞	V		
																		⊞	V		
																		⊞	R3		
																		⊞	P4		
																		⊞	V		
																		⊞	V		
																		⊞	V		
																		⊞	23		
																		LT CABINET	⊞		
SUBTOTALS				30	103	98				368								SUBTOTALS			
TOTALS				30	103	98				368								TOTALS			
INTERSECTION ROUTE FF AT DAVIS BOULEVARD (SIGNAL SHEET 4 OF 7)																					
D-37B																					



DATE PREPARED	
4/4/2025	
ROUTE	STATE
FF	MO
DISTRICT	SHEET NO.
SW	29
COUNTY	
JASPER	
JOB NO.	
J7S3059B	
CONTRACT ID.	

PROJECT NO.

BRIDGE NO.

DESCRIPTION	
DATE	

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION



105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)



601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 572-634-3161
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM

WIRING DIAGRAM

4" CONDUIT (TRENCH)
3-7C#16
1-2C#12 (LUM)
1-6C SENSOR
1-CAT 5 (RADIO)
1-CAT 5 (CCTV)

4" CONDUIT (PUSH)
3-7C#16
1-2C#12 (LUM)
1-6C SENSOR

1-7C#16 JUMPER

4" CONDUIT (TRENCH)
1-7C#16
1-6C SENSOR

3" CONDUIT (TRENCH)
1-7C#16
1-5C#16
1-2C#16

4" CONDUIT (PUSH)
5-7C#16
1-5C#16
1-2C#16
1-2C#12 (LUM)
2-6C SENSOR

3" CONDUIT (TRENCH)
1-5C#16
1-2C#16

4" CONDUIT (PUSH)
1-CAT 5 (RADIO)
1-CAT 5 (CCTV)

4" CONDUIT (PUSH)
1-CAT 5 (RADIO)
1-CAT 5 (CCTV)

3" CONDUIT (TRENCH)
1-5C#16
1-2C#16

4" CONDUIT (PUSH)
2-7C#16
1-5C#16
1-2C#16
1-6C SENSOR
1-CAT 5 (RADIO)
1-CAT 5 (CCTV)

3" CONDUIT (TRENCH)
1-5C#16
1-2C#16

4" CONDUIT (TRENCH)
2-7C#16
1-6C SENSOR

1-7C#16 JUMPER

4" CONDUIT (TRENCH)
3-7C#16
1-6C SENSOR

2" CONDUIT (TRENCH)
1-2C#12 (LUM)

PROPOSED ITS CABINET.
SEE ITS PLANS FOR
DETAILS.

2" CONDUIT (TRENCH)
1-CAT 5 (RADIO)
1-CAT 5 (CCTV)

2" CONDUIT (TRENCH)
1-2C#12 (LUM)

PROPOSED LIGHTING
CABINET. SEE LIGHTING
PLANS FOR DETAILS.


2" CONDUIT (TRENCH)
3-1C#1 (POWER)

EXISTING POWER
SOURCE


CONTRACTOR PROVIDED
(INCLUDED IN COST OF POWER
SUPPLY MIN 3-1C#1 POWER)

ROUTE FF AT DAVIS BOULEVARD
(SIGNAL SHEET 6 OF 7)

D-37D



TRAFFIC PHASING AND COLOR SEQUENCE - ACTUATED CONTROLLERS																																																																			
PHASE 1				PHASE 2				PHASE 3				PHASE 4				PHASE 5				PHASE 6				PHASE 7				PHASE 8				PED Ø2 OVERLAP				PED Ø OVERLAP				PED Ø OVERLAP				PED Ø8 OVERLAP																							
11	12			21	22			31				31	41										71			71	81			23								83																													
	13												42, 43										72				82			24								84																													
RL	R			R	R			RL					R										RL				R			DW									DW																												
YL	Y			Y	Y			YL					Y										YL				Y			FDW									FDW																												
												FYL														FYL																																									
L	G			G	G			L					G										L				G			W									W																												
					S																																																														
11	11			21	21			31				31	41										71			71	81																																								
12	12											42													82																																										
																								DETECTOR ASSIGNMENTS (PEDS. ONLY)				2															8																								
																								OVERLAP PARENT PHASES																																											




RING STRUCTURE

IF CALLED, ALL NON-CONFLICTING PHASES SHALL COMBINE AND TIME CONCURRENTLY. TIME TO BE DETERMINED BY THE ENGINEER AT SIGNAL TURN ON AND SET IN THE CONTROLLER BY THE CONTRACTOR.

FLASHING OPERATION	
ALL APPROACHES	FR
	FY
CONTROLLER TYPE	2070

TRAFFIC SIGNAL CONTROL OPERATION	
INTERSECTION OF ROUTE FF (32ND STREET)	
WITH DAVIS BOULEVARD	

ROUTE FF AT DAVIS BOULEVARD
(SIGNAL SHEET 7 OF 7)



DATE PREPARED	
3/25/2025	
ROUTE	STATE
FF	MO
DISTRICT	SHEET NO.
SW	32
COUNTY	
JASPER	
JOB NO.	
J7S3059B	
CONTRACT ID.	

PROJECT NO.
BRIDGE NO.

DESCRIPTION
DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION


105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

Bartlett & West

601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 572-634-3161
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.


SUMMARY OF COMMUNICATIONS/ITS QUANTITIES					
PAY ITEM	DESCRIPTION	UNIT	QUAN	ROUTE FF/32ND ST.	
				AT HAMMONS BLVD.	AT DAVIS BLVD.
910.37-00	CCTV CAMERA ASSEMBLY, INSTALLED	EA	1		1
910.52-00	CONDUIT, 2 IN., RIGID, IN TRENCH	LF	135		135
910.72-01	CONDUIT, 3 IN., RIGID, PUSHED	LF	80		70
910.82-01	CABLE, 1 AWG, 1 CONDUCTOR, POWER	LF	140		140
910.88-20	PULL BOX, CONCRETE, STANDARD	EA	4		3
910.99-02	MISC. {UBIQUITI NANOBEAM GEN 2 RADIO}	EA	2	1	1
910.99-02 {1}	MISC. {ITS CABINET, TYPE 332}	EA	1		1
910.99-02 {2}	MISC. {INSTALL MODOT FURNISHED ETHERNET SWITCH}	EA	1		1
910.99-02 {3}	MISC. {48 PORT FIBER DISTRIBUTION UNIT}	EA	1		1
910.99-03	MISC. {CABLE, RADIO, ETHERNET CAT 5}	LF	620	320	300
910.99-03{1}	MISC. {CABLE, CCTV, ETHERNET CAT 5}	LF	300		300



FIBER LAYOUT SHOWN FOR ULTIMATE CONFIGURATION.
CONSTRUCTOR SHALL PLUG CABLE FROM PROPOSED RADIO
TO PROPOSED ITS SWITCH (CONTRACTOR PROVIDED).

SUMMARY OF COMMUNICATIONS/ITS PULLBOX LOCATIONS		
ID	STA.	OFFSET
21	34+86.96	42.61 RT.
22	34+09.76	49.38 RT.
23	33+43.62	38.57 RT.
24	32+16.39	36.67 RT.

SUMMARY OF ITS QUANTITIES
COMMUNICATIONS/ITS SHEET 1 OF 4



DATE PREPARED 3/25/2025	
ROUTE FF	STATE MO
DISTRICT SW	SHEET NO. 33
COUNTY JASPER	
JOB NO. J7S3059B	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	

DESCRIPTION	DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION




105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)




601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 572-634-3161
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM

GENERAL NOTE (ITS SHEETS)

1. SEE ROADWAY PLANS FOR DETAILS OF EXISTING EASEMENTS.
2. SEE SIGNAL PLANS FOR DETAILS OF SIGNAL EQUIPMENT.
3. SEE LIGHTING PLANS FOR DETAILS OF LIGHTING EQUIPMENT.



TRAFFIC SIGNALS LEGEND	
	CONTROLLER
	CONTROLLER (EXISTING)
	JUNCTION BOX
	POWER SUPPLY
	WOOD POST
	SIGNAL HEAD (PEDESTRIAN)
	SIGNAL HEAD (STANDARD)
	CCTV CAMERA
	RADAR DETECTION
	PUSH BUTTON DETECTOR
	PREFORMED PULL BOX TYPE 1
	PREFORMED PULL BOX TYPE 2
	ITS PULL BOX TYPE 2 (CONCRETE)
	ITS PULL BOX TYPE 5 (CONCRETE)
	CONCRETE PULL BOX, STANDARD
	CONCRETE PULL BOX, DOUBLE
	30 X 6 LOOP DETECTOR
	CONDUIT PUSHED
	CONDUIT BRIDGE
	CONDUIT EXISTING
	CONDUIT TRENCHED
	MAST ARM - TYPE A BASE
	MAST ARM - TYPE C BASE
	MAST ARM - TYPE F BASE
	LED-A LUMINAIRE



DATE PREPARED 2/28/2025	
ROUTE FF	STATE MO
DISTRICT SW	SHEET NO. 34
COUNTY JASPER	
JOB NO. J7S3059B	
CONTRACT ID.	

PROJECT NO.
BRIDGE NO.

DESCRIPTION	DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

MoDOT


105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

Bartlett & West



601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 872-634-3161
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM

GENERAL NOTE (ITS SHEETS)

1. SEE ROADWAY PLANS FOR DETAILS OF EXISTING EASEMENTS.
2. SEE SIGNAL PLANS FOR DETAILS OF SIGNAL EQUIPMENT.
3. SEE LIGHTING PLANS FOR DETAILS OF LIGHTING EQUIPMENT.



TRAFFIC SIGNALS LEGEND	
	CONTROLLER
	CONTROLLER (EXISTING)
	JUNCTION BOX
	POWER SUPPLY
	WOOD POST
	SIGNAL HEAD (PEDESTRIAN)
	SIGNAL HEAD (STANDARD)
	CCTV CAMERA
	RADAR DETECTION
	PUSH BUTTON DETECTOR
	PREFORMED PULL BOX TYPE 1
	PREFORMED PULL BOX TYPE 2
	ITS PULL BOX TYPE 2 (CONCRETE)
	ITS PULL BOX TYPE 5 (CONCRETE)
	CONCRETE PULL BOX, STANDARD
	CONCRETE PULL BOX, DOUBLE
	30 X 6 LOOP DETECTOR
	CONDUIT PUSHED
	CONDUIT BRIDGE
	CONDUIT EXISTING
	CONDUIT TRENCHED
	MAST ARM - TYPE A BASE
	MAST ARM - TYPE C BASE
	MAST ARM - TYPE F BASE
	LED-A LUMINAIRE



DATE PREPARED 2/28/2025	
ROUTE FF	STATE MO
DISTRICT SW	SHEET NO. 35
COUNTY JASPER	
JOB NO. J7S3059B	
CONTRACT ID. .	
PROJECT NO. .	
BRIDGE NO. .	

DESCRIPTION	DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)




Bartlett & West

601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 572-634-3161
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM

1. SEE ROADWAY PLANS FOR DETAILS OF EXISTING EASEMENTS.

2. SEE SIGNAL PLANS FOR DETAILS OF SIGNAL EQUIPMENT.

3. SEE LIGHTING PLANS FOR DETAILS OF LIGHTING EQUIPMENT.



DATE PREPARED
3/25/2025

ROUTE	STATE
FF	MO

DISTRICT	SHEET NO.
SW	36

COUNTY
JASPER

JOB NO.
J7S3059B

CONTRACT ID.

PROJECT NO.

BRIDGE NO. _____

[illegible]

--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--

[illegible]

--	--	--	--	--	--	--	--

[illegible]

--	--	--	--	--	--	--	--

--	--	--	--	--	--	--

TOL
5102
536)CAP
MO 65
75-66WEST
ITY,
388-2105
ON CH
(1-8)

510



JEFF
ASK-N-ASK



st

es
O 6510
EEING

VO

PERSON C
181
00167 -
T.COM

**tt**

le'
C. SUIT
PHO
F AUTH
WWW.B



PRO STATE OF

ar
1 MONTH
CERTIFIC


60 CE

1 PM 3/25/2025

1 PM 3/25/2025



SIGNING SHEET
SHEET 1 OF 3



DATE PREPARED
3/24/2025

ROUTE	STATE
FF	MO
DISTRICT	SHEET NO.
SW	37
COUNTY	
JASPER	
JOB NO.	
J7S3059B	
CONTRACT ID.	




PROJECT NO.
BRIDGE NO.

DATE	DESCRIPTION

MISSOURI HIGHWAYS AND TRANSPORTATION
COMMISSION


105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

Bartlett & West
601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 972-664-3161
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM



NOTES:
1) ALL SIGN CROSS SECTION ARE CUT IN THE DIRECTION OF TRAVEL.

SIGNING SHEET
SHEET 2 OF 3



DATE PREPARED
2/28/2025
ROUTE FF STATE MO
DISTRICT SW SHEET NO. 38
COUNTY JASPER
JOB NO. J7S3059B
CONTRACT ID.

PROJECT NO.
BRIDGE NO.

DATE	DESCRIPTION

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
MoDOT
105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)


Bartlett & West
601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 572-634-3161
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM

SIGNS					CONCRETE FOOTINGS EMBEDDED	STRUCTURAL STEEL POSTS*					PIPE POSTS*					BACKING BARS**				U- CHANNEL POST	PERFORATED SQUARE STEEL TUBE														EFFECTIVE: 07-01-2024		REMARKS AND OTHER REQUIRED ITEMS
902 SIGNAL SIGNS TABULATED ON D-37A SHEET						ITEM NO. 9031010 CY	POST DES NO.	POST NO.1	POST NO.2	POST NO.3	LBS PER FT	TOTAL ITEM NO. 9031210 LBS	PIPE SIZE	POST NO.1	POST NO.2	LBS PER FT	TOTAL ITEM NO. 9031220 LBS	2" X 3/8" BARS AT 2.55 LBS/FT				ITEM NO. 9031250A LF	2- INCH POST			2.5- INCH POST				BREAK- AWAY ASSEMBLY ITEM NO. 9031241							
SIGN NO.	SIGN SIZE	STATION OR LOG MILE	HORIZ CLEAR IF NOT STD	LOCATION														SIGN DTL SHT NO.	ITEM NO. 9031270A LF		ITEM NO. 9031271A EACH		ITEM NO. 9031273A EACH	ITEM NO. 9031274 EACH	POST NO.1	POST NO.2	TOTAL ITEM NO. 9031280 LF	ITEM NO. 9031272A EACH	ITEM NO. 9031281A EACH		ITEM NO. 9031285 EACH						
																																NO.	LGTH	TOTAL	TOTAL		
1	36"X 48"	99+65.00	STD	RT																		15		15	1												
2	36"X 48"	101+65.00	STD	LT																		15		15	1												
3	36"X 36"	5+50.00	STD	LT																		15		15	1												
					SUBTOTAL																				45	3											
					TOTAL														**						45	3											

*BREAKAWAY ASSEMBLY IS INCIDENTAL FOR STRUCTURAL STEEL AND PIPE POSTS.
**BACKING BARS ARE TOTALED WITH STRUCTURAL STEEL OR PIPE POSTS.

ROUND PIPE POST AND FOOTING DATA TABLE						
NOM. SIZE		WEIGHT		STUB LENGTH	FOOTING	
(IN.)		LBS/FT	LBS/IN		DIA.	DEPTH
2½		5.79	0.48	4'- 3½"	12"	4-6"
4		10.79	0.90	5'- 3½"	18"	5-6"

STRUCTURAL STEEL POST AND FOOTING DATA TABLE													
POST				FOOTING									
				WEIGHT		STUB LENGTH	DIA.	LEVEL GROUND		6:1 GRADE		4:1 GRADE	
POST DES. NO.	NOM. SIZE	LBS/FT	LBS/IN					DEPTH	C.Y.	DEPTH	C.Y.	DEPTH	C.Y.
1	W6	9.0	0.75	3'-0"	15"	3'-0"	0.14	3'-2"	0.15	3'-3"	0.16	3'-6"	0.17
2	W6	15.0	1.25	4'-0"	24"	4'-0"	0.47	4'-2"	0.50	4'-3"	0.51	4'-6"	0.54
3	W8	18.0	1.50	4'-6"	28"	4'-6"	0.71	4'-8"	0.73	4'-9"	0.74	5'-0"	0.78
4	W10	22.0	1.83	5'-0"	36"	5'-0"	1.31	5'-2"	1.36	5'-3"	1.39	5'-6"	1.45
5	W10	26.0	2.17	5'-0"	36"	5'-0"	1.31	5'-3"	1.37	5'-5"	1.43	5'-9"	1.52
6	W12	35.0	2.92	5'-6"	36"	5'-6"	1.44	5'-9"	1.52	5'-11"	1.56	6'-3"	1.65



DATE PREPARED 2/28/2025	
ROUTE FF	STATE MO
DISTRICT SW	SHEET NO. 39
COUNTY JASPER	
JOB NO. J7S3059B	
CONTRACT ID.	

PROJECT NO.

DESCRIPTION	DATE								

D-29

STANDARD SIGN ASSEMBLIES																			
SIGN, TYPE, DESIGNATION, SIZE & NUMBER OF EACH																			
SIGN NO.	STATION OR LOG MILE	LOCATION	SHR2L-1	SHR2L-1															
																			
			R1-1 36"X 36"	R2-1 36"X 48"															
1	99+65.00	RT		1															
2	101+65.00	LT		1															
3	5+50.00	LT	1																
TOTALS			1	2															

SIGN SUMMARY							EFFECTIVE: 10-01-2016	
STANDARD OR SPECIAL SIGN DESIGNATION	SIGN DTL. SHT. NO.	NO. EACH	SIGN SIZE	TYPE & SQUARE FEET				
				FLAT SHEET	FLAT SHEET	STRUCTURAL	STRUCTURAL	
				SH	FLUORESCENT	ST	FLUORESCENT	
				SHF*	STF*	STF*	STF*	
				ITEM NO.	ITEM NO.	ITEM NO.	ITEM NO.	
R1-1 (STOP)		1	36"X 36"	9.0				
R2-1 (SPEED LIMIT)		2	36"X 48"	24.0				
TOTALS				33.0				

*ORANGE, YELLOW AND YELLOW-GREEN

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION




Bartlett & West
601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 872-664-3161
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM

D-30



IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.




pw://bartwest-pw.bentley.com:bartwest-pw-04/Documents/19000/19421.G40 - Jasper FF - Davis Boulevard/OpenRoads Designer/plan_sheets/3_Final Plans/040_PM_01 OF 02_J7S3059_1100.dgn 1:15:21 PM 2/28/2025



pw://bartwest-pw.bentley.com:bartwest-pw-04/Documents/19000/19421.G40 - Jasper FF - Davis Boulevard/OpenRoads Designer/plan_sheets/3 Final Plans/041_PM_02_OF_02_I7S3059_I100.dgn 11:01:48 AM 3/24/2025



CULVERT SECTION SHEET
SHEET 3 OF 3



DATE PREPARED
2/28/2025
ROUTE FF STATE MO
DISTRICT SW SHEET NO. 44
COUNTY JASPER
JOB NO. J7S3059B
CONTRACT ID.

PROJECT NO.
BRIDGE NO.

DATE	DESCRIPTION

MISSOURI HIGHWAYS AND TRANSPORTATION
COMMISSION


105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

Bartlett & West
601 MONROE ST. SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 572-634-3161
CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
WWW.BARTLETTWEST.COM

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

3 (11' x 7') CONCRETE BOX CULVERT


SEC/SUR	18	TWP	27N	RGE	32W
---------	----	-----	-----	-----	-----



Construction joint key not shown for clarity, see standard plans for details.

If any part of the barrel is exposed, the roadway fill shall be warped to provide 12 inches minimum cover. (Roadway Item)

If unsuitable material is encountered, excavation of unsuitable material and furnishing and placing of granular backfill shall be in accordance with Sec 206.



Layout Dimensions								
Var.	Equation	Dim.	Var.	Equation	Dim.	Var.	Equation	Dim.
S	- - -	11'-0"	F	3S + 2TX + 2TI	35'-8"	W	2A + B + C + 2E	93'-2 $\frac{1}{8}$ "
HT	- - -	7'-0"	G	2V	14'-4"	X	3" + TX(tan Z)	8 $\frac{5}{8}$ "
TS	- - -	1'-2"	H	(A + C + E)(tan Z)	31'-2 $\frac{3}{8}$ "	Z	Skew Angle	35°
BS	- - -	9"	I	3"(cos Z)	2 $\frac{1}{2}$ "	BB	(A + B)(sec Z)	39'-0 $\frac{3}{4}$ "
TX	- - -	8"	J	(A + B + E)(tan Z)	34'-0 $\frac{1}{4}$ "	CC	(A + C)(sec Z)	34'-2 $\frac{1}{8}$ "
TI	- - -	8"	K	(3S/2 + TI)(sec Z)	20'-11 $\frac{1}{2}$ "	EE	E(sec Z)	20'-3"
A	- - -	16'-0"	L	2EE + BB + CC	113'-9"	HH	20"(sec Z)	2'-0 $\frac{3}{8}$ "
B	- - -	16'-0"	O	I + YY	7"	QQ	TX(cos Z)	6 $\frac{1}{2}$ "
C	- - -	12'-0"	T	G(sec Z)	17'-6"	YY	TX(sin Z)	4 $\frac{5}{8}$ "
E	G + O + 20"	16'-7"	V	HT + TS - 12"	7'-2"	TW	Max{3'-4" or (BS + 12")}	3'-4"*

Hydrologic Data
Drainage Area = 0.48 mi ²
Design Flood Frequency = 50 years
Design Flood Discharge = 940 cfs
Design Flood (D.F.) Elevation = 1045.6
Base Flood (100-year)
Base Flood Elevation = 1046.1
Base Flood Discharge = 1110 cfs
Estimated Backwater = 0.2 ft
Outlet Velocity = 7.4 ft/s
Roadway Overtopping
Overtopping Flood Discharge = N/A
Overtopping Flood Frequency = >100 years
100-yr. Flood Elevation = 1046.1


Elevations
Upstream (Elev. 1) = 1039.2
Downstream (Elev. 2) = 1038.7
Pr. Gr. at Tie Sta. = 1050.0

Fill Heights
℄ Rdwy at ℄ Culvert = 2.9 ft
Design (All units) = 2 ft - 4 ft

Dimensions are based on end units.
Fill heights are measured from the top of top slab to the
top of earth fill or roadway.

Estimated Quantities			Final
Class 4 Excavation	cu. yard	370	
Class 4 Excavation in Rock	cu. yard	305	
Dewatering	lump sum	1	
Class B-1 Concrete (Culverts-Bridge)	cu. yard	311.6	
Reinforcing Steel (Culverts-Bridge)	pound	47,730	

- * Extend toe wall a minimum of the full height of 3'-4" or 18" into competent shale, measured from the bottom of the bottom slab.



General Notes:

Design Specifications:
2010 AASHTO LRFD Bridge Design Specifications and 2010
Interim Revisions

Design Loading:
 Vehicular = HL-93 minus lane load, Earth = 120 lb/cf
 Equivalent Fluid Pressure = 30 lb/cf (min.), 60 lb/cf (max.)

Design Unit Stresses:
 Class B-1 Concrete (Box Culvert) $f'_c = 4,000$ psi
 Reinforcing Steel (ASTM A615 Grade 60) $f_y = 60,000$ psi

Standard Plans:
703.37, 703.82 703.86, 703.87

Miscellaneous:
MoDOT Construction personnel will indicate the type of box culvert constructed:
☐ Precast Concrete Box used
☐ Cast-in-Place Concrete Box used

When alternate precast concrete box sections are used, the minimum distance from inside face of headwalls to precast sections measured along the shortest wall shall be 3 feet. Reinforcement and dimensions for wings and headwalls shall be in accordance with Missouri Standard Plans.


Channel bottom shall be graded within the right of way for transition of channel bed to culvert openings. Channel banks shall be tapered to match culvert openings. (Roadway Item)

C.P. #100 - Elev. 1058.077, 60D Nail previously set by MoDOT
Sta. 45+99.34, Offset 45.00' Route FF
N: 323433.893, E: 2799908.637

C.P. #51 - Elev. 1056.776, 5/8" I.B. with aluminum cap
Sta. 12+95.44, Offset 47.56' Route FF
N: 323522.082, E: 2796605.907

CULVERT-BRIDGE: DAVIS BLVD. OVER
TRIBUTARY OF SILVER CREEK

DAVIS BLVD. FROM ROUTE FF TO 20TH ST.
ABOUT 0.1 MILES NORTH OF ROUTE FF
TIE STA. 103+12.31



DATE PREPARED
2/28/2025

ROUTE	STATE
FF	MO

DISTRICT	SHEET NO.
BR	1

COUNTY
JASPER

JOB NO.
17S3059B

CONTRACT ID.

PROJECT NO.

BRIDGE NO.
A9696[illegible]MISSOURI HIGHWAYS AND TRANSPORTATION
COMMISSION

JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

Bartlett & West

PHONE 573-634-3181 - FAX 573-634-7904
 CERTIFICATE OF AUTHORITY NO. 000167 - ENGINEERING
 WWW.BARTWEST.COM

Missouri Department of Transportation
Construction and Materials

BORING NO. B-1
Page 1 of 1

Job No.: 15273-026-01

Design:

Bent:

Station: 97+04.1

Offset: CL

Elevation: 1044.1

Requested Station:

Requested Offset:

Requested Elevation:

Drill No.: OWN Engineering

County: Jasper

Skew:

Logged By: Sheri Stevens

Northing: 323786.3

Easting: 2797889

Requested Northing:

Requested Easting:

Equipment: CME 750 Auger Cuttings

Location Note:

Route: FF

Location: Joplin Davis Boulevard Re-Alignment

Operator: Carmen Hunter

Date of Work: 10/05/23-10/05/23

Depth to Water:

Depth Hole Open:

Time Change:

Drilling Method: Continuous Flight Auger

Depth (ft)	Graphic	Description	Elevation (ft)	Sample Type	REC % (RQD %)	Blow Counts (N ₆₀)	Shear Data	Field Tests	Index Tests
0		0.0-1.9' (CH) Brown sandy CLAY (medium stiff, dry)	 1040						LL = 51 PL = 19 Sieve Analysis Sieve # % Passing #10 73.6 #40 65.4 #200 58.8
5		1.9-5.6' (CH) Red sandy CLAY with fine chert gravel (medium stiff, dry)							
Bottom of borehole at 5.9 feet.									

$N_{60} = (Em/60)N_m$ N_{60} - Corrected N value for standard 60% SPT efficiency; Em - Measured hammer efficiency in percent; Nm - Observed N-value
(1) = Assumed, (2) = Actual

Coordinate System: U.S. State Plane 1983 Coordinate Zone: Missouri West Coordinate Proj. Factor: 1.0000

Coordinate Datum: NAD 83 Coordinate Units: U.S. Survey Feet

* Persons using this information are cautioned that the materials shown are determined by the equipment noted and accuracy of the "log of materials" is limited thereby and by judgement of the operator. THIS INFORMATION IS FOR DESIGN PURPOSES ONLY.

Missouri Department of Transportation
Construction and Materials

BORING NO. B-2
Page 1 of 1

Job No.: 15273-026-01

Design:

Bent:

Station: 103+13.8

Offset: 8.1 LT

Elevation: 1047.5

Requested Station:

Requested Offset:

Requested Elevation:

Drill No.: OWN Engineering

County: Jasper

Skew:

Logged By: Sheri Stevens

Northing: 323848.7

Easting: 2798494.3

Requested Northing:

Requested Easting:

Equipment: CME 750 Auger Cuttings

Location Note:

Route: FF

Location: Joplin Davis Boulevard Re-Alignment

Operator: Carmen Hunter

Date of Work: 10/05/23-10/05/23

Depth to Water:

Depth Hole Open:

Time Change:

Drilling Method: Continuous Flight Auger

Depth (ft)	Graphic	Description	Elevation (ft)	Sample Type	REC % (RQD %)	Blow Counts (N ₆₀)	Shear Data	Field Tests	Index Tests
0									
		0.0-0.8' (CL) Dark brown CLAY with cobbles and gravel (medium stiff, dry)	1045						LL = 48 PL = 23 Sieve Analysis Sieve # % Passing #4 79.9 #10 75.8 #40 70.9 #200 63.7
		0.8-10.0' (CL) Red gravelly CLAY with sand (very stiff, moist)							
5			1040						
10		10.0-31.0' Yellowish tan highly weathered shale, with coarse-grained sand to fine gravel (soft)	1035						
15			1030						
20			1025						
25			1020						
30									
		31.0-35.6' Highly weathered limestone	1015						
35									

$N_{60} = (Em/60)N_m$ N_{60} - Corrected N value for standard 60% SPT efficiency; Em - Measured hammer efficiency in percent; Nm - Observed N-value
(1) = Assumed, (2) = Actual

Coordinate System: U.S. State Plane 1983 Coordinate Zone: Missouri West Coordinate Proj. Factor: 1.0000

Coordinate Datum: NAD 83 Coordinate Units: U.S. Survey Feet

* Persons using this information are cautioned that the materials shown are determined by the equipment noted and accuracy of the "log of materials" is limited thereby and by judgement of the operator. THIS INFORMATION IS FOR DESIGN PURPOSES ONLY.



DATE PREPARED
2/28/2025

ROUTE FF STATE MO
DISTRICT BR SHEET NO. 3

COUNTY JASPER
JOB NO. J7S3059B
CONTRACT ID.

PROJECT NO.

BRIDGE NO. A9696

DESCRIPTION	DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

Bartlett & West

601 MONROE STREET, SUITE 201 - JEFFERSON CITY, MO 65101
PHONE 573-634-3161 - FAX 573-634-7304
CERTIFICATE OF AUTHORITY NO. 000107 - ENGINEERING
WWW.BARTLETTWEST.COM

BORING DATA

Note: For locations of borings, see Sheet No. 1.

Job No.: 15273-026-01

Design:

Bent:

Station: 103+91.6

Offset: 45.1 LT

Elevation: 1041.0

Requested Station:

Requested Offset:

Requested Elevation:

Drill No.: OWN Engineering

Missouri Department of Transportation
Construction and Materials

BORING NO. B-3
Page 1 of 1

County: Jasper

Skew:

Logged By: Sheri Stevens

Northing:

Easting:

Requested Northing:

Requested Easting:

Equipment: CME 750

Location Note:

Hammer Efficiency: 92.3%

Route: FF

Location: Joplin Davis Boulevard Re-Alignment

Operator: Carmen Hunter

Date of Work: 10/05/23-10/05/23

Depth to Water:

Depth Hole Open:

Time Change:

Drilling Method: Continuous Flight Auger

Depth (ft)	Graphic	Description	Elevation (ft)	Sample Type	REC % (RQD %)	Blow Counts (N ₆₀)	Shear Data	Field Tests	Index Tests
0									
		0.0-0.8' (CL-ML) Tan sandy SILT to CLAY (soft, dry)	1040						
		0.8-23.1' Tan and gray mottled highly weathered shale, with coarse-grained sand to fine gravel (soft)							
5			1035						
10			1030						
15			1025						
20			1020						
25		23.1-25.5' Very dark gray to black shale (hard)							
		Bottom of borehole at 25.5 feet							

N₆₀ = (Em/60)N_m N₆₀ - Corrected N value for standard 60% SPT efficiency; Em - Measured hammer efficiency in percent; N_m - Observed N-value
 (1) = Assumed, (2) = Actual

Coordinate System: U.S. State Plane 1983 **Coordinate Zone:** Missouri West **Coordinate Proj. Factor:** 1.0000

Coordinate Datum: NAD 83 **Coordinate Units:** U.S. Survey Feet

* Persons using this information are cautioned that the materials shown are determined by the equipment noted and accuracy of the "log of materials" is limited thereby and by judgement of the operator. THIS INFORMATION IS FOR DESIGN PURPOSES ONLY.

Missouri Department of Transportation
Construction and Materials

BORING NO. B-4
Page 1 of 1

Job No.: 15273-026-01

Design:

Bent:

Station: 103+25.4

Offset: 49.4 RT

Elevation: 1041.0

Requested Station:

Requested Offset:

Requested Elevation:

Drill No.: OWN Engineering

County: Jasper

Skew:

Logged By: Sheri Stevens

Northing:

Easting:

Requested Northing:

Requested Easting:

Equipment: CME 750

Location Note:

Hammer Efficiency: 92.3%

Route: FF

Location: Joplin Davis Boulevard Re-Alignment

Operator: Carmen Hunter

Date of Work: 10/05/23-10/05/23

Depth to Water:

Depth Hole Open:

Time Change:

Drilling Method: Continuous Flight Auger

Depth (ft)	Graphic	Description	Elevation (ft)	Sample Type	REC % (RQD %)	Blow Counts (N ₆₀)	Shear Data	Field Tests	Index Tests
0		0.0-1.0' (CL-ML) Tan sandy SILT to CLAY (soft, dry)	1040						
5		1.0-20.0' Tan and gray mottled highly weathered shale, with coarse-grained sand to fine gravel (soft)	1035						
10			1030						
15			1025						
20		20.0-25.5' Gray shale (medium hard to hard)	1020						
25		Bottom of borehole at 25.5 feet.							

N₆₀ = (Em/60)N_m N₆₀ - Corrected N value for standard 60% SPT efficiency; Em - Measured hammer efficiency in percent; N_m - Observed N-value
 (1) = Assumed, (2) = Actual

Coordinate System: U.S. State Plane 1983 **Coordinate Zone:** Missouri West **Coordinate Proj. Factor:** 1.0000

Coordinate Datum: NAD 83 **Coordinate Units:** U.S. Survey Feet

* Persons using this information are cautioned that the materials shown are determined by the equipment noted and accuracy of the "log of materials" is limited thereby and by judgement of the operator. THIS INFORMATION IS FOR DESIGN PURPOSES ONLY.

[illegible]