

REMOVAL OF IMPROVEMENTS						
ROUTE	LOG MILE	-	LOG MILE	DESCRIPTION	UNITS	TOTAL
BUS 49	2.823	-	3.011	CONCRETE	SY	5294.1
BUS 49	2.823	-	3.011	ASPHALT	SY	1764.7
RAMP 1	0.004	-	0.017	CONCRETE	SY	259.3
RAMP 2	0.130	-	0.147	CONCRETE	SY	259.3
RAMP 3	0.130	-	0.140	CONCRETE	SY	105.6
RAMP 3	0.130	-	0.140	ASPHALT	SY	46.9
RAMP 4	0.004	-	0.015	CONCRETE	SY	116.2
RAMP 4	0.004	-	0.015	ASPHALT	SY	51.6
BUS 49		-		SAW CUT	LF	128.0
RAMP 1		-		SAW CUT	LF	34.0
RAMP 2		-		SAW CUT	LF	26.0
RAMP 3		-		SAW CUT	LF	26.0
RAMP 4		-		SAW CUT	LF	26.0
BUS 49		-		EXISTING SIGN	EACH	1.0
TOTAL					1 LUMP SUM	

TEMPORARY EROSION CONTROL						
LM	LM	ROUTE	LOCATION	SEDIMENT REMOVAL	ROCK DITCH CHECK	REMARKS
				CY	LF	
2.823	3.011	BUS 49	VAR	18	180	
TOTALS				18	180	

1 REVISED

PAVEMENT MARKING REMOVAL			
LM	LM	LF	REMARKS
2.600	2.741	4470.00	BUS 49 LANE LINES
2.741	2.823	2597.76	BUS 49 LANE LINES
2.741	2.823	57.00	BUS 49 HASHBARS
0.177	0.253	1203.84	RTE K LANE LINES
	TOTAL	8328.6	
	USE	8329	

MOBILIZATION
1 LUMP SUM


CONTRACTOR FURNISHED STAKING & SURVEYING
1 LUMP SUM

CONCRETE PAVEMENT REPLACEMENT					
LOCATION	BEGIN LOG MILES	END LOG MILES	9" CONCRETE PAVEMENT	SUBGRADE COMPACTION	6" TYPE 5 AGGREGATE
			S.Y.	STA	S.Y.
BUS 49	2.823	2.842	640.0	0.1	640.0
BUS 49	2.842	2.988	4623.0	8.0	4623.0
BUS 49	2.988	3.011	670.0	1.2	670.0
BUS 49/RAMP 1	0.004	0.017	530.0	0.7	530.0
BUS 49/RAMP 2	0.130	0.147	450.0	0.9	450.0
BUS 49/RAMP 3	0.130	0.140	275.0	0.5	275.0
BUS 49/RAMP 4	0.004	0.015	375.0	0.6	375.0
		TOTAL	7563.0	12.0	7563.0
		USE	7563.0	12.0	7563

TEMPORARY REMOVABLE MARKING TAPE				
BEGIN LOG MILE	END LOG MILE	4" WHITE LF	4" YELLOW LF	REMARKS
2.600	3.011	5803	3173	PHASE 1 BUS 49
0.177	0.253	804	402	PHASE 1 ROUTE K
2.600	3.011	5778	2508	PHASE 2 BUS 49
0.177	0.253	804	402	PHASE 2 ROUTE K
	TOTAL	13189	6485	

1 REVISED

STRIPING/PAVEMENT MARKING														
BEGIN LOG MILE	END LOG MILE	LOCATION	6" WATERBORNE SOLID WHITE STRIPE	6" WATERBORNE INTERMITTENT WHITE STRIPE	12" WATERBORNE DOTTED WHITE STRIPE	12" WATERBORNE SOLID WHITE STRIPE	4" WATERBORNE SOLID YELLOW STRIPE	4" WATERBORNE INTERMITTENT YELLOW STRIPE	6" WATERBORNE SOLID YELLOW STRIPE	RIGHT TURN ARROW	LEFT TURN ARROW	PREFORMED WORD ONLY	12" WHITE YIELD LINE TRIANGLES	24" YELLOW STRIPE
			LF	LF	LF	LF	LF	LF	LF	EA	EA	EA	EA	LF
2.600	2.741	BUS 49 LT/CL/RT	1490.0	1490.0			1490.0	1490.0		2.0	2.0			
2.741	2.775	BUS 49 LT/CL/RT	350.0	31.3	43.8		350.0	87.5		1.0		1.0		
2.775	2.798	BUS 49 LT/CL/RT	250.0	31.3	31.3		500.0					1.0		24.0
2.798	2.842	BUS 49 LT/CL/RT	250.0	56.3		225.0	900.0			2.0		1.0	10.0	60.0
2.842	2.988	BUS 49 LT/CL/RT	1942.0				2060.0				4.0			36.0
0.177	0.253	RTE K LT/CL/RT	800.0				1600.0							48.0
0.004	0.0107	RAMP 1 LT/RT	175.0						100.0					
0.130	0.147	RAMP 2 LT/RT	125.0						100.0					
0.130	0.140	RAMP 3 LT/RT	75.0						60.0					
0.004	0.015	RAMP 4 LT/RT	125.0						100.0					
DISTANCE			5582.0	1608.9	75.1	225.0	6900.0	1577.5	360.0					
TOTAL PAINT			7190.9		300.1		8477.5		360.0	5.0	6.0	3.0	10.0	168.0
USE				7191		301		8478	360	11		3	10	168



DATE PREPARED 5/2/2025	
ROUTE 49	STATE MO
DISTRICT SW	SHEET NO. 3
COUNTY VERNON	
JOB NO. JSR0170	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	

DESCRIPTION									

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

1 REVISED

1 ADDED

