OVERLAY AND BRIDGES (CONT.)

LOG MILE	LOG MILE	LOCATION	LENGTH	SP095CLP WIDTH	SP095C WIDTH	BP-1 LEFT SHOULDER WIDTH	BP-1 RIGHT SHOULDER WIDTH	SP095CLP OVERLAY DEPTH	SP095C OVERLAY DEPTH	BP-1 OVERLAY DEPTH	ASPHALTIC CONCRETE MIX SP095CLP (PG 70-22) 2.064 TONS/CY	ASPHALTIC CONCRETE MIX SP095CLP (PG 76-22) 2.064 TONS/CY	ASPHALTIC CONCRETE MIX SP095C (PG 70-22) 2.064 TONS/CY	ASPHALTIC CONCRETE MIX BP-1 (PG 64-22) 1.948 TONS/CY	TACK COAT - LOW TRACKING TACK (0.10 GAL/SY)	TACK COAT - LOW TRACKING TACK (0.05 GAL/SY)	REMARKS
			LF	LF	LF	LF	LF	IN	IN	IN	TON	TON	TON	TON	GAL	GAL	
19.231	19.284	ROUTE 30	280	32	32	-	-	1.5	1.25	2.75	85.6	-	71.3	-	100	50	
19.284	19.336	ROUTE 30	275	28	28	-	-	1.5	1.25	2.75	73.6	-	61.3	-	86	43	
19.336	19.370	ROUTE 30	180	24	24	-	-	1.5	1.25	2.75	41.3	-	34.4	-	48	24	
19.370	19.495	ROUTE 30	660	28	28	-	-	1.5	1.25	2.75	176.6	-	147.2	-	205	103	
19.495	19.701	ROUTE 30	1088	32	32	-	-	1.5	1.25	2.75	332.7	-	277.2	-	387	193	
19.701	19.839	ROUTE 30	729	28	28	-	-	1.5	1.25	2.75	195.0	-	162.5	-	227	113	
19.839	20.259	ROUTE 30	2218	32	32	-	-	1.5	1.25	2.75	678.2	1 REVISED	565.2	-	789	394	
20.259	20.411	ROUTE 30	803	27	-	8.5	8.5	1.75	-	1.75	-	241.7	-	143.6	393	-	
20.411	20.952	ROUTE 30 EB	2856	27	-	4.5	8.5	1.75	-	1.75	-	859.7	-	390.6	1269	-	
20.411	20.952	ROUTE 30 WB	2856	27	-	8.5	8.5	1.75	-	1.75	-	859.7	-	510.8	1396	-	
20.992	21.325	ROUTE 30 EB	1758	27	-	4.5	8.5	1.75	-	1.75	-	529.2	-	240.5	781	-	
20.992	21.325	ROUTE 30 WB	1758	27	-	8.5	8.5	1.75	-	1.75	-	529.2	-	314.4	859	-	
21.325	21.333	ROUTE 30 EB	42	27	-	8.5	8.5	1.75	-	1.75	-	12.6	-	7.5	42	-	DOUBLE TACK COAT
21.325	21.333	ROUTE 30 WB	42	27	-	8.5	8.5	1.75	-	1.75	-	12.6	-	7.5	42	-	DOUBLE TACK COAT
21.457	27.058	ROUTE 30 EB	29573	27	-	4.5	8.5	1.75	-	1.75	-	8901.5	-	4045.0	13144	-	
21.457	27.058	ROUTE 30 WB	29573	27	-	8.5	8.5	1.75	-	1.75	-	8901.5	-	5289.6	14458	-	
27.115	27.575	ROUTE 30 EB	2429	27	-	4.5	8.5	1.75	-	1.75	-	731.1	-	332.2	1080	-	
27.115	27.575	ROUTE 30 WB	2429	27	-	8.5	8.5	1.75	-	1.75	-	731.1	-	434.5	1188	-	
27.575	27.639	ROUTE 30 EB	338	27	-	4.5	8.5	1.75	-	1.75	-	101.7	-	46.2	300	-	DOUBLE TACK COAT
27.575	27.639	ROUTE 30 WB	338	27	-	8.5	8.5	1.75	-	1.75	-	101.7	-	60.5	330	-	DOUBLE TACK COAT
27.676	27.744	ROUTE 30 EB	359	27	-	4.5	8.5	1.75	-	1.75	-	108.1	-	49.1	320	-	DOUBLE TACK COAT
27.676	27.744	ROUTE 30 WB	359	27	-	8.5	8.5	1.75	-	1.75	-	108.1	-	64.2	352	-	DOUBLE TACK COAT
27.744	31.273	ROUTE 30 EB	18633	27	-	4.5	8.5	1.75	-	1.75	-	5608.5	-	2548.6	8281	-	
27.744	31.392	ROUTE 30 WB	19261	27	-	8.5	8.5	1.75	-	1.75	-	5797.6	-	3445.2	9416	-	
										SUB-TOTALS	1583	34136	1319	17930	55493	920	

OVERLAY AND BRIDGES (INTERSECTIONS)

LOG MILE	LOCATION	AREA	OVERLAY DISTANCE FROM SHOULDER	SP095CLP (PG 70-22) OVERLAY DEPTH	SP095CLP (PG 76-22) OVERLAY DEPTH	SP095C (PG 76-22) OVERLAY DEPTH	BP-1 (PG 64-22) OVERLAY DEPTH	ASPHALTIC CONCRETE MIX SP095CLP (PG 70-22) 2.064 TONS/CY	ASPHALTIC CONCRETE MIX SP095CLP (PG 76-22) 2.064 TONS/CY	ASPHALTIC CONCRETE MIX SP095C (PG 70-22) 2.064 TONS/CY	ASPHALTIC CONCRETE MIX BP-1 (PG 64-22) 1.948 TONS/CY	TACK COAT - LOW TRACKING TACK (0.10 GAL/SY)	TACK COAT - LOW TRACKING TACK (0.05 GAL/SY)	REMARKS
		SY	FT	IN	IN	IN	IN	TON	TON	TON	TON	GAL	GAL	
0	ROUTE 30	903	47	1.5	-	1.25	-	78	-	65	-	90	45	ROUTE WW INTERSECTION
0.235	ROUTE 30	903	47	1.5	-	1.25	-	78	-	65	-	90	45	W GRAVOIS AVE
0.453	ROUTE 30	903	47	1.5	-	1.25	-	78	-	65	-	90	45	E GRAVOIS AVE
0.631	ROUTE 30	110	45	1.5	-	1.25	-	10	-	8	-	11	6	S LAY AVE
0.865	ROUTE 30	82	17	1.5	-	1.25	-	7	-	6	-	8	4	SHADY ST
1.043	ROUTE 30	115	26	1.5	-	1.25	-	10	-	8	-	11	6	WALTON ST
1.161	ROUTE 30	281	43	1.5	-	1.25	-	24	-	20	-	28	14	HIGH SCHOOL DR
1.585	ROUTE 30	115	25	1.5	-	1.25	-	10	-	8	-	12	6	VILLAGE CT
1.817	ROUTE 30	352	51	1.5	-	1.25	-	30	-	25	-	35	18	PARKWAY DR
1.917	ROUTE 30	116	17	1.5	-	1.25	-	10	-	8	-	12	6	EXPANSION LN
3.263	ROUTE 30	1750		1.5	-	1.25	-	151	-	125	-	175	88	POND FORD RD
6.657	ROUTE 30	903	45	1.5	-	1.25	-	78	-	65	-	90	45	RIVER BEND RD
6.657	ROUTE 30	1104	107	1.5	-	1.25	-	95	-	79	-	110	55	ROUTE 47
7.092	ROUTE 30	98	20	1.5	-	1.25	-	8	-	7	-	10	5	N BETHEL CHURCH RD
7.092	ROUTE 30	90	88	1.5	-	1.25	-	8	-	7	-	9	5	S BETHEL CHURCH RD
9.259	ROUTE 30	106	33	1.5	-	1.25	-	9	-	8	-	11	5	OAK GROVE CHURCH RD
9.92	ROUTE 30	201	28	2.5	-	2.25	-	29	-	26	-	20	10	ROUTE FF
11.428	ROUTE 30	149	36	1.5	-	1.25	-	13	-	11	-	15	7	N HENDRICKS RD
13.591	ROUTE 30	115	26	1.5	-	1.25	-	10	-	8	-	12	6	COUNTY LINE RD
14.442	ROUTE 30	267	37	1.5	-	1.25	-	23	-	19	-	27	13	ZIMMERMAN RD
14.674	ROUTE 30	137	13	1.5	-	1.25	-	12	-	10	-	14	7	JONES CREEK RD
15.832	ROUTE 30	217	45	1.5	-	1.25	-	19	-	16	-	22	11	OERMANN RD
16.504	ROUTE 30	156	37	1.5	-	1.25	-	14	-	11	-	16	8	RIDGE RD
17.68	ROUTE 30	412	230	1.5	-	1.25	-	36	-	30	-	41	21	TOWNSHIP LN
18.53	ROUTE 30	234	38	1.5	-	1.25	-	20	-	1	-	23	12	N DITMER RIDGE RD
18.53	ROUTE 30	213	28	1.5	-	1.25	-	18	-	15	-	21	11	S DIRMER RIDGE RD
							SUB-TOTALS	875	0	715	0	1003	504	

DISCLAIMER
THE PROFESSIONAL WHOSE SIGNATURE AND PERSONAL SEAL APPEARS HERON ASSUMES RESPONSIBILITY ONLY FOR WHAT APPEARS ON THIS PAGE, AND DISCLAIMS (PURSUANT TO SECTION 327.411 RSMO) SPECIFICATION, ESTIMATES, REPORTS, OR OTHER DOCUMENTS OR INSTRUMENTS NOT SEALED BY THE UNDERSIGNED PROFESSIONAL RELATING TO OR INTENDED TO BE USED FOR ANY PART OR PARTS OF THE PROJECT TO WHICH THIS PAGE REFERS.

SUMMARY OF QUANTITIES
SHEET 5 OF 12

STATE OF MISSOURI
KYLE BAUMANN
NUMBER PE-2023026580
PROFESSIONAL ENGINEER

05/06/2025 11:42:39 AM
Kyle Baumann - Civil
MO PE-2023026580

DATE PREPARED
6-MAY-2025

ROUTE	STATE
30	MO
DISTRICT	SHEET NO.
SL	3

COUNTY
FRANKLIN/ JEFFERSON

JOB NO.
J6S3435

CONTRACT ID.
.

PROJECT NO.
.

BRIDGE NO.
.

DESCRIPTION	DATE
ADDENDUM 1	5/6/25

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

Jacobs
JACOBS ENGINEERING GROUP
501 NORTH BROADWAY
ST.LOUIS, MISSOURI 63102-2121
PHONE: (314) 335-4000
CERTIFICATE OF AUTHORITY #00704

OVERLAY AND BRIDGES (INTERSECTIONS)

LOG MILE	LOCATION	AREA	OVERLAY DISTANCE FROM SHOULDER	SP095CLP (PG 70-22) OVERLAY DEPTH	SP095CLP (PG 76-22) OVERLAY DEPTH	SP095C (PG 76-22) OVERLAY DEPTH	BP-1 (PG 64-22) OVERLAY DEPTH	ASPHALTIC CONCRETE MIX SP095CLP (PG 70-22) 2.064 TONS/CY	ASPHALTIC CONCRETE MIX SP095CLP (PG 76-22) 2.064 TONS/CY	ASPHALTIC CONCRETE MIX SP095C (PG 70-22) 2.064 TONS/CY	ASPHALTIC CONCRETE MIX BP-1 (PG 64-22) 1.948 TONS/CY	TACK COAT - LOW TRACKING TACK (0.10 GAL/SY)	TACK COAT - LOW TRACKING TACK (0.05 GAL/SY)	REMARKS
		SY	FT	IN	IN	IN	IN	TON	TON	TON	TON	GAL	GAL	
19.851	ROUTE 30	150	37	1.5	-	1.25	-	13	-	11	-	15	7	DITMER RD
19.851	ROUTE 30	253	29	1.5	-	1.25	-	22	-	18	-	25	13	FICKEN RD
20.816	ROUTE 30	15987	-	-	1.75	-	-	-	1604	-	-	1599	-	ROUTE NN/B
20.816	ROUTE 30	2856	-	-	-	-	1.75	-	-	-	270	286	-	ROUTE NN/B
21.508	ROUTE 30	8927	-	-	1.75	-	-	-	896	-	-	893	-	S INDUSTRIAL DR
21.508	ROUTE 30	3095	-	-	-	-	1.75	-	-	-	293	309	-	S INDUSTRIAL DR
21.846	ROUTE 30	15987	-	-	1.75	-	-	-	1604	-	-	1599	-	INDUSTRIAL DRIVE/ROUTE BB
21.846	ROUTE 30	2856	-	-	-	-	1.75	-	-	-	270	286	-	INDUSTRIAL DRIVE/ROUTE BB
22.149	ROUTE 30	8927	-	-	1.75	-	-	-	896	-	-	893	-	THE CEDARS CT
22.149	ROUTE 30	3095	-	-	-	-	1.75	-	-	-	293	309	-	THE CEDARS CT
22.692	ROUTE 30	8927	-	-	1.75	-	-	-	896	-	-	893	-	CEDAR SPRINGS RD
22.692	ROUTE 30	3095	-	-	-	-	1.75	-	-	-	293	309	-	CEDAR SPRINGS RD
23.16	ROUTE 30	8927	-	-	1.75	-	-	-	896	-	-	893	-	SILVER LN/GILEAD DR
23.16	ROUTE 30	3095	-	-	-	-	1.75	-	-	-	293	309	-	SILVER LN/GILEAD DR
23.359	ROUTE 30	8927	-	-	1.75	-	-	-	896	-	-	893	-	LOCAL HILLSBORO RD
23.359	ROUTE 30	3095	-	-	-	-	1.75	-	-	-	293	309	-	LOCAL HILLSBORO RD
23.887	ROUTE 30	14893	-	-	1.75	-	-	-	1494	-	-	1489	-	GRAVOIS RD
23.887	ROUTE 30	4008	-	-	-	-	1.75	-	-	-	380	401	-	GRAVOIS RD
24.211	ROUTE 30	14893	-	-	1.75	-	-	-	1494	-	-	1489	-	CEDAR HILL RD
24.211	ROUTE 30	4008	-	-	-	-	1.75	-	-	-	380	401	-	CEDAR HILL RD
24.477	ROUTE 30	8927	-	-	1.75	-	-	-	896	-	-	893	-	SCENIC VIEW LN
24.477	ROUTE 30	3095	-	-	-	-	1.75	-	-	-	293	309	-	SCENIC VIEW LN
25.411	ROUTE 30	8927	-	-	1.75	-	-	-	896	-	-	893	-	WINDCREST DR/EXECUTIVE PKWY
25.411	ROUTE 30	3095	-	-	-	-	1.75	-	-	-	293	309	-	WINDCREST DR/EXECUTIVE PKWY
26.572	ROUTE 30	3941	-	-	1.75	-	-	-	395	-	-	394	-	WEST OF RIVERMONT TRAIL/SCOTSDALE RD
26.705	ROUTE 30	4184	-	-	1.75	-	-	-	420	-	-	418	-	SCOTSDALE BLVD
26.705	ROUTE 30	785	-	-	-	-	1.75	-	-	-	74	79	-	SCOTSDALE BLVD
26.819	ROUTE 30	3941	-	-	1.75	-	-	-	396	-	-	394	-	EAST OF RIVERMONT TRAIL/SCOTSDALE RD
26.873	ROUTE 30	8927	-	-	1.75	-	-	-	896	-	-	893	-	CONRAD SMITH DR
26.873	ROUTE 30	3095	-	-	-	-	1.75	-	-	-	293	309	-	CONRAD SMITH DR
27.044	ROUTE 30	8927	-	-	1.75	-	-	-	896	-	-	893	-	MORNINGSIDE DR
27.044	ROUTE 30	3095	-	-	-	-	1.75	-	-	-	293	310	-	MORNINGSIDE DR
27.465	ROUTE 30	15987	-	-	1.75	-	-	-	1604	-	-	1599	-	ROUTE W/ROUTE MM
27.465	ROUTE 30	2856	-	-	-	-	1.75	-	-	-	270	286	-	ROUTE W/ROUTE MM
27.854	ROUTE 30	14893	-	-	1.75	-	-	-	1494	-	-	1489	-	LOWER BYRNES MILL RD/INDIAN SPRINGS RD
27.854	ROUTE 30	3764	-	-	-	-	1.75	-	-	-	356	376	-	LOWER BYRNES MILL RD/INDIAN SPRINGS RD
29.284	ROUTE 30	3941	-	-	1.75	-	-	-	396	-	-	394	-	WEST OF UPPER BYRNES MILL RD
29.605	ROUTE 30	8927	-	-	1.75	-	-	-	896	-	-	893	-	UPPER BYRNES MILL RD/OSAGE EXECUTIVE CIR
29.605	ROUTE 30	3095	-	-	-	-	1.75	-	-	-	293	309	-	UPPER BYRNES MILL RD/OSAGE EXECUTIVE CIR
29.881	ROUTE 30	3941	-	-	1.75	-	-	-	396	-	-	394	-	EAST OF UPPER BYRNES MILL RD
30.041	ROUTE 30	15987	-	-	1.75	-	-	-	1604	-	-	1599	-	GRAVOIS RD
30.041	ROUTE 30	2856	-	-	-	-	1.75	-	-	-	270	286	-	GRAVOIS RD
30.638	ROUTE 30	8927	-	-	1.75	-	-	-	896	-	-	893	-	CAROL PARK RD
30.638	ROUTE 30	3095	-	-	-		1.75	-	-	-	293	309	-	CAROL PARK RD
30.996	ROUTE 30	8927	-	-	1.75	-	-	-	896	-	-	893	-	OTTOMEYER RD
30.996	ROUTE 30	3095	-	-	-	-	1.75	-	-	-	293	309	-	OTTOMEYER RD
							SUB-TOTALS	35	23649	29	5787	29723	20	
							TOTALS	28113	57785	23413	33624	139014		
							PAY TOTALS	29520	60680	24590	35310	139020		INCLUDES 5% INCREASE FOR IRREGULARITIES

1 REVISED

DISCLAIMER

THE PROFESSIONAL WHOSE SIGNATURE AND PERSONAL SEAL APPEAR HEREON ASSUMES RESPONSIBILITY ONLY FOR WHAT APPEARS ON THIS PAGE, AND DISCLAIMS (PURSUANT TO SECTION 327.411 RSMO) SPECIFICATION, ESTIMATES, REPORTS, OR OTHER DOCUMENTS OR INSTRUMENTS NOT SEALED BY THE UNDERSIGNED PROFESSIONAL RELATING TO OR INTENDED TO BE USED FOR ANY PART OR PARTS OF THE PROJECT TO WHICH THIS PAGE REFERS.

SUMMARY OF QUANTITIES
SHEET 6 OF 12

STATE OF MISSOURI
KYLE BAUMANN
NUMBER
PE-2023026580
PROFESSIONAL ENGINEER

05/06/2025 11:43:00 AM
Kyle Baumann - Civil
MO PE-2023026580

DATE PREPARED
6-MAY-2025

ROUTE	STATE
30	MO
DISTRICT	SHEET NO.
SL	3

COUNTY
FRANKLIN/JEFFERSON

JOB NO.
J6S3435

CONTRACT ID.
.

PROJECT NO.
.

BRIDGE NO.
.

DATE	DESCRIPTION
5/6/25	ADDENDUM 1

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

Jacobs
JACOBS ENGINEERING GROUP
501 NORTH BROADWAY
ST.LOUIS, MISSOURI 63102-2121
PHONE: (314) 335-4000
CERTIFICATE OF AUTHORITY #00704