

REMOVAL OF IMPROVEMENTS			
LOCATIONS	QUANTITIES	UNITS	REMARKS
US169 NB	80	LF	SAW CUT BEG. AND END OF PVM'T.(MILL & FILL 50' & APPR. PVM'T EACH SIDE OF BR. A3345)
US169 NB	80	LF	SAW CUT BEG. AND END OF PVM'T.(MILL & FILL 50' & APPR. PVM'T EACH SIDE OF BR. A3333)
FINAL TOTAL	1	LS	

PAVING QUANTITIES								
BEG. LOG MILE	END LOG MILE	LOCATION	WIDTH LF	EX. SHLDR RT & LT LF	COLDMILLING SQYD	MAIN LANE & SHLDR 1.5" SP125BSM TONS	TACK COAT GAL	REMARKS
14.908	14.921	US169 NB , SOUTH OF BRIDGE A3345	24	16	288.89	23.88	28.89	BEG. OF PROJECT
14.921	14.960	A3345 & BRIDGE APPROACH SLAB						BRIDGE & APPROACH SLAB EXCEPTION-A3345
14.960	14.973	US169 NB, NORTH OF BRIDGE A3345	24	16	288.89	23.88	28.89	
15.298	15.311	US169 NB, SOUTH OF BRIDGE A3333	24	16	298.33	24.66	29.83	
15.311	15.374	A3333 & BRIDGE APPROACH SLAB						BRIDGE & APPROACH SLAB EXCEPTION-A3333
15.374	15.387	US169 NB, NORTH OF BRIDGE A3333	24	16	298.33	24.66	29.83	END OF PROJECT
TOTAL					1174.44	97.08	117.44	
FINAL TOTAL					1174.50	97.10	118.00	

DITCH CLEANOUT					
LOG MILE	LOG MILE	LENGTH	LOCATIONS	DITCH CLEANOUT LF	REMARKS
4.800	4.950	792.00	NE COOKINGHAM DR	792.00	EB & WB ALONG CONC. SLOPE PROTECTION OF EX. BRIDGE A3345
20.520	20.650	686.40	I-435 EB	686.40	EB ALONG CONC. SLOPE PROTECTION OF EX. BRIDGE A3333
34.600	34.740	739.20	I-435 WB	739.20	WB ALONG CONC. SLOPE PROTECTION OF EX. BRIDGE A3333
TOTAL				1478.40	
FINAL TOTAL				1480.00	

SEEDING AND EROSION CONTROL BLANKET							
LOG MILE	LOG MILE	LENGTH LF	WIDTH LF	LOCATIONS	SEEDING COOL SEAS. GRASSES ACRE	TYPE 1A ECB SY	REMARKS
4.800	4.950	792.00	10.00	NE COOKINGHAM DR	0.36	1760.00	EB & WB ALONG CONC. SLOPE PROTECTION OF EX. BRIDGE A3345
20.520	20.650	686.40	10.00	I-435 EB	0.16	762.67	EB ALONG CONC. SLOPE PROTECTION OF EX. BRIDGE A3333
34.600	34.740	739.20	10.00	I-435 WB	0.17	821.33	WB ALONG CONC. SLOPE PROTECTION OF EX. BRIDGE A3333
TOTAL					0.69	3344.00	
FINAL TOTAL					0.70	3344.00	


ROCK BLANKET SLOPE PROTECTION						
LOCATION	LENGTH LF	WIDTH LF	SEPARATION GEOTEXTILE SQYD	FURNISHING TYPE 1 RCK. BLANKET CUYD	PLACING TYPE 1 RCK. BLANKET CUYD	COMMENTS
TOP OF EX. CONC. SLOPE PROTECTION(NORTH SIDE)	37.00	17.00	69.89	46.59	46.59	SLOPE PROTECTION BETWEEN BRIDGE A3333 & A3334
FINAL TOTAL			70.00	47.00	47.00	

PAVEMENT MARKINGS							
BEG. LOG	END LOG	LENGTH LF	6" YELLOW WATERBORNE PAINT WITH TYPE L BEADS LF	6" INTERMITTENT WHITE WATERBORNE PAINT WITH TYPE L BEADS LF	3' DOTTED WHITE WATERBORNE PAINT WITH TYPE L BEADS LF	6" WHITE WATERBORNE PAINT WITH TYPE L BEADS LF	COMMENTS
13.755	15.387	8616.96		2154.24			ROUTE 169 NB
14.320	14.480	844.80			633.60		ROUTE 169 NB
14.908	15.387	2529.12	2529.12			2529.12	ROUTE 169 NB
TOTAL			2529.12	2154.24	633.60	2529.12	
FINAL TOTAL			2530.00	5317.00			

TEMP. MARKING AND REMOVAL OF PAVEMENT MARKINGS							
BEG. LOG	END LOG	LENGTH LF	4" TEMP. REMOVABLE MARKING TAPE YELLOW LF	4" TEMP. REMOVABLE MARKING TAPE, YELLOW REMOVAL LF	INTERMITTENT WHITE PVM'T. MARKING REMOVAL LF	DOTTED WHITE PVM'T. MARKING REMOVAL LF	COMMENTS
13.755	14.395	3379.20			844.80		ROUTE 169 NB
14.320	14.480	844.80				633.60	ROUTE 169 NB
13.755	14.395	3379.20	3379.20	3379.20			ROUTE 169 NB
TOTAL			3379.20	3379.20	844.80	633.60	
FINAL TOTAL			3380.00	4858.00			

PERMANENT AGGREGATE EDGE TREATMENT				
BEG. LOG MILE	END LOGMILE	LENGTH LF	PERM. AGGR. EDGE TREATMENT TYPE 1 OR 5 AGGR. TON	REMARKS
14.908	14.921	68.64	3.18	BEG. OF PROJECT
14.921	14.96			BRIDGE EXCEPTION A3345
14.960	14.973	68.64	3.18	
15.298	15.311	68.64	3.18	
15.311	15.374			BRIDGE EXCEPTION A3333
15.374	15.387	68.64	3.18	END OF PROJECT
TOTAL		274.56	12.72	
FINAL TOTAL			12.80	

MOBILIZATION
1 LUMP SUM



DATE PREPARED
5/9/2025

ROUTE 169	STATE MO
DISTRICT KC	SHEET NO. 3

COUNTY
CLAY

JOB NO.
JKU0039

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION	DATE								

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)