

COLDMILLING (3 IN. OR LESS)								
LOG MILE	LOG MILE	LOCATION	MILL DEPTH	LENGTH	TRAVELED WAY WIDTH	LEFT SHOULDER WIDTH	RIGHT SHOULDER WIDTH	AREA
			IN	FT	FT	FT	FT	SY
0.010	0.029	ROUTE 30	2.75	100	24	8	8	446
0.060	0.214	ROUTE 31	3.75	813	24	8	8	3614
0.253	0.434	ROUTE 30	2.75	956	22	6	6	3610
0.470	0.521	ROUTE 30	2.75	269	38	6	6	1496
0.567	0.803	ROUTE 30	2.75	1246	38	6	6	6923
0.803	0.933	ROUTE 30	2.75	686	39	5.5	6	3851
0.933	0.975	ROUTE 30	2.75	222	38	6	6	1232
0.975	1.156	ROUTE 30	2.75	956	33	1	1	3717
1.156	1.174	ROUTE 30	2.75	95	38	6	6	528
1.174	1.227	ROUTE 30	2.75	280	28	-	4	995
1.227	3.459	ROUTE 30	2.75	11785	24	6	6	47140
3.459	4.474	ROUTE 30	2.75	5359	-	8.5	6	8634
4.653	4.920	ROUTE 30	2.75	1410	-	8.5	6	2271
4.920	6.256	ROUTE 30	2.75	7054	24	6	6	28216
6.256	6.555	ROUTE 30	2.75	1579	24	-	6	5262
6.555	8.337	ROUTE 30	2.75	9409	24	6	6	37636
9.160	9.656	ROUTE 30	2.75	2619	24	6	6	10476
9.656	9.817	ROUTE 30	2.75	850	24	6	-	2834
9.817	9.929	ROUTE 30	2.75	591	24	6	6	2365
9.929	9.965	ROUTE 30	2.75	190	24	6	-	634
9.965	10.826	ROUTE 30	2.75	4546	24	6	6	18184
10.826	10.902	ROUTE 30	2.75	401	24	-	6	1338
10.902	11.447	ROUTE 30	2.75	2878	24	6	6	11510
11.447	11.535	ROUTE 30	2.75	465	24	6	-	1549
11.535	11.793	ROUTE 30	2.75	1362	24	6	6	5449
11.793	11.892	ROUTE 30	2.75	523	24	-	-	1394
11.892	12.685	ROUTE 30	2.75	4187	24	6	6	16748
12.685	12.859	ROUTE 30	2.75	919	24	-	6	3062
12.859	12.915	ROUTE 30	2.75	296	24	6	6	1183
12.915	12.984	ROUTE 30	2.75	364	24	6	-	1214
12.984	13.351	ROUTE 30	2.75	1938	24	6	6	7751
13.351	13.427	ROUTE 30	2.75	401	24	6	-	1338
13.427	13.559	ROUTE 30	2.75	697	24	6	6	2788
13.559	13.657	ROUTE 30	2.75	517	24	4	4	1840
13.657	13.672	ROUTE 30	2.75	79	24	-	4	246
13.672	13.723	ROUTE 30	2.75	269	24	-	-	718
13.723	13.804	ROUTE 30	2.75	428	24	-	4	1331
13.804	13.945	ROUTE 30	2.75	744	24	4	4	2647
13.945	13.980	ROUTE 30	2.75	185	24	-	4	575
13.980	14.157	ROUTE 30	2.75	935	24	-	-	2492
14.157	14.211	ROUTE 30	2.75	285	24	-	4	887
14.211	14.306	ROUTE 30	2.75	502	24	4	4	1783
14.306	14.324	ROUTE 30	2.75	95	24	-	4	296
14.324	14.369	ROUTE 30	2.75	238	24	-	-	634
14.369	14.425	ROUTE 30	2.75	296	31	-	4	1150
14.425	14.528	ROUTE 30	2.75	544	30	4	4	2296
14.528	14.590	ROUTE 30	2.75	327	31	-	4	1273
14.590	14.654	ROUTE 30	2.75	338	30	4	4	1427
SUB-TOTAL								264983

HIGH FRICTION SURFACE TREATMENT		
LOG MILE	LOG MILE	HIGH FRICTION SURFACE TREATMENT-BAUXITE
		SY
6.158	6.482	4562

DISCLAIMER
THE PROFESSIONAL WHOSE SIGNATURE AND PERSONAL SEAL APPEAR HEREON ASSUMES RESPONSIBILITY ONLY FOR WHAT APPEARS ON THIS PAGE, AND DISCLAIMS (PURSUANT TO SECTION 327.411 RSMO) SPECIFICATION, ESTIMATES, REPORTS, OR OTHER DOCUMENTS OR INSTRUMENTS NOT SEALED BY THE UNDERSIGNED PROFESSIONAL RELATING TO OR INTENDED TO BE USED FOR ANY PART OR PARTS OF THE PROJECT TO WHICH THIS PAGE REFERS.

COLDMILLING (3 IN. OR LESS) (CONT.)								
LOG MILE	LOG MILE	LOCATION	MILL DEPTH	LENGTH	TRAVELED WAY WIDTH	LEFT SHOULDER WIDTH	RIGHT SHOULDER WIDTH	AREA
			IN	FT	FT	FT	FT	SY
14.654	14.687	ROUTE 30	2.75	174	24	-	4	542
14.687	14.741	ROUTE 30	2.75	285	24	-	-	760
14.741	14.764	ROUTE 30	2.75	121	24	4	-	378
14.764	14.853	ROUTE 30	2.75	470	24	4	4	1671
14.853	14.974	ROUTE 30	2.75	639	24	4	-	1988
14.974	15.056	ROUTE 30	2.75	433	24	-	-	1155
15.056	15.063	ROUTE 30	2.75	37	24	4	-	115
15.063	15.247	ROUTE 30	2.75	972	24	4	4	3454
15.247	15.554	ROUTE 30	2.75	1621	24	4	-	5043
15.554	15.657	ROUTE 30	2.75	544	24	4	4	1934
15.657	15.793	ROUTE 30	2.75	718	24	4	-	2234
15.793	15.958	ROUTE 30	2.75	871	24	4	4	3098
15.958	15.967	ROUTE 30	2.75	48	24	4	-	148
15.967	16.018	ROUTE 30	2.75	269	24	-	-	718
16.018	16.024	ROUTE 30	2.75	32	24	4	-	99
16.024	16.112	ROUTE 30	2.75	465	24	4	4	1652
16.122	16.150	ROUTE 30	2.75	148	24	-	4	460
16.150	16.211	ROUTE 30	2.75	322	24	-	-	859
16.211	16.215	ROUTE 30	2.75	21	24	4	-	66
16.215	16.270	ROUTE 30	2.75	290	24	4	4	1033
16.270	16.289	ROUTE 30	2.75	100	24	-	4	312
16.289	16.334	ROUTE 30	2.75	238	24	-	-	634
16.334	16.345	ROUTE 30	2.75	58	24	4	-	181
16.345	16.377	ROUTE 30	2.75	169	24	4	4	601
16.377	16.389	ROUTE 30	2.75	63	24	-	4	197
16.389	16.436	ROUTE 30	2.75	248	24	-	-	662
16.436	16.501	ROUTE 30	2.75	343	24	4	4	1220
16.501	16.639	ROUTE 30	2.75	729	24	-	-	1943
16.639	16.900	ROUTE 30	2.75	1378	24	4	4	4900
16.900	16.958	ROUTE 30	2.75	306	24	-	4	953
16.958	16.996	ROUTE 30	2.75	201	24	4	4	713
16.966	17.039	ROUTE 30	2.75	385	24	4	-	1199
17.039	17.120	ROUTE 30	2.75	428	24	4	4	1521
17.120	17.185	ROUTE 30	2.75	343	24	-	-	915
17.185	17.294	ROUTE 30	2.75	576	24	4	4	2046
17.294	17.426	ROUTE 30	2.75	697	24	4	-	2168
17.426	17.631	ROUTE 30	2.75	1082	24	4	4	3849
17.631	17.714	ROUTE 30	2.75	438	24	4	-	1363
17.714	17.793	ROUTE 30	2.75	417	24	4	4	1483
17.793	17.888	ROUTE 30	2.75	502	24	4	-	1561
17.888	18.173	ROUTE 30	2.75	1505	24	4	4	5350
18.173	18.242	ROUTE 30	2.75	364	24	-	4	1133
18.242	18.288	ROUTE 30	2.75	243	24	4	4	864
18.288	18.298	ROUTE 30	2.75	53	24	-	4	164
18.298	18.329	ROUTE 30	2.75	164	24	-	-	436
18.329	18.337	ROUTE 30	2.75	42	24	4	-	131
18.337	18.477	ROUTE 30	2.75	739	24	4	4	2628
SUB-TOTAL								66534

COLDMILLING (3 IN. OR LESS) (CONT.)								
LOG MILE	LOG MILE	LOCATION	MILL DEPTH	LENGTH	TRAVELED WAY WIDTH	LEFT SHOULDER WIDTH	RIGHT SHOULDER WIDTH	AREA
			IN	FT	FT	FT	FT	SY
18.477	18.489	ROUTE 30	2.75	63	24	4	-	197
18.489	18.518	ROUTE 30	2.75	153	24	-	-	408
18.518	18.530	ROUTE 30	2.75	63	24	-	4	197
18.530	18.601	ROUTE 30	2.75	375	24	4	4	1333
18.601	18.650	ROUTE 30	2.75	259	24	-	4	805
18.650	18.686	ROUTE 30	2.75	190	24	-	-	507
18.686	18.707	ROUTE 30	2.75	111	24	4	-	345
18.707	18.975	ROUTE 30	2.75	1415	24	4	4	5031
18.975	19.028	ROUTE 30	2.75	280	24	4	-	871
19.028	19.071	ROUTE 30	2.75	227	24	-	-	605
19.071	19.090	ROUTE 30	2.75	100	24	4	-	312
19.090	19.149	ROUTE 30	2.75	312	24	4	4	1108
19.149	19.231	ROUTE 30	2.75	433	24	4	-	1347
19.231	19.284	ROUTE 30	2.75	280	24	4	4	995
19.284	19.336	ROUTE 30	2.75	275	24	4	-	854
19.336	19.370	ROUTE 30	2.75	180	24	-	-	479
19.370	19.495	ROUTE 30	2.75	660	24	4	-	2053
19.495	19.701	ROUTE 30	2.75	1088	24	4	4	3867
19.701	19.839	ROUTE 30	2.75	729	24	-	4	2267
19.839	20.259	ROUTE 30	2.75	2218	24	4	4	7885
21.325	21.333	ROUTE 30 EB	1.75	42	24	6	10	188
21.325	21.333	ROUTE 30 WB	1.75	42	24	10	10	207
27.575	27.639	ROUTE 30 EB	1.75	338	24	6	10	1502
27.575	27.639	ROUTE 30 WB	1.75	338	24	10	10	1652
27.676	27.744	ROUTE 30 EB	1.75	359	24	6	10	1596
27.676	27.744	ROUTE 30 WB	1.75	359	24	10	10	1755
SUB-TOTAL								38366
TOTAL								369883

MOBILIZATION		
TOTAL	1	LUMP SUM

CONTRACTOR FURNISHED SURVEYING AND STAKING		
TOTAL	1	LUMP SUM

TEMPORARY PAVEMENT MARKING PAINT		
TOTAL	1	LUMP SUM

SUMMARY OF
QUANTITIES
SHEET 1 OF 13



Kyle Baumann

05/27/2025 1:01:30 PM
Kyle Baumann - Civil
MO PE-2023026580

DATE PREPARED
27 -MAY -2025

ROUTE 30	STATE MO
DISTRICT SL	SHEET NO. 3

COUNTY
FRANKLIN /
JEFFERSON

JOB NO.
J6S3435

CONTRACT ID.
.

PROJECT NO.
.

BRIDGE NO.
.

DESCRIPTION	DATE
.	.
.	.
.	.
.	.
.	.
.	.
.	.

MISSOURI HIGHWAYS AND TRANSPORTATION
COMMISSION




105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

FULL DEPTH PAVEMENT REPAIR (CONT)										
REPAIR NUMBER	DIRECTION	LANE	LENGTH	WIDTH	FURNISHING AND PLACING CONCRETE MATERIAL FOR FULL DEPTH PAVEMENT REPAIR	TYPE 1 OR TYPE 5 AGGREGATE FOR BASE (4 IN. THICK) (PAVEMENT REPAIR)	DOWEL BAR (DRILLING) FOR FULL DEPTH PAVEMENT REPAIR	DOWEL BAR (W/ BASKET) FOR FULL DEPTH PAVEMENT REPAIR	SAWCUT	REMARKS
			FT	FT	SY	SY	EA	EA	LF	
238	EB	1	6	12	8.0	8	20	10	36	
239	EB	2	6	12	8.0	8	20	10	36	
240	EB	1	6	12	8.0	8	20	10	36	
241	EB	2	6	12	8.0	8	20	10	36	LOCAL HILLSBORO RD
242	EB	1	6	12	8.0	8	20	10	36	
243	EB	2	6	12	8.0	8	20	10	36	
244	EB	1	6	12	8.0	8	20	10	36	
245	EB	2	6	12	8.0	8	20	10	36	
246	EB	1	6	12	8.0	8	20	10	36	
247	EB	2	6	12	8.0	8	20	10	36	
248	EB	1	6	12	8.0	8	20	10	36	
249	EB	2	6	12	8.0	8	20	10	36	
250	EB	2	6	12	8.0	8	20	10	36	
251	EB	2	6	12	8.0	8	20	10	36	
252	EB	2	6	12	8.0	8	20	10	36	
253	EB	2	6	12	8.0	8	20	10	36	ROUTE MM
254	EB	2	6	12	8.0	8	20	10	36	
255	EB	1	6	12	8.0	8	20	10	36	
256	EB	2	6	12	8.0	8	20	10	36	
257	EB	2	12	12	16.0	16	20	10	48	ROUTE PP
258	WB	2	6	12	8.0	8	20	10	36	
259	WB	1	6	12	8.0	8	20	10	36	
260	WB	2	6	12	8.0	8	20	10	36	
261	WB	1	6	12	8.0	8	20	10	36	
262	WB	2	6	12	8.0	8	20	10	36	
263	WB	1	6	12	8.0	8	20	10	36	
264	WB	2	6	12	8.0	8	20	10	36	ROUTE MM
265	WB	1	12	12	16.0	16	20	10	48	
266	WB	1	17	12	22.7	23	20	10	58	
267	WB	2	15	12	20.0	20	20	10	54	
268	WB	2	6	12	8.0	8	20	10	36	
269	WB	2	6	12	8.0	8	20	10	36	
270	WB	1	6	12	8.0	8	20	10	36	
271	WB	2	6	12	8.0	8	20	10	36	LOCAL HILLSBORO RD
272	WB	2	6	12	8.0	8	20	10	36	
273	WB	2	6	12	8.0	8	20	10	36	
274	WB	1	10	12	13.3	13	20	10	44	
275	WB	2	10	12	13.3	13	20	10	44	
SUB-TOTALS					357.3	357	760	380	1448	
TOTALS					2828.6	2829	5430	2900	11930	
NOTE: SUBGRADE COMPACTION SHALL BE CONSIDERED INCIDENTAL.										

PERMANENT PAVEMENT MARKINGS										
	4 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	6 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	6 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	24 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	PREFORMED THERMOPLASTIC PAVEMENT MARKING, LEFT/RIGHT ARROW	PREFORMED THERMOPLASTIC PAVEMENT MARKING, COMBINATION ST/LT/RT	PREFORMED THERMOPLASTIC PAVEMENT MARKING, WORD (ONLY)	PREFORMED THERMOPLASTIC PAVEMENT MARKING, LANE REDUCTION ARROW	PREFORMED THERMOPLASTIC PAVEMENT MARKING 12 IN. WHITE, YIELD LINE TRIANGLES
	LF	LF	LF	LF	LF	EACH	EACH	EACH	EACH	EACH
TOTAL	172870	406029	114690	1203	1090	157	23	14	6	164

DISCLAIMER
THE PROFESSIONAL WHOSE SIGNATURE AND PERSONAL SEAL APPEAR HEREON ASSUMES RESPONSIBILITY ONLY FOR WHAT APPEARS ON THIS PAGE, AND DISCLAIMS (PURSUANT TO SECTION 327.411 RSMO) SPECIFICATION, ESTIMATES, REPORTS, OR OTHER DOCUMENTS OR INSTRUMENTS NOT SEALED BY THE UNDERSIGNED PROFESSIONAL RELATING TO OR INTENDED TO BE USED FOR ANY PART OR PARTS OF THE PROJECT TO WHICH THIS PAGE REFERS.

TRAFFIC SIGNAL LOOP DETECTORS			
LOG MILE	INTERSECTION	CABLE, LOOP DETECTOR IN DUCT	REMARKS
		LF	
21.846	INDUSTRIAL DR/RTE BB	3054	10 DETECTORS (30' X 6 ' LOOPS)
23.359	LOCAL HILLSBORO RD	592	2 DETECTORS (ONLY SIDE STREETS) (30' X 6 ' LOOPS)
27.465	RTE W/RTE MM	1384	4 DETECTORS (ONLY SIDE STREETS) (30' X 6 ' LOOPS)
TOTAL		5030	



DATE PREPARED 28-MAY-2025	
ROUTE 30	STATE MO
DISTRICT SL	SHEET NO. 3
COUNTY FRANKLIN/ JEFFERSON	
JOB NO. J6S3435	
CONTRACT ID. .	
PROJECT NO. .	
BRIDGE NO. .	

DATE	DESCRIPTION					
	.	.	.	.	.	.

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

JACOBS ENGINEERING GROUP
501 NORTH BROADWAY
ST. LOUIS, MISSOURI 63102-2121
PHONE: (314) 355-4000
FAX: (314) 355-4001
CERTIFICATE OF AUTHORITY #00704

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

SIGN	SIZE IN.	AREA SQ.FT.	QTY EACH	TOTAL AREA SQ.FT.	QTY RELOC EACH	TOTAL RELOC SQ.FT.	SIGN NUM.	DESCRIPTION	SIGN	SIZE IN.	AREA SQ.FT.	QTY EACH	TOTAL SQ.FT.	QTY RELOC EACH	TOTAL RELOC SQ.FT.	SIGN NUM.	DESCRIPTION	ITEM NUMBER	TOTAL QTY	EFFECTIVE: 07-01-2024	DESCRIPTION
WARNING SIGNS									GUIDE SIGNS									6122008		IMPACT ATTENUATOR 40 MPH (SAND BARRELS)	
WO1-1L	48X48	16.00						TURN (SYMBOL LEFT)	E05-1	36X48	12.00						GORE EXIT	6122009		IMPACT ATTENUATOR 45 MPH (SAND BARRELS)	
WO1-1R	48X48	16.00						TURN (SYMBOL RIGHT)	E05-2	48X36	12.00						EXIT OPEN	6122010		IMPACT ATTENUATOR 50 MPH (SAND BARRELS)	
WO1-2L	48X48	16.00						CURVE (SYMBOL LEFT)	E05-2a	48X36	12.00						EXIT CLOSED	6122012		IMPACT ATTENUATOR 55 MPH (SAND BARRELS)	
WO1-2R	48X48	16.00						CURVE (SYMBOL RIGHT)	GO20-1	60X24	10.00	4	40.00				ROAD WORK NEXT XX MILES	6122014		IMPACT ATTENUATOR 60 MPH (SAND BARRELS)	
WO1-3L	48X48	16.00						REVERSE TURN (SYMBOL LEFT)	GO20-2	48X24	8.00	3	24.00				END ROAD WORK	6122017		IMPACT ATTENUATOR 65 MPH (SAND BARRELS)	
WO1-3R	48X48	16.00						REVERSE TURN (SYMBOL RIGHT)	GO20-4	36X18	4.50	1	4.50				PILOT CAR FOLLOW ME	6122019		IMPACT ATTENUATOR 70 MPH (SAND BARRELS)	
WO1-4L	48X48	16.00						REVERSE CURVE (SYMBOL LEFT)	GO20-4a	42X30	8.75	4	35.00				PILOT CAR IN USE WAIT & FOLLOW	6122020		REPLACEMENT SAND BARREL	
WO1-4R	48X48	16.00						REVERSE CURVE (SYMBOL RIGHT)	GO20-4a	18X12	1.50						PILOT CAR IN USE WAIT & FOLLOW	6122030		IMPACT ATTENUATOR (RELOCATION)	
WO1-4bL	48X48	16.00						DOUBLE ARROW REVERSE CURVE (SYMBOL LEFT)	GO20-5aP	36X24	6.00	4	24.00				WORK ZONE (PLAQUE)	6123001		TRUCK MOUNTED ATTENUATOR (TMA)	
WO1-4bR	48X48	16.00						DOUBLE ARROW REVERSE CURVE (SYMBOL RIGHT)	MO4-8a	24X18	3.00						END DETOUR	6161008		ADVANCED WARNING RAIL SYSTEM	
WO1-4cL	48X48	16.00						TRIPLE ARROW REVERSE CURVE (SYMBOL LEFT)	MO4-9L	48X36	12.00						DETOUR (LEFT)	6161012		BUOYS (BOATS KEEP OUT)	
WO1-4cR	48X48	16.00						TRIPLE ARROW REVERSE CURVE (SYMBOL RIGHT)	MO4-9R	48X36	12.00						DETOUR (RIGHT)	6161013		BUOYS (NO WAKE)	
WO1-6	60X30	12.50						HORIZONTAL ARROW (SYMBOL)	MO4-9P	48X12	4.00						STREET NAME (PLAQUE)	6161014		SPECIAL SIGN ASSEMBLY (BOATS KEEP OUT)	
WO1-6a	72X36	18.00						HORIZ. ARROW (SYMBOL ON PERMANENT BARRICADE)	MO4-10L	48X18	6.00						DETOUR ARROW (LEFT)	6161025	100	CHANNELIZER (TRIM LINE)	
WO1-7	60X30	12.50						DOUBLE HEAD HORIZONTAL ARROW (SYMBOL)	MO4-10R	48X18	6.00						DETOUR ARROW (RIGHT)	6161030	3	TYPE III MOVEABLE BARRICADE	
WO1-7a	72X36	18.00						DOUBLE HEAD HORIZ. ARROW (SYMBOL ON PERM. BARR.)	REGULATORY SIGNS									6161033	20	DIRECTION INDICATOR BARRICADE	
WO1-8	18X24	3.00						CHEVRON (SYMBOL)	R1-1	48X48	13.25						STOP	6161040	2	FLASHING ARROW PANEL	
WO1-8a	30X36	7.50						CHEVRON (SYMBOL FOR DIVIDED HIGHWAYS)	R1-2	48TRI.	6.93						YIELD	6161047		TYPE III OBJECT MARKER	
WO3-1	48X48	16.00						STOP AHEAD (SYMBOL)	R1-2a	36X36	9.00						TO ONCOMING TRAFFIC (PLAQUE)	6161055		SEQUENTIAL FLASHING WARNING LIGHT	
WO3-2	48X48	16.00						YIELD AHEAD (SYMBOL)	R1-3P	30X12	2.50						ALL WAY (PLAQUE)	6161070		TUBULAR MARKER	
WO3-3	48X48	16.00						SIGNAL AHEAD (SYMBOL)	R2-1	36X48	12.00	4	48.00				SPEED LIMIT XX	6161095		RADAR SPEED ADVISORY SYSTEM	
WO3-4	48X48	16.00	6	96.00				BE PREPARED TO STOP	R3-1	48X48	16.00						NO RIGHT TURN (SYMBOL)	6161096		CHANGEABLE MESSAGE SIGN, COMMISSION FURNISHED/RETAINED	
WO3-5	48X48	16.00						SPEED LIMIT AHEAD	R3-2	48X48	16.00						NO LEFT TURN (SYMBOL)	6161098A	6*	CHANGEABLE MESSAGE SIGN WITHOUT COMM. INTERFACE- CONTRACTOR FURNISHED/RETAINED	
WO4-1L	48X48	16.00						MERGE (SYMBOL FROM LEFT)	R3-3	36X36	9.00						NO TURNS	6161099		CHANGEABLE MESSAGE SIGN WITH COMM. INTERFACE- CONTRACTOR FURNISHED/RETAINED	
WO4-1R	48X48	16.00						MERGE (SYMBOL FROM RIGHT)	R3-4	48X48	16.00						NO U-TURN (SYMBOL)	6162000A		WORK ZONE TRAFFIC SIGNAL SYSTEM	
WO4-1aL	48X48	16.00						MERGE (LEFT)	R3-7L	30X30	6.25						LEFT LANE MUST TURN LEFT	6162002		TEMPORARY LONG-TERM RUMBLE STRIPS	
WO4-1aR	48X48	16.00	4	64.00				MERGE (RIGHT)	R3-7R	30X30	6.25						RIGHT LANE MUST TURN RIGHT	6173600D		TEMPORARY TRAFFIC BARRIER CONTRACTOR FURNISHED/RETAINED	
WO5-1	48X48	16.00						ROAD/BRIDGE/RAMP NARROWS	R4-1	36X48	12.00	2	24.00				DO NOT PASS	6174000A		TEMP. TRAFFIC BARRIER HEIGHT TRANSITION	
WO5-3	48X48	16.00						ONE LANE BRIDGE	R4-2	36X48	12.00	2	24.00				PASS WITH CARE	6175010A		RELOCATING TEMPORARY TRAFFIC BARRIER	
WO5-5	48X48	16.00						NARROW LANES	R4-7a	36X48	12.00						KEEP RIGHT (HORIZONTAL ARROW)				
WO6-1	48X48	16.00						DIVIDED HIGHWAY (SYMBOL)	R4-8a	36X48	12.00						KEEP LEFT (HORIZONTAL ARROW)				
WO6-2	48X48	16.00						DIVIDED HIGHWAY END (SYMBOL)	R5-1	30X30	6.25						DO NOT ENTER	6176002B		CONTRACTOR FURNISHED/COMMISSION RETAINED	
WO6-3	48X48	16.00						TWO WAY TRAFFIC (SYMBOL)	R5-1a	36X24	6.00						WRONG WAY				
WO7-3a	30X24	5.00						NEXT XX MILES (PLAQUE)	R6-1L	54X18	6.75						ONE WAY ARROW (LEFT)				
WO8-1	48X48	16.00	6	96.00				BUMP	R6-1R	54X18	6.75						ONE WAY ARROW (RIGHT)				
WO8-2	48X48	16.00						DIP	R6-2L	24X30	5.00						ONE WAY (LEFT)				
WO8-3	48X48	16.00						PAVEMENT ENDS	R6-2R	24X30	5.00						ONE WAY (RIGHT)	6176000B		TEMPORARY TRAFFIC BARRIER COMMISSION FURNISHED/RETAINED	
WO8-4	48X48	16.00						SOFT SHOULDER	R9-9	24X12	2.00						SIDEWALK CLOSED				
WO8-5	48X48	16.00						SLIPPERY WHEN WET (SYMBOL)									SIDEWALK CLOSED AHEAD, (ARROW LEFT) CROSS HERE	6177000B		TEMP. TRAFFIC BARRIER HEIGHT TRANSITION	
WO8-6	48X48	16.00						TRUCK CROSSING	R9-11L	24X18	3.00							6208064A		COMMISSION FURNISHED/RETAINED	
WO8-6c	48X48	16.00						TRUCK ENTRANCE												TEMPORARY RAISED PAVEMENT MARKER	
WO8-7	36X36	9.00						LOOSE GRAVEL	R9-11R	24X18	3.00							9029400		TEMPORARY TRAFFIC SIGNALS	
WO8-7a	36X36	9.00						FRESH OIL / LOOSE GRAVEL	R10-6	24X36	6.00							9029401		TEMPORARY TRAFFIC SIGNALS AND LIGHTING	
WO8-9	48X48	16.00						LOW SHOULDER	R11-2	48X30	10.00	1	10.00				STOP HERE ON RED (45° ARROW)				
WO8-11	48X48	16.00	16	256.00				UNEVEN LANES									ROAD CLOSED				
WO8-12	48X48	16.00	8	128.00				NO CENTER LINE	R11-3a	60X30	12.50						ROAD CLOSED XX MILES AHEAD				
WO8-15	48X48	16.00						GROOVED PAVEMENT	R11-4	60X30	12.50						LOCAL TRAFFIC ONLY				
WO8-15P	30X24	5.00						MOTORCYCLE (PLAQUE)	CONST-3A	60X48	20.00	2	40.00				ROAD CLOSED TO THRU TRAFFIC				
WO8-17L	48X48	16.00	16	256.00				SHOULDER DROP-OFF (SYMBOL LEFT)	CONST-3X	56X12	4.67						FINE SIGN				
WO8-17R	48X48	16.00	16	256.00				SHOULDER DROP-OFF (SYMBOL RIGHT)	MISCELLANEOUS SIGNS												
WO8-17P	30X24	5.00	32	160.00				SHOULDER DROP-OFF (PLAQUE)	CONST-5	48X36	12.00						POINT OF PRESENCE				
W10-1	42RND.	9.62						RAILROAD CROSSING	CONST-5	96X48	32.00						POINT OF PRESENCE				
WO12-1	24X24	4.00						DOUBLE DOWN ARROW (SYMBOL)	CONST-8	48X36	12.00	5	60.00				WORK ZONE NO PHONE ZONE				
WO12-2	48X48	16.00						LOW CLEARANCE (SYMBOL)													
WO12-2x	24X18	3.00						LOW CLEARANCE (PLAQUE)													
WO12-2a	84X24	14.00						OVERHEAD LOW CLEARANCE (FEET AND INCHES)													
WO12-4	120X60	50.00						LOW CLEARANCE XX FT XX IN XX MILES AHEAD													
WO12-5	120X60	50.00						WIDTH RESTRICTION XX FT XX IN XX MILES AHEAD													
WO13-1	30X30	6.25						ADVISORY SPEED (PLAQUE)													
WO16-2	30X24	5.00						XXX FEET (PLAQUE)													
WO16-3	30X24	5.00						X MILE (PLAQUE)													
WO20-1	48X48	16.00	20	320.00				ROAD/BRIDGE/RAMP WORK AHEAD													
WO20-2	48X48	16.00						DETOUR AHEAD													
WO20-3	48X48	16.00						ROAD CLOSED AHEAD	616-10.05												
WO20-4	48X48	16.00	6	96.00				ONE LANE ROAD AHEAD	CONSTRUCTION SIGNS												
WO20-5	48X48	16.00	4	64.00				RIGHT/CENTER/LEFT LANE CLOSED AHEAD	616-10.10												
WO20-5a	48X48	16.00						2 RIGHT/CENTER/LEFT LANES CLOSED AHEAD	RELOCATED SIGNS												
WO20-6a	48X48	16.00	4	64.00				RIGHT/CENTER/LEFT LANE CLOSED													
WO20-7a	48X48	16.00	6	96.00				FLAGGER (SYMBOL)													
WO21-2	36X36	9.00						FRESH OIL													
WO21-5	48X48	16.00						SHOULDER WORK / SHOULDER WORK AHEAD													
WO22-1	48X48	16.00						BLASTING ZONE AHEAD													
WO22-2	42X36	10.50						TURN OFF 2-WAY RADIO AND PHONE													
WO22-3	42X36	10.50						END BLASTING ZONE													
GO22-1	21X15	2.19	4	8.76				WET PAINT (ARROW PIVOTS)													
																		SUMMARY OF QUANTITIES		SHEET 13 OF 13	



05/28/2025 12:24:58 PM
Kyle Baumann - Civil
MO PE-2023026580

DATE PREPARED

28-MAY-2025

ROUTE 30 STATE MO

DISTRICT SL SHEET NO. 3

COUNTY FRANKLIN/ JEFFERSON

JOB NO. J6S3435

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL JEFFERSON CITY, MO 65102

1-888-ASK-M