

ROCK BLANKET								
STA	STA	LOCATION	FURNISHING TYPE 2 ROCK BLANKET (CY)	PLACING TYPE 2 ROCK BLANKET (CY)	FURNISHING TYPE 1 ROCK DITCH LINER (CY)	PLACING TYPE 1 ROCK DITCH LINER (CY)	PERMANENT EROSION CONTROL GEOTEXTILE (SY)	REMARKS
116+30.00	118+77.00	RTE AF LT & RT	1159	1159	-	-	1300	
118+77.00	118+80.00	RTE AF LT & RT	-	-	6	6	19	
118+80.00	119+35.00	RTE AF LT	335	335	-	-	234	
118+80.00	119+35.00	RTE AF RT	250	250	-	-	223	
121+10.33	121+84.33	RTE AF LT	391	391	-	-	268	
121+10.33	121+84.33	RTE AF RT	293	293	-	-	255	
121+84.33	121+87.33	RTE AF LT & RT	-	-	2	2	6	
TOTAL			2428	2428	8	8	2305	

1

GRADING AND EARTHWORK									
STA	STA	LOCATION	AVERAGE WIDTH (FT)	GRAVEL A OR CRUSHED STONE B (TON)	LINEAR GRADING CLASS 2 (STA)	ESTIMATED EARTHWORK CUT * (CY)	ESTIMATED EARTHWORK FILL * (CY)	CLASS A EXCAVATION (CY)	REMARKS
122+15.00	124+50.00	RTE AF LT	10	67.7	2.5	-	-	-	MATERIAL FOR TEMPORARY ENTRANCE
122+15.00	124+50.00	RTE AF LT	10	-	2.5	-	-	-	REMOVAL OF TEMPORARY ENTRANCE
121+93.00	-	RTE AF RT	10	11.3	0.4	-	-	-	REGRADE NORTHWEST PRIVATE ENTRANCE TO RW
122+03.00	-	RTE AF LT	20	20.8	0.3	-	-	-	REGRADE SOUTHWEST PRIVATE ENTRANCE TO RW
116+30.00	119+35.00	RTE AF LT & RT	VAR	-	3.1	70.0	30.0	-	REGRADE RTE AF
121+10.33	122+97.42	RTE AF LT & RT	VAR	-	1.9	59.6	131.3	-	REGRADE RTE AF
119+00.00	119+33.00	RTE AF LT & RT	VAR	-	-	-	-	205.0	REMOVAL OF EXIST. ROADWAY FILL AT BENT 1 NOT COVERED BY EXCAVATION QUANTITY FOUND IN BRIDGE PLANS
TOTAL				100	10.7	130	161	205	
PLACE GRAVEL AT ENTRANCES AS DIRECTED BY ENGINEER. CLASS A EXCAVATION NOT INCLUDED IN ESTIMATED CUT AND FILL QUANTITY. * ESTIMATED CUT AND FILL IS FOR INFORMATIONAL PURPOSES ONLY. REGRADING OF NEW ROADWAY IS INCLUDED IN LINEAR GRADING CLASS 2.									

PIPE CULVERTS				
STA	STA	LOCATION	18" GROUP C PIPE (FT)	REMARKS
123+70.00	124+26.00	RTE AF LT	56	TO BE REMOVED WITH TEMP. ENTRANCE
TOTAL			56	
LOCATION IS APPROXIMATE, PLACE AS DIRECTED BY ENGINEER				

TEMPORARY EROSION CONTROL							
STA	STA	LOCATION	SILT FENCE (FT)	TEMPORARY BERM TYPE C (FT)	ROCK DITCH CHECK (FT)	SEDIMENT REMOVAL (CY)	REMARKS
116+30.00	118+77.00	RTE AF LT & RT	499	-	-	5	
118+77.00	119+39.75	RTE AF LT & RT	-	192	-	2	
121+06.50	121+87.33	RTE AF LT & RT	-	204	-	2	
121+87.33	121+96.00	RTE AF LT	30	-	-	1	
VAR	VAR	RTE AF LT & RT	-	-	48	4	
TOTAL			529	396	48	14	
ROCK DITCH CHECKS TO BE PLACED AS DIRECTED BY ENGINEER							

STATE OF MISSOURI

JACOB CAPEDEE

NUMBER

PE-2018021161

PROFESSIONAL ENGINEER

Jacob Capede

JACOB CAPEDEE - CIVIL

MO-PE-2018021161

DATE PREPARED

9/12/2025

ROUTE

AF

STATE

MO

DISTRICT

SE

SHEET NO.

3

COUNTY

WRIGHT

JOB NO.

J9S3691

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

MoDOT

105 WEST CAPITOL

JEFFERSON CITY, MO 65102

1-888-ASK-MODOT (1-888-275-6636)