

REMOVAL OF IMPROVEMENTS							
APPROX. LOG MILE	LOCATION	LENGTH (FT)	AVERAGE WIDTH (FT)	ASPHALT PAVEMENT (SY)	FULL DEPTH SAW CUT (LF)	SHEET NUMBER	Remarks
0.108	OZA56 S	36	13	52.00	62	13	FULL DEPTH REPAIR 1
0.114	OZA56 S	37	10	41.11	57	13	FULL DEPTH REPAIR 2
-	UDRW. 5	5	5	2.78	20	14	FULL DEPTH REPAIR 3
-	UDRW. 8	15	4	6.67	23	14	FULL DEPTH REPAIR 4
-	UDRW. 10	32	13	46.22	45	15	FULL DEPTH REPAIR 5
-	UDRW. 10	30	10	33.33	40	15	FULL DEPTH REPAIR 6
-	STATE PARK RD 1	-	-	461.44	396	16	FULL DEPTH REPAIR 7
0.402	OZA18 J	15	27.5	45.83	65	21	FULL DEPTH REPAIR 8
0.402	OZA18 J	60	15	100.00	15	21	FULL DEPTH REPAIR 9
-	OZA20 K	-	-	258.11	75	22	FULL DEPTH REPAIR 10
0.426	OZA20 K	10	20	22.22	40	22	FULL DEPTH REPAIR 11
0.453	OZA20 K	70	18	140.00	36	22	FULL DEPTH REPAIR 12
3.055	OZA25 M	58	20	128.89	98	23	FULL DEPTH REPAIR 13
3.044	OZA25 M	70	15	116.67	100	23	FULL DEPTH REPAIR 14
0.085	OZA22 L	90	11	110.00	101	23	FULL DEPTH REPAIR 15
0.071	OZA22 L	35	19	73.89	73	23	FULL DEPTH REPAIR 16
2.171	OZA25 M	150	10	166.67	170	23	FULL DEPTH REPAIR 17
1.074	OZA30 O	25	25	69.44	100	25	FULL DEPTH REPAIR 18
			USE	1	LUMP SUM		

CONSTRUCTION SIGNING						
SIGN NO.	SIGN	SIZE (IN)	AREA (SF)	QTY.	TOTAL AREA	DESCRIPTION
2	WO20-1	48 X 48	16	9	144	ROAD WORK AHEAD
7	WO20-4	48 X 48	16	4	64	ONE LANE ROAD AHEAD
8	WO20-7a	48 X 48	16	9	144	FLAGGER (SYMBOL)
11	WO3-4	48 X 48	16	5	80	BE PREPARED TO STOP
36	WO8-11	48 X 48	16	4	64	UNEVEN LANES
53	GO20-4	36 X 18	4.5	1	4.5	PILOT CAR FOLLOW ME
58	GO20-4a	18 X 12	1.5	2	3	PILOT CAR IN USE WAIT & FOLLOW
59	CONST-8	48 X 36	12	2	24	WORK ZONE NO PHONE ZONE
60	GO20-4a	24 X 18	3	2	6	PILOT CAR IN USE WAIT & FOLLOW
					533.5	CONSTRUCTION SIGNS SUBTOTAL
ITEM NO. 616-10.05					534	USE

OTHER TRAFFIC CONTROL ITEMS	
ITEM	QTY
CHANNELIZERS (TRIM LINE)	275
6161098A CHANGEABLE MESSAGE SIGN	4

PATCHING ROUTES	
ITEM	QTY
REPLACEMENT OF DAMAGED PAVEMENT	270 TONS
REMOVAL OF DAMAGED PAVEMENT	1090 SY


GRAVEL (A) OR CRUSHED STONE (B)	
LOCATION	GRAVEL (A) OR CRUSHED STONE (B) (TONS)
PARK ROADS	125
TOTAL	125
USE	125

MOBILIZATION
1 LUMP SUM

PAVEMENT MARKING*										
AREA	CLASS 1 PAVEMENT MARKING					SEE SPECIAL SHEETS			PREFORMED THERMOPLASTIC	
	NO BEADS		TYPE P BEADS			BLUE HANDICAP PARKING SYMBOL (EACH)	WHITE STRAIGHT ARROW MARKING (EACH)	WHITE LEFT/RIGHT ARROW MARKING (EACH)	LT/RT TURN ARROW (EACH)	24" STOP BAR WHITE (FT)
	4" SOLID BLUE (FT)	4" SOLID WHITE (FT)	4" SOLID WHITE (FT)	4" DASHED WHITE (FT)	4" SOLID YELLOW (FT)					
RTE 134	375	4115	0	0	0	4	2	0	0	0
MCCUBBINS DR	90	635	0	0	0	1	0	0	0	0
OSAGE BEACH PKWY	1145	2550	1410	265	160	11	23	6	2	80
TOTAL	1610	7300	1410	265	160	16	25	6	2	80
PAY TOTAL	1610	7300	1675		160	16	25	6	2	80

*REPLACE WHERE EXISTING, PAVEMENT MARKING IN DRIVING LANES REQUIRE TYPE P BEADS

1 ADDED



DATE PREPARED 10/2/2025	
ROUTE VAR	STATE MO
DISTRICT CD	SHEET NO. 3
COUNTY CAMDEN/MILLER	
JOB NO. JCDP0006	
CONTRACT ID.	

PROJECT NO.
BRIDGE NO.

DESCRIPTION	DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION



105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

