CLASS B PARTIAL DEPTH PAVEMENT REPAIR

PATCH NUMBER	DIRECTION *	LOG MILE *	LANE NUMBER *	LENGTH FT	WIDTH FT	FURNISHING AND PLACING SY	REMOVAL SY
1	EB	0	0	6	12	2.6	8
2	0	0	0	6	12	2.6	8
3	0	0	0	6	12	2.6	8
4	0	0	0	6	12	2.6	8
5	0	0	0	40	6	8.8	26.7
6	0	0	0	6	12	2.6	8
7	0	0	0	10	4	1.4	4.4
8	0	0	0	6	12	2.6	8
9	0	0	0	40	4	6	17.8
10	0	0	0	8	4	1.2	3.6
11	0	0	0	6	12	2.6	8
12	0	0	0	6	12	2.6	8
13	0	0	0	6	12	2.6	8
14	0	0	0	6	12	2.6	8
15	0	0	0	6	12	2.6	8
16	0	0	0	6	12	2.6	8
17	0	0	0	6	12	2.6	8
18	0	0	0	10	4	1.4	4.4
19	0	0	0	10	4	1.4	4.4
20	0	0	0	20	4	3	8.9
21	0	0	0	6	12	2.6	8
22	0	0	0	8	4	1.2	3.6
23	0	0	0	8	12	3.6	10.7
24	0	0	0	15	4	2.2	6.7
25	0	0	0	6	12	2.6	8
					SUB TOTAL	69.2	211.2

* LOCATION TO BE DETERMINED BY THE ENGINEER

CLASS B PARTIAL DEPTH PAVEMENT REPAIR

PATCH NUMBER	DIRECTION *	LOG MILE *	LANE NUMBER *	LENGTH FT	WIDTH FT	FURNISHING AND PLACING SY	REMOVAL SY
26	WB	0	0	20	4	3	8.9
27	0	0	0	10	4	1.4	4.4
28	0	0	0	10	4	1.4	4.4
29	0	0	0	10	4	1.4	4.4
30	0	0	0	10	4	1.4	4.4
31	0	0	0	25	4	3.8	11.1
32	0	0	0	8	4	1.2	3.6
33	0	0	0	8	4	1.2	3.6
34	0	0	0	8	4	1.2	3.6
35	0	0	0	6	6	1.4	4
36	0	0	0	6	6	1.4	4
37	0	0	0	6	6	1.4	4
38	0	0	0	6	6	1.4	4
39	0	0	0	6	6	1.4	4
40	0	0	0	6	6	1.4	4
41	0	0	0	8	4	1.2	3.6
42	0	0	0	8	4	1.2	3.6
43	0	0	0	8	4	1.2	3.6
44	0	0	0	8	4	1.2	3.6
45	0	0	0	10	6	2.2	6.7
46	0	0	0	8	4	1.2	3.6
47	0	0	0	25	4	3.8	11.1
48	0	0	0	8	4	1.2	3.6
49	0	0	0	6	12	2.6	8
50	0	0	0	6	12	2.6	8
51	0	0	0	10	6	2.2	6.7
52	0	0	0	10	4	1.4	4.4
53	0	0	0	6	12	2.6	8
54	0	0	0	20	4	3	8.9
55	0	0	0	20	4	3	8.9
56	0	0	0	15	4	2.2	6.7
57	0	0	0	8	4	1.2	3.6
58	0	0	0	10	4	1.4	4.4
59	0	0	0	8	4	1.2	3.6
60	0	0	0	10	4	1.4	4.4
61	0	0	0	10	4	1.4	4.4
62	0	0	0	8	4	1.2	3.6
63	0	0	0	6	12	2.6	8
64	0	0	0	6	12	2.6	8
65	0	0	0	6	12	2.6	8
66	0	0	0	6	12	2.6	8
67	0	0	0	6	12	2.6	8
68	0	0	0	6	12	2.6	8
69	0	0	0	6	12	2.6	8
70	0	0	0	6	12	2.6	8
71	0	0	0	6	12	2.6	8
72	0	0	0	6	12	2.6	8
73	0	0	0	6	12	2.6	8
74	0	0	0	15	4	2.2	6.7
75	0	0	0	6	12	2.6	8
76	0	0	0	6	12	2.6	8
77	0	0	0	200	2	9.8	44.4
78	0	0	0	25	2	1.2	5.6
79	0	0	0	30	2	1.4	6.7
80	0	0	0	30	2	16.1	6.7
81	0	0	0	40	2	2	8.9
82	0	0	0	10	2	0.4	2.2
					SUB TOTAL	131.9	380.6
					SUB TOTAL	69.2	211.2
					PAY TOTAL	201.1	591.8

* LOCATION TO BE DETERMINED BY THE ENGINEER

TEMPORARY EROSION CONTROL

ALTERNATE 1

LOG MI.	LOG MI.	LOCATION	TYPE I DITCH CHECK L.F.	SEDIMENT REMOVAL CY	REMARKS
13.544	13.544	ROUTE 58 LT AND RT-BOTH ENDS	200	8	CULVERT
13.544	13.701	ROUTE 58 LT AND RT-BOTH ENDS	1458	19	BETWEEN CULVERTS
13.701	13.701	ROUTE 58 LT AND RT-BOTH ENDS	200	8	CULVERT
13.701	13.842	ROUTE 58 LT AND RT-BOTH ENDS	1288	17	BETWEEN CULVERTS
13.842	13.842	ROUTE 58 LT AND RT-BOTH ENDS	200	8	CULVERT
13.842	14.079	ROUTE 58 LT AND RT-BOTH ENDS	2302	31	BETWEEN CULVERTS
14.079	14.079	ROUTE 58 LT AND RT-BOTH ENDS	200	8	CULVERT
14.079	14.199	ROUTE 58 LT AND RT-BOTH ENDS	1068	14	BETWEEN CULVERTS
14.199	14.199	ROUTE 58 LT AND RT-BOTH ENDS	200	8	CULVERT
14.199	14.558	ROUTE 58 LT AND RT-BOTH ENDS	3592	48	BETWEEN CULVERTS
14.558	14.558	ROUTE 58 LT AND RT-BOTH ENDS	200	8	CULVERT
14.558	14.878	ROUTE 58 LT AND RT-BOTH ENDS	3180	42	BETWEEN CULVERTS
14.878	14.878	ROUTE 58 LT AND RT-BOTH ENDS	200	8	CULVERT
14.878	15.077	ROUTE 58 LT AND RT-BOTH ENDS	1902	25	BETWEEN CULVERTS
15.077	15.077	ROUTE 58 LT AND RT-BOTH ENDS	200	8	CULVERT
15.077	15.258	ROUTE 58 LT AND RT-BOTH ENDS	1712	23	BETWEEN CULVERTS
15.258	15.258	ROUTE 58 LT AND RT-BOTH ENDS	200	8	CULVERT
15.258	15.819	ROUTE 58 LT AND RT-BOTH ENDS	5724	76	BETWEEN CULVERTS
15.819	15.819	ROUTE 58 LT AND RT-BOTH ENDS	200	8	CULVERT
15.819	15.860	ROUTE 58 LT AND RT-BOTH ENDS	232	3	BETWEEN CULVERTS
15.860	15.860	ROUTE 58 LT AND RT-BOTH ENDS	200	8	BRIDGE A7011
15.860	16.162	ROUTE 58 LT AND RT-BOTH ENDS	2990	40	BETWEEN CULVERTS
16.162	16.162	ROUTE 58 LT AND RT-BOTH ENDS	200	8	CULVERT
		PAY TOTAL	27848	434	

1

15.819	15.872
15.872	15.892
15.892	16.162
16.162	16.162

1

–	–
392	112
–	–
441	126
–	–
735	210
–	–
238	68
–	–
889	254
–	–
630	180
–	–
826	236
–	–
567	162
–	–
1099	314
–	–
224	64
–	–
406	116
–	–
12,894	1,842

BITUMINOUS SHOULDER RUMBLE STRIP

CONT. LOG MI. TO	CONT. LOG MI.	LOCATION	LENGTH STA.	REMARKS
13.544	15.857	ROUTE 58 LT AND RT	244	TO BRIDGE A7011 EXCEPTION
15.877	18.710	ROUTE 58 LT AND RT	300	TO BRIDGE A8913 EXCEPTION
20.466	21.325	ROUTE 58 LT AND RT	90	TO BRIDGE B0226 EXCEPTION
21.345	25.181	ROUTE 58 LT AND RT	406	SPEED LIMIT CHANGE INTO TOWN
25.675	25.748	ROUTE 58 LT AND RT	8	TO BRIDGE B0234 EXCEPTION
25.768	27.632	ROUTE 58 LT AND RT	196	END OF PROJECT
13.544	27.632	ROUTE 58 LT AND RT	294	EXCEPTION FOR ENTRANCES AND CROSSROADS
		PAY TOTAL	950	

1 REVISED

SUMMARY OF QUANTITIES
SHEET 3 OF 4

STATE OF MISSOURI
JODIE LYNN PUHR
NUMBER PE-2014000073
PROFESSIONAL ENGINEER
10/10/2025 4:32:41 PM
JODIE LYNN PUHR - CIVIL
MO-PE-2014000073

DATE PREPARED 10/10/2025

ROUTE	STATE
58	MO
DISTRICT	SHEET NO.
KC	3

COUNTY CASS

JOB NO. JKU0400

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)