

MEDIAN AND ISLANDS								
LOCATION	LOGMILE START	LOGMILE END	LENGTH (LF)	AREA (SY)	6 IN. CONC. MEDIAN STRIP (SY)	4 IN. CONC. MEDIAN STRIP (SY)	6 IN. CONC. CURB TYPE S (LF)	REMARKS
EASTBOUND MO 78								
ISLAND 2 ON PLANS SHEET	0.043	0.070	142.6	258	239.8	0	327	
ISLAND 1 ON PLANS SHEET	0.057	0.069	63.4	185	173.4	0	209	
ISLAND 3 ON PLANS SHEET	0.057	0.065	42.2	125	115.1	0	178	
MEDIAN 4 ON PLANS SHEET	0.080	0.122	221.8	324	26.8	275.2	468	
ISLAND 5 ON PLANS SHEET	0.137	0.145	42.2	35	30.7	0	78	
ISLAND 6 ON PLANS SHEET	0.137	0.145	42.2	88	81.0	0	126	
MEDIAN 7 ON PLANS SHEET	0.136	0.290	813.1	1063	35.0	940.7	1654	
TELEVISION PL TO STARK AVE	0.311	0.750	2317.9	4032	16.7	3763.8	4596	
STARK AVE PAST BLUE RIDGE TERR	0.764	1.301	2835.4	5061	26.3	4720.3	5728	
S CRYSLER AVE TO GRAND AVE	3.265	3.418	807.8	967	15.6	864.3	1636	
TOTAL					760.4	10564.3	15000	


ALL REPLACED MEDIANS LONGER THAN 150' HAVE 15' 6 IN. CONC. AS ENDS

PAVED APPROACHES		
LOGMILE	PAVED APPROACH 8 IN (SY)	REMARKS
EASTBOUND MO 78		
0.299	103.1	SOUTH ON TELEVISION PL
2.758	52.4	KCMO LIBRARY
5.518	61.3	CASEY'S
TOTAL	216.8	

FULL-DEPTH PAVEMENT REPAIR					
LOCATION	FURNISHING/PLACING CONC. FOR FULL-DEPTH PAVEMENT REPAIR (SY)	SUBGRADE COMPACTION 6 IN. DEPTH FOR FULL-DEPTH PAVEMENT REPAIR (SY)	TYPE 1 OR 5 AGGREGATE 4 IN. THICK FOR FULL-DEPTH PAVEMENT REPAIR (SY)	DOWEL BARS DRILL, FURNISHING, INSTALL (EACH)	FULL-DEPTH PAVEMENT REPAIR SAW CUTS (LF)
MO 78	2674	2674	2674	10027.5	12033
TOTAL	2674	267	267	10028	12033

PARTIAL-DEPTH PAVEMENT REPAIR		
LOCATION	REMOVAL FOR CLASS A PARTIAL DEPTH REPAIR (SY)	FURNISHING/PLACING FOR CLASS A PARTIAL DEPTH PAVEMENT REPAIR (CY)
MO 78	7264.0	505.0
TOTAL	7264	505

2 DELETED



DATE PREPARED
10/15/2025

ROUTE 78	STATE MO
DISTRICT KC	SHEET NO. 3

COUNTY
JACKSON

JOB NO.
JKU0042

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DATE	DESCRIPTION
10/15/25	ADDENDUM 2

MISSOURI HIGHWAYS AND TRANSPORTATION
COMMISSION



105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)