


TABLE OF CONTENTS

- A. Construction Requirements
- B. Deflection And Haunching
- C. Strengthening Existing Beams

 <p>09/18/2025 12:02:48 PM TIMOTHY D. LEAF - CIVIL MO-PE-2012000778</p>	<p>MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION 105 W. CAPITOL AVE. JEFFERSON CITY, MO 65101 Phone (888) 275-6636</p>
	<p>If a seal is present on this sheet, JSP's has been electronically sealed and dated.</p>
	<p>JOB NO. JCD0074 Cole County, MO Date Prepared: 9/18/2025</p>
<p>Only the following items of the Job Special Provisions (Bridge) are authenticated by this seal: All</p>	

JOB SPECIAL PROVISIONS (BRIDGE)

A. CONSTRUCTION REQUIREMENTS

1.0 Description. This provision contains general construction requirements for this project.

2.0 Construction Requirements. The plans and the asbestos and lead inspection report(s) for the existing structure(s) are included in the contract in the bridge electronic deliverables zip file for informational purposes only.

2.1 In order to assure the least traffic interference, the work shall be scheduled so that the bridge closure is for the absolute minimum amount of time required to complete the work. The bridge shall not be closed until material is available for continuous construction and the contractor is prepared to diligently pursue the work until the closed bridge is opened to traffic.

2.2 The existing slab for the bridge(s) to be redecked was constructed as composite or non-composite as indicated in the table below.

Bridge No.	Type of deck
X0035	Non-composite

2.3 Provisions shall be made to prevent any debris and material from falling into the waterway. If determined necessary by the engineer, any debris and material that falls below the bridge outside the previously specified limits shall be removed as approved by the engineer at the contractor's expense.

2.4 Any damage sustained to the remaining structure as a result of the contractor's operations shall be repaired or the material replaced as approved by the engineer at the contractor's expense.

2.5 Provisions shall be made to prevent damage to any existing utilities. Any damage sustained to the utilities as a result of the contractor's operations shall be the responsibility of the contractor. All costs of repair and disruption of service shall be as determined by the utility owners and as approved by the engineer.

3.0 Coating Information.

3.1 Environmental Contact. Environmental Section may be contacted at the below address or phone number. The Missouri Department of Health may be contacted at (573) 751-6102.

MoDOT - Design Division - Environmental Section
P.O. Box 270
105 W. Capitol Ave., Jefferson City, MO 65102
Telephone: (573) 526-4778

3.2 Approved Smelter and Hazardous Waste Treatment, Storage and Disposal Facility. The following is the approved smelter and hazardous waste treatment, storage and disposal facility:

Doe Run Company - Resource Recycling Division - Buick Facility
Highway KK
Boss, MO 65440
Telephone: (573) 626-4813

4.0 Method of Measurement. No measurement will be made.

5.0 Basis of Payment. Payment for the above described work will be considered completely covered by the contract unit price for other items included in the contract.

B. DEFLECTION AND HAUNCHING

1.0 Description. The contractor shall determine haunching based on field measurements, existing bridge plans and/or adjusted dead load deflections based on the difference between the new and existing dead load weights. A spreadsheet showing adjusted girder or beam deflections due to the weight of the new deck and barriers is included in the contract in the bridge electronic deliverables zip file.

2.0 Construction Requirements. In order to properly form the haunches for the new deck, the contractor shall survey top of deck elevations above each girder or beam including centerline of roadway and along each girder or beam line (top or bottom flange) prior to deck removal followed by surveying elevations of the girders or beams (top or bottom flange) after deck removal.

3.0 Method of Measurement. No measurement will be made.

4.0 Basis of Payment. Payment for the above described work will be considered completely covered by the contract unit price for other items included in the contract.

C. STRENGTHENING EXISTING BEAMS

1.0 Description. This work shall consist of strengthening existing beams as shown on the plans after the deck has been removed.

2.0 Materials. Shop drawings shall be submitted to Fabrication@modot.mo.gov.

3.0 Construction Requirements. Structural steel construction shall be in accordance with [Sec 712](#). Prior to installation of the new structural steel, the existing steel shall be carefully inspected for irregularities. Any irregularities shall be brought to the attention of the engineer.

3.1 Contact Surfaces. The surfaces of the existing flanges that will come into contact with the new steel plates shall be cleaned to an SSPC-SP2 degree of cleanliness. The surfaces of new steel shall be cleaned to an SSPC-SP6 degree of cleanliness. The existing and new plate contact surfaces shall be coated with one coat of gray epoxy-mastic primer (non-aluminum) in accordance with [Sec 1081](#).

3.2 Welding Requirements. The areas to be welded shall be cleaned to an SSPC-SP11 degree of cleanliness. All welding shall be performed by a certified welder in accordance with [Sec 712](#). All welding shall be in accordance with [Sec 712](#). E7018 welding electrode or self- shielded welding process from the MoDOT approved electrode list shall be used.

3.3 Gray Epoxy-Mastic Primer. Any surrounding touch up areas and any existing paint damaged by the repair work shall be cleaned and coated with one coat of gray epoxy-mastic primer (non-aluminum) in accordance with [Sec 1081](#).

4.0 Method of Measurement. No measurement will be made.

5.0 Basis of Payment. Payment for the above described work, including all material, equipment, labor and any other incidental work needed to complete this item, will be considered completely covered by the contract lump sum price for Strengthening Existing Beams.