PAVEMENT MARKING

LOG MILE	LOG MILE	LENGTH FT	EDGE LINES 4" SOLID WHITE CLASS 1 TYPE P BEADS FT	TURN LANES 4" SOLID WHITE CLASS 1 TYPE P BEADS FT	CROSSWALKS 4" SOLID WHITE CLASS 1 TYPE P BEADS FT	STOP BAR 24" SOLID WHITE PREFORMED THERMOPLASTIC FT	CENTERLINE 4" INT. YELLOW ACRYLIC CLASS 1 FT	CENTERLINE 4" SOLID YELLOW ACRYLIC CLASS 1 FT	CENTERLINE 4" DBL SOLID YELLOW ACRYLIC CLASS 1 FT	24" SOLID YELLOW PREFORMED THERMOPLASTIC FT	TYPE 2 PREFORMED THERMOPLASTIC LEFT/RIGHT ARROW EA	COMMENTS
36.761	37.28	2740.32	5480.64				685.1					INT. YELLOW CENTERLINE
37.28	37.4	633.60	1267.2				158.4	633.60				SOLID W/ INT. YELLOW CENTERLINE
37.4	37.84	2323.20	4646.4						4646.4			DBL SOLID YELLOW CENTERLINE
37.84	37.94	528.00	1056				132.0	528.00				SOLID W/ INT. YELLOW CENTERLINE
37.94	39.96	10665.60	21331.2						21331.2			DBL SOLID YELLOW CENTERLINE
38.96	39.18	1161.60	2323.2				290.4	1161.60				SOLID W/ INT. YELLOW CENTERLINE
39.18	39.44	1372.80	2745.6						2745.6			DBL SOLID YELLOW CENTERLINE
39.44	39.57	686.40	1372.8				171.6	686.40				SOLID W/ INT. YELLOW CENTERLINE
39.57	39.79	1161.60	2323.2						2323.2			DBL SOLID YELLOW CENTERLINE
39.79	39.91	633.60	1267.2				158.4	633.60				SOLID W/ INT. YELLOW CENTERLINE
39.91	40.13	1161.60	2323.2						2323.2			DBL SOLID YELLOW CENTERLINE
40.13	40.53	2112.00	4224				528.0	2112.00				SOLID W/ INT. YELLOW CENTERLINE
40.53	40.73	1056.00	2112						2112.0			DBL SOLID YELLOW CENTERLINE
40.73	40.85	633.60	1267.2				158.4	633.60				SOLID W/ INT. YELLOW CENTERLINE
40.85	41.19	1795.20	3590.4						3590.4			DBL SOLID YELLOW CENTERLINE
41.19	41.28	475.20	950.4				118.8	475.20				SOLID W/ INT. YELLOW CENTERLINE
41.28	41.39	580.80	1161.6						1161.6			DBL SOLID YELLOW CENTERLINE
41.39	41.47	422.40	844.8				105.6	422.40				SOLID W/ INT. YELLOW CENTERLINE
41.47	41.51	211.20	422.4						422.4			DBL SOLID YELLOW CENTERLINE
41.51	41.65	739.20	1478.4				184.8	739.20				SOLID W/ INT. YELLOW CENTERLINE
41.65	41.77	633.60	1267.2				158.4					INT. YELLOW CENTERLINE
41.77	41.87	528.00	1056.00	528.0			132.0	528.00			2	RT TURN, N PARK RD
41.87	42.08	1108.80	2217.60				277.2	1108.80	2217.6			EDGE LINES, SOLID W/ INT. & DBL YELLOW CENTERLINE
42.13	42.14	52.80	105.60				13.2	52.80				SOLID W/ INT. YELLOW CENTERLINE
42.14	42.74	3168.00	6336.00				792.0					INT. YELLOW CENTERLINE
42.74	42.83	475.20	950.40				118.8	475.20				SOLID W/ INT. YELLOW CENTERLINE
42.83	43.08	1320.00	2640.00						2640.0			DBL SOLID YELLOW CENTERLINE
43.08	43.22	739.20	1478.40				184.8	739.20				SOLID W/ INT. YELLOW CENTERLINE
42.133	43.22	5739.36	11478.72									EDGE LINES
43.22	43.77	2904.00	5808.00				726.0					EDGE LINES, INT. YELLOW CENTERLINE
43.77	43.82	264.00			60.0	14.0			1056.0	25.0		PAINTED MEDIAN
43.82	43.88	316.80		316.8	84.0	22.0			1267.2		2	LT TURN, W WASHINGTON ST
43.88	44.06	950.40					475.2	1900.8			8	NB & SB LT TURN LANE, SOLID W/ INT. YELLOW
44.06	44.13	369.60		369.6	168.0	14.0	184.8	739.2			2	NB & SB LT TURN LANE, SOLID W/ INT. YELLOW
44.13	44.17	211.20		422.4	84.0	26.0	105.6		422.4		3	LT TURN, RT TURN, 6TH ST
44.17	44.25	422.40		844.8	84.0	26.0			844.8		3	LT TURN, RT TURN, 6TH ST
44.25	44.45	1056.00					528.0	2112.00			6	NB & SB LT TURN LANE, SOLID W/ INT. YELLOW
44.45	44.73	1478.40			84.0	24.0	739.2	2956.80			10	NB & SB LT TURN LANE, SOLID W/ INT. YELLOW
44.73	44.83	528.00					264.0		2112.0	100.0		PAINTED MEDIAN, TURN LANE, SOLID W/ INT. YELLOW
44.83	44.87	211.20					105.6	422.40		45.0		TURN LANE, SOLID W/ INT. YELLOW
44.87	44.94	369.60		369.6					1478.4		1	LT TURN, PAINTED MEDIAN
44.94	45.054	601.92							1203.8	45.0	1	LT TURN, PAINTED MEDIAN
45.054	45.21	823.68		9022.9	84.0	32.0			1647.4	45.0	2	LT TURN, PAINTED MEDIAN, NE 144TH ST
45.21	45.31	528.00	1056.00	528.0	84.0	22.0			1056.0	15	2	LT TURN, PAINTED MEDIAN, W 19TH ST
45.31	45.35	211.20	422.40						422.4			EDGE LINES, DBL SOLID YELLOW CENTERLINES
45.35	45.44	475.20	950.40	950.4					950.4	30.0	2	EDGE LINES, DBL SOLID YELLOW CENTERLINES
45.44	45.52	422.40	844.80	422.4					844.8		2	LT TURN, PAINTED MEDIAN, GREENFIELD DR
45.52	45.71	1003.20	2006.40	1003.2					2006.4	45.0		EDGE LINES, DBL SOLID YELLOW CENTERLINES
45.71	45.75	211.20	422.40	211.2					422.4	45.0	2	LT TURN, PAINTED MEDIAN, MEADOWBROOK DR
45.75	45.79	211.20	422.40	211.2								LT EDGE LINE
45.79	45.84	264.00	528.00	264.0					844.8	45.0	1	RT TURN, PAINTED MEDIAN, MEADOWBROOK DR
		SUBTOTAL 1	118375.1			180.0	88649.9			440.0	49.0	

1 REVISED

SUMMARY OF QUANTITIES
SHEET 2 OF 6

STATE OF MISSOURI
BENJAMIN STEPHEN MCCABE SR. NUMBER PE-2003015005
PROFESSIONAL ENGINEER
10/30/2025 7:41:59 AM
BENJAMIN STEPHEN MCCABE SR - CIVIL
MO-PE-2003015005

DATE PREPARED 10/29/2025
ROUTE 33 | STATE MO
DISTRICT KC | SHEET NO. 3
COUNTY CLAY
JOB NO. JKU0035
CONTRACT ID.
PROJECT NO.
BRIDGE NO.

DESCRIPTION | DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

PAVEMENT MARKING

LOG MILE	LOG MILE	LENGTH FT	EDGE LINES 4" SOLID WHITE CLASS 1 TYPE P BEADS FT	TURN LANES 4" SOLID WHITE CLASS 1 TYPE P BEADS FT	CROSSWALKS 4" SOLID WHITE CLASS 1 TYPE P BEADS FT	STOP BAR 24" SOLID WHITE PREFORMED THERMOPLASTIC FT	CENTERLINE 4" INT. YELLOW ACRYLIC CLASS 1 FT	CENTERLINE 4" SOLID YELLOW ACRYLIC CLASS 1 FT	CENTERLINE 4" DBL SOLID YELLOW ACRYLIC CLASS 1 FT	24" SOLID YELLOW PREFORMED THERMOPLASTIC FT	TYPE 2 PREFORMED THERMOPLASTIC LEFT/RIGHT ARROW EA	COMMENTS
45.84	46.03	1019.04	2038.08						2038.1			EDGE LINES, DBL SOLID YELLOW CENTERLINES
46.07	46.97	4736.16	9472.32						9472.3			DBL SOLID YELLOW CENTERLINE
46.97	47.13	850.08	1700.16				212.5	850.08				SOLID W/ INT. YELLOW CENTERLINE
47.13	47.63	2634.72	5269.44						5269.4			DBL SOLID YELLOW CENTERLINE
47.63	47.99	1900.80	3801.60				475.2	1900.80				SOLID W/ INT. YELLOW CENTERLINE
47.99	48.23	1272.48	2544.96				318.1					INT. YELLOW CENTERLINE
48.23	48.37	733.92	1467.84				183.5	733.92				SOLID W/ INT. YELLOW CENTERLINE
48.37	48.54	897.60	1795.20						1795.2			DBL SOLID YELLOW CENTERLINE
48.54	48.63	475.20	950.40				118.8	475.20				SOLID W/ INT. YELLOW CENTERLINE
48.63	48.76	686.40	1372.80				171.6					INT. YELLOW CENTERLINE
48.76	48.89	681.12	1362.24				170.3	681.12				SOLID W/ INT. YELLOW CENTERLINE
48.89	48.97	427.68	855.36						855.4			DBL SOLID YELLOW CENTERLINE
48.97	49.02	258.72	517.44				64.7	258.72				SOLID W/ INT. YELLOW CENTERLINE
49.02	49.13	580.80	1161.60				145.2					INT. YELLOW CENTERLINE
49.13	49.27	744.48	1488.96				186.1	744.48				SOLID W/ INT. YELLOW CENTERLINE
49.27	49.41	739.20	1478.40						1478.4			DBL SOLID YELLOW CENTERLINE
46.07	49.41	17619.36	35238.72									EDGE LINES
49.41	49.46	264.00	528.00	264.0					528.0		1	RT TURN, US 69
		SUBTOTAL 1	118375.1			180.0		88649.9		440.0	49	
		SUBTOTAL 2	73307.52			22.0		29127.1		0	1	
		PAY TOTAL	191683			202.0		117777		440	50	

1 REVISED

RUMBLE STRIP QUANTITIES

BEGINNING LOG MILE	END LOG MILE	LENGTH FT	SHOULDER RUMBLE STRIP STA.	CENTERLINE RUMBLE STRIP STA.	COMMENTS
37.241	43.051	30677	613.54	306.8	BEGIN KEARNEY EXCEPTION
46.093	49.269	16769	335.38	167.7	END KEARNEY EXCEPTION, END OF PROJECT
	EXCEPTIONS	30140	-301.4	0.0	137 ENTRANCES (220 FT PER ENTRANCE)
	EXCEPTIONS	1360	-27.2	0.0	MEADOWBROOK LEFT TURN LANE
	EXCEPTIONS	424	-8.5	0.0	BRIDGES
		TOTALS	612	475	

MOBILIZATION
ONE LUMP SUM

SUMMARY OF QUANTITIES
SHEET 3 OF 6

STATE OF MISSOURI
BENJAMIN STEPHEN MCCABE SR. NUMBER PE-2003015005
PROFESSIONAL ENGINEER
10/30/2025 7:41:17 AM
BENJAMIN STEPHEN MCCABE SR - CIVIL
MO-PE-2003015005

DATE PREPARED 10/29/2025
ROUTE 33 | STATE MO
DISTRICT KC | SHEET NO. 3
COUNTY CLAY
JOB NO. JKU0035
CONTRACT ID.
PROJECT NO.
BRIDGE NO.

DESCRIPTION | DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)