

MODIFIED COLDMILLING (DEPTH TRANSITIONS)							
LOG MILE	LOG MILE	ROUTE	LENGTH (MI)	WIDTH (FT)	LENGTH (FT)	MODIFIED COLDMILLING (SY)	REMARKS
0.000	0.002	46		10	139	154.44	BEG. US 59 & MO 46
		46		20	10	22.22	RTE MM
		46		20	10	44.44	RTE N (BOTH SIDE)
		46		20	10	22.22	RTE EE
		46		20	10	22.22	RTE HH
		46		20	10	22.22	RTE PP
1.585	1.613	46	0.028	22	150	366.67	BRIDGE A9306
1.641	1.669	46	0.028	22	150	366.67	BRIDGE A9306
6.202	6.230	46	0.028	22	150	366.67	BRIDGE B0018
6.256	6.284	46	0.028	22	150	366.67	BRIDGE B0018
7.056	7.084	46	0.028	22	150	366.67	BRIDGE B0017
7.103	7.131	46	0.028	20	150	333.33	BRIDGE B0017
7.580	7.608	46	0.028	20	150	333.33	BRIDGE B0013
7.629	7.657	46	0.028	20	150	333.33	BRIDGE B0013
15.111	15.139	46	0.028	20	150	333.33	END OF JOB MO 46
TOTAL						3454.43	
PAY TOTAL						3454	

BITUMINOUS PAVEMENT							
LOG MILE	LOG MILE	ROUTE	LENGTH (MI)	WIDTH (FT)	BITUMINOUS MIXTURE PG58-28H (BP-2) (TONS)	TACK COAT (GALLONS)	REMARKS
0.000	0.021	46	VAR.	VAR.	46.67	15.44	TRANSITION AREA THROUGH RADIUS, INTERSECTION US 59 & MO 46
0.021	1.613	46	1.592	22	1695.16	2054.74	FROM MO 46 TO BRIDGE A9306 (RUMBLE PLACEMENT IN AREA)
1.641	6.230	46	4.589	22	4886.37	5922.87	FROM BRIDGE A9306 TO BRIDGE B0018
6.256	7.084	46	0.828	22	881.65	1068.67	FROM BRIDGE B0018 TO BRIDGE B0017
7.103	7.608	46	0.505	20	488.84	592.53	FROM BRIDGE B0017 TO BRIDGE B0013
7.629	15.139	46	7.510	20	7269.68	8811.73	FROM BRIDGE B0013 TO END OF PROJECT
0.000	15.139	46	15.139		2256.75		SURFACE IRREGULARITIES 150 TON/PER MILE
		46			350.50		2% SAFETY EDGE
		46	VAR.	VAR.	108.14	131	STATE ROUTES MM,N,EE,HH,PP
TOTAL					17983.76	18596.99	
PAY TOTAL					17983.8	18597	

SHOULDER TREATMENT									
LOG MILE		ROUTE	COUNTY	LENGTH (MI)	WIDTH (FT)	DEPTH (IN)	GRAVEL (A) OR CRUSHED STONE (B) (TONS)	PERMANENT AGGREGATE EDGE TREATMENT (TONS)	Remarks
0.000	1.613	46	NODAWAY	1.613	12	3	1514.07		BEG. JOB TO BRIDGE A9306
1.641	6.230	46	NODAWAY	4.589	12	3	4307.54		FROM BRIDGE A9306 TO BRIDGE B0018
6.256	7.084	46	NODAWAY	0.828	12	3	777.22		FROM BRIDGE B0018 TO BRIDGE B0017
7.103	7.608	46	NODAWAY	0.505	4	2		105.34	FROM BRIDGE B0017 TO BRIDGE B0013
7.629	15.139	46	NODAWAY	7.510	4	2		1566.53	FROM BRIDGE B0013 TO END OF JOB
TOTAL							6598.83	1671.87	
PAY TOTAL							6599	1671.9	

ASPHALT RESEARCH
1 LUMP SUM
\$6,500.00

ASPHALT RESEARCH
1 LUMP SUM
\$10,000.00

1 REVISD



DATE PREPARED 12/15/2025	
ROUTE 46	STATE MO
DISTRICT NW	SHEET NO. 3

COUNTY
ATCHISON/NODAWAY

JOB NO.
JNW0041


CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DATE	DESCRIPTION	ASPHALT RESEARCH	REVISION						
12-15-25									

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION



105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)