REMOVAL OF IMPROVEMENTS			
STATION	STATION	LOCATION	DESCRIPTION
7+50	9+48	RT	1138 SF SHOULDER REMOVAL
7+50	9+76	LT	1342 SF SHOULDER REMOVAL
10+16	12+25	RT	1255 SF SHOULDER REMOVAL
10+45	12+25	LT	1043 SF SHOULDER REMOVAL
7+22	12+38	RT	GUARDRAIL REMOVAL
7+54	12+68	LT	GUARDRAIL REMOVAL
LOCATIONS AND QUANTITIES ARE APPROXIMATE FOLLOW SEC 202.30 NO DIRECT PAYMENT WILL BE MADE FOR SAW CUTS REQUIRED FOR REMOVAL			
LUMP SUM - 1			

BASE AND PAVEMENT											
SHEET	STA	STA	LOC	COLDMILLING BIT PVMT 3" THICK OR LESS (SY)	TYPE 1 AGG. BASE (6" THICK) (SY)	TACK COAT (GAL)	2" BITUMINOUS PAVEMENT PG64-22 (BP-1) (TON)	6" BITUMINOUS PAVEMENT PG64-22 (BASE) (TON)	A2 SHOULDER (SY)	BIT. SHOULDER RUMBLE STRIP (STA)	REMARKS
4	7+50	9+50	CL	533.3		53.3					
4	7+50	12+25	CL				137.1				
4	7+50	12+25	RT AND LT						633.3	9.5	
4	9+50	10+50	CL		266.7			86.4			
4	10+50	12+25	CL	466.7		46.7					
	SUBTOTAL			1000	266.7	100	137.1	86.4	633.3	9.5	
	PAY TOTAL			1000	267	100	137.1	86.4	633.3	9.5	

*BP-1 - 1.948 Ton/cy

*Base - 1.943 Ton/cy

MOBILIZATION
LUMP SUM -1

CONTRACTOR FURNISHED SURVEYING AND STAKING
LUMP SUM - 1

DRAINAGE STRUCTURES 2 REVISED											
SHEET	STA	STA	LOC	24" GROUP C PIPE (FT)	30" GROUP C PIPE (FT)	24 IN. OR ALLOWED SUBSTITUTE GROUP C FLARED END SECTION (EACH)	30 IN. OR ALLOWED SUBSTITUTE GROUP C FLARED END SECTION (EACH)	24 IN. FLAPGATE (EACH)	30 IN. FLAP GATE (EACH)	MODIFIED LINEAR GRADING TYPE 2 (STA)	REMARKS
4	8+49		RT			1					
4	8+49	9+41	RT	91.8						0.5	
4	9+41		RT					1			
4	9+80		RT					1			
4	9+80	10+73	RT	92.9						0.5	
4	10+73		RT			1					
4	9+60		LT				1				
4	9+60	10+29	LT		69.6					0.5	
4	10+29		LT						1		
4	10+75		LT						1		
4	10+75	11+23	LT		49.3					0.5	
4	11+23		LT				1				
	TOTALS			184.7	118.9	2	2	2	2	2	
	PAY TOTALS			185	119	2	2	2	2	2	

EARTHWORK						
SHEET	BEGIN STATION	END STATION	CLASS A EXCAVATION CY	COMPACTING EMBANKMENT CY	EMBANKMENT IN PLACE CY	REMARKS
4	7+50	12+25	75	60	260	
4	7+50	12+25			50	GUARDRAIL WIDENING
	TOTAL		75	60	310	

POROUS BACKFILL							
SHEET	STA	STA	DEPTH (FT)	LENGTH FROM CULVERT (FT)	WIDTH (FT)	POROUS BACKFILL (CY)	REMARKS
9	9+35.66	10+29.22	10	5	67.41	225.3	WEST
9	9+75.62	10+70.41	10	5	67.41	228.3	EAST
	SUBTOTAL					453.6	
	PAY TOTAL					454.0	

GUARDRAIL						
SHEET	STA	STA	LOC	MGS GUARDRAIL LF	TYPE A CRASHWORTHY END TERMINAL (MASH) (EACH)	REMARKS
4	8+01.84	10+66.50	RT	143.72	2	
4	9+31.52	11+97.83	LT	145.41	2	
			TOTAL	290	4	

SUMMARY OF QUANTITIES
SHEET 1 OF 3

STATE OF MISSOURI
ERIC BRAFF
NUMBER E-30103
REGISTERED PROFESSIONAL ENGINEER

DATE PREPARED 01/09/2026
ROUTE 25 | STATE MO
DISTRICT SE | SHEET NO. 3
COUNTY CAPE GIRARDEAU
JOB NO. J9P3772
CONTRACT ID.
PROJECT NO.
BRIDGE NO. A9731

DESCRIPTION | DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

Cape Girardeau, MO Office
3437 William St, Cape Girardeau, MO 63701
Certificate of Authority: F2007028644
Phone: 573-222-5632 / BFWengineers.com
Copyright © Bacon Farmer Workman Engineering & Testing, Inc.

$FILE$ $TIME$ $DATE$ REV.