PAVEMENT

SHEET NO.	STA TO STA		LOCATION		ALTERNATE PAVEMENT A OR B +	TYPE A2 SHOULDER, ALTERNATE C OR D ++	TYPE 5 AGGREGATE FOR BASE (6 IN. THICK)	CONCRETE PAVEMENT (8 1/2 IN. NON-REINFORCED, 15 FT. JOINTS)	CONTRAST CONCRETE PAVEMENT, 8.5"	TYPE A2 SHOULDER	3 IN. CONCRETE MEDIAN STRIP	6 IN. CONCRETE MEDIAN STRIP	INTEGRAL CURB (OVER 6 IN. HEIGHT) TYPE A	CONCRETE CURB LOW PROFILE TYPE E	SHOULDER RUMBLE STRIP
					SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	LF	LF	STA
4	86+60.00	93+50.00	ROUTE K	LT/RT	989.5	856.2	1846								13.8
5	93+50.00	107+00.00	ROUTE K	LT/RT	2506.7	1630.8	4138								27.0
6	107+00.00	120+50.00	ROUTE K	LT/RT	3035.3	1433.3	4469								27.0
7	120+50.00	134+00.00	ROUTE K	LT/RT	2509.2	1678.2	4187								27.0
8	134+00.00	147+50.00	ROUTE K	LT/RT	3579.0	1661.2	5240								27.0
9	147+50.00	161+00.00	ROUTE K	LT/RT	2431.2	1793.9	4225								27.0
10	161+00.00	174+50.00	ROUTE K	LT/RT	1073.1	989.4	5023	1712.4	1137.5	230.2			251	1732	2.6
10	500+00.00	503+03.70	RAB WEST	LT/RT			1899	1899.0		238.6	7.4	218.8			4.4
10	600+88.95	605+03.03	RAB EAST	LT/RT			947	946.6		48.0	10.9	79.0			0.7
10	700+90.11	701+65.07	RAB SOUTH	LT/RT			459	458.9				63.1			
11	174+50.00	188+00.00	ROUTE K	LT/RT	3435.9	1372.2	7058	2149.3	70.6	339.6		248.1		531	10.5
12	188+00.00	201+50.00	ROUTE K	LT/RT	4337.9	1673.8	6012								27.0
13	201+50.00	215+00.00	ROUTE K	LT/RT	4320.5	1421.9	5742								27.0
14	215+00.00	228+50.00	ROUTE K	LT/RT	2893.6	1773.0	6171	1504.6							27.0
15	228+50.00	242+00.00	ROUTE K	LT/RT	4968.4	1575.3	6544								27.0
16	242+00.00	248+00.00	ROUTE K	LT/RT	1807.9	606.3	2414								12.0
	TOTALS				**37888.2**	**18465.5**	**66372**	**8670.8**	**1208.1**	**876.4**	**18.3***	**609***	**251**	**2263**	**287.0**

NOTE: ALTERNATE PAVEMENT B - 8.5" PCCP OVER 6" TYPE 5 AGGREGATE BASE USED TO DESIGN THE PROJECT.
* FOR INFORMATION ONLY

+	ALTERNATE A	ALTERNATE B
	1 3/4" SP125C W/PG 70-22 OVER 3" SP190C W/PG 70-22 OVER 5 1/4" SP190C W/PG 64-22	8.5" PCCP AT 15 FT. JOINTS W/ 1 1/4" DOWELS

++	ALTERNATE C	ALTERNATE D
	TYPE 2 SHOULDER, HMA	TYPE 2 SHOULDER, PCCP

1 CONTRAST 6" TYPE A INTEGRAL CURB

1 REVISED

TYPE 5 AGGREGATE BASE (4 IN.)	
SCHEDULE	AGGREGATE BASE SY
SIDE STREETS AND ENTRANCES	8210
PAVEMENT - RELOCATED NOTRE DAME DRIVE	4479
TOTAL	**12689**

1 88

1105
88
1193

SIDE STREETS AND ENTRANCES

SHEET NO.	STATION	LOCATION		EXIST. SURFACE	TYPE 5 AGG. BASE (4 IN)	PAVED APPROACH (7 IN)	PAVED APPROACH (8 IN)	GRAVEL (A) OR CRUSHED STONE (B)	3 IN. CONCRETE MEDIAN STRIP	6 IN. CONCRETE MEDIAN STRIP	REMARKS
					SY	SY	SY	SY	SY	SY	
4	88+28.15	ROUTE K	RT	AGGREGATE				40			
4	91+09.26	ROUTE K	RT	AGGREGATE				323			
5	95+17.93	ROUTE K	LT	ASPHALT	701		701.1			26.8	CR 319
5	102+74.56	ROUTE K	RT	AGGREGATE				257			
5	102+96.17	ROUTE K	LT	AGGREGATE				23			
6	108+24.63	ROUTE K	RT	CONCRETE	137	136.8					
6	109+96.48	ROUTE K	RT	AGGREGATE				80			
6	111+26.48	ROUTE K	LT	AGGREGATE				28			
6	112+56.00	ROUTE K	RT	CONCRETE	268		267.6				GREENBRIER DR
6	114+53.36	ROUTE K	RT	ASPHALT	243		243.4				
6	116+17.91	ROUTE K	RT	AGGREGATE				114			
6	116+69.89	ROUTE K	RT	AGGREGATE				105			
6	117+29.42	ROUTE K	RT	CONCRETE	238		238.1				
6	118+15.35	ROUTE K	RT	ASPHALT	248		247.8				HILLVALE DR
6	119+81.85	ROUTE K	LT	AGGREGATE				19			
7	124+23.24	ROUTE K	RT	ASPHALT	270		269.6				FORESTER DR
7	126+15.99	ROUTE K	RT	AGGREGATE				74			
7	133+19.11	ROUTE K	RT	ASPHALT	67	67.3					
8	135+26.61	ROUTE K	RT	ASPHALT	89	88.9					
8	135+27.03	ROUTE K	LT	ASPHALT	708		708.0				CR 318
8	140+51.88	ROUTE K	LT	AGGREGATE				68			
8	147+14.18	ROUTE K	RT	ASPHALT	297		296.9				CR 206
9	160+22.68	ROUTE K	LT	AGGREGATE				24			
10	162+00.65	ROUTE K	LT	AGGREGATE				48			
10	163+29.02	ROUTE K	LT	ASPHALT	176		175.7				PARKWOOD LAKE ST
10	168+51.54	ROUTE K	LT	AGGREGATE				54			
11	604+47.14	RAB EAST	LT	ASPHALT	150	150.3					
11	178+98.99	ROUTE K	RT	ASPHALT	76	75.6					
11	187+79.57	ROUTE K	RT	ASPH/AGGR	17	16.8		46			
11	187+92.45	ROUTE K	LT	ASPHALT	71	70.6					
12	190+97.64	ROUTE K	RT	ASPH/AGGR	37	37.3		29			
12	192+37.49	ROUTE K	LT	ASPH/AGGR	313		312.9	5			SCHABBING LANE
12	192+91.86	ROUTE K	RT	AGGREGATE				101			
12	199+14.91	ROUTE K	LT	ASPH/AGGR	202		201.5	10			ONYX LANE
13	201+98.29	ROUTE K	RT	AGGREGATE				101			
13	202+81.19	ROUTE K	LT	CONCRETE	566		565.6				
13	204+54.79	ROUTE K	LT	ASPHALT	292		291.6				
13	206+30.37	ROUTE K	LT	ASPHALT	354		353.5				
13	207+97.50	ROUTE K	RT	AGGREGATE				53			
13	208+32.98	ROUTE K	LT	CONCRETE	169		169.2				
13	210+47.86	ROUTE K	RT	AGGREGATE				48			
13	210+48.08	ROUTE K	LT	CONCRETE	131		131.3				
13	214+82.70	ROUTE K	LT	ASPHALT	491		490.9				CR 317
15	229+55.17	ROUTE K	RT	ASPHALT	861		861.3				CR 203
15	229+85.28	ROUTE K	LT	AGGREGATE				18			
15	236+67.36	ROUTE K	LT	ASPHALT	347		347.3				CR 317
15	236+81.92	ROUTE K	RT	ASPHALT	247		247.4				ROBIN LANE
16	243+06.51	ROUTE K	RT	CONCRETE	311		311.3				JIMMY JOHN'S ENTRANCE
16	245+23.66	ROUTE K	RT	CONCRETE	133		133.2				
16	247+40.00	ROUTE K	RT						36		
	TOTALS				**8210***	**644**	**7,565**	**1,668**	**35.5***	**26.8***	

* FOR INFORMATION ONLY

PAVEMENT - RELOCATED NOTRE DAME DRIVE

SHEET NO.	STA TO STA		LOCATION		7" PCCP	TYPE 5 AGG. BASE (4 IN)	UPRIGHT CURB AND GUTTER
					SQ YD	SQ YD	LF
10	701+60	710+56	RAB SOUTH	LT/RT	3981.1	4479	498
	TOTALS				**3,981.1**	**4479***	**498**

* FOR INFORMATION ONLY

1 UPRIGHT 6" CURB AND GUTTER

LF
1926
1,926

CONCRETE MEDIAN

SCHEDULE	3 IN. CONCRETE MEDIAN STRIP	6 IN. CONCRETE MEDIAN STRIP
	SY	SY
PAVEMENT	18.3	609
SIDE STREETS AND ENTRANCES	35.5	26.8
TOTAL	**53.8**	**635.8**

TUBULAR MARKERS

SHEET NO.	TUBULAR MARKERS EA	REMARKS
10	12	TUBULAR MARKERS INSTALLED AT CENTER POINTS OF SPLITTER ISLANDS AT THE ROUNDABOUT
11	1	
TOTAL	**13**	

REMOVAL OF RUMBLE STRIPS

STA TO STA		LOCATION		COLDMILLING BITUMINOUS PAVEMENT (3 IN, THICK OR LESS)	SP 125C W/PG 70-22
				SY	TONS
86+60.00	146+65.00	ROUTE K	RT	972	106.4
86+60.00	147+72.00	ROUTE K	LT	1277	139.8
TOTALS				**2249**	**246.2**

DISCLAIMER
THE PROFESSIONAL WHOSE SIGNATURE AND PERSONAL SEAL APPEAR HEREON ASSUMES RESPONSIBILITY ONLY FOR WHAT APPEARS ON THIS PAGE, AND DISCLAIMS (PURSUANT TO SECTION 327.411 RSMO) SPECIFICATION, ESTIMATES, REPORTS, OR OTHER DOCUMENTS OR INSTRUMENTS NOT SEALED BY THE UNDERSIGNED PROFESSIONAL RELATING TO OR INTENDED TO BE USED FOR ANY PART OR PARTS OF THE PROJECT TO WHICH THIS PAGE REFERS.

QUANTITY SHEET
SHEET 3 OF 9

STATE OF MISSOURI
MICHAEL L. BROWN
NUMBER 2001015611
REGISTERED PROFESSIONAL ENGINEER

THIS SHEET HAS BEEN SIGNED, SEALED & DATED ELECTRONICALLY.

DATE PREPARED 2/5/2026
ROUTE K | STATE MO
DISTRICT SE | SHEET NO. 3
COUNTY CAPE GIRARDEAU
JOB NO. J9S3847
CONTRACT ID.
PROJECT NO.
BRIDGE NO.

DESCRIPTION
DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

TREKK DESIGN GROUP, LLC
1411 East 104th St.
Kansas City, MO 64131
Tel (816) 874-4655
Fax (816) 874-4675
www.trekkdesigngroup.com
Missouri Cert. of Authority 2002010300

G:\23-0234 MoDOT SE Route K\Design\CADD\Sheets\FINAL\003_QU_01-08_J9S3847_I1.dgn 9:35:23 AM 2/5/2026