



BENJAMIN A. ROSS  
REGISTERED PROFESSIONAL ENGINEER E-30054

DATE PREPARED  
1/5/2026

ROUTE AC STATE MO  
DISTRICT CD SHEET NO. 3

COUNTY  
BOONE

JOB NO.  
JCD0123

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DATE	DESCRIPTION
2/9/26	PAVEMENT MARKING ITEM CHANGE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION  
  
 105 WEST CAPITOL JEFFERSON CITY, MO 65102  
 1-888-ASK-MODOT (1-888-275-6636)

DELIVERING YOUR VISION™  
 1115 Fay Street, Columbia, MO 65201  
 572-449-2848 • www.esandc.com  
 MO Land Surveying Corp. # 22040404872  
 MO Engineering Corp. # 22040404872

SUMMARY OF QUANTITY SHEET  
SHEET 5 OF 10

APPROACHES, CURB & GUTTER, AND MEDIAN STRIP (CONTINUED)

STA.	STA.	LOCATION	8 IN. NON-REINF CONCRETE PAVEMENT	8 IN. PAVED APPROACH	6 IN. CONCRETE MEDIAN STRIP	8 IN. TYPE A INTEGRAL CURB	TYPE 5 AGGREGATE BASE	DELINEATOR POST (WHITE)	REMARKS
			(SQYD)	(SQYD)	(SQYD)	(LF)	(SY)	(EACH)	
92+90.71	93+05.31	LT	4.1		3				CONDUIT PATCH
93+02.15	93+07.53	LT			3			2	NW QUAD BEARFIELD
93+66.04	93+83.79	LT	4.5		3				CONDUIT PATCH
99+37.42	99+44.74	LT					9		
99+48.71	99+49.71	LT					3		
99+86.37	99+89.16	LT					4		
99+97.89	100+04.25	LT					7		
99+06.48	99+45.80	RT		3.3			14	3.3	
103+84.29	104+09.09	RT					27		
104+17.42	104+21.54	RT					6		
104+81.76	105+04.60	RT			16				Ponderosa Dr.
105+23.92	105+27.20	RT					5		
105+34.16	105+60.95	RT					30		
108+62.44	108+63.15	LT					1		
108+73.23	108+76.13	LT					12		
109+18.33	109+21.32	LT					15		
109+29.95	109+37.17	LT					8		
108+55.80	108+62.73	RT					6		
108+71.58	108.75.16	RT					10		
109+17.08	109+17.60	RT					1		
109+27.40	109+33.64	RT					5		
SUBTOTAL			8.6	3.3	25	163	6.3	5	
SUBTOTAL TABLE 1			345.4	372.3	63	749	717.7	9	
TOTAL			354	375.6	88	912	738	14	

1 PREFORMED THERMOPLASTIC

PAVEMENT MARKING

STA.	STA.	LOCATION	PLURAL COMPONENT	PAVEMENT MARKING	PAVEMENT MARKING	REMARKS
			24 IN WHITE (LF)	REMOVAL (LF)	24 IN X 36 IN YIELD TRIANGLE (EACH)	
13+21.00	13+25.00			46		EASTBOUND STOP BAR ON ROUTE AC
13+11.10	13+11.10		39			EASTBOUND STOP BAR ON ROUTE AC
13+52.97	13+85.63		33	33		SB BUTTONWOOD AT RTE AC
14+40.00	14+48.00			34		WB RTE AC LANE AT BUTTONWOOD
14+54.63	14+54.63		36			WB RTE AC TURN LANE AT BUTTONWOOD
104+68.57	104+81.57		13	13		PONDEROSA LT TURN LANE ONTO RTE AC
105+00.53	105+20.90				7	RT MERGE TO RTE AC
TOTAL			121	126	7	

UTILITY ITEMS

STA.	STA.	LOCATION	ADJUST	REMARKS
			WATER VALVE FRAME AND COVER (LF)	
14+06.92			1	NE QUAD BUTTONWOOD DR.
16+82.56			2	IN SIDEWALK N ROUTE AC
TOTAL			3	

CONTRACTOR FURNISHED SURVEYING & STAKING  
1 LUMP SUM

MOBILIZATION  
1 LUMP SUM

ADDITIONAL MOBILIZATION FOR SEEDING  
3 EACH