CONCRETE ISLANDS

SHEET	ROUTE	BEGIN STA.	END STA.	LOCATION	CONCRETE MEDIAN STRIP (3") (SY)	TYPE A CURB AND GUTTER (LF)	REMARKS
~~11~~	~~HWY 67~~	~~573+08.79~~	~~573+75.62~~	~~LT/RT~~	~~132.3~~		
~~13~~	~~HWY 67~~	~~582+52.32~~	~~584+20.05~~	~~LT/RT~~	~~415.9~~		
13	HWY 67	582+81.92	583+75.00	LT		412.0	GRASS ISLAND
13	HWY 67	583+62.17	583+93.26	RT	63.8		
13	HWY 67	583+97.12	584+40.38	RT	87.4		
14	HWY 67	602+04.65	602+53.04	LT	95.7		
14	HWY 67	602+54.37	603+00.66	LT	99.7		
~~14~~	~~HWY 67~~	~~602+53.42~~	~~605+86.00~~	~~LT/RT~~	~~1107.2~~		
14	HWY 67	603+09.35	603+50.63	RT	136.4		
~~16~~	~~HWY 67~~	~~612+49.08~~	~~613+10.13~~	~~LT/RT~~	~~127.6~~		
				PROJECT TOTALS	2,266.0	412	

1 REVISED

63.8
87.4
95.7
99.7
136.4
483.0

TEMPORARY EROSION CONTROL

SHEET	ROUTE	BEGIN STA.	END STA.	LOCATION	SILT FENCE (LF)	ROCK DITCH CHECKS (LF)	ALTERNATING ROCK DITCH (LF)	SEDIMENT REMOVAL (CY)	REMARKS
39	SB HWY 67	571+76.73		CL			10	1.0	1 DITCH CHECK
39	SB HWY 67	572+57.43	573+85.12	CL		20		2.0	2 DITCH CHECKS AT 160' SPACING
39-40	SB HWY 67	572+94.1	583+06.89	RT		180		18.0	18 DITCH CHECKS AT 60' SPACING
39-40	SB HWY 67	574+30.11	575+80.00	CL			40	4.0	4 DITCH CHECKS AT 50' SPACING
39-40	SB HWY 67	574+70.90	582+21.28	CL			50	5.0	5 DITCH CHECKS AT 150' SPACING
40	67/RTE A	581+77.33	22+83.62	LT		50		5.0	5 DITCH CHECKS AT 50' SPACING
40	SB HWY 67	582+50.22		CL		10		1.0	1 DITCH CHECK
40	RTE A	23+08.77		LT		10		1.0	1 DITCH CHECK
40	NB HWY 67	584+35.93	585+22.73	LT		30		3.0	3 DITCH CHECKS AT 43' SPACING
40	NB HWY 67	584+50.15		CL		10		1.0	1 DITCH CHECK
40	SB HWY 67	584+59.89		RT		10		1.0	1 DITCH CHECK
40	NB HWY 67	586+74.00	589+76.76	LT		30		3.0	3 DITCH CHECKS AT 150' SPACING
40	SB HWY 67	585+94.53	590+44.81	CL			40	4.0	4 DITCH CHECKS AT 150' SPACING
41	NB HWY 67	596+00.12		LT		10		1.0	1 DITCH CHECK
41	SB HWY 67	596+26.73	600+76.17	CL			40	4.0	4 DITCH CHECKS AT 150' SPACING
41	SB HWY 67	597+02.90	602+25.78	RT	529	20		7.3	SILT FENCE AND 2 DITCH CHECKS
41	SB HWY 67	602+25.65		CL		10		1.0	1 DITCH CHECK
41	SB HWY 67	603+66.71	603+82.33	RT		40		4.0	4 DITCH CHECKS AT 17' SPACING
41-42	NB HWY 67	604+55.94	610+23.06	LT		50		5.0	5 DITCH CHECKS AT 150' SPACING
41-42	NB HWY 67	605+20.30	609+76.79	CL			40	4.0	4 DITCH CHECKS AT 150' SPACING
42	NB HWY 67	611+19.80	611+98.89	CL			30	3.0	3 DITCH CHECKS AT 37' SPACING
42	NB HWY 67	611+72.39	613+22.89	LT		30		3.0	3 DITCH CHECKS AT 100' SPACING
42	SB HWY 67	612+38.07		CL		10		1.0	1 DITCH CHECK
42	SB HWY 67	613+55.39		CL		10		1.0	1 DITCH CHECK
42	SB HWY 67	615+00.00	616+54.38	CL			2	2.0	2 DITCH CHECKS AT 150' SPACING
				PROJECT TOTALS	529	530	252	85	

PAVEMENT

SHEET	ROUTE	BEGIN STA.	END STA.	LOCATION	9" CONCRETE PAVEMENT (15' JOINTS) (SY)	TYPE 5 AGGREGATE FOR BASE (6") (SY)	REMARKS
4-5	HWY 67	572+79.20	583+28.29	RT/LT	2,979.4	2,979.4	NB DECEL LANE / SB LT TURN LANE TO RTE A
4-5	HWY 67	573+00.00	584+59.10	RT	2,212.8	2,212.8	SB DECEL LANE
5	HWY 67	582+24.07	590+23.85	LT	1,544.8	1,544.8	NB DECEL LANE TO RTE A
6	HWY 67	597+28.47	604+11.55	RT	1,804.1	1,804.1	SB DECEL LANE TO RTE C
6-7	HWY 67	601+73.59	613+22.00	LT	2,207.7	2,207.7	NB DECEL LANE TO RTE C
6-7	HWY 67	603+37.96	613+39.59	RT/LT	3,548.4	3,548.4	SB DECEL LANE / NB LT TURN LANE TO RTE C
				PROJECT TOTALS	14,297.2	14,297.2	
				A2 SHOULDER SUBTOTALS		1,485.9	
				PAY TOTALS	14,297.2	15,783	

EARTHWORK

SHEET	ROUTE	BEGIN STATION	END STATION	LOCATION	COMPACTING EMBANKMENT (CY)	UNCLASSIFIED EXCAVATION (CY)	COMPACTING IN CUT (STA)	REMARKS
4-7	HWY 67	571+75.00	617+00.00	LT/RT	4521.00	7397.00	41.00	
				PROJECT TOTALS	4,521	7,397	41	

1 REVISED 03-11-2026

SUMMARY OF QUANTITIES
SHEET 2 OF 7

STATE OF MISSOURI
MARK C. FISHER
NUMBER PE-2797
PROFESSIONAL ENGINEER
THIS SHEET HAS BEEN SIGNED, SEALED AND DATED ELECTRONICALLY.

DATE PREPARED 3/11/2026
ROUTE 67 | STATE MO
DISTRICT SE | SHEET NO. 3
COUNTY MADISON
JOB NO. JSE0069
CONTRACT ID.
PROJECT NO.
BRIDGE NO.

DESCRIPTION | DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

GARVER, LLC.
7509 NW TIFFANY SPRINGS PARKWAY, SUITE 200
KANSAS CITY, MO 64153
PHONE: (816) 298-6465
CERTIFICATE OF AUTHORITY NO. 2008013090

LIGHTING POLE AND EQUIPMENT

POLE NUMBER	ROUTE	STATION	OFFSET	POLE TYPE AT DESIGN 2 45 FT (EACH)	POLE FOUNDATION 45 FT (EACH)	BRACKET ARM 15 FT (EACH)	LUMINAIRE LED-B (EACH)	CABLE #10 AWG, 1C POLE & BRACKET (LF)
ROUTE A								
1A01	67	584+75	75'LT	1	1	1	1	120
1B01	A	22+60	34'LT	1	1	1	1	120
1B02	67	582+90	75'RT	1	1	1	1	120
1B03	67	580+90	75'RT	1	1	1	1	120
ROUTE C								
1A01	67	602+46	144'LT	1	1	1	1	120
1B01	67	603+75	85'LT	1	1	1	1	120
1B02	67	606+20	82'LT	1	1	1	1	120
1B03	C	7+00	33'LT	1	1	1	1	120
1B04	67	602+05	85'RT	1	1	1	1	120
PROJECT TOTALS				9	9	9	9	1080

LIGHTING CABLE/CABLE-CONDUIT

FROM	TO	CENTER TO CENTER (LF)	CABLE-CONDUIT 1 IN. - 2C#8 AWG & 1 BARE NEUTRAL (LF)	TYPE I TRENCHING (LF)	CABLE #2 AWG, 1C POWER CABLE (LF)	REMARKS
ROUTE A						
EX PS1	PS1	63			318	3 - 1C#2 POWER CABLES
PS1	CONT1	10			78	3 - 1C#2 POWER CABLES
CIRCUIT 1A						
CONT1	1A01	56	72	62		CIRCUIT 1A
CIRCUIT 1B						
CONT1	PB1	126	137	129		CIRCUIT 1B
PB1	PB2	55	61			CIRCUIT 1B
PB2	1B01	11	20	12		CIRCUIT 1B
PB2	PB3	236	242	234		CIRCUIT 1B
PB3	PB4	141	147			CIRCUIT 1B
PB4	1B02	91	104	92		CIRCUIT 1B
PB4	1B03	111	125	112		CIRCUIT 1B
ROUTE C						
EX PS2	PS2	58			303	3 - 1C#2 POWER CABLES
PS2	CONT2	13			87	3 - 1C#2 POWER CABLES
CIRCUIT 1A						
CONT2	PB1	36	47	39		CIRCUIT 1A-TRENCH FOR CIRCUIT 1B
PB1	1A01	13	22	14		CIRCUIT 1A
CIRCUIT 1B						
CONT2	PB1	36	49			CIRCUIT 1B, USE TRENCH FROM CIRCUIT 1A
PB1	PB2	36	42			CIRCUIT 1B
PB2	1B01	119	133	120		CIRCUIT 1B
1B01	PB3	25	35	26		CIRCUIT 1B
PB3	1B02	221	241	222		CIRCUIT 1B
PB3	PB4	162	168			CIRCUIT 1B
PB4	1B03	107	121	108		CIRCUIT 1B
1B03	PB5	6	15	7		CIRCUIT 1B
PB5	PB6	50	56			CIRCUIT 1B
PB6	1B04	118	132	119		CIRCUIT 1B
PROJECT TOTALS			1,970	1,296	790	

240 VOLT BASE MOUNTED CONTROL STATION

ROUTE	STATION	OFFSET	(EACH)	BREAKER (AMPS) MAIN	CIRCUIT 1A	CIRCUIT 1B	CIRCUIT 2A	CIRCUIT 2B
A (CONT1)	584+67	130'LT	1	100	15	15	15	15
67 (CONT2)	602+15	156'LT	1	100	15	15	15	15
PROJECT TOTAL			2					

RIGID CONDUIT

FROM	TO	CENTER TO CENTER (LF)	2 IN IN TRENCH (LF)	4 IN IN TRENCH (LF)	4 IN PUSHED (LF)
ROUTE A					
EX PS1	PS1	63	67		
PS1	CONT1	10	18		
PB1	PB2	55		27	26
PB3	PB4	141		49	90
ROUTE C					
EX PS2	PS2	58	62		
PS2	CONT2	13	21		
PB1	PB2	36		7	27
PB3	PB4	162		91	69
PB5	PB6	50		48	
PROJECT TOTALS			168	222	212

1 REVISED

PULL BOX, PREFORMED CLASS 1

~~PULL BOX, CONCRETE~~

* ITEMS FOR WHICH SEPARATE PAYMENT WILL NOT BE MADE

PULL BOX NUMBER	ROUTE	STATION	OFFSET	* DRAIN TYPE	(EACH)
ROUTE A					
1	A	22+50	20'RT	I	1
2	A	22+50	36'LT	I	1
3	67	582+00	65'LT	I	1
4	67	582+00	75'RT	I	1
ROUTE C					
1	67	602+53	154'LT	I	1
2	67	602+89	154'LT	I	1
3	67	604+00	85'LT	I	1
4	67	604+00	77'RT	I	1
5	C	7+05	31'LT	I	1
6	C	7+05	19'RT	I	1
PROJECT TOTAL					10

TYPE 2 POWER SUPPLY ASSEMBLY, LIGHTING ONLY

ROUTE	STATION	OFFSET	(EACH)	VOLT
A (PS1)	584+67	140'LT	1	240/120
C (PS2)	602+13	143'LT	1	240/120
PROJECT TOTAL			2	

1 REVISED 03-12-2026

SUMMARY OF QUANTITIES
SHEET 6 OF 7

STATE OF MISSOURI
MARK C. FISHER
NUMBER PE-22071
PROFESSIONAL ENGINEER
THIS SHEET HAS BEEN SIGNED, SEALED AND DATED ELECTRONICALLY.

DATE PREPARED 3/12/2026
ROUTE 67 | STATE MO
DISTRICT SE | SHEET NO. 3
COUNTY MADISON
JOB NO. JSE0069
CONTRACT ID.
PROJECT NO.
BRIDGE NO.

DESCRIPTION
DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

GARVER, LLC.
7509 NW TIFFANY SPRINGS
PARKWAY, SUITE 200
KANSAS CITY, MO 64153
PHONE: (816) 298-6465
CERTIFICATE OF AUTHORITY
NO. 2008013090