GUARDRAIL

STATION	ROADWAY	MGS GUARDRAIL FT	TYPE A CET (MASH) EA	MGS BRIDGE APPROACH TRANSITION SECTION (REGULAR/NO CURB) EA	COMMENTS
	WB			1	NE CORNER A2725 BUILD GUARDRAIL
	WB	50.0			NE A2725 BUILD GUARDRAIL
	WB			1	SE CORNER A2725 BUILD GUARDRAIL
	WB	87.5			SE CORNER A2725 BUILD GUARDRAIL
	EB			1	NE CORNER A8163 BUILD TEMPORARY GUARDRAIL
	EB	87.5			NE CORNER A8163 BUILD TEMPORARY GUARDRAIL
	EB		1		NE CORNER A8163 BUILD TEMPORARY GUARDRAIL
	EB			1	SE CORNER A8163 BUILD TEMPORARY GUARDRAIL
	EB		1		SE CORNER A8163 BUILD TEMPORARY GUARDRAIL
	WB			1	NW CORNER BRIDGE A5007 BUILD TEMPORARY GUARDRAIL
	WB		1		NW CORNER BRIDGE A5007 BUILD TEMPORARY GUARDRAIL
	WB			1	SW CORNER BRIDGE A5007 BUILD TEMPORARY GUARDRAIL
	WB	87.5			SW CORNER BRIDGE A5007 BUILD TEMPORARY GUARDRAIL
	WB		1		SW CORNER BRIDGE A5007 BUILD TEMPORARY GUARDRAIL
	EB			1	NW CORNER BRIDGE A2726 BUILD GUARDRAIL
	EB	62.5			NW CORNER BRIDGE A2726 BUILD GUARDRAIL
	EB			1	SW CORNER BRIDGE A2726 BUILD GUARDRAIL
	EB	62.5			SW CORNER BRIDGE A2726 BUILD GUARDRAIL
	SUBTOTALS	437.5	4	8	
	PAY TOTALS	438.0	4.0	8.0	

ASPHALT

LOCATION	STATION BEGIN	STATION END	AREA SF	2" SP125C 70-22 TONS	TACK COAT GAL	2" COLDMILL SY	COMMENTS
BR A2725	688+63.74	689+13.74	1900	3.88	21.1	211.1	WEST END OF BRIDGE - SHEET 004
BR A2725	692+82.93	692+32.93	1900	3.88	21.1	211.1	EAST END OF BRIDGE - SHEET 004
BR A2726	766+18.66	765+68.66	1900	3.88	21.1	211.1	WEST END OF BRIDGE - SHEET 006
BR A2726	769+68.66	769+18.66	1900	3.88	21.1	211.1	EAST END OF BRIDGE - SHEET 006
			TOTAL	15.5	84	844	

A2 SHOULDER

LOCATION	STATION BEGIN	STATION END	A2 SHOULDER AREA S.Y.	6" TYPE 5 SHOULDER AGGREGATE FOR BASE S.Y.	COMMENTS
EB	710+63.31 R2	714+53.61 R2	43.44	43.44	A2 SHOULDER REPLACEMENT - PHASE 3
WB	717+71.76 R2	721+70.98 R2	44.33	44.33	A2 SHOULDER REPLACEMENT - PHASE 3
WB	801+29.95 R2	804+30.22 R2	33.33	33.33	A2 SHOULDER REPLACEMENT - PHASE 3
EB	807+27.56 R2	810+00.13 R2	30.33	30.33	A2 SHOULDER REPLACEMENT - PHASE 3
		TOTAL	151.43	151.43	
		PAY TOTAL	151.4	151	

EARTHWORK

ROADWAY	START STA	END STA	CONST. PHASE	CL. A EXCAVATION CY	COMPACTING EMBANKMENT CY	ENBANKMENT IN PLACE CY	EXCESS CY	COMMENTS
710+63.28 R2	721+70.98 R2	X-OVER 1	1	281	224.8	857.2		CONSTRUCT X-OVER 1
801+29.94 R2	810+00.10 R2	X-OVER 2	1	229	183.2	22.8		CONSTRUCT X-OVER 2
710+63.28 R2	721+70.98 R2	X-OVER 1	3	1082	337.2	744		REMOVE X-OVER 1
801+29.94 R2	810+00.10 R2	X-OVER 2	3	206	274.8		69	REMOVE X-OVER 2
			TOTALS	1798.0	1020.0	1624.0	69.0	
			PAY TOTALS	1800	1020	1625	69*	

*FOR INFORMATIONAL USE ONLY

0	744	744
745.2	880.0	206
745	880	950.0
		950*

1 REVISED

SUMMARY OF QUANTITIES
SHEET 3 OF 4

STATE OF MISSOURI
CHRISTOPHER ALAN WEST
NUMBER PE-2014017034
PROFESSIONAL ENGINEER
03/16/2026 12:47:34 PM
CHRISTOPHER ALAN WEST - CIVIL
MO-PE-2014017034

DATE PREPARED
3/16/2026

ROUTE	STATE
24	MO
DISTRICT	SHEET NO.
KC	3

COUNTY
JACKSON

JOB NO.
JKU0038

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DATE	DESCRIPTION

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)