MOBILIZATION
PAY TOTAL = 1 LUMP SUM

CONTRACTOR FURNISHED SURVEYING & STAKING
PAY TOTAL = 1 LUMP SUM

REMOVAL OF IMPROVEMENTS		
LOCATION OR LOG MILE	ITEM	QUANTITY
I-29 (NB/SB) AND MO-169 (NB/SB)	GUARDRAIL	2070 LF
MO-169 (NB/SB)	PAVED DITCH	110 LF
I-29 (NB/SB) AND MO-169 (NB/SB)	SAW CUTS	300 LF
I-29 (NB/SB)	SIGNS (SALVAGE)	2 EA
TOTAL	1	LUMP SUM

1

TEMP. TRAFFIC BARRIER SUMMARY (FOR INFORMATION ONLY)				
BRIDGE PROJECT NO.	PHASE	TEMP. TRAFFIC BARRIER (FT)	TEMP. TRAFFIC BARRIER RELOCATION (FT)	REMARKS
A17445	1	1055		I-29 NB
	2		1055	I-29 NB
A17446	1	856		I-29 SB
	2		856	I-29 SB
A35273	1	615		US-169 NB
	2		615	US-169 NB
A35283	1	614		US-169 SB
	2		614	US-169 SB
	TOTAL	3140	3140	

GUARDRAIL														
BEGIN ± LOG	END ± LOG	LOCATION	MGS GUARDRAIL (LF)	GUARDRAIL TYPE A (LF)	BRIDGE ANCHOR SECTION (EA)	TRANSITION SECTION (EA)	(MASH) TYPE A CRASHWORTHY END TERMINAL (EA)	TYPE A CRASHWORTHY END TERMINAL (EA)	END ANCHOR (EA)	MGS END ANCHOR (EA)	GUARD CABLE ANCHOR (EA)	MGS VERTICAL CONC. BARRIER TRANS. (EA)	CONC. TRAFFIC BARRIER TYPE B (LF)	REMARKS
18.838	18.869	I-29		284.25	1	1		1						NB UPSTREAM RIGHT SHLDR
18.838	18.869	I-29		284.25	1	1		1						NB UPSTREAM LEFT SHLDR
18.897	18.924	I-29		159.25	1	1			1					NB DOWNSTREAM RIGHT SHLDR
18.897	18.906	I-29			1									NB DOWNSTREAM LEFT SHLDR
109.799	109.852	I-29		334.25	1	1		1						SB UPSTREAM LEFT SHLDR
109.808	109.853	I-29		271.25	1	1		1						SB UPSTREAM RIGHT SHLDR
109.88	109.906	I-29		146.75	1	1			1					SB DOWNSTREAM LEFT SHLDR
11.732	11.862	MO-169		471.75	1	1		1						NB UPSTREAM LEFT SHLDR
11.82	11.862	MO-169		184.25	1	1		1						NB UPSTREAM RIGHT SHLDR
11.91	11.951	MO-169		234.25	1	1			1					NB DOWNSTREAM RIGHT SHLDR
114.923	114.991	MO-169		484.25	1	1		1						SB UPSTREAM LEFT SHLDR
114.958	114.991	MO-169		259.25	1	1		1						SB UPSTREAM RIGHT SHLDR
		TOTAL	0	3113.75	12	11	0	8	3	0	0	0	0	

TYPE 2 ROCK BLANKET								
BEGIN ± LOG	END ± LOG	LOCATION	AREA (SF)	DEPTH (SF)	FURNISHING TYPE 2 ROCK BLANKET (CY)	PLACING TYPE 2 ROCK BLANKET (CY)	PERMAMENT EROSION CONTROL GEOTEXTILE (SY)	REMARKS
11.919	11.926	MO-169	422.0	3	47	47	47	NB DOWNSTREAM LEFT SHLDR
11.908	11.919	MO-169	422.0	3	47	47	47	NB DOWNSTREAM RIGHT SHLDR
4.966	4.977	MO-169	422.0	3	47	47	47	SOUTHBOUND UPSTREAM LEFT SHLDR
4.966	4.977	MO-169	422.0	3	47	47	47	SOUTHBOUND UPSTREAM RIGHT SHLDR
				TOTAL	188	188	188	

1 REVISED

SUMMARY OF QUANTITIES

SHEET 1 OF 6

STATE OF MISSOURI
THANKAM MATHEW
NUMBER PE-2014000056
PROFESSIONAL ENGINEER
04/01/2026 7 PM
THANKAM.MATHEW - CIVIL
MO-PE-2014000056

DATE PREPARED 3/31/2026

ROUTE	STATE
VAR	MO
DISTRICT	SHEET NO.
KC	3

COUNTY VARIOUS

JOB NO. J4P3093

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION | DATE | REV.

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)