

FENCE									
SHEET NO.	FROM STA	TO STA	ROADWAY	LOCATION	CHAIN-LINK FENCE (RETAINING WALLS)	CHAIN-LINK FENCE (60 IN.)	BLACK POWDER COATED CHAIN-LINK FENCE (60 IN.)	DRIVE GATE (CHAIN-LINK)	WALK GATE (CHAIN-LINK)
					LF	LF	LF	EA	EA
8	711+62.11	712+04.63	I-270	WALL A9498	43				
8	712+78.62	713+30.47	I-270	WALL A9498	52				
8	711+59.70	712+23.77	I-270	WALL A9501	64				
8	712+99.55	713+65.73	I-270	WALL A9501	66				
10	735+56.00	737+37.00	I-270	RT		167		1	
10	737+37.00	739+45.00	I-270	RT			412		1
SUBTOTAL					225	167	412	1	1
PAY TOTAL					225	167	412	1	1

PAVEMENT EDGE TREATMENT					
SHEET NO.	FROM STA	TO STA	ROADWAY	LOCATION	PAVEMENT EDGE TREATMENT
					LF
9	722+76.85	732+00.00	I-270	LT	923
9, 10	731+95.00	738+60.00	I-270	RT	665
SUBTOTAL					1588
PAY TOTAL					1588


2

CONCRETE CURB RAMP								
SHEET NO.	FROM STA	TO STA	ROADWAY	LOCATION	APPROX. CONC. CURB RAMP AREA (FOR INFO ONLY)	CONCRETE CURB RAMP	TRUNCATED DOMES	NOTES
					SY	EA	SF	
11	10+25.56	10+50.42	LILAC AVE	LT	14.6	1	18	LARGE RADIUS PERPENDICULAR
11	11+14.99	11+41.41	LILAC AVE	LT	14.6	1	22	LARGE RADIUS PERPENDICULAR
11	11+32.93	11+60.46	LILAC AVE	RT	21.4	1	25	BLENDED TRANSITION
11	12+67.40	12+93.53	LILAC AVE	LT	14.5	1	22	LARGE RADIUS PERPENDICULAR
11	12+79.59	13+07.69	LILAC AVE	RT	15.3	1	25	LARGE RADIUS PERPENDICULAR
11	13+49.17	13+76.07	LILAC AVE	LT	16.9	1	24	LARGE RADIUS PERPENDICULAR
11	13+64.37	13+88.43	LILAC AVE	RT	14.7	1	18	LARGE RADIUS PERPENDICULAR
11	14+46.81	14+53.90	LILAC AVE	LT	4.7	1		GRADE TRANSITION SECTION
11	14+58.19	14+65.20	LILAC AVE	RT	4.7	1		GRADE TRANSITION SECTION
11	16+33.35	16+40.35	LILAC AVE	LT	4.7	1		GRADE TRANSITION SECTION
11	16+44.73	16+51.73	LILAC AVE	RT	4.7	1		GRADE TRANSITION SECTION
11	17+00.96	17+23.83	LILAC AVE	LT	13.9	1	15	LARGE RADIUS PERPENDICULAR
11	17+18.51	17+43.54	LILAC AVE	RT	16.1	1	21	LARGE RADIUS PERPENDICULAR
11	17+87.91	18+17.90	LILAC AVE	LT	16.1	1	28	LARGE RADIUS PERPENDICULAR
11	17+94.87	18+22.10	LILAC AVE	RT	15.0	1	24	LARGE RADIUS PERPENDICULAR
11	19+66.55	19+95.87	LILAC AVE	LT	15.7	1	27	LARGE RADIUS PERPENDICULAR
11	19+82.42	20+07.84	LILAC AVE	RT	14.3	1	21	LARGE RADIUS PERPENDICULAR
11	20+68.78	20+96.36	LILAC AVE	RT	15.3	1	24	LARGE RADIUS PERPENDICULAR
11	20+71.23	20+96.54	LILAC AVE	LT	14.3	1	21	LARGE RADIUS PERPENDICULAR
11	21+77.26	21+98.35	LILAC AVE	LT	12.7	1	15	LARGE RADIUS PERPENDICULAR
11	21+83.79	22+06.80	LILAC AVE	RT	13.1	1	16	LARGE RADIUS PERPENDICULAR
11	22+37.24	22+48.39	LILAC AVE	LT	7.0	1	12	SMALL RADIUS PERPENDICULAR
11	22+48.39	22+59.61	LILAC AVE	LT	7.1	1	12	SMALL RADIUS PERPENDICULAR
SUBTOTAL					291.4	23	390	
PAY TOTAL						23	390	

SLOPE PROTECTION							
SHEET NO.	FROM STA	TO STA	ROADWAY	LOCATION	AREA FYI	SLOPE PROTECTION	REMARKS
						SY	
8	711+99	712+84	I-270	RT	506.3	56	
8	712+18	713+05	I-270	LT	518.1	58	
SUBTOTAL						114	
PAY TOTAL						114	

SIDEWALK							
SHEET NO.	FROM STA	TO STA	ROADWAY	LOCATION	CONCRETE SIDEWALK, 4 IN.	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK)	REMARKS
					SY	SY	
11	10+05.10	10+25.56	LILAC AVE	LT	13.6	14	
11	11+41.41	12+67.40	LILAC AVE	LT	84.0	84	
11	11+60.46	12+79.59	LILAC AVE	RT	79.4	79	
11	13+76.07	14+46.81	LILAC AVE	LT	51.1	51	6.5' WIDTH
11	13+88.43	14+58.19	LILAC AVE	RT	50.4	50	6.5' WIDTH
11	16+40.35	17+00.96	LILAC AVE	LT	43.8	44	6.5' WIDTH
11	16+51.73	17+18.51	LILAC AVE	RT	48.2	48	6.5' WIDTH
11	18+17.90	19+66.55	LILAC AVE	LT	99.1	99	
11	18+22.10	19+82.42	LILAC AVE	RT	106.9	107	
11	20+96.36	21+83.79	LILAC AVE	RT	58.3	58	
11	20+96.54	21+77.26	LILAC AVE	LT	53.8	54	
SUBTOTAL					688.6	688	
PAY TOTAL					688.6	688	

SUMMARY OF QUANTITIES  
SHEET 11 OF 18



THIS SHEET HAS BEEN SIGNED, SEALED, AND DATED ELECTRONICALLY.  
DATE PREPARED: 3/25/2026  
ROUTE: I-270 STATE: MO  
DISTRICT: SL SHEET NO.: 3  
COUNTY: ST. LOUIS  
JOB NO.: J613020D  
CONTRACT ID.

PROJECT NO.  
BRIDGE NO.

DATE	DESCRIPTION	ADDED	QUANTITY	TABLE
6/16/26				



HDR Engineering, Inc.  
1001 Highlands Plaza Drive  
Suite 200  
St. Louis, MO 63110-1337  
314-425-9300  
Certificate of Authority: 000856

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.