CULVERT/INLET CLEANOUTS

PLAN SHEET NO	ROADWAY	STATION	LOCATION	INLET CLEAN OUT (EA)	REMARKS
6	I-64 EB	39+22	RT	1	RIGHT SHOULDER DRAINS
7	I-64 EB	41+40	RT	1	RIGHT SHOULDER DRAINS
7	I-64 EB	44+76	RT	1	RIGHT SHOULDER DRAINS
7	I-64 EB	48+05	RT	1	RIGHT SHOULDER DRAINS
7	I-64 EB	49+17	RT	1	RIGHT SHOULDER DRAINS
7	I-64 EB	49+60	RT	1	RIGHT SHOULDER DRAINS
7	I-64 EB	49+70	RT	1	RIGHT SHOULDER DRAINS
7	I-64 EB	50+80	RT	1	RIGHT SHOULDER DRAINS
7	I-64 EB	52+23	RT	1	RIGHT SHOULDER DRAINS
8	I-64 EB	55+23	RT	1	RIGHT SHOULDER DRAINS
9	I-64 EB	72+05	RT	1	RIGHT SHOULDER DRAINS
13	I-64 EB	129+58	RT	1	RIGHT SHOULDER DRAINS
14	I-64 EB	145+69	RT	1	RIGHT SHOULDER DRAINS
14	I-64 EB	145+93	RT	1	RIGHT SHOULDER DRAINS
14	I-64 WB	138+84	RT	1	RIGHT SHOULDER DRAINS
14	I-64 WB	147+49	RT	1	RIGHT SHOULDER DRAINS
15	I-64 EB	153+30	RT	1	RIGHT SHOULDER DRAINS
15	I-64 EB	154+24	RT	1	RIGHT SHOULDER DRAINS
15	I-64 WB	153+04	RT	1	RIGHT SHOULDER DRAINS
15	I-64 WB	155+49	RT	1	RIGHT SHOULDER DRAINS
15	I-64 WB	156+01	RT	1	RIGHT SHOULDER DRAINS
15	I-64 WB	158+15	RT	1	RIGHT SHOULDER DRAINS
15	I-64 WB	160+63	RT	1	RIGHT SHOULDER DRAINS
15	I-64 WB	160+83	RT	1	RIGHT SHOULDER DRAINS
16	I-64 EB	165+96	RT	1	RIGHT SHOULDER DRAINS
16	I-64 EB EXIT AT VANDEVENTER	167+38	RT	1	RIGHT SHOULDER DRAINS
16	I-64 EB	168+99	RT	1	RIGHT SHOULDER DRAINS
16	I-64 EB EXIT AT VANDEVENTER	169+21	RT	1	RIGHT SHOULDER DRAINS
16	I-64 EB EXIT AT VANDEVENTER	169+25	LT	1	LEFT SHOULDER DRAINS
16	I-64 EB	169+95	RT	1	RIGHT SHOULDER DRAINS
16	I-64 EB EXIT AT VANDEVENTER	170+89	RT	1	RIGHT SHOULDER DRAINS
16	I-64 EB EXIT AT VANDEVENTER	171+92	RT	1	RIGHT SHOULDER DRAINS
16	I-64 EB EXIT AT VANDEVENTER	171+99	LT	1	LEFT SHOULDER DRAINS
16	I-64 WB	166+23	RT	1	RIGHT SHOULDER DRAINS
16	I-64 WB	168+63	RT	1	RIGHT SHOULDER DRAINS
16	I-64 WB	170+12	RT	1	RIGHT SHOULDER DRAINS
17	I-64 WB	177+82	RT	1	RIGHT SHOULDER DRAINS
SUB TOTALS				37	
PAY TOTALS				37	

PARTIAL DEPTH CONCRETE PAVEMENT REPAIR USING HOT APPLIED POLYMER MODIFIED REPAIR MATERIAL

PLAN SHEET NO	ROADWAY	BEGIN STATION	END STATION	LENGTH	WIDTH	HOT APPLIED POLYMER MODIFIED REPAIR MATERIAL	REMARKS
				(L.F.)	(L.F.)	(LBS)	
14	I-64 EB	136+41	141+51	510	4	61536	LEFTLANE, 3" THICKNESS, BULKED 25%
14	I-64 WB	136+50	141+50	500	4	60330	LEFTLANE, 3" THICKNESS, BULKED 25%
SUB TOTALS						121866	
PAY TOTALS						121866	

4 REVISED

SUMMARY OF QUANTITIES

STATE OF MISSOURI
HEATHER M. COPELAND
NUMBER PE-2009018706
PROFESSIONAL ENGINEER
09/17/2026 8:10:33 AM
HEATHER M. COPELAND - CIVIL
MO-PE-2009018706

DATE PREPARED
9/17/2026

ROUTE	STATE
I-64	MO
DISTRICT	SHEET NO.
SL	3

COUNTY
ST. LOUIS CITY

JOB NO.
JSL0129

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION	DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

QUANTITY SHEET
SHEET 3 OF 5

REV.