PAVEMENT AND BASE

PLAN SHEET NO.	STATION	STATION	LOCATION	CENTERLINE	TYPE 1 AGGREGATE FOR BASE (8 IN. THICK)	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK)	TYPE 5 AGGREGATE FOR BASE (6 IN. THICK)	BITUMINOUS PAVEMENT DEPTH	BITUMINOUS PAVEMENT MIXTURE PG64-22, (BP-1)	MISC. {O?TIONAL PAVEMENT-ASFHALT OR CONCRETE}	TACK COAT	COLDMILLING BITUMINOUS PAVEMENT FOR REMOVAL OF SURFACING (3 IN. THICK OR LESS)	LINEAR GRADING, CLASS 2	MISC. {LINEAR GRADING, CLASS 2 (MODIFIED)}	PAVEMENT EDGE TREATMENT	REMARKS
					SQ YD	SQ YD	SQ YD	IN	TONS	SQ YD	GAL	SQ YD	STA	STA	LF	
1	700+10.40	702+25.00	CL	RELOCATED MO 64	-	-	177.0	-	-	177.0	-	-	-	-	-	MO 64
2	702+25.00	707+50.00	CL	RELOCATED MO 64	-	-	1,153.0	-	-	:,153.0	-	-	-	-	-	MO 64
3	707+50.00	711+25.00	CL	RELOCATED MO 64	-	-	40.0	-	-	40.0	-	-	-	-	-	MO 64
4	711+25.00	714+50.00	CL	RELOCATED MO 64	-	-	923.0	-	-	923.0	-	-	-	-	-	MO 64
5	714+50.00	718+85.00	CL	RELOCATED MO 64	-	-	1,546.0	-	-	:,546.0	-	-	-	-	-	MO 64
6	718+85.00	722+67.50	CL	RELOCATED MO 64	-	-	1,275.0	-	-	:,275.0	-	-	-	-	-	MO 64
2	10+12.94	11+21.97	CL	CR 64-99	-	-	960.0	-	-	960.0	-	-	-	-	-	CR 64-99
2	11+21.97	11+70.02	CL	CR 64-99	-	-	275.0	-	-	275.0	-	-	-	-	-	CR 64-99
3	30+13.21	31+05.23	CL	BSSP1 RD.	-	-	844.0	-	-	844.0	-	-	-	-	-	BSSP1 RD.
3	40+12.00	40+83.59	CL	MARIGOLD DR.	-	-	759.0	-	-	759.0	-	-	-	-	-	MARIGOLD DR.
3	40+83.59	41+96.00	CL	MARIGOLD DR.	-	-	317.0	-	-	-	-	-	-	-	-	MARIGOLD DR.
QUANTITIES REVISED 1	TCP	0+00.00	4+67.15	CL	TEMP. MARIGOLD	-	-	1,603.0	-	-	-	-	-	-	0.0	-	INSTALL TEMPORARY MARIGOLD DR.
	TCP	0+00.00	4+67.15	CL	TEMP. MARIGOLD	-	-	-	-	-	-	-	-	-	0.0	-	REMOVE TEMP. MARIGOLD DR.
	TCP	701+29.15	706+13.84	RT	RELOCATED MO 64	62.5	-	-	-	-	-	-	-	-	-	FOR TEMP. PAVEMENT (USE AS DIRECTED BY ENGINEER)
	TCP	718+84.85	724+67.50	RT	RELOCATED MO 64	62.5	-	-	-	-	-	-	-	-	-	FOR TEMP. PAVEMENT (USE AS DIRECTED BY ENGINEER)
2	704+32.6	705+96.25	LT	RELOCATED MO 64	-	207.0	-	-	-	-	-	-	-	-	-	SHARED USE PATH & CURB RAMP
3	711+13.75	711+25.00	LT	RELOCATED MO 64	-	13.0	-	-	-	-	-	-	-	-	-	SHARED USE PATH
4	711+25.00	712+36.90	LT	RELOCATED MO 64	-	153.0	-	-	-	-	-	-	-	-	-	SHARED USE PATH & CURB RAMP
1-2	700+38.10	703+29.70	LT	RELOCATED MO 64	-	-	495.9	-	-	495.9	-	-	-	-	-	MO 64
1-2	700+66.66	703+29.70	RT	RELOCATED MO 64	-	-	446.9	-	-	446.9	-	-	-	-	-	MO 64
1	700+10.40	700+38.10	LT	RELOCATED MO 64	-	-	-	3.0	3.0	-	4.0	40.0	-	-	-	** WEDGING LAYER 1
1	700+10.40	700+66.66	RT	RELOCATED MO 64	-	-	-	3.0	5.0	-	8.5	85.0	-	-	-	** WEDGING LAYER 2
6	721+16.51	721+50.00	RT	RELOCATED MO 64	-	-	-	6.0	14.0	-	12.0	120.0	-	-	-	** WEDGING LAYER. CONTRACTOR SHALL COLDMILL THIS AREA TO A DEPTH OF 3 IN. TO 6 IN. PAID FOR USING TWO LAYERS OF 3 IN. THICK OR LESS COLDMILLING.
6	721+50.00	722+00.00	RT	RELOCATED MO 64	-	-	-	6.0	20.0	-	17.6	176.0	-	-	-	** WEDGING LAYER 3
6	722+00.00	722+42.00	RT	RELOCATED MO 64	-	-	-	3.0	4.0	-	7.0	70.0	-	-	-	** WEDGING LAYER 4
6	722+42.00	722+67.50	CL	RELOCATED MO 64	-	-	-	1.8	3.0	-	7.8	78.0	-	-	-	DITCH GRADING WEST OF MARIGOLD DR.
3-4	710+05.10	712+43.59	LT	RELOCATED MO 64	-	-	-		-	-	-	-	2.5	-	-	WEST WILDLIFE TRAIL
2	706+30.79	706+35.79	CL	RELOCATED MO 64	-	-	83.0		-	-	-	-	-	-	-	EAST WILDLIFE TRAIL
3	710+74.36	710+79.36	CL	RELOCATED MO 64	-	-	89.0		-	-	-	-	-	-	-	TCP-PHASE 1B TEMP. BARRIER
TCP	703+82.77	706+20.87	LT	RELOCATED MO 64	-	-	182.0		-	-	-	-	2.3	-	-	TCP-PHASE 1B TEMP. BARRIER
TCP	710+88.17	712+80.03	LT	RELOCATED MO 64	-	-	159.0		-	-	-	-	2.0	-	-	TCP-PHASE 1C TEMP WIDENING INSTALL CONSTRUCT PAVEMENT EDGE TREATMENT OUT OF ASPHALT
TCP	00+00.00	1+50.00	CL	TEMP. MARIGOLD	-	-	659.0	6.0	75.0	-	65.9	-	-	2.6	219	TCP-PHASE 1C TEMP. WIDENING REMOVAL
TCP	00+00.00	1+50.00	CL	TEMP. MARIGOLD	-	-	-		-	-	-	-	-	2.6	-	TCP-PHASE 2A TEMP. WIDENING INSTALL CONSTRUCT PAVEMENT EDGE TREATMENT OUT OF ASPHALT
TCP	701+29.15	706+13.74	RT	RELOCATED MO 64	-	-	791.0	6.0	90.0	-	79.1	-	-	9.0	859	TCP-PHASE 2A TEMP. WIDENING INSTALL CONSTRUCT PAVEMENT EDGE TREATMENT OUT OF ASPHALT
TCP	702+37.17	703+77.33	LT	RELOCATED MO 64	-	-	172.0	6.0	20.0	-	17.2	-	-	2.4	200	TCP-PHASE 2A TEMP. WIDENING INSTALL CONSTRUCT PAVEMENT EDGE TREATMENT OUT OF ASPHALT
TCP	718+84.85	12+69.70	RT	RELOCATED MO 64 & EXIST MO 64	-	-	476.0	6.0	54.0	-	47.6	-	-	6.1	571	TCP-PHASE 2A TEMP WIDENING INSTALL CONSTRUCT PAVEMENT EDGE TREATMENT OUT OF ASPHALT
TCP	701+29.15	12+69.70	LT & RT	RELOCATED MO 64 & EXIST MO 64	-	-	-		-	-	-	-	-	17.5	-	TCP-PHASE 2A TEMP. WIDENING REMOVAL
TCP	699+54.37	701+32.59	LT	RELOCATED MO 64	-	-	52.0	6.0	6.0	-	5.2	-	-	1.2	-	TCP-PHASE 3A TEMP WIDENING INSTALL CONSTRUCT PAVEMENT EDGE TREATMENT OUT OF ASPHALT
TCP	704+09.46	704+50.71	LT	RELOCATED MO 64	-	-	101.0	6.0	12.0	-	10.1	-	-	1.1	109	TCP-PHASE 3A TEMP WIDENING INSTALL CONSTRUCT PAVEMENT EDGE TREATMENT OUT OF ASPHALT
TCP	704+09.46	704+50.71	LT	RELOCATED MO 64	-	372	-		-	-	-	-	-	2.3	-	TCP-PHASE 3A TEMP. WIDENING REMOVAL
				SHARED USE PATH	-	-	-	-	-	-	-	-	-	-	-	SHARED USE PATH ALONG MO 64
				TOTAL	125.0	745.0	13578.8	-	306.0	8894.8	282.0	569.0	6.9	44.8	*1958	
				TOTAL QUANTITY FROM LINEAR GRADING (QUANITY SHEET 5 OF 6)	-	-	-	-	-	-	-	-	-	9.0	-	
PAY TOTAL REVISED 1				PAY TOTAL	125	745	13,579	-	306.0	8,895.0	282	569	6.9	54.0	-	

APPLICATION RATES
BP-1 : 2.0355 TONS/CY
TACK COAT: 0.1 GAL/SY

TOTAL REVISED 1

* NO DIRECT PAY FOR PAVEMENT EDGE TREATMENT, SEE JSP'S.
** WEDGING LAYERS SHALL BE USED WHEN DIRECTED BY ENGINEER.

CLEARING AND GRUBBING

PLAN SHEET NO.	STATION	STATION	LOCATION	CENTERLINE	CLEARING AND GRUBBING	REMARKS
					AC	
1-3	700+10.40	708+24.67	CL	RELOCATED MO 64	2.675	WEST OF NIANGUA RIVER
3-7	709+97.75	722+67.50	CL	RELOCATED MO 64	6.18	EAST OF NIANGUA RIVER
				TOTAL	8.86	-
				PAY TOTAL	**9.0**	

MOBILIZATION

1 LUMP SUM

CONTRACTOR FURNISHED SURVEYING AND STAKING

1 LUMP SUM

ROCK SLABS

MISC. {ROCK SLAB (MEAN SIZE 3'X3'X9")}	REMARKS
EA	
75	PLACED AT THE DISCRETION OF THE ENGINEER
75.0	**PAY TOTAL**

CONCRETE

PLAN SHEET NO.	STATION	STATION	LOCATION	CENTERLINE	CONCRETE SIDEWALK 4 IN	CONCRETE CURB RAMPS	TRUNCATED DOMES	CONCRETE CURB (6 IN. HEIGHT AND UNDER) TYPE S	REMARKS
					SQ YD	SQ YD	SQ FT	LF	
2 OF 7	702+25	707+50	LT	RELOCATED MO 64	185.36	20.86	2.22	-	SHARED USE PATH
3 OF 7	707+50	711+25	LT	RELOCATED MO 64	12.48	-	-	-	SHARED USE PATH
4 OF 7	711+25	714+50	LT	RELOCATED MO 64	127.92	24.52	2.22	-	SHARED USE PATH
2 OF 7	704+12.11	704+33.57	LT	RELOCATED MO 64	-	-	-	30	WEST OF BRIDGE
2 OF 7	712+36.49	712+64.79	LT	RELOCATED MO 64	-	-	-	30	EAST OF BRIDGE
				TOTAL	325.76	45.38	4.44	60	-
				PAY TOTAL	**326**	**46**	**5**	**60**	

PAVEMENT MARKINGS

PLAN SHEET NO.	STATION	STATION	LOCATION	CENTERLINE	4 IN. WHITE CLASS 1 PAVEMENT MARKING PAINT (18-MIL, TYPE P BEADS)	4 IN. YELLOW CLASS 1 PAVEMENT MARKING PAINT (18-MIL, TYPE P BEADS)	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	BITUMINOUS SHOULDER RUMBLE STRIP	BITUMINOUS CENTERLINE RUMBLE STRIP	PAVEMENT MARKING REMOVAL	4 IN TEMPORARY PAVEMENT MARKING PAINT	REMARKS
					LF	LF	LF	STA	STA	LF	LF	
1-2	700+10.40	705+96.25	CL	RELOCATED MO 64	-	-	-	11.7	5.86	-	-	EXCLUDES BRIDGE AND BRIDGE APPROACH SLAB
3-6	711+13.75	722+67.50	CL	RELOCATED MO 64	-	-	-	23.1	11.54	-	-	EXCLUDES BRIDGE AND BRIDGE APPROACH SLAB
1-6	700+10.40	722+67.50	CL	RELOCATED MO 64	4,514.20	4,514.20	-	-	-	-	-	ALONG MO 64
TCP	0+0.00	4+67.15	CL	TEMP MARIGOLD	-	-	-	-	-	934.00	934.00	PHASE 2 - TEMP MARIGOLD WHITE EDGELINE
TCP	0+00	4+67.15	CL	TEMP MARIGOLD	-	-	-	-	-	934.00	934.00	PHASE 2 - TEMP MARIGOLD YELLOW CENTERLINE
TCP	697+40.40	706+16.00	CL	RELOCATED MO 64	-	-	-	-	-	1,752.00	1,752.00	PHASE 2A - TEMP WIDENING YELLOW CENTERLINE
TCP	697+40.40	706+16.00	CL	RELOCATED MO 64	-	-	-	-	-	1,752.00	1,752.00	PHASE 2A - TEMP WIDENING WHITE EDGELINE
TCP	718+47.48	725+37.50	CL	RELOCATED MO 64	-	-	-	-	-	1,380.00	1,380.00	PHASE 2A - TEMP WIDENING YELLOW CENTERLINE
TCP	718+47.48	725+37.50	CL	RELOCATED MO 64	-	-	-	-	-	1,380.00	1,380.00	PHASE 2A - TEMP WIDENING WHITE EDGELINE
PAVEMENT MARKING & SIGNING	-	-	CL	CR 64-999	-	-	18.00	-	-	-	-	SIDESTREET STOP BARS
PAVEMENT MARKING & SIGNING	-	-	CL	MARIGOLD DR	-	-	20.16	-	-	-	-	SIDESTREET STOP BARS
PAVEMENT MARKING & SIGNING	-	-	CL	BSSP1 RD	-	-	12.00	-	-	-	-	SIDESTREET STOP BARS
				TOTAL	4,514.20	4,514.20	50.16	34.80	17.40	8,132.00	8,132.00	-
				PAY TOTAL	**4,515**	**4,515**	**51**	**34.8**	**17.4**	**8,132**	**8,132**	

1 SHEET REVISED

SUMMARY OF QUANTITIES
SHEET 1 OF 6

STATE OF MISSOURI
DENNIS J KOSCIELSKI
NUMBER PE-2005000712
PROFESSIONAL ENGINEER

THIS SHEET HAS BEEN SIGNED, SEALED AND DATED ELECTRONICALLY.

DATE PREPARED
8/12/2026

ROUTE	STATE
64	MO
DISTRICT	SHEET NO.
SW	3

COUNTY
DALLAS/LACLEDE

JOB NO.
J7P3542

CONTRACT ID.

PROJECT NO.

BRIDGE NO.
A9346

DATE	DESCRIPTION
11/03/2026	REVISED QUANTITY

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

© Copyright Hanson Professional Services Inc. 2026

HANSON
Hanson Professional Services Inc.
600 Washington Ave., Suite 950
St. Louis, Missouri 63101
Professional Engineer 001632
www.hanson-inc.com
314.770.0467