MoDOT J6P3510E DISTRICTWIDE ADA

FINAL COST ESTIMATE

MODOT ITEM NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY
202-20.10	REMOVAL OF IMPROVEMENTS	LS	1
207-99.09	MISC. LINEAR GRADING, CLASS 2 - (MODIFIED)	STA	194.1
304-05.04	TYPE 5 AGGREGATE FOR BASE (4IN. THICK)	SQYD	15,581
401-99.05	MISC. ASPHALT SIDEWALK	SQYD	1,773.3
401-99.05	MISC. ASPHALT REPAIR	SQYD	171.1
407-10.05	TACK COAT	GAL	251
502-13.10	CONCRETE PAVEMENT 10 IN. NON-REINFORCED, 15 FT JOINTS	SQYD	286.4
602-99.02	MISC. CURB REFLECTORS	EA	111
603-99.02	MISC. ADJUST WATER VALVE TO GRADE	EA	5
604-20.10	ADJUSTING MANHOLE	EA	12
604-20.20	ADJUSTING BASIN OR INLET	EA	25
604-99.02	MISC. DRAINAGE FLUME	EA	2
608-10.12	TRUNCATED DOMES	SQFT	1,880
608-30.06	6 IN. CONCRETE MEDIAN STRIP	SQYD	229.5
608-40.24	SIDEWALK HAND-RAILING WITH BALUSTERS	LF	412
608-50.08	PAVED APPROACH, 8 IN.	SQYD	5,904.9
608-60.04	CONCRETE SIDEWALK, 4 IN.	SQYD	6,564.2
608-60.07	CONCRETE SIDEWALK, 7 IN.	SQYD	193.6
608-99.02	MISC. CONCRETE CURB RAMP	EA	204
608-99.02	MISC. CONCRETE CURB RAMP - DECORATIVE CONCRETE	EA	30
608-99.05	MISC. CONCRETE SIDEWALK, 4 IN. - DECORATIVE CONCRETE	SQYD	583.3
608-99.05	PAVED APPROACH, 10 IN., HIGH EARLY STRENGTH	SQYD	103.8
609-10.10	CONCRETE CURB (6 IN. HEIGHT AND UNDER) TYPE S	LF	784
609-10.51	CURB AND GUTTER, TYPE A	LF	37
609-10.52	CURB AND GUTTER, TYPE B	LF	383
609-20.11	INTEGRAL CURB (6 IN. HEIGHT AND UNDER) TYPE A	LF	501
609-20.21	INTEGRAL CURB (OVER 6 IN. HEIGHT) TYPE A	LF	60
613-20.18	FURNISHING AND PLACING CONCRETE MATERIAL FOR CLASS A PARTIAL DEPTH PAVEMENT REPAIR	CUYD	2.3
613-20.19	REMOVAL FOR CLASS A PARTIAL DEPTH PAVEMENT REPAIR	SQYD	27.0
613-30.20	FURNISHING AND PLACING BITUMINOUS MATERIAL FOR CLASS C PARTIAL DEPTH PAVEMENT REPAIR	TONS	4.6
613-30.21	REMOVAL FOR CLASS C PARTIAL DEPTH PAVEMENT REPAIR	SQYD	28.4
616-99.01	TRAFFIC CONTROL	LS	1
616-99.02	MISC. ADA COMPLIANT MOVEABLE BARRICADES	EA	20
617-36.00D	TEMPORARY TRAFFIC BARRIER, CONTRACTOR FURNISHED / RETAINED	LF	200
617-50.10A	RELOCATING TEMPORARY TRAFFIC BARRIER	LF	200
617-99.02	MISC. RELOCATING CONCRETE BARRIER BLOCK	EA	20
617-99.02	MISC. SPEED BUMP	EA	2
618-10.00	MOBILIZATION	LS	1
620-00.09	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 6 IN. WHITE	LF	1,931
620-00.15	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. WHITE	LF	7,552
620-00.21	PREFORMED THERMOPLASTIC PAVEMENT MARKING, LEFT/RIGHT ARROW	EA	7
620-00.24	PREFORMED THERMOPLASTIC PAVEMENT MARKING, STRAIGHT ARROW	EA	3
620-00.42	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 24 IN. X 36 IN., YIELD LINE TRIANGLE	EA	14
620-59.02	6 IN. WHITE CLASS 2 PAVEMENT MARKING PAINT (25-MIL, TYPE L BEADS)	LF	36
620-59.03	6 IN. YELLOW CLASS 2 PAVEMENT MARKING PAINT (25-MIL, TYPE L BEADS)	LF	301
620-70.01	PAVEMENT MARKING REMOVAL	LF	9,859
620-70.02	PAVEMENT MARKING REMOVAL (SYMBOLS)	EA	8
620-99.02	TUBULAR MARKER	EA	10
622-99.03	MISC. SIDEWALK EDGE GRINDING	LF	6
731-99.02	MISC. INLET TOP REPLACEMENT (IN KIND)	EA	3
803-10.00	TURF TYPE TALL FESCUE SODDING	SQYD	5,436
803-99.05	MISC. LANDSCAPING RESTORATION	SQYD	162
806-10.07	CURB INLET CHECK	EA	84
806-10.16	SEDIMENT REMOVAL	CUYD	130
806-10.19	SILT FENCE	LF	4,585
902-27.08	POST, SIGNAL 8 FT.	EA	14
902-53.00	CONDUIT, 3 IN., TRENCH WITH TRACER WIRE	LF	1,085
902-83.08	CABLE, 16 AWG 2 CONDUCTOR	LF	10,100
902-83.10	CABLE, 16 AWG 5 CONDUCTOR	LF	2,040
902-91.00	BASE, CONCRETE	CY	6.7
902-99.02	MISC. COUNTDOWN PEDESTRIAN SIGNAL HEAD, TYPE 1S	EA	29
902-99.02	MISC. ACCESSIBLE PEDESTRIAN PUSHBUTTON AND SIGNING	EA	118
902-99.02	MISC. PUSHBUTTON EXTENSION	EA	11
902-99.02	MISC. PEDESTRIAN PUSHBUTTON STANCHION, 4 FT	EA	49
902-99.02	MISC. ADJUST PULL BOX TO GRADE	EA	8
902-99.02	MISC. POT HOLING UTILITY FACILITIES	EA	15
903-12.20	PIPE POSTS	LBS	530
903-12.70A	2 IN. PSST POST - 12 GA	LF	21
903-12.73A	DRIVEN POST ANCHOR FOR 2 IN. PSST - 7 GA.	EA	2
903-50.04	SH-FLAT SHEET	SQFT	26
903-50.69	SHF-FLAT SHEET FLUORESCENT	SQFT	32
903-99.02	MISC. REMOVE AND RELOCATE EXISTING GROUND MOUNTED SIGN	EA	16

2 → 15,760

2 → 448.9

2 → 1,926

2 → 6596.3, 205.5, 211

2 → 403

DISCLAIMER

THE PROFESSIONAL WHOSE SIGNATURE AND PERSONAL SEAL APPEAR HEREON ASSUMES RESPONSIBILITY ONLY FOR WHAT APPEARS ON THIS PAGE, AND DISCLAIMS (PURSUANT TO SECTION 327.411 RSMO) ANY RESPONSIBILITY FOR ALL OTHER PLANS, SPECIFICATIONS, ESTIMATES, REPORTS, OR OTHER DOCUMENTS OR INSTRUMENTS NOT SEALED BY THE UNDERSIGNED PROFESSIONAL RELATING TO OR INTENDED TO BE USED FOR ANY PART OR PARTS OF THE PROJECT TO WHICH THIS PAGE REFERS.

STATE OF MISSOURI · PROFESSIONAL ENGINEER

EMMA C. WOODS
NUMBER PE-2024003794

THIS SHEET HAS BEEN SIGNED, SEALED, AND DATED ELECTRONICALLY

DATE PREPARED: 11/11/2026

ROUTE: VAR | STATE: MO

DISTRICT: SL | SHEET NO.: 3

COUNTY: VARIOUS

JOB NO.: J6P3510E

CONTRACT ID.:

PROJECT NO.:

BRIDGE NO.:

REV.	DESCRIPTION	DATE
2	QUANTITIES UPDATE	11/10/26

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

EDSI
ENGINEERING DESIGN SOURCE, INC.
16305 Swingley Ridge Rd., Suite 500
Chesterfield, Missouri 63017
T. 636 537 5585
F. 636 537 0275
Missouri State Engineering Corporation #001523

2 REVISED

SCHEDULE OF QUANTITIES

SHEET 1 OF 21

N:\E23038 MoDOT J6M3510 Districtwide ADA\05_Roadway\drawings\Output\J6P3510E\03_QU_01_J6P3510E_I1.dgn 7:28:38 AM 11/11/2026

DISCLAIMER

THE PROFESSIONAL WHOSE SIGNATURE AND PERSONAL SEAL APPEAR HEREON ASSUMES RESPONSIBILITY ONLY FOR WHAT APPEARS ON THIS PAGE, AND DISCLAIMS (PURSUANT TO SECTION 327.411 RSMO) ANY RESPONSIBILITY FOR ALL OTHER PLANS, SPECIFICATIONS, ESTIMATES, REPORTS, OR OTHER DOCUMENTS OR INSTRUMENTS NOT SEALED BY THE UNDERSIGNED PROFESSIONAL RELATING TO OR INTENDED TO BE USED FOR ANY PART OR PARTS OF THE PROJECT TO WHICH THIS PAGE REFERS.

STATE OF MISSOURI
EMMA C. WOODS
NUMBER PE-2024003794
PROFESSIONAL ENGINEER

THIS SHEET HAS BEEN SIGNED, SEALED, AND DATED ELECTRONICALLY

DATE PREPARED
11/11/2026

ROUTE	STATE
VAR	MO

DISTRICT	SHEET NO.
SL	3

COUNTY
VARIOUS

JOB NO.
J6P3510E

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

ADJUST TO GRADE

OVERALL SHEET NUMBER	TO OVERALL SHEET NUMBER	ROADWAY	LOCATION	ADJUSTING BASIN OR INLET (EA)	ADJUSTING MANHOLE (EA)	ADJUST PULL BOX TO GRADE (EA)	ADJUST WATER VALVE TO GRADE (EA)	REMARKS
4	7	VALLEY SCHOOL DR	LT					Att manhole
			SUBTOTAL					
9	17	I-44	LT/RT	4		2		
			SUBTOTAL	**4**		**2**		
19	25	V MEMORIAL PRKWY	LT/RT	3		2		
			SUBTOTAL	**3**		**2**		
45	50	I-70 SOR	LT/RT	10	8			
			SUBTOTAL	**10**	**8**			
56	63	MO 367 EOR	LT/RT	5	4	2	3	
			SUBTOTAL	**5**	**4**	**2**	**3**	
70	79	MID RIVERS MALL DR	LT/RT	3		2	2	
			SUBTOTAL	**3**		**2**	**2**	
			TOTALS	**25**	**12**	**8**	**5**	

REMOVE AND RELOCATE EXISTING GROUND MOUNT SIGN

OVERALL SHEET NUMBER	SIGN NO.	STATION	ROADWAY	LOCATION	REMOVE AND RELOCATE EXISTING GROUND MOUNT SIGN (EA)	REMARKS
6	1	21+34	VALLEY SCHOOL DR	LT	1	STREET NAMES
				SUBTOTAL	**1**	
12	2	11+45	DE TONTY ST	RT	1	ASSEMBLY
14	3	15+77	DE TONTY ST	RT	1	BUS STOP
				SUBTOTAL	**2**	
55	1	72+88	MO 367 EOR	RT	1	ASSEMBLY
57	2	20+28.	DUNN RD	RT	1	ASSEMBLY
59	3	13+05.	MO 367 WOR	RT	1	ASSEMBLY
60	4	38+40	MO 367 WOR	RT	1	ASSEMBLY
60	5	38+82	MO 367 WOR	RT	1	ASSEMBLY
62	6	105+11	MO 367 WOR	LT	1	R1-2
65	7	30+28	DUNN RD	RT	1	R1-1
66	8	34+94.	DUNN RD	RT	1	SPECIAL (BUS STOP)
				SUBTOTAL	**8**	
70	1A	10+53.59	SPENCER LOOP	LT	1	W12-1
75	2	12+64.72	VETERANS MEM PKWY	RT	1	R1-1
81	3	30+46.73	MID RIVERS MALL DR	LT	1	BLACK POWDER COATED BASE; R1-2
83	4	16+34.9	BRYAN RD	LT	1	R1-2
83	6	16+61.65	BRYAN RD	RT	1	R1-2
				SUBTOTAL	**5**	
				TOTAL	**16**	

PAVEMENT

ADDED 2

OVERALL SHEET NUMBER	CENTERLINE STATION	ROADWAY	LOCATION	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK) (SQYD)	CONCRETE PAVEMENT (10 IN. NON-REINFORCED, 15 FT JOINTS) (SQYD)	REMARKS
17	15+58	MISSISSIPPI AVE	LT	43.6	43.6	ALLEY WAY
			SUBTOTAL	**43.6**	**43.6**	
28	34+67	I-64 OUTER ROAD	RT	162.5	162.5	
			SUBTOTAL	**162.5**	**162.5**	
40	69+15.01	I-70 SOR	RT	119.4	119.4	
42	21+81.41	MO 115 EB	RT	123.4	123.4	
			SUBTOTAL	**242.8**	**242.8**	
			SUBTOTALS*	**286.4**		*SEE SUBTOTAL SCHEDULE FOR FINAL PAY ITEM TOTAL
			TOTAL		**286.4**	

2

448.9	
	448.9

SUBTOTALS

APPLICATION	TRUNCATED DOMES (SQFT)	TYPE 5 AGGREGATE FOR BASE (4 IN THICK) (SQYD)	TACK COAT (GAL)	REMARKS
ISLAND & MEDIAN	344.8	193.6	N/A	
SIDESTREETS	N/A	286.4	N/A	
DRIVEWAYS	N/A	6,246.6	17.6	
SIDEWALK	1,534.5	8,761.8	232.7	
CURB	N/A	92.2	N/A	
TOTAL	**1,880**	**15,581**	**251**	

2

SUBTOTALS

APPLICATION	TRUNCATED DOMES (SQFT)	TYPE 5 AGGREGATE FOR BASE (4 IN THICK) (SQYD)	TACK COAT (GAL)	REMARKS
ISLAND & MEDIAN	390.6	205.4	N/A	
SIDESTREETS	N/A	448.9	N/A	
DRIVEWAYS	N/A	6,246.6	17.6	
SIDEWALK	1,534.5	8,761.8	232.7	
CURB	N/A	96.6	N/A	
TOTAL	**1,926**	**15,760**	**251**	

POT HOLING (EA)	
TOTAL	15

MOBILIZATION (LS)	
TOTAL	1

TRAFFIC CONTROL (LS)	
TOTAL	1

CURB (SEE NEXT PAGE FOR ADDITIONAL CURB QUANTITIES)

ADDED 2

OVERALL SHEET NUMBER	FROM STATION	TO STATION	ROADWAY	LOCATION	CURB AND GUTTER TYPE A (LF)	CURB AND GUTTER TYPE B (LF)	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK) (SQYD)	INTEGRAL CURB (6 IN. HEIGHT AND UNDER) TYPE A (LF)	INTEGRAL CURB (OVER 6 IN. HEIGHT) TYPE A (LF)	CONCRETE CURB (6 IN. HEIGHT AND UNDER) TYPE S (LF)	REMARKS
32	13+87	14+10	MO 40/61 OUTER ROAD	LT		20.0	4.4				
				SUBTOTAL		**20.0**	**4.4**				

2 REVISED

SCHEDULE OF QUANTITIES

SHEET 2 OF 21

DESCRIPTION	DATE
2 QUANTITIES UPDATE	11/10/26

REV.

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

EDSI
ENGINEERING DESIGN SOURCE, INC.
16305 Swingley Ridge Rd., Suite 500
Chesterfield, Missouri 63017
T. 636 537 5585
F. 636 537 0275
Missouri State Engineering Corporation #001523

CURB

OVERALL SHEET NUMBER	FROM STATION	TO STATION	ROADWAY	LOCATION	CURB AND GUTTER TYPE A (LF)	CURB AND GUTTER TYPE B (LF)	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK) (SQYD)	INTEGRAL CURB (6 IN. HEIGHT AND UNDER) TYPE A (LF)	INTEGRAL CURB (OVER 6 IN. HEIGHT) TYPE A (LF)	CONCRETE CURB (6 IN. HEIGHT AND UNDER) TYPE S (LF)	REMARKS
5	15+32.55	15+82.55	VALLEY PARK DR	LT					50		BACK OF SIDEWALK
7	44+76.93	44+84.60	VALLEY PARK DR	LT				15			BACK AND FRONT OF SIDEWALK
				SUBTOTAL				**15**	**50**		
10	13+03.61	13+45.36	HAMPTON	RT				47.9			BACK OF SIDEWALK
10	13+66.90	13+75.85	HAMPTON	LT					9.4		BACK OF SIDEWALK
10	14+51.72	15+13.65	HAMPTON	RT				59			FRONT OF SIDEWALK
11	17+80.54	17+94.90	HAMPTON	LT		15	3.3				
11	18+73.10	18+78.85	HAMPTON	LT						6.7	
11	19+30.59	19+68.37	HAMPTON	RT						36.4	
11	19+63.79	19+66.76	HAMPTON	LT						3	
11	19+80.17	19+98.58	HAMPTON	LT						22	
15	10+44.52	10+67.26	COPELIN	RT						8.3	
16	11+88.83	12+24.35	NEBRASKA	RT						35.5	
16	11+90.57	12+22.72	NEBRASKA	LT						32.2	
17	15+80.65	15+82.34	MISSISSIPPI	RT				23.6			
				SUBTOTAL		**15**	**3.3**	**130.5**	**9.4**	**144.1**	
21	93+14.04	93+24.83	I-70 OUTER RD	LT				35.7			
22	104+04.78	104+06.73	I-70 OUTER RD	RT		20.6	4.6				
22	104+55.63	104+61.67	I-70 OUTER RD	LT		20.1	4.5				
22	104+75.84	104+83.48	I-70 OUTER RD	LT		9.7	2.2				
22	104+93.48	105+62.07	I-70 OUTER RD	LT		66.9	14.9				
22	105+84.83	106+17.08	I-70 OUTER RD	LT		29.9	6.6				
23	107+83.16	108+56.56	I-70 OUTER RD	LT		70.6	15.7				
23	109+88.05	110+78.93	I-70 OUTER RD	LT		91.1	20.2				
23	111+92.04	112+38.98	I-70 OUTER RD	LT		47.7	10.6				
				SUBTOTAL		**356.6**	**79.2**	**35.7**			
27			CLARK AVE AND 14TH ST	LT				10.0			
				SUBTOTAL				**10.0**			
35	13+13.66	13+15.40	I-70 SOR	RT						12	
36	15+64.73	15+74.31	I-70 SOR	RT		11		10			
36	16+07.25	16+20.65	I-70 SOR	RT						24	
38	47+97.87	48+14.87	I-70 SOR	RT				20		18	
38	48+10.86	48+16.44	I-70 SOR	RT				6			
38	48+45.35	48+93.97	I-70 SOR	RT						49	
40	68+92.04	69+00.04	I-70 SOR	RT				9			BRENTON AVE
40-41	69+55.25	70+39.81	I-70 SOR	RT				85			
41	70+78.31	71+19.34	I-70 SOR	RT				63			
41	71+18.56	18+65.11	I-70 SOR/MO 115 EB	RT						120	
41	18+04.64	18+37.26	MO 115 EB	RT				35			
41	20+30.96	20+46.17	MO 115 EB	RT				15			
42	22+12.3	22+19.23	MO 115 EB	RT						7	
42	22+86.01	23+26.62	MO 115 EB	RT						40	
42	23+91.33	24+43.77	MO 115 EB	RT						52	
45	33+06.92	33+09.24	MO 115 EB	RT						4	
46	38+55.59	38+75.65	MO 115 EB	RT						20	
46	33+01.55	33+11.55	MO 115 WB	RT						10	
46	34+01.27	34+11.81	MO 115 WB	RT						10	
46	34+17.81	34+26.07	MO 115 WB	RT						12	
47	5+43.73	5+67.42	MCKIBBON	LT				34			
47	6+29.84	6+48.59	MCKIBBON	LT						19	
				SUBTOTAL		**11**		**276**		**397**	
55	72+88.00	72+88.40	MO 367 EOR	LT						15	
55	72+91.49	72+94.06	MO 367 EOR	RT						3	
56	110+19.77	110+24.26	MO 367 EOR	LT						12	
56	111+35.47	111+39.73	MO 367 EOR	RT						6	
56	112+75.80	112+78.70	MO 367 EOR	RT						7	
56	113+09.72	113+10.64	MO 367 EOR	LT						4	
60	38+40.67	38+48.02	MO 367 WOR	RT						12	
60	38+84.31	38+90.58	MO 367 WOR	RT						10	
61	64+89.56	64+91.42	MO 367 WOR	RT						8	
62	103+61.77	103+63.88	MO 367 WOR	RT						7	
62	103+79.02	103+80.77	MO 367 WOR	LT						4	
62	104+31.99	104+47.86	MO 367 WOR	RT						7	
62	105+65.69	105+72.59	MO 367 WOR	RT						11	
62	106+45.99	106+47.99	MO 367 WOR	RT						3	
				SUBTOTAL						**109**	
73	22+18.79	22+23.61	TR HUGHES BLVD	RT						5.3	
73	22+56.70	22+59.16	TR HUGHES BLVD	RT						5.4	
74	36+40.52	36+42.64	TR HUGHES BLVD	LT						5.0	
74	36+74.58	36+77.27	TR HUGHES BLVD	RT						5.3	
74	36+89.75	36+94.41	TR HUGHES BLVD	LT						5.0	
74	37+12.32	37+17.09	TR HUGHES BLVD	RT						5.0	
78	12+52.42	12+74.26	MID RIVERS MALL RD	LT	24.1		6.6				
78	14+98.95	15+31.80	MID RIVERS MALL RD	LT				33.3			
79	17+68.89	17+60.10	MID RIVERS MALL RD	LT						15.2	
79	17+55.35	17+60.32	MID RIVERS MALL RD	LT						5.8	
79	17+54.94	17+79.84	MID RIVERS MALL RD	LT						5.1	
79	18+74.71	18+86.14	MID RIVERS MALL RD	RT	12.3		3.0				
81	32+65.33	33+12.53	MID RIVERS MALL RD	LT						51.6	
81-82	33+39.98	33+48.03	MID RIVERS MALL RD	LT						25.0	
				SUBTOTAL	**36.4**		**9.6**	**33.3**		**133.8**	
				SUBTOTALS*			**92.2**				*SEE SUBTOTAL SCHEDULE FOR FINAL PAY ITEM
				TOTAL	**37**	**383**		**501**	**60**	**784**	

2

	96.6
403	

DISCLAIMER
THE PROFESSIONAL WHOSE SIGNATURE AND PERSONAL SEAL APPEAR HEREON ASSUMES RESPONSIBILITY ONLY FOR WHAT APPEARS ON THIS PAGE, AND DISCLAIMS (PURSUANT TO SECTION 327.411 RSMO) ANY RESPONSIBILITY FOR ALL OTHER PLANS, SPECIFICATIONS, ESTIMATES, REPORTS, OR OTHER DOCUMENTS OR INSTRUMENTS NOT SEALED BY THE UNDERSIGNED PROFESSIONAL RELATING TO OR INTENDED TO BE USED FOR ANY PART OR PARTS OF THE PROJECT TO WHICH THIS PAGE REFERS.

STATE OF MISSOURI
EMMA C. WOODS
NUMBER PE-2024003794
PROFESSIONAL ENGINEER

THIS SHEET HAS BEEN SIGNED, SEALED, AND DATED ELECTRONICALLY

DATE PREPARED
11/11/2026

ROUTE	STATE
VAR	MO

DISTRICT	SHEET NO.
SL	3

COUNTY
VARIOUS

JOB NO.
J6P3510E

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

REV.	DESCRIPTION	DATE
2	QUANTITIES UPDATE	11/10/26

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

EDSI
ENGINEERING DESIGN SOURCE, INC.
16305 Swingley Ridge Rd., Suite 500
Chesterfield, Missouri 63017
T. 636 537 5585
F. 636 537 0275
Missouri State Engineering Corporation #001523

2 REVISED

SCHEDULE OF QUANTITIES

SHEET 3 OF 21

N:\E23038 MoDOT J6M3510 Districtwide ADA\05_Roadway\drawings\Output\J6P3510E\03_QU_03_J6P3510E_I1.dgn 7:28:45 AM 11/11/2026

EARTHWORK (CONTINUED)

OVERALL SHEET NUMBER	FROM STATION	TO STATION	ROADWAY	LOCATION	LINEAR GRADING, CLASS 2 - MODIFIED (STA)	REMARKS
55	74+50.66		MO 367 EOR	LT	0.6	DRIVEWAY
55	74+74.2	75+42.17	MO 367 EOR	LT	0.7	
56	110+08.19	110+23.96	MO 367 EOR	LT	0.1	
56	110+81.33	111+02.13	MO 367 EOR	RT	0.3	
56	110+82.26	110+07.66	MO 367 EOR	RT	0.2	
56	111+30.45	112+79.75	MO 367 EOR	LT	1.6	
56	112+06.07	112+23.65	MO 367 EOR	RT	0.2	
56	113+10.64	113+41.52	MO 367 EOR	LT	0.3	
57	135+31.03	135+43.89	MO 367 EOR	RT	0.2	
57	20+66.75	20+79.15	DUNN RD	LT	0.4	
57-58	15+70.99	20+35.72	DUNN RD	LT	5.3	
59	13+15.96	13+21.66	MO 367 WOR	RT	0.2	
59	13+61.87	13+80.16	MO 367 WOR	RT	0.3	
60	38+42.17	38+50.84	MO 367 WOR	RT	0.3	
60	38+81.46	38+90.07	MO 367 WOR	RT	0.3	
61	63+91.13	63+03.83	MO 367 WOR	LT	0.2	
61	64+00.64	64+15.96	MO 367 WOR	RT	0.2	
61	64+82.95	64+95.36	MO 367 WOR	LT	0.3	
61	64+92.42	65+27.71	MO 367 WOR	RT	0.8	
62	103+61.26	104+54.84	MO 367 WOR	RT	1.1	
62	103+72.99	103+81.55	MO 367 WOR	LT	0.2	
62	104+77.67	105+10.67	MO 367 WOR	LT	0.4	
62	105+19.36	105+42.38	MO 367 WOR	RT	0.3	
62	105+67.46	106+44.46	MO 367 WOR	RT	1.1	
63	118+09.5	119+47.88	MO 367 WOR	RT	1.5	
63	119+67.47		MO 367 WOR	RT	0.4	DRIVEWAY
63	119+87.25	121+78.48	MO 367 WOR	RT	1.8	
63	121+95.94		MO 367 WOR	RT	0.3	DRIVEWAY
63-64	122+09.42	127+27.74	MO 367 WOR	RT	5.2	
64	127+06.78	127+21.37	MO 367 WOR	RT	0.3	
64-65	26+19.24	29+59.37	DUNN RD	RT	4.0	
65-66	30+25.04	35+61.55	DUNN RD	RT	5.4	
				SUBTOTAL	**49.9**	
70	10+31.32	10+55.71	SPENCER LOOP S	LT	0.4	
71	20+96.58	21+19.43	SPENCER RD	LT	0.2	
71	25+60.92	25+89.94	SPENCER RD	LT	0.3	
72	11+55.57	11+70.13	VETERANS MEMORIAL PKWY	RT	0.1	
72-73	12+29.38	14+09.99	VETERANS MEMORIAL PKWY	RT	2.1	
73	22+15.93	22+58.70	TR HUGHES BLVD	RT	0.1	
74	36+40.97	36+95.61	TR HUGHES BLVD	LT	0.7	
74	36+75.03	37+19.37	TR HUGHES BLVD	RT	0.5	
75	12+17.00	12+25.69	VETERANS MEMORIAL PKWY	RT	0.3	
75	12+96.99	13+32.40	VETERANS MEMORIAL PKWY	RT	3.0	
76	29+93.88		VETERANS MEMORIAL PKWY	RT	1.2	
76	31+51.88		VETERANS MEMORIAL PKWY	RT	1.2	
76	31+90.25	34+46.24	VETERANS MEMORIAL PKWY	RT	2.8	
77	34+58.77		VETERANS MEMORIAL PKWY	RT	1.3	DRIVEWAY
78	12+41.10	12+83.70	MID RIVERS MALL DR	RT	0.6	
78	12+56.30		MID RIVERS MALL DR	LT	0.4	
78	13+70.21	17+52.02	MID RIVERS MALL DR	RT	4.0	
78	13+66.67	15+49.90	MID RIVERS MALL DR	LT	2.0	
78	15+64.99		MID RIVERS MALL DR	LT	0.6	
78-79	15+80.37	17+61.51	MID RIVERS MALL DR	LT	2.0	
79	18+44.12	18+77.62	MID RIVERS MALL DR	RT	0.5	
79	18+46.67		MID RIVERS MALL DR	LT	1.2	
79	21+22.93	22+10.38	MID RIVERS MALL DR	LT	0.9	
80	22+37.70	22+86.40	MID RIVERS MALL DR	LT	0.5	
81	32+76.95	32+82.79	MID RIVERS MALL DR	LT	0.1	
83	16+28.46	16+54.57	BRYAN RD	RT	0.2	
83	16+40.78	16+64.92	BRYAN RD	LT	0.3	
				SUBTOTAL	**27.3**	
				TOTAL	**194.1**	

ADDED 2

ISLAND & MEDIAN

OVERALL SHEET NUMBER	FROM STATION	TO STATION	ROADWAY	LOCATION	INTERSECTION QUADRANT	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK) (SQYD)	6 IN. CONCRETE MEDIAN STRIP (SQYD)	CONCRETE SIDEWALK, 7 IN. (SQYD)	TRUNCATED DOMES (SQFT)	TUBULAR MARKERS (EA)	CURB REFLECTORS (EA)	REMARKS
32	14+22	14+33	MO 40/61 OUTER ROAD	LT	NW	5.0		5.0	23.5			
33	19+79	19+93	MO 40/61 OUTER ROAD	LT		6.9		6.9	22.3			
					SUBTOTAL	**11.9**		**11.9**	**45.8**			
56	110+45.68	110+68.52	MO 367 EOR	LT	NE	22.5	9.3	22.5	42.3		9	
62	105+19.36	105+42.38	MO 367 WOR	RT	SW	18.0	8.1	18.0	33.9		9	
					SUBTOTAL	**40.5**	**17.4**	**40.5**	**76.2**		**18**	
62	12+97.02	13+10.30	W TERRA LN	RT			6.3					FILL IN CUT-THRU
					SUBTOTAL		**6.3**					
70	10+32.78	10+56.89	SPENCER LOOP S	LT	SE		32.6			3	9	
73	22+33.62	22+50.48	TR HUGHES BLVD	LT	S	13.4	4.6	13.4	30		9	
73	22+94.10	23+08.99	TR HUGHES BLVD	LT	E	14.0	4.6	14.0	34		9	
73	22+99.36	23+24.58	TR HUGHES BLVD	RT	N	21.0	7.2	21.0	30		9	
74	35+39.42	36+08.04	TR HUGHES BLVD	LT	SE	47.0	93.7	47.0	35	1	9	
74	36+06.14	36+21.59	TR HUGHES BLVD	RT	SW	13.1	13.6	13.1	31	1	9	
75	15+88.01	16+02.62	VETERANS MEMORIAL PKWY	RT	S	6.4	2.3	6.4	24		9	
79	17+60.10	17+68.90	MID RIVERS MALL DR	LT	S	10.5	3.5	10.5	24		3	
83	16+60.98	16+84.32	BRYAN RD	RT	SW	12.3	13.8	12.3	20	1	9	
83	16+66.32	16+86.55	BRYAN RD	LT	SE	6.4	17.6	6.4	20	3	9	
83	16+75.22	16+89.37	BRYAN RD	LT & RT	S	9.0	12.3	9.0	20	1	9	
					SUBTOTAL	**153.1**	**205.7**	**153.0**	**268.6**	**10**	**93**	
					SUBTOTALS*	**193.6**			**344.8**			*SEE SUBTOTAL SCHEDULE FOR FINAL PAY ITEM TOTAL
					TOTALS		**229.5**	**193.6**		**10**	**111**	

2 **205.4**

2 **205.5** | **390.6**

DISCLAIMER
THE PROFESSIONAL WHOSE SIGNATURE AND PERSONAL SEAL APPEAR HEREON ASSUMES RESPONSIBILITY ONLY FOR WHAT APPEARS ON THIS PAGE, AND DISCLAIMS (PURSUANT TO SECTION 327.411 RSMO) ANY RESPONSIBILITY FOR ALL OTHER PLANS, SPECIFICATIONS, ESTIMATES, REPORTS, OR OTHER DOCUMENTS OR INSTRUMENTS NOT SEALED BY THE UNDERSIGNED PROFESSIONAL RELATING TO OR INTENDED TO BE USED FOR ANY PART OR PARTS OF THE PROJECT TO WHICH THIS PAGE REFERS.

STATE OF MISSOURI
EMMA C. WOODS
NUMBER PE-2024003794
PROFESSIONAL ENGINEER

THIS SHEET HAS BEEN SIGNED, SEALED, AND DATED ELECTRONICALLY

DATE PREPARED
11/11/2026

ROUTE	STATE
VAR	MO

DISTRICT	SHEET NO.
SL	3

COUNTY
VARIOUS

JOB NO.
J6P3510E

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

DESCRIPTION
2 QUANTITIES UPDATE

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

EDSI
ENGINEERING DESIGN SOURCE, INC.
16305 Swingley Ridge Rd., Suite 500
Chesterfield, Missouri 63017
Missouri State Engineering Corporation #001523
T. 636 537 5585
F. 636 537 0275

2 REVISED

SCHEDULE OF QUANTITIES

SHEET 6 OF 21

REV.

N:\E23038 MoDOT J6M3510 Districtwide ADA\05_Roadway\drawings\Output\J6P3510E\03_QU_06_J6P3510E_I1.dgn 7:28:48 AM 11/11/2026

DISCLAIMER

THE PROFESSIONAL WHOSE SIGNATURE AND PERSONAL SEAL APPEAR HEREON ASSUMES RESPONSIBILITY ONLY FOR WHAT APPEARS ON THIS PAGE, AND DISCLAIMS (PURSUANT TO SECTION 327.411 RSMO) ANY RESPONSIBILITY FOR ALL OTHER PLANS, SPECIFICATIONS, ESTIMATES, REPORTS, OR OTHER DOCUMENTS OR INSTRUMENTS NOT SEALED BY THE UNDERSIGNED PROFESSIONAL RELATING TO OR INTENDED TO BE USED FOR ANY PART OR PARTS OF THE PROJECT TO WHICH THIS PAGE REFERS.

SIDEWALK (CONTINUED)

PLAN SHEET NUMBER	FROM STATION	TO STATION	ROADWAY	LOCATION	SUGGESTED ADA RAMP TYPE	TRUNCATED DOMES (SF)	SIDEWALK EDGE GRINDING (LF)	CONCRETE CURB RAMP (EA)	CONCRETE SIDEWALK, 4 IN. (SQYD)	ASPHALT SIDEWALK, 5.75 IN. (SQYD)	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK) (SQYD)	TACK COAT (GAL)	REMARKS
74	37+12.51	37+19.37	TR HUGHES BLVD	RT					3.1		3.1		
75	12+17.00	12+27.16	VETERANS MEMORIAL PKWY	RT	C6	17		1					
75	12+19.65	12+25.69	VETERANS MEMORIAL PKWY	RT					6.1		6.1		
75	12+96.99	13+27.36	VETERANS MEMORIAL PKWY	RT	C2	20		1					
75	12+98.64	13+04.07	VETERANS MEMORIAL PKWY	RT					7.6		7.6		
75	13+27.37	13+32.38	VETERANS MEMORIAL PKWY	RT					3.0		3.0		
76	29+93.88	30+78.8	VETERANS MEMORIAL PKWY	RT					56.0		56.0		
76	30+78.46	31+12.28	VETERANS MEMORIAL PKWY	RT	C6	32		1					
76	31+90.25	32+10.70	VETERANS MEMORIAL PKWY	RT	C6	21		1					
76-77	32+04.83	34+24.61	VETERANS MEMORIAL PKWY	RT					155.7		155.7		
77	34+23.78	34+46.24	VETERANS MEMORIAL PKWY	RT	C5	12		1					
78	12+41.10	12+46.41	MID RIVERS MALL DR	RT					3.4		3.4		
78	12+46.17	12+82.73	MID RIVERS MALL DR	RT	C2	24		2					
78	12+56.30	12+62.58	MID RIVERS MALL DR	LT					2.6		2.6		
78	12+60.49	12+83.96	MID RIVERS MALL DR	LT	C8	12		2					
78	12+77.43	12+83.70	MID RIVERS MALL DR	RT					3.4		3.4		
78	12+79.08	12+87.64	MID RIVERS MALL DR	LT					4.6		4.6		
78	13+66.67	13+73.86	MID RIVERS MALL DR	LT					2.8		2.8		
78	13+67.26	13+99.14	MID RIVERS MALL DR	LT	C8	12		2					
78	13+70.21	13+96.55	MID RIVERS MALL DR	RT	C8	13		2					
78	13+71.84	13+78.81	MID RIVERS MALL DR	RT					3.3		3.3		
78-79	13+93.06	17+52.02	MID RIVERS MALL DR	RT					210.2		210.2		
78	13+96.80	15+32.49	MID RIVERS MALL DR	LT					90.8		90.8		
78	15+31.74	15+49.90	MID RIVERS MALL DR	LT	C5	12		1					
78	15+80.37	15+98.99	MID RIVERS MALL DR	LT	C5	12		1					
78-79	15+98.19	17+32.53	MID RIVERS MALL DR	LT					85.7		85.7		
79	17+30.54	17+61.51	MID RIVERS MALL DR	LT	C8	22		2					
79	17+54.00	17+59.08	MID RIVERS MALL DR	LT					2.2		2.2		
79	18+44.12	18+77.62	MID RIVERS MALL DR	RT	C2	24		2					
79	18+46.67	18+57.18	MID RIVERS MALL DR	LT					4.4		4.4		
79	18+48.00	91+01.41	MID RIVERS MALL DR	LT	C2	24		2					
79	19+00.64	19+72.38	MID RIVERS MALL DR	LT					46.4		46.4		
79	21+22.93	22+10.38	MID RIVERS MALL DR	LT					57.2		57.2		
80	22+37.70	22+86.40	MID RIVERS MALL DR	LT					34.4		34.4		
81	32+76.95	32+82.79	MID RIVERS MALL DR	LT					2.8		2.8		
83	16+28.46	16+35.59	BRYAN RD	RT								3.1	
83	16+32.62	16+54.57	BRYAN RD	RT	C3	11		1					
83	16+40.78	16+49.05	BRYAN RD	LT								3.8	
83	16+45.15	16+64.92	BRYAN RD	LT	C3	12		1					
				SUBTOTAL		**407**		**32**	**981.3**		981.3	6.8	
					DECORATIVE SUBTOTALS	**53**		**30**	**583.3**				**RED AND OR STAMPED SIDEWALK OR CURB RAMPS, YELLOW DOMES**
					SUBTOTALS*	**1534.5**					**8761.8**	**232.7**	*SEE SUBTOTAL SCHEDULE FOR FINAL PAY ITEM TOTAL
					TOTALS		**6**	**204**	**6564.2**	**1773.3**			

2 SEE NEXT PAGE FOR ADDITIONAL SIDEWALK QUANTITIES AND REVISED TOTALS

MISC

OVERALL SHEET NUMBER	STATION	TO STATION	ROADWAY	LOCATION	DRAINAGE FLUME (EA)	RELOCATING CONCRETE BARRIER BLOCK (EA)	SPEED BUMP (EA)	INLET TOP REPLACEMENT (IN KIND) (EA)	SIDEWALK HAND-RAILING (LF)	REMOVAL FOR CLASS C PARTIAL DEPTH PAVEMENT REPAIR	FURNISHING AND PLACING BITUMINOUS MATERIAL FOR CLASS C PARTIAL DEPTH PAVEMENT REPAIR	REMOVAL FOR CLASS A PARTIAL DEPTH PAVEMENT REPAIR	FURNISHING AND PLACING CONCRETE MATERIAL FOR CLASS A PARTIAL DEPTH PAVEMENT REPAIR	REMARKS
23	113+43		VETERANS MEM.	RT				1						
36	15+87.01		I-70 SOR	RT										
38	42+09.29	43+46.08	I-70 SOR	RT	1									
38	48+07.67		I-70 SOR	RT			2							
41	70+44.55	70+73.46	I-70 SOR	RT	1									
41	71+57.65		I-70 SOR	RT		2								
42	22+38.39	22+61.68	I-70 SOR	RT		2								
42	23+49.32	23+72.69	I-70 SOR	RT		3								
43	30+28.05	30+52.45	MO 115 EB	LT		2								
45	32+02.65	32+13.18	MO 115 EB	LT		2								
43	25+89.75	26+05.77	MO 115 WB	LT		4								
43	26+24.37	26+35.23	MO 115 WB	RT		2								
43	26+44.13	26+55.88	MO 115 WB	LT		3								
44	27+76.91	27+94.35	MO 115 WB	RT				1						
46	33+41.74		MO 115 WB	RT					138					
24	17+86	20+60	VALLEY SCHOOL DR	LT					274					
10	14+12		HAMPTON AVE	LT				1						
73	22+12.48		BELLEAU CREEK RD	LT						10.8	1.7			
74	35+26.04		TR HUGHES BLVD	LT								26.9	2.2	
74	35+81.75		TR HUGHES BLVD	LT						17.6	2.8			
				TOTALS	**2**	**20**	**2**	**3**	**412**	**28.4**	**4.6**	**27.0**	**2.3**	

2 REVISED

SCHEDULE OF QUANTITIES

SHEET 19 OF 21

EMMA C. WOODS
NUMBER PE-2024003794
STATE OF MISSOURI * PROFESSIONAL ENGINEER *
THIS SHEET HAS BEEN SIGNED, SEALED, AND DATED ELECTRONICALLY

DATE PREPARED 11/11/2026

ROUTE VAR | STATE MO

DISTRICT SL | SHEET NO. 3

COUNTY VARIOUS

JOB NO. J6P3510E

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

2 QUANTITIES UPDATE

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

EDSI
ENGINEERING DESIGN SOURCE, INC.
16305 Swingley Ridge Rd., Suite 500
Chesterfield, Missouri 63017
Missouri State Engineering Corporation #001523
T. 636 537 5585
F. 636 537 0275

REV.

ADDED 2

SIDEWALK (CONTINUED)													
PLAN SHEET NUMBER	FROM STATION	TO STATION	ROADWAY	LOCATION	SUGGESTED ADA RAMP TYPE	TRUNCATED DOMES (SF)	SIDEWALK EDGE GRINDING (LF)	CONCRETE CURB RAMP (EA)	CONCRETE SIDEWALK, 4 IN. (SQYD)	ASPHALT SIDEWALK, 5.75 IN. (SQYD)	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK) (SQYD)	TACK COAT (GAL)	REMARKS
27	15+47	15+53	I-64 OUTER ROAD	RT	C6	16.6		1					
27	18+05	18+27	I-64 OUTER ROAD	RT	C6	24.4		1					
				SUBTOTAL		**41.0**		**2.0**					
29	5+69	5+90	I-70 OUTER ROAD	LT					13.5		13.5		
29	5+81	5+98	I-70 OUTER ROAD	RT	C5	10.0		1					
				SUBTOTAL		**10.0**		**1.0**	**13.5**		**13.5**		
32	13+92	14+10	MO 40/61 OUTER ROAD	LT	C1	12.1		1					
32	14+69	14+83	MO 40/61 OUTER ROAD	LT	C5	10.0		1					
32	15+32	15+43	MO 40/61 OUTER ROAD	LT					5.9		5.9		
32	18+68	18+79	MO 40/61 OUTER ROAD	LT					6.0		6.0		
33	19+35	19+51	MO 40/61 OUTER ROAD	LT	C1	12.1		1					
33	20+21	20+46	MO 40/61 OUTER ROAD	LT	C6	24.1		1					
33	21+48	21+53	MO 40/61 OUTER ROAD	LT					3.3		3.3		
33	22+38		MO 40/61 OUTER ROAD	LT			6						
33	23+02	23+07	MO 40/61 OUTER ROAD	LT					3.3		3.3		
33	23+71		MO 40/61 OUTER ROAD	LT			6						
				SUBTOTAL		**58.2**	**12.0**	**4.0**	**18.6**		**18.6**		

2

SUBTOTALS*	**1643.7**					**8793.9**	**232.7**	*SEE SUBTOTAL SCHEDULE FOR FINAL PAY ITEM TOTAL
TOTALS		**18**	**211**	**6596.3**	**1773.3**			

DISCLAIMER

THE PROFESSIONAL WHOSE SIGNATURE AND PERSONAL SEAL APPEAR HEREON ASSUMES RESPONSIBILITY ONLY FOR WHAT APPEARS ON THIS PAGE, AND DISCLAIMS (PURSUANT TO SECTION 327.411 RSMO) ANY RESPONSIBILITY FOR ALL OTHER PLANS, SPECIFICATIONS, ESTIMATES, REPORTS, OR OTHER DOCUMENTS OR INSTRUMENTS NOT SEALED BY THE UNDERSIGNED PROFESSIONAL RELATING TO OR INTENDED TO BE USED FOR ANY PART OR PARTS OF THE PROJECT TO WHICH THIS PAGE REFERS.

STATE OF MISSOURI
EMMA C. WOODS
NUMBER PE-2024003794
PROFESSIONAL ENGINEER

THIS SHEET HAS BEEN SIGNED, SEALED, AND DATED ELECTRONICALLY

DATE PREPARED: 11/11/2026

ROUTE	STATE
VAR	MO
DISTRICT	**SHEET NO.**
SL	3

COUNTY: VARIOUS

JOB NO.: J6P3510E

CONTRACT ID.:

PROJECT NO.:

BRIDGE NO.:

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

DESCRIPTION	DATE
2 QUANTITIES UPDATE	11/10/26

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

EDSI
ENGINEERING DESIGN SOURCE, INC.
16305 Swingley Ridge Rd., Suite 500
Chesterfield, Missouri 63017
T. 636 537 5585
F. 636 537 0275
Missouri State Engineering Corporation #001523

STANDARD SIGN ASSEMBLIES															SIGN SUMMARY				
					TYPE													SIZE, TYPE & SQUARE FEET	
SIGN NUMBER	OVERALL SHEET NUMBER	STATION	LOCATION	ROADWAY	W11-2	W16-7P	R5-1	R3-2	R1-1	SIGN DESCRIPTION, SIZES & PEDESTRIAN 36" X 36"	SIGN DESCRIPTION, SIZES & DIAGONAL DOWNWARD ARROW (PLAQUE) 21" X 15"	SIGN DESCRIPTION, SIZES & DO NOT ENTER 30" X 30"	SIGN DESCRIPTION, SIZES & NO LEFT TURN 24" X 24"	SIGN DESCRIPTION, SIZES & STOP 36" X 36"	STANDARD SIGN OR SPECIAL SIGN NUMBER	SIGN DETAIL SHEET NO.	NO. EACH	FLAT SHEET SIZE (SQFT) ITEM NO. 903-50.04A	FLAT SHEET FLUORESCENT YELLOW GREEN ITEM NO. 903-50.69A (SQFT)
1	12	11+45	RT	I-44 ST LOUIS/DE TONTY ST			1	1	1						R5-1		1	6.25	
1	78	15+47	LT	MID RIVERS MALL DR					1						W16-7P		2	9.00	18.00
4	83	16+60	LT	BRYAN RD	1	1									W16-7PL		2	3.75	7.50
5	83	16+39	RT	BRYAN RD	1	1									R1-1		1	6.25	6.25
				TOTAL	**2**	**2**	**1**	**1**	**2**								**TOTAL**	**26**	**32**

SIGNALS

MODOT ITEM NUMBER	ITEM DESCRIPTION	UNIT	SUBTOTALS
902-27.08	POST, SIGNAL 8 FT. OR 2.4 M	EACH	14
902-53.00	CONDUIT, 3 IN., TRENCH WITH TRACER WIRE	LF	1085
902-83.08	CABLE, 16 AWG 2 CONDUCTOR	LF	10100
902-83.10	CABLE, 16 AWG 5 CONDUCTOR	LF	2040
902-91.00	BASE, CONCRETE	CY	6.7
902-99.02	COUNTDOWN PEDESTRIAN SIGNAL HEAD, TYPE 1S	EACH	29
902-99.02	ACCESSIBLE PEDESTRIAN PUSHBUTTON AND SIGNING	EACH	118
902-99.02	PUSHBUTTON EXTENSION	EACH	11
902-99.02	4 FT. PED STANCHION	EACH	49

OVERALL SHEET NUMBER	SIGNS 902 SIGNAL SIGNS TABULATED ON D-37A SHEET						CONCRETE FOOTINGS EMBEDDED	PIPE POSTS					BACKING BARS					U-CHANNEL POST	PERFORATED SQUARE STEEL TUBE										BREAK-AWAY ASSEMBLY	REMARKS AND OTHERS REQUIRED ITEMS
														2" X 3/8" BARS @ 2.55 LBS PER LIN FT					2 IN. POST					2.5 IN. POST						
	SIGN NO.	SIGN SIZE	STATION	HORZ CLEAR IF NOT STD	LOCATION	SIGN DTL. SHT. NO.	ITEM NO. 9031010	PIPE SIZE	POST NO. 1	POST NO. 2	LBS PER FT	TOTAL ITEM NO. 9031220	NO. EACH	LGTH	TOTAL	TOTAL	ITEM NO. 9031250A	POST NO. 1	POST NO. 2	TOTAL ITEM NO. 9031270A	DRIVEN 7-GA. ITEM NO. 9031273A	CONCRETE 7-GA. ITEM NO. 9031274	POST NO. 1	POST NO. 2	TOTAL ITEM NO. 9031280	ANCHORS DRIVEN 7-GA. ITEM NO. 9031281A	ANCHORS CONCRETE 7-GA. ITEM NO. 9031285	ITEM NO. 9031241	
							CY	IN.	LF	LF		LBS		IN.	LF	LBS	LF	LF	LF	LF	EA	EA	LF	LF	LF	EA	EA	EA	
6	1	ASSEMBLY	21+34		LT			4	15		10.79	161.9																	STREET NAMES ON EXISTING PIPE POST
12	2	ASSEMBLY	11+45		DE TONTY ST			4	15		10.79	161.9																	ASSEMBLY
14	3		15+77		DE TONTY ST													10		10	1								BUS STOP
78	1	30"x30"	15+47		MID RIVERS MALL DR													11		11	1								
83	7	36"x36", 30"x18"	16+60		BRYAN RD		0.13	2.5	17		5.79	98.4																	
83	5	36"x36", 30"x18"	16+39		BRYAN RD		0.13	2.5	17		5.79	98.4																	
					TOTAL							**530**								**21**	**2**								

2 REVISED

SCHEDULE OF QUANTITIES

SHEET 20 OF 21

REV.

N:\E23038 MoDOT J6M3510 Districtwide ADA\05_Roadway\drawings\Output\J6P3510E\03_QU_20_J6P3510E_I1.dgn 7:28:56 AM 11/11/2026

SCALE

0 20 40 60

DISCLAIMER

THE PROFESSIONAL WHOSE SIGNATURE AND PERSONAL SEAL APPEAR HEREON ASSUMES RESPONSIBILITY ONLY FOR WHAT APPEARS ON THIS PAGE, AND DISCLAIMS (PURSUANT TO SECTION 327.411 RSMO) ANY RESPONSIBILITY FOR ALL OTHER PLANS, SPECIFICATIONS, ESTIMATES, REPORTS, OR OTHER DOCUMENTS OR INSTRUMENTS NOT SEALED BY THE UNDERSIGNED PROFESSIONAL RELATING TO OR INTENDED TO BE USED FOR ANY PART OR PARTS OF THE PROJECT TO WHICH THIS PAGE REFERS.

EXIST. R/W

EXIST. R/W

35

EXIST. R/W

01880000300
100 - 100 S 9TH ST
NF
CITY OF ST LOUIS
Date 2/3/1996, Daily 19

EXIST. R/W

END WORK
CLARK AVE
STA 35+00

EXIST. R/W

EXIST. R/W

STREET CONCRETE
STA. 34+67 RT
36'-6" WIDE PAVED
APPROACH (8")
MAX GRADE=2.1%
ADA PATHWAY
(10' WIDE)

2 10"

04260000100
908 - 922 CLARK AV
NF
LCRA
Date 10/15/1992, Daily 66

04260000150
904 - 904 CLARK AV
NF
STATE OF MO
Date , Daily 0

04260000180
311 - 311 S 9TH ST
NF
LCRA
Date 10/15/1992, Daily 66

04250000111
318 - 320 S 9TH ST
NF
811 SPRUCE ST LLC
Date 6/9/2022, Daily 178

04260000050
320 - 320 S 10TH ST
NF
STATE OF MO
Date , Daily 0

EXIST. R/W

EXIST. R/W

PLAN SHEET LEGEND

- EXISTING RIGHT-OF-WAY
- EXISTING EASEMENT
- PERMANENT HIGHWAY EASEMENT (P.H.E.)
- TEMPORARY CONSTRUCTION EASEMENT (T.C.E.)
- SLOPED CONCRETE
- SIDEWALK REMOVAL
- CURB RAMP REPLACEMENT & CURB RAMPS
- SIDEWALK/CONCRETE REPLACEMENT

2 REVISED

PLAN SHEET

I-64 OUTER ROAD
SHEET 3 OF 3

EMMA C. WOODS
NUMBER
PE-2024003794
STATE OF MISSOURI
PROFESSIONAL ENGINEER

THIS SHEET HAS BEEN SIGNED, SEALED, AND DATED ELECTRONICALLY

DATE PREPARED
11/11/2026

ROUTE	STATE
VAR	MO
DISTRICT	SHEET NO.
SL	28

COUNTY
VARIOUS

JOB NO.
J6P3510E

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

REV.	DESCRIPTION	DATE
2	ENTRANCE THICKNESS CHANGE	11/10/26

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

EDSI
ENGINEERING DESIGN SOURCE, INC.
16305 Swingley Ridge Rd., Suite 500
Chesterfield, Missouri 63017
T. 636 537 5585
F. 636 537 0275
Missouri State Engineering Corporation #001523

N:\E23038 MoDOT J6M3510 Districtwide ADA\05_Roadway\drawings\Output\J6P3510E\101-03_PP_J6P3510E_I20.dgn 8:21:33 AM 11/11/2026