PIPE STORM SEWER

LOCATION	FROM NODE ID	STATION	OFFSET	TO NODE ID	STATION	OFFSET	GROUP A (SMOOTH) PIPE 12 IN (LF)	15 IN (LF)	18 IN (LF)	18 IN HOR. ELLIP. (LF)	24 IN (LF)	24 IN HOR. ELLIP. (LF)	30IN (LF)	30 IN HOR. ELLIP. (LF)	36 IN (LF)	PIPE COLLAR EA	CL. 3 EXC (CY)	REMARKS
BLANCHE STREET TO UNDER RR BRIDGE AREA TO OUTFALL AT STA. 493+69.38 LEFT CONTINUED																		
CONST. B.L.	494T23	494+21.65	30.00 RT	494DI24	494+35.76	30.00 RT		9									1.7	
CONST. B.L.	494DI24	494+35.76	30.00 RT	494DI18	494+35.82	30.00 LT		58									22	
CONST. B.L.	494DI25	494+40.94	30.00 RT	494DI19	494+41.02	30.00 LT		56									21	
CONST. B.L.	494DI26	494+46.26	30.00 RT	494DI20	494+46.24	30.00 LT		58.0									21.8	
CONST. B.L.	494DI26	494+46.26	30.00 RT	494T27	494+60.81	30.00 RT		9									1.8	
CONST. B.L.	494T27	494+60.81	30.00 RT	494DI28	494+75.29	30.00 RT		15									3.9	
CONST. B.L.	489DI29	489+44.00	31.50 LT	491DI12	491+16.11	30.00 LT		170									60.7	
CONST. B.L.	491DI12	491+16.11	30.00 LT	492DI11	492+91.61	30.00 LT		174									60.6	
CONST. B.L.	492DI11	492+91.61	30.00 LT	493T2	493+69.36	30.00 LT		76									27	
CONST. B.L.	493T2	493+69.36	30.00 LT	493MH1	493+69.38	50.00 LT									18		27.7	
CONST. B.L.	493MH1	493+69.38	50.00 LT	PIPE COLLAR	493+69.39	56.04 LT									4	1	10.4	
CONST. B.L.	493MH1	493+69.38	50.00 LT	494T17	494+10.50	30.00 LT					39						59	
CONST. B.L.	494T17	494+10.50	30.00 LT	494DI18	494+35.82	30.00 LT												
CONST. B.L.	494DI18	494+35.82	30.00 LT	494DI19	494+41.02	30.00 LT		2									0	
CONST. B.L.	494DI19	494+41.02	30.00 LT	494DI20	494+46.24	30.00 LT		2									0	
CONST. B.L.	494DI20	494+46.24	30.00 LT	494T21	494+56.45	30.00 LT												
CONST. B.L.	494T21	494+56.45	30.00 LT	494DI22	494+71.20	30.00 LT		10									1.9	
RTE 96 EAST OF RR BRIDGE TO GARRISION STREET AND SIDE STREETS TO OUTFALL AT EXISTING 12'X4' REINFORCED BOX CULVERT STA. 496+81.50																		
CONST. B.L. DOUBLE 12'X4' CONN	496+81.50	EXISTING		496DIL1	497+02.00	30.00 LT									26		40	
CONST. B.L.	496DIL1	497+02.00	30.00 LT	497DIL2	497+74.00	30.50 LT									71		107.4	
CONST. B.L.	497DIL2	497+74.00	30.50 LT	498DIL1	498+42.00	31.50 LT									66		97.9	
CONST. B.L.	498DIL1	498+42.00	31.50 LT	499DIL1	499+10.00	31.50 LT							66				66	
CONST. B.L.	499DIL1	499+10.00	31.50 LT	500DIL1	500+05.00	31.50 LT							93				84.6	
CONST. B.L.	500DIL1	500+05.00	31.50 LT	500DIL2	500+86.00	31.50 LT							79				71.3	
CONST. B.L.	500DIL2	500+86.00	31.50 LT	501DIL2	501+74.00	31.50 LT							85				77.3	
CONST. B.L.	501DIL2	501+74.00	31.50 LT	502DIL4	502+76.00	31.50 LT							98				89.9	
CONST. B.L.	502DIL4	502+76.00	31.50 LT	504DIL1	504+00.00	32.50 LT							121				98.4	
CONST. B.L.	504DIL1	504+00.00	32.50 LT	504DIL2	504+27.05	33.50 LT					25						15.6	
CONST. B.L.	504DIL2	504+27.05	33.50 LT	504DIL3	504+45.00	33.50 LT					16						8.6	
CONST. B.L.	504DIL3	504+45.00	33.50 LT	504MHL1	504+78.00	36.00 LT					31						19.6	
CONST. B.L.	504MHL1	504+78.00	36.00 LT	505DIL1	505+08.17	33.50 LT					28						17.8	
CONST. B.L.	505DIL1	505+08.17	33.50 LT	505DIL2	505+63.92	33.50 LT					54						36.3	
CONST. B.L.	505DIL2	505+63.92	33.50 LT	506DIL4	506+77.20	33.50 LT					112						80.3	
CONST. B.L.	506DIL4	506+77.20	33.50 LT	506MHL1	506+94.70	33.38 LT					15						8.5	
CONST. B.L.	506MHL1	506+94.70	33.38 LT	507MHL1	507+46.77	32.28 LT					49						35.7	
CONST. B.L.	507MHL1	507+46.77	32.28 LT	507DIL2	507+70.40	32.50 LT		21									9.5	
CONST. B.L.	501DIL2	501+74.00	31.50 LT	501DIL1	501+94.75	48.28 LT		25									14.6	
CONST. B.L.	501DIL1	501+94.75	48.28 LT	501DIL3	501+97.18	115.69 LT		66									28.6	
CONST. B.L.	502DIL4	502+76.00	31.50 LT	502DIL3	502+55.88	51.51 LT			27								18.4	
CONST. B.L.	502DIL3	502+55.88	51.51 LT	502DIL2	502+56.42	113.17 LT		60									26.6	
CONST. B.L.	502DIL2	507+70.40	32.50 LT	PIPE COLLAR	504+54.00	117.88 LT		4								1	5.1	
CONST. B.L.	504MHL1	506+94.70	33.38 LT	504DIL4	504+77.69	49.73 LT		11									3.9	
CONST. B.L.	506MHL1	507+46.77	32.28 LT	506DIL3	506+96.90	50.63 LT		15									5.3	
CONST. B.L.	506DIL3	506+96.90	50.63 LT	506DIL2	506+98.87	92.60 LT		41									15.8	
CONST. B.L.	507MHL1	504+78.00	36.00 LT	507DIL1	507+48.13	50.39 LT		16									6.1	
CONST. B.L. DOUBLE 12'X4' CONN	496+81.50	EXISTING		497DIR1	497+00.00	30.00 RT					22						14.6	
CONST. B.L.	497DIR1	497+00.00	30.00 RT	497DIR2	497+75.00	30.50 RT					24						61.2	
CONST. B.L.	497DIR2	497+75.00	30.50 RT	498DIR1	498+75.00	31.50 RT					98						74.6	
CONST. B.L.	498DIR1	498+75.00	31.50 RT	499DIR1	499+75.00	31.50 RT			98								49.5	
CONST. B.L.	499DIR1	499+75.00	31.50 RT	500DIR1	500+50.00	31.50 RT			73								36.6	
CONST. B.L.	500DIR1	500+50.00	31.50 RT	501DIR1	501+25.00	31.50 RT			73								34.7	
CONST. B.L.	501DIR1	501+25.00	31.50 RT	502DIR1	502+75.00	29.50 RT		150									63.7	
CONST. B.L.	502DIR1	502+75.00	29.50 RT	505DIR1	505+00.00	29.50 RT		223									85.6	
CONST. B.L.	505DIR1	505+00.00	29.50 RT	505DIR2	505+50.00	29.50 RT		48									20.9	
SUBTOTALS THIS SHEET							0	1319	271	0	513	0	542	0	185	2	1850	
SUBTOTALS CARRIED FROM PREVIOUS SHEET							261	1686	361	239	265	42	61	64	0	2	1437	
PIPE AND EXCAVATION SUBTOTALS CARRIED FROM CROSS-ROAD CULVERTS											314						280	
EXCAVATION SUBTOTAL CARRIED FROM CAST IN PLACE STORM STRUCTURES																	121	
EXCAVATION SUBTOTAL CARRIED FROM PRECAST STORM STRUCTURES																	593	
USE							261	3005	632	239	1092	42	603	64	185	4	3688	

1 ADDED

4281

1 REVISED

SUMMARY OF QUANTITIES
SHEET 14 OF 16

STATE OF MISSOURI
SEAN MATLOCK
NUMBER E-27133
PROFESSIONAL ENGINEER

DATE PREPARED 11/16/2026

ROUTE	STATE
96	MO
DISTRICT	SHEET NO.
SW	3

COUNTY JASPER

JOB NO. JSR0060

CONTRACT ID. -

PROJECT NO. -

BRIDGE NO. -

DESCRIPTION | DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

2215 Fairlawn Dr
Carthage, MO 64836
417.358.9551
COA# 00062
weareown.com
Engineering beyond.

WARNING SIGNS

SIGN	SIZE IN.	AREA SQ.FT.	QTY EACH	TOTAL AREA SQ.FT.	QTY RELOC EACH	TOTAL RELOC SQ.FT.	SIGN NO.	DESCRIPTION
WO1-1L	48X48	16.00						TURN (SYMBOL LEFT)
WO1-1R	48X48	16.00						TURN (SYMBOL RIGHT)
WO1-2L	48X48	16.00						CURVE (SYMBOL LEFT)
WO1-2R	48X48	16.00						CURVE (SYMBOL RIGHT)
WO1-3L	48X48	16.00						REVERSE TURN (SYMBOL LEFT)
WO1-3R	48X48	16.00						REVERSE TURN (SYMBOL RIGHT)
WO1-4L	48X48	16.00						REVERSE CURVE (SYMBOL LEFT)
WO1-4R	48X48	16.00						REVERSE CURVE (SYMBOL RIGHT)
WO1-4bL	48X48	16.00						DOUBLE ARROW REVERSE CURVE (SYMBOL LEFT)
WO1-4bR	48X48	16.00						DOUBLE ARROW REVERSE CURVE (SYMBOL RIGHT)
WO1-4cL	48X48	16.00						TRIPLE ARROW REVERSE CURVE (SYMBOL LEFT)
WO1-4cR	48X48	16.00						TRIPLE ARROW REVERSE CURVE (SYMBOL RIGHT)
WO1-6	60X30	12.50						HORIZONTAL ARROW (SYMBOL)
WO1-6a	72X36	18.00						HORIZ. ARROW (SYMBOL ON PERMANENT BARRICADE)
WO1-7	60X30	12.50						DOUBLE HEAD HORIZONTAL ARROW (SYMBOL)
WO1-7a	72X36	18.00	15	270.00				DOUBLE HEAD HORIZ. ARROW (SYMBOL ON PERM. BARR.)
WO1-8	18X24	3.00						CHEVRON (SYMBOL)
WO1-8a	30X36	7.50						CHEVRON (SYMBOL FOR DIVIDED HIGHWAYS)
WO3-1	48X48	16.00						STOP AHEAD (SYMBOL)
WO3-2	48X48	16.00						YIELD AHEAD (SYMBOL)
WO3-3	48X48	16.00						SIGNAL AHEAD (SYMBOL)
WO3-4	48X48	16.00						BE PREPARED TO STOP
WO3-5	48X48	16.00	3	48.00				SPEED LIMIT AHEAD
WO4-1L	48X48	16.00						MERGE (SYMBOL FROM LEFT)
WO4-1R	48X48	16.00						MERGE (SYMBOL FROM RIGHT)
WO4-1aL	48X48	16.00						MERGE (LEFT)
WO4-1aR	48X48	16.00						MERGE (RIGHT)
WO5-1	48X48	16.00						ROAD/BRIDGE/RAMP NARROWS
WO5-3	48X48	16.00						ONE LANE BRIDGE
WO5-5	48X48	16.00	3	48.00				NARROW LANES
WO6-1	48X48	16.00						DIVIDED HIGHWAY (SYMBOL)
WO6-2	48X48	16.00						DIVIDED HIGHWAY END (SYMBOL)
WO6-3	48X48	16.00						TWO WAY TRAFFIC (SYMBOL)
WO7-3a	30X24	5.00	3	15.00				NEXT 2 MILES (PLAQUE)
WO8-1	48X48	16.00	2	32.00				BUMP
WO8-2	48X48	16.00						DIP
WO8-3	48X48	16.00						PAVEMENT ENDS
WO8-4	48X48	16.00						SOFT SHOULDER
WO8-5	48X48	16.00						SLIPPERY WHEN WET (SYMBOL)
WO8-6	48X48	16.00						TRUCK CROSSING
WO8-6c	48X48	16.00						TRUCK ENTRANCE
WO8-7	36X36	9.00						LOOSE GRAVEL
WO8-7a	36X36	9.00						FRESH OIL / LOOSE GRAVEL
WO8-9	48X48	16.00						LOW SHOULDER
WO8-11	48X48	16.00	2	32.00				UNEVEN LANES
WO8-12	48X48	16.00						NO CENTER LINE
WO8-15	48X48	16.00						GROOVED PAVEMENT
WO8-15P	30X24	5.00						MOTORCYCLE (PLAQUE)
WO8-17L	48X48	16.00						SHOULDER DROP-OFF (SYMBOL LEFT)
WO8-17R	48X48	16.00						SHOULDER DROP-OFF (SYMBOL RIGHT)
WO8-17P	30X24	5.00						SHOULDER DROP-OFF (PLAQUE)
W10-1	42RND.	9.62						RAILROAD CROSSING
WO12-1	24X24	4.00						DOUBLE DOWN ARROW (SYMBOL)
WO12-2	48X48	16.00						LOW CLEARANCE (SYMBOL)
WO12-2x	24X18	3.00						LOW CLEARANCE (PLAQUE)
WO12-2a	84X24	14.00						OVERHEAD LOW CLEARANCE (FEET AND INCHES)
WO12-4	120X60	50.00						LOW CLEARANCE XX FT XX IN XX MILES AHEAD
WO12-5	120X60	50.00						WIDTH RESTRICTION XX FT XX IN XX MILES AHEAD
WO13-1	30X30	6.25						ADVISORY SPEED (PLAQUE)
WO16-2	30X24	5.00						XXX FEET (PLAQUE)
WO16-3	30X24	5.00						X MILE (PLAQUE)
WO20-1	48X48	16.00	24	384.00				ROAD/BRIDGE/RAMP WORK AHEAD
WO20-2	48X48	16.00						DETOUR AHEAD
WO20-3	48X48	16.00	2	32.00				ROAD CLOSED AHEAD
WO20-4	48X48	16.00						ONE LANE ROAD AHEAD
WO20-5	48X48	16.00	2	32.00				RIGHT/CENTER/LEFT LANE CLOSED AHEAD
WO20-5a	48X48	16.00						2 RIGHT/CENTER/LEFT LANES CLOSED AHEAD
WO20-6a	48X48	16.00	2	32.00				RIGHT/CENTER/LEFT LANE CLOSED
WO20-7a	48X48	16.00						FLAGGER (SYMBOL)
WO21-2	36X36	9.00						FRESH OIL
WO21-5	48X48	16.00	2	32.00				SHOULDER WORK / SHOULDER WORK AHEAD
WO22-1	48X48	16.00						BLASTING ZONE AHEAD
WO22-2	42X36	10.50						TURN OFF 2-WAY RADIO AND PHONE
WO22-3	42X36	10.50						END BLASTING ZONE
GO22-1	21X15	2.19	2	4.38				WET PAINT (ARROW PIVOTS)

GUIDE SIGNS

SIGN	SIZE IN.	AREA SQ.FT.	QTY EACH	TOTAL SQ.FT.	QTY RELOC EACH	TOTAL RELOC SQ.FT.	SIGN NO.	DESCRIPTION
E05-1	36X48	12.00						GORE EXIT
E05-2	48X36	12.00						EXIT OPEN
E05-2a	48X36	12.00	2	24.00				EXIT CLOSED
GO20-1	60X24	10.00	3	30.00				ROAD WORK NEXT 2 MILES
GO20-2	48X24	8.00	3	24.00				END ROAD WORK
GO20-4	36X18	4.50						PILOT CAR FOLLOW ME
GO20-4a	42X30	8.75						PILOT CAR IN USE WAIT & FOLLOW
GO20-4a	18X12	1.50						PILOT CAR IN USE WAIT & FOLLOW
GO20-5aP	36X24	6.00	8	48.00				WORK ZONE (PLAQUE)
MO4-8a	24X18	3.00						END DETOUR
MO4-9L	48X36	12.00						DETOUR (LEFT)
MO4-9R	48X36	12.00						DETOUR (RIGHT)
MO4-9P	48X12	4.00						STREET NAME (PLAQUE)
MO4-10L	48X18	6.00						DETOUR ARROW (LEFT)
MO4-10R	48X18	6.00						DETOUR ARROW (RIGHT)

REGULATORY SIGNS

SIGN	SIZE IN.	AREA SQ.FT.	QTY EACH	TOTAL SQ.FT.	QTY RELOC EACH	TOTAL RELOC SQ.FT.	SIGN NO.	DESCRIPTION
R1-1	48X48	13.25						STOP
R1-2	48TRI.	6.93						YIELD
R1-2a	36X36	9.00						TO ONCOMING TRAFFIC (PLAQUE)
R1-3P	30X12	2.50						ALL WAY (PLAQUE)
R2-1	36X48	12.00	10	120.00				SPEED LIMIT (5@25 - 5@35)
R3-1	48X48	16.00						NO RIGHT TURN (SYMBOL)
R3-2	48X48	16.00	2	32.00				NO LEFT TURN (SYMBOL)
R3-3	36X36	9.00						NO TURNS
R3-4	48X48	16.00						NO U-TURN (SYMBOL)
R3-7L	30X30	6.25	2	12.50				LEFT LANE MUST TURN LEFT
R3-7R	30X30	6.25						RIGHT LANE MUST TURN RIGHT
R4-1	36X48	12.00						DO NOT PASS
R4-2	36X48	12.00						PASS WITH CARE
R4-7a	36X48	12.00	2	24.00				KEEP RIGHT (HORIZONTAL ARROW)
R4-8a	36X48	12.00						KEEP LEFT (HORIZONTAL ARROW)
R5-1	30X30	6.25						DO NOT ENTER
R5-1a	36X24	6.00						WRONG WAY
R6-1L	54X18	6.75						ONE WAY ARROW (LEFT)
R6-1R	54X18	6.75						ONE WAY ARROW (RIGHT)
R6-2L	24X30	5.00						ONE WAY (LEFT)
R6-2R	24X30	5.00						ONE WAY (RIGHT)
R9-9	24X12	2.00	8	16.00				SIDEWALK CLOSED
R9-11L	24X18	3.00	2	6.00				SIDEWALK CLOSED AHEAD, (ARROW LEFT) CROSS HERE
R9-11R	24X18	3.00	2	6.00				SIDEWALK CLOSED AHEAD, (ARROW RIGHT) CROSS HERE
R10-6	24X36	6.00						STOP HERE ON RED (45^ ARROW)
R11-2	48X30	10.00	14	140.00				ROAD CLOSED
R11-3a	60X30	12.50						ROAD CLOSED XX MILES AHEAD LOCAL TRAFFIC ONLY
R11-4	60X30	12.50	5	62.50				ROAD CLOSED TO THRU TRAFFIC
CONST-3A	60X48	20.00						FINE SIGN
CONST-3X	56X12	4.67						SPEEDING/PASSING (PLATE)

MISCELLANEOUS SIGNS

SIGN	SIZE IN.	AREA SQ.FT.	QTY EACH	TOTAL SQ.FT.	QTY RELOC EACH	TOTAL RELOC SQ.FT.	SIGN NO.	DESCRIPTION
CONST-5	48X36	12.00						POINT OF PRESENCE
CONST-5	96X48	32.00	3	96.00				POINT OF PRESENCE
CONST-8	48X36	12.00	3	36.00				WORK ZONE NO PHONE ZONE
CONST-DR	A72X36	18.00	44	792.00				DETOUR ROUE ASSEMBLY

616-10.05 CONSTRUCTION SIGNS	TOTAL 2431

616-10.10 RELOCATED SIGNS	TOTAL

EFFECTIVE: 07-01-2025

ITEM NUMBER	TOTAL QTY	DESCRIPTION
6122008		IMPACT ATTENUATOR 40 MPH (SAND BARRELS)
6122009	2	IMPACT ATTENUATOR 45 MPH (SAND BARRELS)
6122010		IMPACT ATTENUATOR 50 MPH (SAND BARRELS)
6122012		IMPACT ATTENUATOR 55 MPH (SAND BARRELS)
6122014		IMPACT ATTENUATOR 60 MPH (SAND BARRELS)
6122017		IMPACT ATTENUATOR 65 MPH (SAND BARRELS)
6122019		IMPACT ATTENUATOR 70 MPH (SAND BARRELS)
6122020		REPLACEMENT SAND BARREL
6122030	2	IMPACT ATTENUATOR (RELOCATION)
6122040		WORK ZONE CRASH CUSHION (NARROW)
6122041		WORK ZONE CRASH CUSHION (RELOCATION)
6123001	2 | 1	TRUCK MOUNTED ATTENUATOR (TMA) ← 1
6161012		BUOYS (BOATS KEEP OUT)
6161013		BUOYS (NO WAKE)
6161014		SPECIAL SIGN ASSEMBLY (BOATS KEEP OUT)
6161020		CHANNELIZER (DRUM-LIKE)
6161022		CHANNELIZER (CONE)
6161025	160	CHANNELIZER (TRIM-LINE)
6161026		CHANNELIZER (VERTICAL PANEL)
6161030	17	TYPE 3 MOVEABLE BARRICADE
6161033		DIRECTION INDICATOR BARRICADE
6161040	4	FLASHING ARROW PANEL
6161047		TYPE 3 OBJECT MARKER
6161055		SEQUENTIAL FLASHING WARNING LIGHT
6161070		TUBULAR MARKER
6161095		RADAR SPEED ADVISORY SYSTEM
6161096		CHANGEABLE MESSAGE SIGN, COMMISSION FURNISHED/RETAINED
6161098A		CHANGEABLE MESSAGE SIGN WITHOUT COMM. INTERFACE, CONTRACTOR FURNISHED/RETAINED
6161099	12	CHANGEABLE MESSAGE SIGN WITH COMM. INTERFACE, CONTRACTOR FURNISHED/RETAINED
6162000A		WORK ZONE TRAFFIC SIGNAL SYSTEM
6162002		TEMPORARY LONG-TERM RUMBLE STRIPS
6173600D		TEMPORARY TRAFFIC BARRIER, CONTRACTOR FURNISHED/RETAINED
6173700B	3175	TEMP. TRAFFIC BARRIER ANCHORED, CONTRACTOR FURNISHED/RETAINED
6173706		TEMP. TRAFFIC BARRIER STIFFNESS TRANSITION CONTRACTOR FURNISHED/RETAINED
6174000A	2	TEMP. TRAFFIC BARRIER HEIGHT TRANSITION, CONTRACTOR FURNISHED/RETAINED
6175010A		RELOCATING TEMPORARY TRAFFIC BARRIER
6175011B	7575	RELOCATING TEMP. TRAFFIC BARRIER ANCHORED
6175013		RELOCATING TEMP. TRAFFIC BARRIER STIFFNESS
6175020A		RELOCATING TEMP. TRAFFIC BARRIER HEIGHT
6208064A		TEMPORARY RAISED PAVEMENT MARKER
9029400	1	TEMPORARY TRAFFIC SIGNALS
9029401		TEMPORARY TRAFFIC SIGNALS AND LIGHTING
6169902	10	ADA COMPLIANT MOVEABLE BARRICADE
4011209	1728 TONS	BITUMINOUS PAVEMENT MIXTURE PG 64-22 (BP-1 AS APPROVED BY ENGINEER) TEMP SURF

1 REVISED

SUMMARY OF QUANTITIES
SHEET 16 OF 16

STATE OF MISSOURI
SEAN L. MATLOCK
NUMBER E-27133
PROFESSIONAL ENGINEER

DATE PREPARED
11/16/2026

ROUTE	STATE
96	MO
DISTRICT	SHEET NO.
SW	3

COUNTY
JASPER

JOB NO.
JSR0060

CONTRACT ID.
-

PROJECT NO.
-

BRIDGE NO.
-

DESCRIPTION | DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

2215 Fairlawn Dr
Carthage, MO 64836
417.358.9551
COA# 00062
weareown.com
OWN
Engineering beyond.