CERTIFIED BY DESIGN STATE DESIGN ENGINEER

8/24/2012

Missouri Department of Transportation

Vendor Ranking

Call Order: C02
Contract ID: 120824-C02
Counties: CLAY
Letting Date: August 24, 2012 11:00 a.m.
District(s): Kansas City
Contract Time: DT - 12/1/2012

Contract Description: J4S2392B - ROUTE 69 - CLAY COUNTY
Project(s):

Rank	Vendor ID/Name		Total Bid	Percent Of Low Bid
1	0010188	Ideker, Inc.	$2,757,480.76	100.00%
2	0010528	Chester Bross Const. Co./C.B. Equipment Inc.	$2,809,283.79	101.88%
3	0010141	APAC-Kansas, Inc., Kansas City Division	$2,873,509.53	104.21%
4	0011249	Superior Bowen Asphalt Company, L.L.C.	$2,894,212.62	104.96%

CONTRACT ID: 120824-C02
LETTING DATE: 08/24/12

TABULATION OF BIDS

Call No: C02	Ideker, Inc. Low Bid	Chester Bross Const. Co./CB Equip. Inc. 2nd Low	APAC-Kansas, Inc., Kansas City Division 3rd Low	Superior Bowen Asphalt Company, L.L.C. 4th Low		

Project J4S2392B: Coldmilling, resurfacing (SP), shoulders (BP-1)

Section 0001: ROADWAY ITEMS - J4S2392B

0010	**207-20.00**	**LINEAR GRADING CLASS 2**				**30 STA**
Bid Price	**1066.67**	**475.00**	**1335.00**	**1133.00**		
Bid Amount	$32,000.10	$14,250.00	$40,050.00	$33,990.00		
0020	**304-99.10**	**MISC. TYPE 5 AGGREGATE**				**4,479.10 TONS**
Bid Price	**16.64**	**16.25**	**22.80**	**20.30**		
Bid Amount	$74,532.22	$72,785.38	$102,123.48	$90,925.73		
0030	**310-50.02**	**GRAVEL (A) OR CRUSHED STONE (B)**				**34 TONS**
Bid Price	**43.00**	**80.00**	**220.00**	**69.10**		
Bid Amount	$1,462.00	$2,720.00	$7,480.00	$2,349.40		
0040	**401-12.09**	**BITUMINOUS PAVEMENT MIXTURE PG64-22, (BP-1)**				**6,146.20 TONS**
Bid Price	**48.90**	**46.35**	**55.05**	**52.43**		
Bid Amount	$300,549.18	$284,876.37	$338,348.31	$322,245.27		
0050	**403-01.32**	**ASPHALTIC CONCRETE MIXTURE PG 76-22 (SP125BSM MIX)**				**10,061.70 TONS**
Bid Price	**81.15**	**87.65**	**91.35**	**86.75**		
Bid Amount	$816,506.96	$881,908.01	$919,136.30	$872,852.48		
0060	**403-02.17**	**ASPHALTIC CONCRETE MIXTURE PG 76-22 (SP190B MIX)**				**13,326.10 TONS**
Bid Price	**55.74**	**58.95**	**61.80**	**63.80**		
Bid Amount	$742,796.81	$785,573.60	$823,552.98	$850,205.18		
0070	**407-10.05**	**TACK COAT**				**7,330 GAL**
Bid Price	**0.42**	**0.01**	**2.00**	**2.40**		
Bid Amount	$3,078.60	$73.30	$14,660.00	$17,592.00		
0080	**606-10.11A**	**GUARDRAIL TYPE A, 7 FT. POST, 3 FT. - 1.5 IN SPACING**				**9,300 LF**
Bid Price	**24.91**	**25.40**	**24.90**	**24.20**		
Bid Amount	$231,663.00	$236,220.00	$231,570.00	$225,060.00		
0090	**606-30.15**	**TYPE A CRASHWORTHY END TERMINAL**				**60 EA**
Bid Price	**1819.91**	**1835.00**	**1820.00**	**1749.00**		
Bid Amount	$109,194.60	$110,100.00	$109,200.00	$104,940.00		
0100	**612-30.00A**	**TRUCK OR TRAILER MOUNTED ATTENUATOR (TMA)**				**2 EA**
Bid Price	**500.00**	**1476.00**	**1010.00**	**500.00**		
Bid Amount	$1,000.00	$2,952.00	$2,020.00	$1,000.00		
0110	**613-30.18**	**FURNISHING AND PLACING BITUMINOUS MATERIAL FOR CLASS B PARTI AL DEPTH PAVEMENT REPAIR**				**537 TONS**
Bid Price	**60.96**	**66.00**	**39.15**	**26.70**		
Bid Amount	$32,735.52	$35,442.00	$21,023.55	$14,337.90		

TABULATION OF BIDS

Call No: C02	Ideker, Inc. Low Bid	Chester Bross Const. Co./CB Equip. Inc. 2nd Low	APAC-Kansas, Inc., Kansas City Division 3rd Low	Superior Bowen Asphalt Company, L.L.C. 4th Low		
0120	**613-30.19**	**REMOVAL FOR CLASS B PARTIAL DEPTH PAVEMENT REPAIR**				**2,761.80 SQYD**
Bid Price	**22.86**	**29.50**	**25.60**	**21.00**		
Bid Amount	$63,134.75	$81,473.10	$70,702.08	$57,997.80		
0130	**616-10.05**	**CONSTRUCTION SIGNS**				**2,501 SQFT**
Bid Price	**5.00**	**5.25**	**5.10**	**5.00**		
Bid Amount	$12,505.00	$13,130.25	$12,755.10	$12,505.00		
0140	**616-10.08**	**ADVANCED WARNING RAIL SYSTEM**				**8 EA**
Bid Price	**50.00**	**52.50**	**50.85**	**50.00**		
Bid Amount	$400.00	$420.00	$406.80	$400.00		
0150	**616-10.09**	**FLAG ASSEMBLY**				**120 EA**
Bid Price	**14.00**	**15.00**	**14.25**	**14.00**		
Bid Amount	$1,680.00	$1,800.00	$1,710.00	$1,680.00		
0160	**616-10.25**	**CHANNELIZER (TRIM LINE)**				**220 EA**
Bid Price	**18.00**	**19.00**	**18.30**	**18.00**		
Bid Amount	$3,960.00	$4,180.00	$4,026.00	$3,960.00		
0170	**616-10.40**	**FLASHING ARROW PANEL**				**2 EA**
Bid Price	**600.00**	**630.00**	**610.00**	**600.00**		
Bid Amount	$1,200.00	$1,260.00	$1,220.00	$1,200.00		
0180	**616-10.98**	**CHANGEABLE MESSAGE SIGN, CONTRACTOR FURNISHED, CONTRACTOR RE TAINED**				**2 EA**
Bid Price	**1400.00**	**1470.00**	**1425.00**	**1400.00**		
Bid Amount	$2,800.00	$2,940.00	$2,850.00	$2,800.00		
0190	**618-10.00**	**MOBILIZATION**				**LUMP SUM**
Lump Sum	**$91,171.60**	**$122,000.00**	**$52,350.00**	**$106,428.00**		
0200	**620-51.20**	**TYPE 2 PREFORMED MARKING TAPE (GROOVED), 24 IN., WHITE**				**194 LF**
Bid Price	**15.00**	**15.75**	**15.10**	**15.00**		
Bid Amount	$2,910.00	$3,055.50	$2,929.40	$2,910.00		
0210	**620-51.30**	**TYPE 2 PREFORMED MARKING TAPE (GROOVED), LEFT/RIGHT ARROW**				**2 EA**
Bid Price	**275.00**	**288.75**	**275.00**	**275.00**		
Bid Amount	$550.00	$577.50	$550.00	$550.00		
0220	**620-61.06**	**ACRYLIC WATERBORNE PAVEMENT MARKING PAINT, 6 IN., WHITE**				**44,033 LF**
Bid Price	**0.09**	**0.10**	**0.09**	**0.10**		
Bid Amount	$3,962.97	$4,403.30	$3,962.97	$4,403.30		
0230	**620-61.19**	**ACRYLIC WATERBORNE PAVEMENT MARKING PAINT, 6 IN., YELLOW**				**33,904 LF**
Bid Price	**0.09**	**0.10**	**0.09**	**0.10**		
Bid Amount	$3,051.36	$3,390.40	$3,051.36	$3,390.40		
0240	**622-10.01**	**COLDMILLING BITUMINOUS PAVEMENT FOR REMOVAL OF SURFACING (3 IN. THICK OR LESS)**				**107,468 SQYD**
Bid Price	**1.24**	**0.68**	**0.49**	**0.76**		
Bid Amount	$133,260.32	$73,078.24	$52,659.32	$81,675.68		

TABULATION OF BIDS

Call No: C02	Ideker, Inc. Low Bid	Chester Bross Const. Co./CB Equip. Inc. 2nd Low	APAC-Kansas, Inc., Kansas City Division 3rd Low	Superior Bowen Asphalt Company, L.L.C. 4th Low		
0250	**622-40.10**	**MODIFIED COLDMILLING (DEPTH TRANSITIONS)**				**23,644 SQYD**
Bid Price	**2.71**	**1.75**	**1.25**	**2.42**		
Bid Amount	$64,075.24	$41,377.00	$29,555.00	$57,218.48		
0260	**626-10.00A**	**BITUMINOUS SHOULDER RUMBLE STRIP**				**673.60 STA**
Bid Price	**16.23**	**18.15**	**9.55**	**7.50**		
Bid Amount	$10,932.53	$12,225.84	$6,432.88	$5,052.00		
SECTION TOTALS	**$2,741,112.76**	**$2,792,211.79**	**$2,854,325.53**	**$2,877,668.62**		

Section 0002: SIGNAL ITEMS - J4S2392B

0270	**902-85.00**	**CABLE, LOOP DETECTOR, IN DUCT**				**3,520 LF**
Bid Price	**4.65**	**4.85**	**5.45**	**4.70**		
Bid Amount	$16,368.00	$17,072.00	$19,184.00	$16,544.00		

Contract Totals - 120824-C02

	$2,757,480.76	**$2,809,283.79**	**$2,873,509.53**	**$2,894,212.62**		

CERTIFIED BY DESIGN STATE DESIGN ENGINEER

8/24/2012

Missouri Department of Transportation

Vendor Ranking

Call Order: C03
Contract ID: 120824-C03
Counties: PLATTE
Letting Date: August 24, 2012 11:00 a.m.
District(s): Kansas City
Contract Time: DT - 10/12/2012

Contract Description: J4M0252 - ROUTE 635 - PLATTE COUNTY
Project(s):

Rank	Vendor ID/Name		Total Bid	Percent Of Low Bid
1	0010142	Clarkson Construction Company	$74,264.87	100.00%
2	0010211	Leavenworth Excavating & Equip. Company, Inc.	$82,691.25	111.35%
3	0010739	Radmacher Brothers Excavating Co. Inc.	$92,716.30	124.85%
4	0012219	Freeman Concrete Construction LLC	$122,256.50	164.62%

CONTRACT ID: 120824-C03
LETTING DATE: 08/24/12

TABULATION OF BIDS

Call No: C03	Clarkson Construction Company Low Bid	Leavenworth Excavating & Equip. 2nd Low	Radmacher Brothers Excavating Co. Inc. 3rd Low	Freeman Concrete Construction LLC 4th Low		

Project J4M0252: Culvert and slide repair

Section 0001: ROADWAY ITEMS - J4M0252

0010	**201-30.00**	**CLEARING AND GRUBBING**				**1 ACRE**
Bid Price	**5500.00**	**800.00**	**4400.00**	**10100.00**		
Bid Amount	$5,500.00	$800.00	$4,400.00	$10,100.00		
0020	**202-20.10**	**REMOVAL OF IMPROVEMENTS**				**LUMP SUM**
Lump Sum	**$4,000.00**	**$8,775.00**	**$8,100.00**	**$9,700.00**		
0030	**203-55.00**	**EMBANKMENT IN PLACE**				**584 CUYD**
Bid Price	**14.00**	**17.50**	**31.50**	**47.00**		
Bid Amount	$8,176.00	$10,220.00	$18,396.00	$27,448.00		
0040	**206-30.00**	**CLASS 3 EXCAVATION**				**105 CUYD**
Bid Price	**10.00**	**26.55**	**15.90**	**100.00**		
Bid Amount	$1,050.00	$2,787.75	$1,669.50	$10,500.00		
0050	**206-35.00**	**CULVERT CLEANOUT**				**1 EA**
Bid Price	**2000.00**	**1700.00**	**5900.00**	**4400.00**		
Bid Amount	$2,000.00	$1,700.00	$5,900.00	$4,400.00		
0060	**401-12.09**	**BITUMINOUS PAVEMENT MIXTURE PG64-22, (BP-1)**				**3.80 TONS**
Bid Price	**500.00**	**616.00**	**460.00**	**960.00**		
Bid Amount	$1,900.00	$2,340.80	$1,748.00	$3,648.00		
0070	**604-40.12**	**PIPE COLLAR, TYPE B**				**1 EA**
Bid Price	**500.00**	**1600.00**	**5200.00**	**1000.00**		
Bid Amount	$500.00	$1,600.00	$5,200.00	$1,000.00		
0080	**606-10.10**	**GUARDRAIL TYPE A**				**240 LF**
Bid Price	**18.81**	**20.85**	**16.10**	**19.00**		
Bid Amount	$4,514.40	$5,004.00	$3,864.00	$4,560.00		
0090	**606-23.00A**	**TRANSITION SECTION, 6.5 FT. POSTS**				**1 EA**
Bid Price	**359.00**	**397.50**	**470.00**	**360.00**		
Bid Amount	$359.00	$397.50	$470.00	$360.00		
0100	**606-24.00**	**BRIDGE ANCHOR SECTION (THRIE BEAM)**				**1 EA**
Bid Price	**1675.00**	**3000.00**	**1700.00**	**1675.00**		
Bid Amount	$1,675.00	$3,000.00	$1,700.00	$1,675.00		
0110	**606-66.10**	**END ANCHOR**				**1 EA**
Bid Price	**877.00**	**971.00**	**810.00**	**880.00**		
Bid Amount	$877.00	$971.00	$810.00	$880.00		
0120	**609-10.60**	**PAVED DITCH**				**55.60 SQYD**
Bid Price	**55.00**	**90.25**	**120.00**	**145.00**		
Bid Amount	$3,058.00	$5,017.90	$6,672.00	$8,062.00		
0130	**612-30.00A**	**TRUCK OR TRAILER MOUNTED ATTENUATOR (TMA)**				**1 EA**
Bid Price	**1500.00**	**1500.00**	**290.00**	**4250.00**		
Bid Amount	$1,500.00	$1,500.00	$290.00	$4,250.00		

TABULATION OF BIDS

Call No: C03	Clarkson Construction Company Low Bid	Leavenworth Excavating & Equip. 2nd Low	Radmacher Brothers Excavating Co. Inc. 3rd Low	Freeman Concrete Construction LLC 4th Low		
0140	**616-10.05**	**CONSTRUCTION SIGNS**				**268 SQFT**
Bid Price	**9.00**	**9.95**	**8.40**	**9.00**		
Bid Amount	$2,412.00	$2,666.60	$2,251.20	$2,412.00		
0150	**616-10.08**	**ADVANCED WARNING RAIL SYSTEM**				**1 EA**
Bid Price	**50.00**	**55.35**	**89.00**	**50.00**		
Bid Amount	$50.00	$55.35	$89.00	$50.00		
0160	**616-10.09**	**FLAG ASSEMBLY**				**13 EA**
Bid Price	**18.00**	**19.95**	**52.50**	**18.00**		
Bid Amount	$234.00	$259.35	$682.50	$234.00		
0170	**616-10.25**	**CHANNELIZER (TRIM LINE)**				**47 EA**
Bid Price	**30.00**	**33.20**	**37.00**	**30.00**		
Bid Amount	$1,410.00	$1,560.40	$1,739.00	$1,410.00		
0180	**616-10.40**	**FLASHING ARROW PANEL**				**1 EA**
Bid Price	**400.00**	**443.00**	**525.00**	**400.00**		
Bid Amount	$400.00	$443.00	$525.00	$400.00		
0190	**616-10.98**	**CHANGEABLE MESSAGE SIGN, CONTRACTOR FURNISHED, CONTRACTOR RE TAINED**				**1 EA**
Bid Price	**1100.00**	**1200.00**	**1600.00**	**1100.00**		
Bid Amount	$1,100.00	$1,200.00	$1,600.00	$1,100.00		
0200	**618-10.00**	**MOBILIZATION**				**LUMP SUM**
Lump Sum	**$8,001.47**	**$15,400.00**	**$10,000.00**	**$10,800.00**		
0210	**620-03.06**	**TYPE 1 PREFORMED MARKING TAPE, 6 IN., WHITE**				**4,130 LF**
Bid Price	**1.50**	**1.65**	**1.30**	**1.50**		
Bid Amount	$6,195.00	$6,814.50	$5,369.00	$6,195.00		
0220	**620-59.02**	**6 IN. WHITE HIGH BUILD ACRYLIC WATERBORNE PAVEMENT MARKING P AINT**				**1,820 LF**
Bid Price	**1.00**	**0.15**	**0.30**	**0.15**		
Bid Amount	$1,820.00	$273.00	$546.00	$273.00		
0230	**620-59.06**	**12 IN. WHITE HIGH BUILD ACRYLIC WATERBORNE PAVEMENT MARKING PAINT**				**900 LF**
Bid Price	**2.00**	**0.30**	**0.60**	**0.25**		
Bid Amount	$1,800.00	$270.00	$540.00	$225.00		
0240	**620-59.22**	**6 IN. WHITE WET REFLECTIVE HIGH BUILD ACRYLIC WATERBORNE PAV EMENT MARKING PAINT**				**578 LF**
Bid Price	**1.50**	**0.30**	**0.95**	**0.25**		
Bid Amount	$867.00	$173.40	$549.10	$144.50		
0250	**620-70.01**	**PAVEMENT MARKING REMOVAL**				**2,260 LF**
Bid Price	**1.60**	**0.20**	**0.60**	**0.20**		
Bid Amount	$3,616.00	$452.00	$1,356.00	$452.00		
0260	**725-03.18A**	**18 IN. PIPE GROUP B**				**78 LF**
Bid Price	**110.00**	**72.65**	**60.00**	**111.00**		
Bid Amount	$8,580.00	$5,666.70	$4,680.00	$8,658.00		

TABULATION OF BIDS

Call No: C03	Clarkson Construction Company Low Bid	Leavenworth Excavating & Equip. 2nd Low	Radmacher Brothers Excavating Co. Inc. 3rd Low	Freeman Concrete Construction LLC 4th Low		
0270	**732-00.18A**	**18 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION**				**1 EA**
Bid Price	**350.00**	**610.00**	**315.00**	**800.00**		
Bid Amount	$350.00	$610.00	$315.00	$800.00		
0280	**805-10.00A**	**SEEDING - COOL SEASON MIXTURES**				**0.10 ACRE**
Bid Price	**15000.00**	**18300.00**	**15750.00**	**15000.00**		
Bid Amount	$1,500.00	$1,830.00	$1,575.00	$1,500.00		
0290	**806-10.16**	**SEDIMENT REMOVAL**				**4 CUYD**
Bid Price	**5.00**	**39.75**	**210.00**	**55.00**		
Bid Amount	$20.00	$159.00	$840.00	$220.00		
0300	**806-10.22**	**TYPE II DITCH CHECK**				**4 EA**
Bid Price	**200.00**	**186.00**	**210.00**	**200.00**		
Bid Amount	$800.00	$744.00	$840.00	$800.00		
SECTION TOTALS	**$74,264.87**	**$82,691.25**	**$92,716.30**	**$122,256.50**		

Contract Totals - 120824-C03

	$74,264.87	**$82,691.25**	**$92,716.30**	**$122,256.50**		

CERTIFIED BY DESIGN STATE DESIGN ENGINEER

8/24/2012

Missouri Department of Transportation

Vendor Ranking

Call Order: D01
Contract ID: 120824-D01
Counties: OSAGE
Letting Date: August 24, 2012 11:00 a.m.
District(s): Central
Contract Time: DT - 9/1/2014

Contract Description: J5P0951B - ROUTE 50 - OSAGE COUNTY
Project(s): FAF-50-3 (82)

Rank	Vendor ID/Name		Total Bid	Percent Of Low Bid
1	0040360	Iron Mountain Trap Rock Co./dba Iron Mountain Const. Service	$25,541,654.86	100.00%
2	0026489	C. J. Moyna & Sons, Inc.	$25,625,611.57	100.33%
3	0010120	Bloomsdale Excavating Company, Incorporated	$25,628,509.83	100.34%
4	0010528	Chester Bross Const. Co./C.B. Equipment Inc.	$25,739,048.08	100.77%
5	0010445	Emery Sapp & Sons Inc.	$26,624,512.64	104.24%
6	0010206	Kolb Grading, LLC	$27,589,518.01	108.02%
7	0011035	Millstone Bangert, Inc.	$28,774,465.75	112.66%
8	0011540	Lehman Construction, L.L.C.	$29,499,451.71	115.50%
9	0012034	H. R. Quadri Contractors, LLC	$30,690,454.66	120.16%
10	0011224	Kat Excavation, Inc.	$30,934,940.39	121.12%
11	0010189	Illinois Valley Paving a division of United Contractors	$31,257,886.78	122.38%

Call Order: D01 **Contract ID:** 120824-D01 **Counties:** OSAGE

Letting Date: August 24, 2012 11:00 a.m. **District(s):** Central

Contract Time: DT - 9/1/2014

Contract Description: J5P0951B - ROUTE 50 - OSAGE COUNTY **Project(s):** FAF-50-3 (82)

Rank	Vendor ID/Name		Total Bid	Percent Of Low Bid
		Midw		
12	0010142	Clarkson Construction Company	$32,239,802.68	126.22%

Alternate Pavement - The Mainline Life Cycle Cost Adjustment Factor to be applied to asphalt bid comparison is $1,377,700

Alternate Pavement - The A2 Shoulder Life Cycle Cost Adjustment Factor to be applied to asphalt bid comparison is $18,600

CONTRACT ID: 120824-D01
LETTING DATE: 08/24/12

TABULATION OF BIDS

Call No: D01	Iron Mountain Trap Rock Company Low Bid	C. J. Moyna & Sons, Inc. 2nd Low	Bloomsdale Excavating Company, Inc. 3rd Low	Chester Bross Const. Co./CB Equip. Inc. 4th Low	Emery Sapp & Sons Inc. 5th Low	Kolb Grading, LLC 6th Low

Project J5P0951B: Grading, drainage, alternate pavement and bridges

Section 0001: ROADWAY ITEMS - J5P0951B

0010	104-10.00	TEMPORARY SURFACING				708 CUYD
Bid Price	**42.00**	**24.00**	**24.44**	**24.85**	**31.00**	**30.00**
Bid Amount	$29,736.00	$16,992.00	$17,303.52	$17,593.80	$21,948.00	$21,240.00
0020	**201-30.00**	**CLEARING AND GRUBBING**				**62 ACRE**
Bid Price	**5300.00**	**3350.00**	**4057.24**	**3450.00**	**4300.00**	**5650.00**
Bid Amount	$328,600.00	$207,700.00	$251,548.88	$213,900.00	$266,600.00	$350,300.00
0030	**202-20.10**	**REMOVAL OF IMPROVEMENTS**				**LUMP SUM**
Lump Sum	**$115,000.00**	**$110,000.00**	**$65,289.67**	**$118,000.00**	**$98,000.00**	**$115,000.00**
0040	**202-40.38**	**REMOVAL OF TRANSITE (CATEGORY II NON-FRIABLE)**				**10,625 SQFT**
Bid Price	**2.75**	**2.75**	**2.90**	**2.85**	**2.25**	**2.25**
Bid Amount	$29,218.75	$29,218.75	$30,812.50	$30,281.25	$23,906.25	$23,906.25
0050	**202-40.40**	**REMOVAL OF MISCELLANEOUS ACM (FRIABLE)**				**600 SQFT**
Bid Price	**7.00**	**20.00**	**21.12**	**20.70**	**14.00**	**14.00**
Bid Amount	$4,200.00	$12,000.00	$12,672.00	$12,420.00	$8,400.00	$8,400.00
0060	**202-40.46**	**REMOVAL OF CAULKING/GLAZING COMPOUNDS (WINDOWS/DOORS) (CATEG ORY II NONFRIABLE)**				**430 LF**
Bid Price	**5.00**	**10.00**	**10.56**	**10.35**	**3.50**	**3.50**
Bid Amount	$2,150.00	$4,300.00	$4,540.80	$4,450.50	$1,505.00	$1,505.00
0070	**202-40.70**	**REMOVAL OF FLOOR SHEETING ACM ON WOOD (FRIABLE)**				**1,170 SQFT**
Bid Price	**6.25**	**5.00**	**5.28**	**5.15**	**5.60**	**5.60**
Bid Amount	$7,312.50	$5,850.00	$6,177.60	$6,025.50	$6,552.00	$6,552.00
0080	**202-40.72**	**REMOVAL OF FLOOR SHEETING ACM ON CONCRETE (FRIABLE)**				**30 SQFT**
Bid Price	**6.50**	**15.00**	**15.84**	**15.50**	**15.00**	**15.00**
Bid Amount	$195.00	$450.00	$475.20	$465.00	$450.00	$450.00
0090	**202-40.98**	**REMOVAL OF FLOOR TILE AND MASTIC ACM ON CONCRETE (CATEGORY I NON-FRIABLE)**				**3,400 SQFT**
Bid Price	**2.95**	**2.50**	**2.64**	**2.60**	**2.50**	**2.50**
Bid Amount	$10,030.00	$8,500.00	$8,976.00	$8,840.00	$8,500.00	$8,500.00
0100	**202-70.00**	**DISPOSAL AND PLUGGING OF WELLS**				**3 EA**
Bid Price	**2500.00**	**2500.00**	**2112.14**	**2588.00**	**2500.00**	**2500.00**
Bid Amount	$7,500.00	$7,500.00	$6,336.42	$7,764.00	$7,500.00	$7,500.00
0110	**202-99.50**	**DEMOLITION AND REMOVAL OF BUILDINGS 4 (J5P0951B)**				**LUMP SUM**
Lump Sum	**$1,592.81**	**$2,000.00**	**$1,108.48**	**$2,070.00**	**$2,500.00**	**$2,500.00**

TABULATION OF BIDS

Call No: D01	Iron Mountain Trap Rock Company Low Bid	C. J. Moyna & Sons, Inc. 2nd Low	Bloomsdale Excavating Company, Inc. 3rd Low	Chester Bross Const. Co./CB Equip. Inc. 4th Low	Emery Sapp & Sons Inc. 5th Low	Kolb Grading, LLC 6th Low
0120 202-99.50 DEMOLITION AND REMOVAL OF BUILDINGS 5 (J5P0951B)						**LUMP SUM**
Lump Sum	**$14,265.01**	**$35,000.00**	**$6,289.60**	**$36,235.00**	**$32,000.00**	**$32,000.00**
0130 202-99.50 DEMOLITION AND REMOVAL OF BUILDINGS 9 (J5P0951B)						**LUMP SUM**
Lump Sum	**$6,875.41**	**$20,000.00**	**$3,273.03**	**$20,705.00**	**$16,000.00**	**$16,000.00**
0140 202-99.50 DEMOLITION AND REMOVAL OF BUILDINGS 16 (J5P0951B)						**LUMP SUM**
Lump Sum	**$9,516.70**	**$6,000.00**	**$1,557.50**	**$6,211.00**	**$3,500.00**	**$3,500.00**
0150 202-99.50 DEMOLITION AND REMOVAL OF BUILDINGS 17 (J5P0951B)						**LUMP SUM**
Lump Sum	**$2,135.13**	**$1,000.00**	**$896.88**	**$1,035.00**	**$1,000.00**	**$1,000.00**
0160 202-99.50 DEMOLITION AND REMOVAL OF BUILDINGS 18 (J5P0951B)						**LUMP SUM**
Lump Sum	**$3,878.59**	**$3,000.00**	**$3,273.03**	**$3,105.00**	**$3,500.00**	**$3,500.00**
0170 202-99.50 DEMOLITION AND REMOVAL OF BUILDINGS 27 (J5P0951B)						**LUMP SUM**
Lump Sum	**$907.88**	**$2,000.00**	**$1,953.34**	**$2,070.00**	**$1,500.00**	**$1,500.00**
0180 203-10.00 CLASS A EXCAVATION						**716,361 CUYD**
Bid Price	**2.25**	**1.80**	**2.45**	**1.86**	**2.29**	**2.57**
Bid Amount	$1,611,812.25	$1,289,449.80	$1,755,084.45	$1,332,431.46	$1,640,466.69	$1,841,047.77
0190 203-20.00 CLASS C EXCAVATION						**1,165,196 CUYD**
Bid Price	**5.25**	**5.50**	**4.25**	**5.69**	**6.44**	**6.35**
Bid Amount	$6,117,279.00	$6,408,578.00	$4,952,083.00	$6,629,965.24	$7,503,862.24	$7,398,994.60
0200 203-60.00 COMPACTING EMBANKMENT						**1,771,727 CUYD**
Bid Price	**0.10**	**0.10**	**0.25**	**0.10**	**0.31**	**0.25**
Bid Amount	$177,172.70	$177,172.70	$442,931.75	$177,172.70	$549,235.37	$442,931.75
0210 203-70.75 COMPACTING IN CUT						**292 STA**
Bid Price	**100.00**	**50.00**	**297.29**	**51.75**	**420.00**	**450.00**
Bid Amount	$29,200.00	$14,600.00	$86,808.68	$15,111.00	$122,640.00	$131,400.00
0220 203-99.01 MISC. LAGOON CLOSURE						**LUMP SUM**
Lump Sum	**$40,000.00**	**$2,500.00**	**$10,283.07**	**$2,588.00**	**$65,000.00**	**$6,500.00**
0230 206-30.00 CLASS 3 EXCAVATION						**374 CUYD**
Bid Price	**15.00**	**14.00**	**7.30**	**14.10**	**28.00**	**40.00**
Bid Amount	$5,610.00	$5,236.00	$2,730.20	$5,273.40	$10,472.00	$14,960.00
0240 206-33.00 CLASS 4 EXCAVATION						**1,906 CUYD**
Bid Price	**22.00**	**10.00**	**51.24**	**17.60**	**9.50**	**10.00**
Bid Amount	$41,932.00	$19,060.00	$97,663.44	$33,545.60	$18,107.00	$19,060.00
0250 206-34.00 CLASS 4 EXCAVATION IN ROCK						**53 CUYD**
Bid Price	**65.00**	**50.00**	**134.76**	**207.00**	**90.00**	**50.00**
Bid Amount	$3,445.00	$2,650.00	$7,142.28	$10,971.00	$4,770.00	$2,650.00
0260 207-10.00 LINEAR GRADING CLASS 1						**17 STA**
Bid Price	**865.00**	**800.00**	**416.78**	**828.00**	**195.00**	**750.00**
Bid Amount	$14,705.00	$13,600.00	$7,085.26	$14,076.00	$3,315.00	$12,750.00

TABULATION OF BIDS

Call No: D01	Iron Mountain Trap Rock Company Low Bid	C. J. Moyna & Sons, Inc. 2nd Low	Bloomsdale Excavating Company, Inc. 3rd Low	Chester Bross Const. Co./CB Equip. Inc. 4th Low	Emery Sapp & Sons Inc. 5th Low	Kolb Grading, LLC 6th Low
0270 208-10.00 INTERCEPTION DITCH						**101 100F**
Bid Price	**125.00**	**120.00**	**132.31**	**124.00**	**160.00**	**100.00**
Bid Amount	$12,625.00	$12,120.00	$13,363.31	$12,524.00	$16,160.00	$10,100.00
0280 214-20.00 FURNISHING ROCK FILL						**10,972 CUYD**
Bid Price	**1.00**	**0.01**	**4.59**	**0.01**	**5.70**	**0.01**
Bid Amount	$10,972.00	$109.72	$50,361.48	$109.72	$62,540.40	$109.72
0290 214-30.00 PLACING ROCK FILL						**10,972 CUYD**
Bid Price	**9.00**	**18.00**	**2.74**	**18.65**	**0.75**	**10.00**
Bid Amount	$98,748.00	$197,496.00	$30,063.28	$204,627.80	$8,229.00	$109,720.00
0300 215-10.00A SHAPING SLOPES, CLASS I						**72 100F**
Bid Price	**235.00**	**20.00**	**266.02**	**20.70**	**325.00**	**275.00**
Bid Amount	$16,920.00	$1,440.00	$19,153.44	$1,490.40	$23,400.00	$19,800.00
0310 303-99.05 MISC. ROCK BASE OPTIONAL ROCK BASE						**404,510 SQYD**
Bid Price	**2.40**	**2.15**	**2.70**	**2.55**	**1.07**	**1.25**
Bid Amount	$970,824.00	$869,696.50	$1,092,177.00	$1,031,500.50	$432,825.70	$505,637.50
0320 304-01.43 TYPE 1 AGGREGATE FOR BASE (4 IN. THICK)						**16,835 SQYD**
Bid Price	**4.00**	**3.60**	**5.64**	**4.70**	**4.55**	**4.00**
Bid Amount	$67,340.00	$60,606.00	$94,949.40	$79,124.50	$76,599.25	$67,340.00
0330 304-99.05 MISC. TYPE 1 AGGREGATE FOR BASE (2 IN. THICK)						**8,877.20 SQYD**
Bid Price	**2.00**	**2.00**	**4.65**	**2.85**	**2.80**	**4.00**
Bid Amount	$17,754.40	$17,754.40	$41,278.98	$25,300.02	$24,856.16	$35,508.80
0340 310-70.02 GRAVEL (A) OR CRUSHED STONE (B) OR CHAT (C)						**1,173 TONS**
Bid Price	**35.00**	**12.00**	**14.65**	**12.40**	**25.00**	**15.00**
Bid Amount	$41,055.00	$14,076.00	$17,184.45	$14,545.20	$29,325.00	$17,595.00
0350 401-01.51 TYPE A3 SHOULDER						**82,473 SQYD**
Bid Price	**17.00**	**18.20**	**13.55**	**13.30**	**17.20**	**16.75**
Bid Amount	$1,402,041.00	$1,501,008.60	$1,117,509.15	$1,096,890.90	$1,418,535.60	$1,381,422.75
0360 401-12.09 BITUMINOUS PAVEMENT MIXTURE PG64-22, (BP-1)						**320.10 TONS**
Bid Price	**75.87**	**78.00**	**80.12**	**78.55**	**68.63**	**75.87**
Bid Amount	$24,285.99	$24,967.80	$25,646.41	$25,143.86	$21,968.46	$24,285.99
0370 401-30.00 BITUMINOUS PAVEMENT MIXTURE PG64-22 (BASE)						**746.30 TONS**
Bid Price	**61.74**	**71.35**	**65.20**	**64.00**	**64.15**	**61.74**
Bid Amount	$46,076.56	$53,248.51	$48,658.76	$47,763.20	$47,875.15	$46,076.56
0380 401-99.05 MISC. OPTIONAL PAVEMENT (6 IN. THICK)						**24,881.70 SQYD**
Bid Price	**21.51**	**23.75**	**22.72**	**22.25**	**21.35**	**21.51**
Bid Amount	$535,205.37	$590,940.38	$565,312.22	$553,617.83	$531,224.30	$535,205.37
0390 401-99.05 MISC. OPTIONAL PAVEMENT (6.5 IN. OR 7 IN. THIC K)						**3,703.10 SQYD**
Bid Price	**24.51**	**24.50**	**25.88**	**25.35**	**19.40**	**24.51**
Bid Amount	$90,762.98	$90,725.95	$95,836.23	$93,873.59	$71,840.14	$90,762.98
0400 401-99.05 MISC. OPTIONAL PAVEMENT (7 IN. THICK)						**4,687.10 SQYD**
Bid Price	**24.48**	**27.70**	**25.85**	**25.35**	**27.50**	**24.48**
Bid Amount	$114,740.21	$129,832.67	$121,161.54	$118,817.99	$128,895.25	$114,740.21

TABULATION OF BIDS

Call No: D01	Iron Mountain Trap Rock Company Low Bid	C. J. Moyna & Sons, Inc. 2nd Low	Bloomsdale Excavating Company, Inc. 3rd Low	Chester Bross Const. Co./CB Equip. Inc. 4th Low	Emery Sapp & Sons Inc. 5th Low	Kolb Grading, LLC 6th Low
0410 401-99.05	**MISC. OPTIONAL PAVEMENT (7.5 IN. THICK)**					**549.50 SQYD**
Bid Price	**34.42**	**31.00**	**36.35**	**35.65**	**26.80**	**34.42**
Bid Amount	$18,913.79	$17,034.50	$19,974.33	$19,589.68	$14,726.60	$18,913.79
0420 402-05.20	**BITUMINOUS PAVEMENT MIXTURE PG64-22 (SURFACE LEVELING)**					**278.40 TONS**
Bid Price	**81.08**	**90.00**	**85.63**	**84.00**	**68.63**	**81.08**
Bid Amount	$22,572.67	$25,056.00	$23,839.39	$23,385.60	$19,106.59	$22,572.67
0430 407-10.05	**TACK COAT**					**230 GAL**
Bid Price	**2.00**	**5.00**	**5.28**	**5.00**	**5.00**	**5.00**
Bid Amount	$460.00	$1,150.00	$1,214.40	$1,150.00	$1,150.00	$1,150.00
0440 504-10.00	**CONCRETE APPROACH PAVEMENT**					**219.30 SQYD**
Bid Price	**90.00**	**130.00**	**126.73**	**128.50**	**105.00**	**125.00**
Bid Amount	$19,737.00	$28,509.00	$27,791.89	$28,180.05	$23,026.50	$27,412.50
0450 604-40.11	**PIPE COLLAR, TYPE A**					**1 EA**
Bid Price	**2800.00**	**1500.00**	**4396.74**	**1500.00**	**3600.00**	**3000.00**
Bid Amount	$2,800.00	$1,500.00	$4,396.74	$1,500.00	$3,600.00	$3,000.00
0460 604-40.12	**PIPE COLLAR, TYPE B**					**8 EA**
Bid Price	**1290.00**	**1000.00**	**570.80**	**1000.00**	**1500.00**	**1000.00**
Bid Amount	$10,320.00	$8,000.00	$4,566.40	$8,000.00	$12,000.00	$8,000.00
0470 606-10.10	**GUARDRAIL TYPE A**					**6,575 LF**
Bid Price	**16.00**	**16.00**	**16.90**	**16.55**	**16.00**	**16.00**
Bid Amount	$105,200.00	$105,200.00	$111,117.50	$108,816.25	$105,200.00	$105,200.00
0480 606-10.11A	**GUARDRAIL TYPE A, 7 FT. POST, 3 FT. - 1.5 IN SPACING**					**1,325 LF**
Bid Price	**28.50**	**28.50**	**30.10**	**29.50**	**28.50**	**28.50**
Bid Amount	$37,762.50	$37,762.50	$39,882.50	$39,087.50	$37,762.50	$37,762.50
0490 606-10.40	**GUARDRAIL TYPE D**					**13 LF**
Bid Price	**20.00**	**20.00**	**21.12**	**20.70**	**20.00**	**20.00**
Bid Amount	$260.00	$260.00	$274.56	$269.10	$260.00	$260.00
0500 606-23.00A	**TRANSITION SECTION, 6.5 FT. POSTS**					**5 EA**
Bid Price	**300.00**	**300.00**	**316.82**	**310.50**	**300.00**	**300.00**
Bid Amount	$1,500.00	$1,500.00	$1,584.10	$1,552.50	$1,500.00	$1,500.00
0510 606-24.00	**BRIDGE ANCHOR SECTION (THRIE BEAM)**					**5 EA**
Bid Price	**1800.00**	**1800.00**	**1900.93**	**1865.00**	**1800.00**	**1800.00**
Bid Amount	$9,000.00	$9,000.00	$9,504.65	$9,325.00	$9,000.00	$9,000.00
0520 606-30.15	**TYPE A CRASHWORTHY END TERMINAL**					**11 EA**
Bid Price	**1950.00**	**1950.00**	**2059.34**	**2018.00**	**1950.00**	**1950.00**
Bid Amount	$21,450.00	$21,450.00	$22,652.74	$22,198.00	$21,450.00	$21,450.00
0530 606-30.17	**TYPE C CRASHWORTHY END TERMINAL**					**1 EA**
Bid Price	**14500.00**	**14500.00**	**15313.02**	**15000.00**	**14500.00**	**14500.00**
Bid Amount	$14,500.00	$14,500.00	$15,313.02	$15,000.00	$14,500.00	$14,500.00
0540 606-66.10	**END ANCHOR**					**8 EA**
Bid Price	**950.00**	**950.00**	**1003.27**	**985.00**	**950.00**	**950.00**
Bid Amount	$7,600.00	$7,600.00	$8,026.16	$7,880.00	$7,600.00	$7,600.00

TABULATION OF BIDS

Call No: D01	Iron Mountain Trap Rock Company Low Bid	C. J. Moyna & Sons, Inc. 2nd Low	Bloomsdale Excavating Company, Inc. 3rd Low	Chester Bross Const. Co./CB Equip. Inc. 4th Low	Emery Sapp & Sons Inc. 5th Low	Kolb Grading, LLC 6th Low
0550 607-10.50 CHAIN-LINK FENCE (RETAINING WALLS)						**226 LF**
Bid Price	**19.50**	**50.00**	**20.59**	**20.20**	**19.50**	**19.50**
Bid Amount	$4,407.00	$11,300.00	$4,653.34	$4,565.20	$4,407.00	$4,407.00
0560 607-11.01 MODIFIED CONCRETE GUTTER TYPE A						**226 LF**
Bid Price	**52.00**	**55.00**	**63.36**	**67.00**	**45.00**	**55.00**
Bid Amount	$11,752.00	$12,430.00	$14,319.36	$15,142.00	$10,170.00	$12,430.00
0570 609-20.11 INTEGRAL CURB (6 IN. HEIGHT AND UNDER) TYPE A						**20 LF**
Bid Price	**31.50**	**30.00**	**105.61**	**20.00**	**22.50**	**25.00**
Bid Amount	$630.00	$600.00	$2,112.20	$400.00	$450.00	$500.00
0580 609-60.20 FURNISHING TYPE 2 ROCK DITCH LINER						**8,546 CUYD**
Bid Price	**0.01**	**0.01**	**3.64**	**0.01**	**26.00**	**0.01**
Bid Amount	$85.46	$85.46	$31,107.44	$85.46	$222,196.00	$85.46
0590 609-60.30A FURNISHING TYPE 3 ROCK DITCH LINER						**7,069 CUYD**
Bid Price	**0.01**	**0.01**	**3.64**	**0.01**	**26.00**	**0.01**
Bid Amount	$70.69	$70.69	$25,731.16	$70.69	$183,794.00	$70.69
0600 609-60.42 PLACING TYPE 2 ROCK DITCH LINER						**8,546 CUYD**
Bid Price	**19.00**	**22.00**	**16.45**	**22.75**	**16.25**	**30.00**
Bid Amount	$162,374.00	$188,012.00	$140,581.70	$194,421.50	$138,872.50	$256,380.00
0610 609-60.43 PLACING TYPE 3 ROCK DITCH LINER						**7,069 CUYD**
Bid Price	**18.00**	**22.00**	**16.45**	**22.75**	**15.25**	**30.00**
Bid Amount	$127,242.00	$155,518.00	$116,285.05	$160,819.75	$107,802.25	$212,070.00
0620 609-60.50 BEDDING MATERIAL FOR ROCK DITCH LINER						**2,570 CUYD**
Bid Price	**42.00**	**22.00**	**13.98**	**22.75**	**39.00**	**20.00**
Bid Amount	$107,940.00	$56,540.00	$35,928.60	$58,467.50	$100,230.00	$51,400.00
0630 609-70.00 ROCK LINING						**1,764 CUYD**
Bid Price	**19.00**	**22.00**	**15.28**	**22.75**	**40.00**	**30.00**
Bid Amount	$33,516.00	$38,808.00	$26,953.92	$40,131.00	$70,560.00	$52,920.00
0640 611-30.20 FURNISHING TYPE 2 ROCK BLANKET						**988 CUYD**
Bid Price	**0.01**	**0.01**	**7.84**	**0.01**	**26.00**	**0.01**
Bid Amount	$9.88	$9.88	$7,745.92	$9.88	$25,688.00	$9.88
0650 611-30.40 PLACING TYPE 2 ROCK BLANKET						**988 CUYD**
Bid Price	**12.25**	**18.00**	**10.64**	**18.65**	**17.50**	**30.00**
Bid Amount	$12,103.00	$17,784.00	$10,512.32	$18,426.20	$17,290.00	$29,640.00
0660 611-60.10A SLOPE PROTECTION						**40 SQYD**
Bid Price	**103.00**	**40.00**	**184.81**	**41.40**	**70.00**	**58.50**
Bid Amount	$4,120.00	$1,600.00	$7,392.40	$1,656.00	$2,800.00	$2,340.00
0670 611-70.00A GABIONS						**78 CUYD**
Bid Price	**215.00**	**50.00**	**137.29**	**51.75**	**130.00**	**130.00**
Bid Amount	$16,770.00	$3,900.00	$10,708.62	$4,036.50	$10,140.00	$10,140.00
0680 612-20.14 IMPACT ATTENUATOR (14 SAND BARRELS)						**6 EA**
Bid Price	**2800.00**	**2500.00**	**3168.21**	**2070.00**	**2000.00**	**2000.00**
Bid Amount	$16,800.00	$15,000.00	$19,009.26	$12,420.00	$12,000.00	$12,000.00

TABULATION OF BIDS

Call No: D01	Iron Mountain Trap Rock Company Low Bid	C. J. Moyna & Sons, Inc. 2nd Low	Bloomsdale Excavating Company, Inc. 3rd Low	Chester Bross Const. Co./CB Equip. Inc. 4th Low	Emery Sapp & Sons Inc. 5th Low	Kolb Grading, LLC 6th Low
0690 612-20.20 REPLACEMENT SAND BARREL						**14 EA**
Bid Price	**500.00**	**300.00**	**369.62**	**51.75**	**50.00**	**50.00**
Bid Amount	$7,000.00	$4,200.00	$5,174.68	$724.50	$700.00	$700.00
0700 614-10.22 GRATE AND BEARING PLATE (3 FT. X 3 FT. OR 914 MM X 914 MM)						**10 EA**
Bid Price	**900.00**	**965.00**	**513.93**	**965.00**	**865.00**	**850.00**
Bid Amount	$9,000.00	$9,650.00	$5,139.30	$9,650.00	$8,650.00	$8,500.00
0710 614-10.24 GRATE AND BEARING PLATE (5 FT. X 3 FT. OR 1524 MM X 914 MM)						**9 EA**
Bid Price	**1325.00**	**2000.00**	**541.59**	**2000.00**	**890.00**	**1700.00**
Bid Amount	$11,925.00	$18,000.00	$4,874.31	$18,000.00	$8,010.00	$15,300.00
0720 614-11.21 CURVED VANE GRATE AND FRAME (4 FT X 2 FT OR 1200MM X 600MM)						**9 EA**
Bid Price	**715.00**	**2150.00**	**624.54**	**2150.00**	**650.00**	**650.00**
Bid Amount	$6,435.00	$19,350.00	$5,620.86	$19,350.00	$5,850.00	$5,850.00
0730 616-10.05 CONSTRUCTION SIGNS						**1,912 SQFT**
Bid Price	**15.00**	**7.50**	**8.45**	**8.80**	**8.50**	**8.00**
Bid Amount	$28,680.00	$14,340.00	$16,156.40	$16,825.60	$16,252.00	$15,296.00
0740 616-10.08 ADVANCED WARNING RAIL SYSTEM						**5 EA**
Bid Price	**50.00**	**105.00**	**52.80**	**57.00**	**55.00**	**50.00**
Bid Amount	$250.00	$525.00	$264.00	$285.00	$275.00	$250.00
0750 616-10.09 FLAG ASSEMBLY						**21 EA**
Bid Price	**20.00**	**25.00**	**21.12**	**26.00**	**25.00**	**20.00**
Bid Amount	$420.00	$525.00	$443.52	$546.00	$525.00	$420.00
0760 616-10.10 RELOCATED SIGNS						**32 SQFT**
Bid Price	**10.00**	**10.00**	**7.39**	**10.35**	**10.00**	**7.00**
Bid Amount	$320.00	$320.00	$236.48	$331.20	$320.00	$224.00
0770 616-10.25 CHANNELIZER (TRIM LINE)						**90 EA**
Bid Price	**50.00**	**32.00**	**31.68**	**18.65**	**18.00**	**30.00**
Bid Amount	$4,500.00	$2,880.00	$2,851.20	$1,678.50	$1,620.00	$2,700.00
0780 616-10.30 TYPE III MOVEABLE BARRICADE						**79 EA**
Bid Price	**175.00**	**230.00**	**184.81**	**98.35**	**95.00**	**175.00**
Bid Amount	$13,825.00	$18,170.00	$14,599.99	$7,769.65	$7,505.00	$13,825.00
0790 616-10.98 CHANGEABLE MESSAGE SIGN, CONTRACTOR FURNISHED, CONTRACTOR RE TAINED						**4 EA**
Bid Price	**3500.00**	**13500.00**	**3696.25**	**5176.00**	**6200.00**	**3500.00**
Bid Amount	$14,000.00	$54,000.00	$14,785.00	$20,704.00	$24,800.00	$14,000.00
0800 617-30.00 CONCRETE TRAFFIC BARRIER, TYPE C						**2,997 LF**
Bid Price	**38.00**	**58.30**	**54.65**	**48.65**	**47.00**	**47.00**
Bid Amount	$113,886.00	$174,725.10	$163,786.05	$145,804.05	$140,859.00	$140,859.00
0810 617-36.00D TEMPORARY TRAFFIC BARRIER, CONTRACTOR FURNISHED / RETAINED						**1,882 LF**
Bid Price	**25.00**	**15.00**	**23.23**	**24.85**	**15.00**	**15.00**
Bid Amount	$47,050.00	$28,230.00	$43,718.86	$46,767.70	$28,230.00	$28,230.00

TABULATION OF BIDS

Call No: D01	Iron Mountain Trap Rock Company Low Bid	C. J. Moyna & Sons, Inc. 2nd Low	Bloomsdale Excavating Company, Inc. 3rd Low	Chester Bross Const. Co./CB Equip. Inc. 4th Low	Emery Sapp & Sons Inc. 5th Low	Kolb Grading, LLC 6th Low
0820 618-10.00 MOBILIZATION						**LUMP SUM**
Lump Sum	**$775,000.00**	**$1,650,000.00**	**$1,802,806.00**	**$1,435,000.00**	**$1,675,000.00**	**$2,060,000.00**
0830 619-10.00 PAVEMENT EDGE TREATMENT						**7,104 LF**
Bid Price	**3.25**	**4.00**	**3.28**	**4.15**	**0.60**	**1.00**
Bid Amount	$23,088.00	$28,416.00	$23,301.12	$29,481.60	$4,262.40	$7,104.00
0840 620-51.20 TYPE 2 PREFORMED MARKING TAPE (GROOVED), 24 IN., WHITE						**204 LF**
Bid Price	**20.00**	**30.00**	**24.82**	**23.80**	**23.00**	**20.00**
Bid Amount	$4,080.00	$6,120.00	$5,063.28	$4,855.20	$4,692.00	$4,080.00
0850 620-51.30 TYPE 2 PREFORMED MARKING TAPE (GROOVED), LEFT/RIGHT ARROW						**26 EA**
Bid Price	**330.00**	**395.00**	**343.22**	**347.00**	**335.00**	**330.00**
Bid Amount	$8,580.00	$10,270.00	$8,923.72	$9,022.00	$8,710.00	$8,580.00
0860 620-51.40 TYPE 2 PREFORMED MARKING TAPE (GROOVED), 24 IN. WHITE, YIELD LINE TRIANGLES						**28 EA**
Bid Price	**35.00**	**60.00**	**52.80**	**31.05**	**30.00**	**35.00**
Bid Amount	$980.00	$1,680.00	$1,478.40	$869.40	$840.00	$980.00
0870 620-59.22 6 IN. WHITE WET REFLECTIVE HIGH BUILD ACRYLIC WATERBORNE PAV EMENT MARKING PAINT						**16,754 LF**
Bid Price	**0.40**	**0.38**	**0.46**	**0.40**	**0.39**	**0.40**
Bid Amount	$6,701.60	$6,366.52	$7,706.84	$6,701.60	$6,534.06	$6,701.60
0880 620-60.00B 4 IN. WHITE ACRYLIC WATERBORNE PAVEMENT MARKING PAINT						**15,967 LF**
Bid Price	**0.20**	**0.12**	**0.24**	**0.15**	**0.13**	**0.20**
Bid Amount	$3,193.40	$1,916.04	$3,832.08	$2,395.05	$2,075.71	$3,193.40
0890 620-60.01B 4 IN. YELLOW ACRYLIC WATERBORNE PAVEMENT MARKING PAINT						**26,819 LF**
Bid Price	**0.20**	**0.12**	**0.24**	**0.14**	**0.13**	**0.20**
Bid Amount	$5,363.80	$3,218.28	$6,436.56	$3,754.66	$3,486.47	$5,363.80
0900 620-61.06 ACRYLIC WATERBORNE PAVEMENT MARKING PAINT, 6 IN., WHITE						**74,485 LF**
Bid Price	**0.20**	**0.15**	**0.17**	**0.14**	**0.14**	**0.20**
Bid Amount	$14,897.00	$11,172.75	$12,662.45	$10,427.90	$10,427.90	$14,897.00
0910 620-61.08 ACRYLIC WATERBORNE PAVEMENT MARKING PAINT, 8 IN., WHITE						**214 LF**
Bid Price	**1.00**	**0.50**	**2.64**	**1.30**	**1.25**	**1.00**
Bid Amount	$214.00	$107.00	$564.96	$278.20	$267.50	$214.00
0920 620-61.19 ACRYLIC WATERBORNE PAVEMENT MARKING PAINT, 6 IN., YELLOW						**68,730 LF**
Bid Price	**0.20**	**0.15**	**0.17**	**0.15**	**0.14**	**0.20**
Bid Amount	$13,746.00	$10,309.50	$11,684.10	$10,309.50	$9,622.20	$13,746.00
0930 620-61.22 ACRYLIC WATERBORNE PAVEMENT MARKING PAINT, 12 IN., WHITE						**727 LF**
Bid Price	**0.40**	**0.25**	**1.21**	**1.35**	**1.30**	**0.40**
Bid Amount	$290.80	$181.75	$879.67	$981.45	$945.10	$290.80

TABULATION OF BIDS

Call No: D01	Iron Mountain Trap Rock Company Low Bid	C. J. Moyna & Sons, Inc. 2nd Low	Bloomsdale Excavating Company, Inc. 3rd Low	Chester Bross Const. Co./CB Equip. Inc. 4th Low	Emery Sapp & Sons Inc. 5th Low	Kolb Grading, LLC 6th Low
0940 620-61.24 ACRYLIC WATERBORNE PAVEMENT MARKING PAINT, 24 IN., WHITE						**577 LF**
Bid Price	**2.00**	**0.35**	**3.91**	**3.10**	**3.00**	**2.00**
Bid Amount	$1,154.00	$201.95	$2,256.07	$1,788.70	$1,731.00	$1,154.00
0950 620-61.25 ACRYLIC WATERBORNE PAVEMENT MARKING PAINT, 24 IN., YELLOW						**264 LF**
Bid Price	**2.00**	**0.50**	**3.91**	**3.10**	**3.00**	**2.00**
Bid Amount	$528.00	$132.00	$1,032.24	$818.40	$792.00	$528.00
0960 620-70.01 PAVEMENT MARKING REMOVAL						**18,385 LF**
Bid Price	**0.50**	**0.50**	**0.58**	**0.42**	**0.41**	**0.50**
Bid Amount	$9,192.50	$9,192.50	$10,663.30	$7,721.70	$7,537.85	$9,192.50
0970 620-99.02 MISC. TYPE 2 PERFORMED MARKING TAPE LANE REDUC TION ARROW (GROOVED)						**2 EA**
Bid Price	**1585.00**	**1870.00**	**1742.52**	**491.00**	**475.00**	**1585.00**
Bid Amount	$3,170.00	$3,740.00	$3,485.04	$982.00	$950.00	$3,170.00
0980 620-99.02 MISC. PAVEMENT MARKING REMOVAL (LEFT TURN ARRO W)						**3 EA**
Bid Price	**50.00**	**85.00**	**184.81**	**202.00**	**195.00**	**50.00**
Bid Amount	$150.00	$255.00	$554.43	$606.00	$585.00	$150.00
0990 622-40.10 MODIFIED COLDMILLING (DEPTH TRANSITIONS)						**229 SQYD**
Bid Price	**10.00**	**28.00**	**21.12**	**20.00**	**20.00**	**20.00**
Bid Amount	$2,290.00	$6,412.00	$4,836.48	$4,580.00	$4,580.00	$4,580.00
1000 624-01.03A PERMANENT EROSION CONTROL GEOTEXTILE						**52,990 SQYD**
Bid Price	**2.00**	**1.90**	**1.31**	**1.95**	**1.80**	**1.85**
Bid Amount	$105,980.00	$100,681.00	$69,416.90	$103,330.50	$95,382.00	$98,031.50
1010 624-01.04A SEPARATION GEOTEXTILE						**1,059 SQYD**
Bid Price	**3.00**	**3.10**	**3.27**	**3.20**	**3.10**	**2.50**
Bid Amount	$3,177.00	$3,282.90	$3,462.93	$3,388.80	$3,282.90	$2,647.50
1020 624-99.05 MISC. GEOSYNTHETIC REINFORCEMENT						**3,639 SQYD**
Bid Price	**3.00**	**4.00**	**5.30**	**4.15**	**4.15**	**4.00**
Bid Amount	$10,917.00	$14,556.00	$19,286.70	$15,101.85	$15,101.85	$14,556.00
1030 627-40.00 CONTRACTOR FURNISHED SURVEYING AND STAKING						**LUMP SUM**
Lump Sum	**$200,000.00**	**$120,000.00**	**$218,695.20**	**$200,000.00**	**$120,000.00**	**$125,000.00**
1040 703-40.41 CLASS B-1 CONCRETE (CULVERTS)						**916.80 CUYD**
Bid Price	**450.00**	**285.00**	**300.98**	**388.25**	**346.00**	**285.00**
Bid Amount	$412,560.00	$261,288.00	$275,938.46	$355,947.60	$317,212.80	$261,288.00
1050 703-44.13 MEDIAN BARRIER CURB TRANSITION (TYPE C)						**10 LF**
Bid Price	**150.00**	**200.00**	**105.61**	**48.65**	**47.00**	**47.00**
Bid Amount	$1,500.00	$2,000.00	$1,056.10	$486.50	$470.00	$470.00
1060 706-10.30 REINFORCING STEEL (CULVERTS)						**151,540 LB**
Bid Price	**1.00**	**1.23**	**1.30**	**1.04**	**1.00**	**1.20**
Bid Amount	$151,540.00	$186,394.20	$197,002.00	$157,601.60	$151,540.00	$181,848.00
1070 720-10.00 MECHANICALLY STABILIZED EARTH WALL SYSTEMS						**2,563 SQFT**
Bid Price	**45.00**	**45.50**	**41.19**	**40.37**	**44.40**	**39.00**
Bid Amount	$115,335.00	$116,616.50	$105,569.97	$103,468.31	$113,797.20	$99,957.00

TABULATION OF BIDS

Call No: D01	Iron Mountain Trap Rock Company Low Bid	C. J. Moyna & Sons, Inc. 2nd Low	Bloomsdale Excavating Company, Inc. 3rd Low	Chester Bross Const. Co./CB Equip. Inc. 4th Low	Emery Sapp & Sons Inc. 5th Low	Kolb Grading, LLC 6th Low
1080 725-03.15A 15 IN. PIPE GROUP B						**232 LF**
Bid Price	**28.00**	**30.00**	**30.64**	**30.00**	**32.00**	**46.00**
Bid Amount	$6,496.00	$6,960.00	$7,108.48	$6,960.00	$7,424.00	$10,672.00
1090 725-03.18A 18 IN. PIPE GROUP B						**489 LF**
Bid Price	**33.00**	**33.00**	**33.42**	**33.00**	**34.00**	**47.00**
Bid Amount	$16,137.00	$16,137.00	$16,342.38	$16,137.00	$16,626.00	$22,983.00
1100 725-03.24A 24 IN. PIPE GROUP B						**399 LF**
Bid Price	**36.00**	**36.00**	**40.05**	**36.00**	**39.00**	**56.00**
Bid Amount	$14,364.00	$14,364.00	$15,979.95	$14,364.00	$15,561.00	$22,344.00
1110 725-04.15 15 IN. PIPE GROUP C						**190 LF**
Bid Price	**28.00**	**30.00**	**28.72**	**30.00**	**30.00**	**40.00**
Bid Amount	$5,320.00	$5,700.00	$5,456.80	$5,700.00	$5,700.00	$7,600.00
1120 725-04.18 18 IN. PIPE GROUP C						**173 LF**
Bid Price	**33.00**	**32.00**	**30.38**	**32.00**	**33.00**	**44.00**
Bid Amount	$5,709.00	$5,536.00	$5,255.74	$5,536.00	$5,709.00	$7,612.00
1130 725-04.24 24 IN. PIPE GROUP C						**89 LF**
Bid Price	**30.00**	**36.00**	**43.53**	**36.00**	**38.00**	**60.00**
Bid Amount	$2,670.00	$3,204.00	$3,874.17	$3,204.00	$3,382.00	$5,340.00
1140 725-04.36 36 IN. PIPE GROUP C						**173 LF**
Bid Price	**51.00**	**51.00**	**43.54**	**51.00**	**52.00**	**65.00**
Bid Amount	$8,823.00	$8,823.00	$7,532.42	$8,823.00	$8,996.00	$11,245.00
1150 725-04.42 42 IN. PIPE GROUP C						**59 LF**
Bid Price	**54.00**	**50.00**	**59.77**	**50.00**	**54.00**	**75.00**
Bid Amount	$3,186.00	$2,950.00	$3,526.43	$2,950.00	$3,186.00	$4,425.00
1160 725-04.60 60 IN. PIPE GROUP C						**163 LF**
Bid Price	**90.00**	**70.00**	**80.34**	**70.00**	**83.00**	**100.00**
Bid Amount	$14,670.00	$11,410.00	$13,095.42	$11,410.00	$13,529.00	$16,300.00
1170 726-10.15 15 IN. PIPE GROUP A						**1,598 LF**
Bid Price	**35.00**	**30.00**	**27.05**	**30.00**	**33.00**	**40.00**
Bid Amount	$55,930.00	$47,940.00	$43,225.90	$47,940.00	$52,734.00	$63,920.00
1180 726-10.18 18 IN. PIPE GROUP A						**266 LF**
Bid Price	**38.00**	**34.00**	**31.85**	**34.00**	**31.00**	**50.00**
Bid Amount	$10,108.00	$9,044.00	$8,472.10	$9,044.00	$8,246.00	$13,300.00
1190 726-10.24 24 IN. PIPE GROUP A						**897 LF**
Bid Price	**42.00**	**55.00**	**41.99**	**55.00**	**39.00**	**51.00**
Bid Amount	$37,674.00	$49,335.00	$37,665.03	$49,335.00	$34,983.00	$45,747.00
1200 726-10.36 36 IN. PIPE GROUP A						**397 LF**
Bid Price	**80.00**	**98.00**	**86.73**	**98.00**	**74.00**	**130.00**
Bid Amount	$31,760.00	$38,906.00	$34,431.81	$38,906.00	$29,378.00	$51,610.00
1210 726-10.42 42 IN. PIPE GROUP A						**466 LF**
Bid Price	**86.00**	**105.00**	**92.93**	**105.00**	**80.00**	**140.00**
Bid Amount	$40,076.00	$48,930.00	$43,305.38	$48,930.00	$37,280.00	$65,240.00
1220 726-10.48 48 IN. PIPE GROUP A						**755 LF**
Bid Price	**100.00**	**115.00**	**104.80**	**115.00**	**91.00**	**118.00**
Bid Amount	$75,500.00	$86,825.00	$79,124.00	$86,825.00	$68,705.00	$89,090.00

TABULATION OF BIDS

Call No: D01	Iron Mountain Trap Rock Company Low Bid	C. J. Moyna & Sons, Inc. 2nd Low	Bloomsdale Excavating Company, Inc. 3rd Low	Chester Bross Const. Co./CB Equip. Inc. 4th Low	Emery Sapp & Sons Inc. 5th Low	Kolb Grading, LLC 6th Low
1230 726-10.54 54 IN. PIPE GROUP A						**403 LF**
Bid Price	**135.00**	**145.00**	**158.26**	**145.00**	**121.00**	**180.00**
Bid Amount	$54,405.00	$58,435.00	$63,778.78	$58,435.00	$48,763.00	$72,540.00
1240 726-10.60 60 IN. PIPE GROUP A						**37 LF**
Bid Price	**165.00**	**150.00**	**159.42**	**150.00**	**144.00**	**180.00**
Bid Amount	$6,105.00	$5,550.00	$5,898.54	$5,550.00	$5,328.00	$6,660.00
1250 726-10.66 66 IN. PIPE GROUP A						**196 LF**
Bid Price	**170.00**	**160.00**	**194.58**	**160.00**	**149.00**	**200.00**
Bid Amount	$33,320.00	$31,360.00	$38,137.68	$31,360.00	$29,204.00	$39,200.00
1260 726-10.72 72 IN. PIPE GROUP A						**260 LF**
Bid Price	**195.00**	**195.00**	**240.55**	**195.00**	**180.00**	**220.00**
Bid Amount	$50,700.00	$50,700.00	$62,543.00	$50,700.00	$46,800.00	$57,200.00
1270 726-99.03 MISC. 48 IN RCP (SPECIAL DESIGN)						**614 LF**
Bid Price	**225.00**	**200.00**	**202.52**	**200.00**	**168.00**	**217.00**
Bid Amount	$138,150.00	$122,800.00	$124,347.28	$122,800.00	$103,152.00	$133,238.00
1280 726-99.03 MISC. 60 IN RCP (SPECIAL DESIGN)						**650 LF**
Bid Price	**270.00**	**255.00**	**275.54**	**255.00**	**231.00**	**290.00**
Bid Amount	$175,500.00	$165,750.00	$179,101.00	$165,750.00	$150,150.00	$188,500.00
1290 731-10.33 PRECAST CONCRETE DROP INLET 3 FT X 3 FT						**33 FT**
Bid Price	**340.00**	**645.00**	**531.24**	**645.00**	**570.00**	**300.00**
Bid Amount	$11,220.00	$21,285.00	$17,530.92	$21,285.00	$18,810.00	$9,900.00
1300 731-10.42 PRECAST CONCRETE DROP INLET 4 FT X 2 FT						**34 FT**
Bid Price	**490.00**	**615.00**	**466.58**	**615.00**	**500.00**	**300.00**
Bid Amount	$16,660.00	$20,910.00	$15,863.72	$20,910.00	$17,000.00	$10,200.00
1310 731-10.53 PRECAST CONCRETE DROP INLET 5 FT X 3 FT						**34 FT**
Bid Price	**535.00**	**975.00**	**574.89**	**975.00**	**765.00**	**400.00**
Bid Amount	$18,190.00	$33,150.00	$19,546.26	$33,150.00	$26,010.00	$13,600.00
1320 732-00.15A 15 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION						**6 EA**
Bid Price	**225.00**	**235.00**	**457.49**	**235.00**	**330.00**	**300.00**
Bid Amount	$1,350.00	$1,410.00	$2,744.94	$1,410.00	$1,980.00	$1,800.00
1330 732-00.18A 18 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION						**3 EA**
Bid Price	**250.00**	**265.00**	**474.11**	**265.00**	**355.00**	**350.00**
Bid Amount	$750.00	$795.00	$1,422.33	$795.00	$1,065.00	$1,050.00
1340 732-00.24A 24 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION						**1 EA**
Bid Price	**440.00**	**550.00**	**797.50**	**550.00**	**405.00**	**400.00**
Bid Amount	$440.00	$550.00	$797.50	$550.00	$405.00	$400.00
1350 732-06.15A 15 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION						**2 EA**
Bid Price	**720.00**	**400.00**	**457.50**	**400.00**	**500.00**	**500.00**
Bid Amount	$1,440.00	$800.00	$915.00	$800.00	$1,000.00	$1,000.00

TABULATION OF BIDS

Call No: D01	Iron Mountain Trap Rock Company Low Bid	C. J. Moyna & Sons, Inc. 2nd Low	Bloomsdale Excavating Company, Inc. 3rd Low	Chester Bross Const. Co./CB Equip. Inc. 4th Low	Emery Sapp & Sons Inc. 5th Low	Kolb Grading, LLC 6th Low
1360 732-06.18A	**18 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION**					**2 EA**
Bid Price	**760.00**	**440.00**	**474.09**	**440.00**	**540.00**	**550.00**
Bid Amount	$1,520.00	$880.00	$948.18	$880.00	$1,080.00	$1,100.00
1370 732-06.24A	**24 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION**					**8 EA**
Bid Price	**850.00**	**570.00**	**797.54**	**570.00**	**625.00**	**650.00**
Bid Amount	$6,800.00	$4,560.00	$6,380.32	$4,560.00	$5,000.00	$5,200.00
1380 732-06.36A	**36 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION**					**2 EA**
Bid Price	**1150.00**	**1025.00**	**1650.30**	**1025.00**	**940.00**	**1100.00**
Bid Amount	$2,300.00	$2,050.00	$3,300.60	$2,050.00	$1,880.00	$2,200.00
1390 732-06.42A	**42 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION**					**4 EA**
Bid Price	**1250.00**	**1180.00**	**1705.61**	**1180.00**	**1000.00**	**1500.00**
Bid Amount	$5,000.00	$4,720.00	$6,822.44	$4,720.00	$4,000.00	$6,000.00
1400 732-06.48A	**48 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION**					**6 EA**
Bid Price	**1310.00**	**1250.00**	**1818.42**	**1250.00**	**1200.00**	**1700.00**
Bid Amount	$7,860.00	$7,500.00	$10,910.52	$7,500.00	$7,200.00	$10,200.00
1410 732-06.54A	**54 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION**					**4 EA**
Bid Price	**1360.00**	**1306.00**	**2530.99**	**1306.00**	**1250.00**	**2000.00**
Bid Amount	$5,440.00	$5,224.00	$10,123.96	$5,224.00	$5,000.00	$8,000.00
1420 732-06.60A	**60 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION**					**1 EA**
Bid Price	**2700.00**	**1435.00**	**3084.01**	**1435.00**	**1500.00**	**2300.00**
Bid Amount	$2,700.00	$1,435.00	$3,084.01	$1,435.00	$1,500.00	$2,300.00
1430 732-06.66A	**66 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION**					**2 EA**
Bid Price	**4300.00**	**3250.00**	**4216.03**	**3250.00**	**4200.00**	**4000.00**
Bid Amount	$8,600.00	$6,500.00	$8,432.06	$6,500.00	$8,400.00	$8,000.00
1440 732-06.72A	**72 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION**					**2 EA**
Bid Price	**4690.00**	**4500.00**	**4437.25**	**4500.00**	**4600.00**	**5000.00**
Bid Amount	$9,380.00	$9,000.00	$8,874.50	$9,000.00	$9,200.00	$10,000.00
1450 732-08.15A	**15 IN. OR ALLOWED SUBSTITUTE GROUP C FLARED END SECTION**					**4 EA**
Bid Price	**204.00**	**200.00**	**241.78**	**200.00**	**300.00**	**300.00**
Bid Amount	$816.00	$800.00	$967.12	$800.00	$1,200.00	$1,200.00
1460 732-08.36A	**36 IN. OR ALLOWED SUBSTITUTE GROUP C FLARED END SECTION**					**4 EA**
Bid Price	**415.00**	**500.00**	**787.53**	**500.00**	**530.00**	**600.00**
Bid Amount	$1,660.00	$2,000.00	$3,150.12	$2,000.00	$2,120.00	$2,400.00

TABULATION OF BIDS

Call No: D01	Iron Mountain Trap Rock Company Low Bid	C. J. Moyna & Sons, Inc. 2nd Low	Bloomsdale Excavating Company, Inc. 3rd Low	Chester Bross Const. Co./CB Equip. Inc. 4th Low	Emery Sapp & Sons Inc. 5th Low	Kolb Grading, LLC 6th Low
1470 732-08.42A	**42 IN. OR ALLOWED SUBSTITUTE GROUP C FLARED END SECTION**					**2 EA**
Bid Price	**900.00**	**750.00**	**1182.34**	**750.00**	**950.00**	**900.00**
Bid Amount	$1,800.00	$1,500.00	$2,364.68	$1,500.00	$1,900.00	$1,800.00
1480 732-10.14A	**18 IN. OR ALLOWED SUBSTITUTE SAFETY SLOPE END SECTION**					**4 EA**
Bid Price	**665.00**	**700.00**	**840.68**	**700.00**	**600.00**	**1000.00**
Bid Amount	$2,660.00	$2,800.00	$3,362.72	$2,800.00	$2,400.00	$4,000.00
1490 732-10.16A	**24 IN. OR ALLOWED SUBSTITUTE SAFETY SLOPE END SECTION**					**10 EA**
Bid Price	**760.00**	**1050.00**	**1172.50**	**1050.00**	**800.00**	**1200.00**
Bid Amount	$7,600.00	$10,500.00	$11,725.00	$10,500.00	$8,000.00	$12,000.00
1500 732-99.02	**MISC. 48 IN PRECAST CONC FES (SPECIAL DESIGN)**					**2 EA**
Bid Price	**1750.00**	**1200.00**	**1877.50**	**1200.00**	**1370.00**	**1200.00**
Bid Amount	$3,500.00	$2,400.00	$3,755.00	$2,400.00	$2,740.00	$2,400.00
1510 732-99.02	**MISC. 60 IN PRECAST CONC FES (SPECIAL DESIGN)**					**2 EA**
Bid Price	**2900.00**	**1500.00**	**3878.63**	**1500.00**	**1680.00**	**2000.00**
Bid Amount	$5,800.00	$3,000.00	$7,757.26	$3,000.00	$3,360.00	$4,000.00
1520 805-10.00A	**SEEDING - COOL SEASON MIXTURES**					**82.70 ACRE**
Bid Price	**1450.00**	**1650.00**	**1636.91**	**1370.00**	**1550.00**	**1550.00**
Bid Amount	$119,915.00	$136,455.00	$135,372.46	$113,299.00	$128,185.00	$128,185.00
1530 805-20.00A	**SEEDING - WARM SEASON MIXTURES**					**45.70 ACRE**
Bid Price	**1450.00**	**1650.00**	**1742.52**	**1578.00**	**1650.00**	**1650.00**
Bid Amount	$66,265.00	$75,405.00	$79,633.16	$72,114.60	$75,405.00	$75,405.00
1540 806-10.10A	**TYPE B BERM**					**12,367 LF**
Bid Price	**2.00**	**0.50**	**1.13**	**0.52**	**0.75**	**1.00**
Bid Amount	$24,734.00	$6,183.50	$13,974.71	$6,430.84	$9,275.25	$12,367.00
1550 806-10.11	**SLOPE DRAINS**					**1,985 LF**
Bid Price	**10.00**	**2.00**	**14.35**	**2.07**	**7.50**	**8.00**
Bid Amount	$19,850.00	$3,970.00	$28,484.75	$4,108.95	$14,887.50	$15,880.00
1560 806-10.15	**SEDIMENT BASIN**					**430 CUYD**
Bid Price	**33.00**	**12.00**	**16.58**	**12.40**	**17.00**	**15.00**
Bid Amount	$14,190.00	$5,160.00	$7,129.40	$5,332.00	$7,310.00	$6,450.00
1570 806-10.16	**SEDIMENT REMOVAL**					**1,601 CUYD**
Bid Price	**29.00**	**6.00**	**14.54**	**6.20**	**14.00**	**10.00**
Bid Amount	$46,429.00	$9,606.00	$23,278.54	$9,926.20	$22,414.00	$16,010.00
1580 806-10.17	**TEMPORARY SEEDING AND MULCHING**					**51.30 ACRE**
Bid Price	**750.00**	**900.00**	**792.05**	**673.00**	**750.00**	**0.01**
Bid Amount	$38,475.00	$46,170.00	$40,632.17	$34,524.90	$38,475.00	$0.51
1590 806-10.19	**SILT FENCE**					**40,693 LF**
Bid Price	**2.00**	**1.95**	**2.06**	**1.90**	**1.95**	**1.95**
Bid Amount	$81,386.00	$79,351.35	$83,827.58	$77,316.70	$79,351.35	$79,351.35

TABULATION OF BIDS

Call No: D01	Iron Mountain Trap Rock Company Low Bid	C. J. Moyna & Sons, Inc. 2nd Low	Bloomsdale Excavating Company, Inc. 3rd Low	Chester Bross Const. Co./CB Equip. Inc. 4th Low	Emery Sapp & Sons Inc. 5th Low	Kolb Grading, LLC 6th Low
1600 806-10.22 TYPE II DITCH CHECK						**638 EA**
Bid Price	**150.00**	**135.00**	**116.17**	**186.00**	**110.00**	**110.00**
Bid Amount	$95,700.00	$86,130.00	$74,116.46	$118,668.00	$70,180.00	$70,180.00
1610 806-10.23 SEDIMENT TRAP						**3,280 CUYD**
Bid Price	**15.00**	**6.00**	**15.80**	**6.20**	**8.00**	**15.00**
Bid Amount	$49,200.00	$19,680.00	$51,824.00	$20,336.00	$26,240.00	$49,200.00
1620 806-10.25 INLET CHECK						**20 EA**
Bid Price	**75.00**	**155.00**	**132.01**	**103.50**	**125.00**	**55.00**
Bid Amount	$1,500.00	$3,100.00	$2,640.20	$2,070.00	$2,500.00	$1,100.00
1630 806-10.50 TYPE C BERM						**595 LF**
Bid Price	**20.00**	**0.01**	**17.90**	**0.01**	**24.00**	**20.00**
Bid Amount	$11,900.00	$5.95	$10,650.50	$5.95	$14,280.00	$11,900.00
1640 806-99.05 MISC. CONCRETE BLOCK MAT						**2,630 SQYD**
Bid Price	**42.50**	**46.00**	**52.28**	**47.60**	**49.50**	**49.50**
Bid Amount	$111,775.00	$120,980.00	$137,496.40	$125,188.00	$130,185.00	$130,185.00
1650 806-99.07 MISC FURNISHING ROCK FOR SEDIMENT TRAPS/BASIN S						**3,710 CUYD**
Bid Price	**28.00**	**24.00**	**20.34**	**24.85**	**30.00**	**30.00**
Bid Amount	$103,880.00	$89,040.00	$75,461.40	$92,193.50	$111,300.00	$111,300.00
SECTION TOTALS	**$16,659,723.33**	**$17,263,649.60**	**$16,649,880.73**	**$17,188,497.68**	**$18,852,281.94**	**$19,289,573.70**

Section 0002: ALT A - SUPERPAVE PAVEMENT - J5P0951B

1660 403-04.01 8 INCHES, ASPHALTIC CONCRETE PAVEMENT SP125C						**187,857.10 SQYD**
Bid Price						
Bid Amount						
1670 620-99.03 MISC. MISC. 7 IN. GROOVE FOR PAVEMENT MARKING (ASHPHALT)						**16,711 LF**
Bid Price						
Bid Amount						
1680 626-10.00A BITUMINOUS SHOULDER RUMBLE STRIP						**1,224.20 STA**
Bid Price						
Bid Amount						
1690 626-10.01 BITUMINOUS CENTERLINE RUMBLE STRIP						**7.70 STA**
Bid Price						
Bid Amount						
SECTION TOTALS	**$0.00**	**$0.00**	**$0.00**	**$0.00**	**$0.00**	**$0.00**

Section 0003: ALT B - PCCP PAVEMENT - J5P0951B

1700 502-13.08 CONCRETE PAVEMENT (8 IN. NON-REINFORCED, 15 FT. JOINTS)						**187,857.10 SQYD**
Bid Price	**26.00**	**24.25**	**25.87**	**24.25**	**21.10**	**24.25**
Bid Amount	$4,884,284.60	$4,555,534.68	$4,859,863.18	$4,555,534.68	$3,963,784.81	$4,555,534.68

TABULATION OF BIDS

Call No: D01	Iron Mountain Trap Rock Company Low Bid	C. J. Moyna & Sons, Inc. 2nd Low	Bloomsdale Excavating Company, Inc. 3rd Low	Chester Bross Const. Co./CB Equip. Inc. 4th Low	Emery Sapp & Sons Inc. 5th Low	Kolb Grading, LLC 6th Low
1710 620-59.35	**9 IN. BLACK ACRYLIC WATERBORNE CONTRAST PAVEMENT MARKING PAI NT**					**16,711 LF**
Bid Price	**0.13**	**0.30**	**0.14**	**0.41**	**0.40**	**0.13**
Bid Amount	$2,172.43	$5,013.30	$2,339.54	$6,851.51	$6,684.40	$2,172.43
1720 620-99.03	**MISC. MISC. 10 IN. GROOVE FOR PAVEMENT MARKING (CONCRETE)**					**16,711 LF**
Bid Price	**0.50**	**0.60**	**0.53**	**0.73**	**0.70**	**0.50**
Bid Amount	$8,355.50	$10,026.60	$8,856.83	$12,199.03	$11,697.70	$8,355.50
1730 626-20.00A	**PORTLAND CEMENT CONCRETE SHOULDER RUMBLE STRIP**					**1,224.20 STA**
Bid Price	**50.00**	**18.45**	**31.68**	**25.90**	**25.00**	**35.00**
Bid Amount	$61,210.00	$22,586.49	$38,782.66	$31,706.78	$30,605.00	$42,847.00
1740 626-20.01	**PORTLAND CEMENT CONCRETE CENTERLINE RUMBLE STRIP**					**7.70 STA**
Bid Price	**155.00**	**30.00**	**179.53**	**170.80**	**165.00**	**175.00**
Bid Amount	$1,193.50	$231.00	$1,382.38	$1,315.16	$1,270.50	$1,347.50
SECTION TOTALS	**$4,957,216.03**	**$4,593,392.07**	**$4,911,224.59**	**$4,607,607.16**	**$4,014,042.41**	**$4,610,257.11**

Section 0004: ALT C - ASPHALT A2 SHOULDERS - J5P0951B

1750 401-01.50	**TYPE A2 SHOULDER**					**5,043.30 SQYD**
Bid Price	**25.00**	**28.00**	**22.23**	**21.80**		**25.00**
Bid Amount	$126,082.50	$141,212.40	$112,112.56	$109,943.94		$126,082.50

Section 0005: ALT D - CONCRETE A2 SHOULDERS - J5P0951B

1760 502-13.40	**TYPE A2 SHOULDER**					**5,043.30 SQYD**
Bid Price					**23.30**	
Bid Amount					$117,508.89	

Section 0006: LIGHTING ITEMS - J5P0951B

1770 901-10.62	**LIGHTING POLE, 45 FT. OR 13.5 M, TYPE AT DESIGN 2**					**3 EA**
Bid Price	**2040.00**	**1938.00**	**2046.66**	**2100.00**	**2040.00**	**2040.00**
Bid Amount	$6,120.00	$5,814.00	$6,139.98	$6,300.00	$6,120.00	$6,120.00
1780 901-11.15	**BRACKET ARM, 15 FT. OR 4.6 M**					**3 EA**
Bid Price	**515.00**	**560.00**	**591.40**	**533.00**	**515.00**	**515.00**
Bid Amount	$1,545.00	$1,680.00	$1,774.20	$1,599.00	$1,545.00	$1,545.00
1790 901-13.10	**LUMINAIRE, 250 WATT HIGH PRESSURE SODIUM**					**3 EA**
Bid Price	**287.00**	**300.00**	**316.82**	**297.00**	**287.00**	**287.00**
Bid Amount	$861.00	$900.00	$950.46	$891.00	$861.00	$861.00
1800 901-22.30	**BASE MOUNTED CONTROL STATION 240 VOLT - 4 CIRCUIT**					**1 EA**
Bid Price	**2706.00**	**5614.00**	**5928.78**	**2800.00**	**2706.00**	**2706.00**
Bid Amount	$2,706.00	$5,614.00	$5,928.78	$2,800.00	$2,706.00	$2,706.00

TABULATION OF BIDS

Call No: D01	Iron Mountain Trap Rock Company Low Bid	C. J. Moyna & Sons, Inc. 2nd Low	Bloomsdale Excavating Company, Inc. 3rd Low	Chester Bross Const. Co./CB Equip. Inc. 4th Low	Emery Sapp & Sons Inc. 5th Low	Kolb Grading, LLC 6th Low
1810 901-30.02 CONDUIT, 2 IN. RIGID, IN TRENCH						**48 LF**
Bid Price	**11.30**	**8.00**	**8.45**	**11.70**	**11.30**	**11.30**
Bid Amount	$542.40	$384.00	$405.60	$561.60	$542.40	$542.40
1820 901-30.03 CONDUIT, 3 IN. RIGID, IN TRENCH						**62 LF**
Bid Price	**13.40**	**8.50**	**8.98**	**13.85**	**13.40**	**13.40**
Bid Amount	$830.80	$527.00	$556.76	$858.70	$830.80	$830.80
1830 901-40.03 CONDUIT, 3 IN. RIGID, PUSHED						**58 LF**
Bid Price	**31.90**	**21.00**	**22.18**	**33.00**	**31.90**	**31.90**
Bid Amount	$1,850.20	$1,218.00	$1,286.44	$1,914.00	$1,850.20	$1,850.20
1840 901-50.20 TRENCHING TYPE II						**2,560 LF**
Bid Price	**4.75**	**3.00**	**3.17**	**5.00**	**4.75**	**4.75**
Bid Amount	$12,160.00	$7,680.00	$8,115.20	$12,800.00	$12,160.00	$12,160.00
1850 901-61.10 PULL BOX, PREFORMED CLASS 1						**7 EA**
Bid Price	**708.00**	**930.00**	**982.15**	**733.00**	**708.00**	**708.00**
Bid Amount	$4,956.00	$6,510.00	$6,875.05	$5,131.00	$4,956.00	$4,956.00
1860 901-70.02 CABLE, 2 AWG 1 CONDUCTOR						**170 LF**
Bid Price	**2.85**	**2.28**	**2.41**	**2.95**	**2.85**	**2.85**
Bid Amount	$484.50	$387.60	$409.70	$501.50	$484.50	$484.50
1870 901-71.10 CABLE, 10 AWG 1 CONDUCTOR, POLE AND BRACKET						**360 LF**
Bid Price	**0.55**	**1.00**	**1.06**	**0.57**	**0.55**	**0.55**
Bid Amount	$198.00	$360.00	$381.60	$205.20	$198.00	$198.00
1880 901-74.07 CABLE-CONDUIT, 1 IN., 2 CONDUCTORS AND 1 BARE NEUTRAL, 8 AWG						**3,040 LF**
Bid Price	**3.40**	**2.80**	**2.96**	**3.50**	**3.40**	**3.40**
Bid Amount	$10,336.00	$8,512.00	$8,998.40	$10,640.00	$10,336.00	$10,336.00
1890 901-82.45 POLE FOUNDATION (45 FT. OR 13.5 M MOUNTING HEIGHT)						**3 EA**
Bid Price	**1130.00**	**1000.00**	**1056.07**	**1170.00**	**1130.00**	**1130.00**
Bid Amount	$3,390.00	$3,000.00	$3,168.21	$3,510.00	$3,390.00	$3,390.00
1900 901-86.12 POWER SUPPLY ASSEMBLY, TYPE 2, 240/120 VOLT SERVICE, LIGHTIN G ONLY						**1 EA**
Bid Price	**2619.10**	**4262.00**	**4500.97**	**2710.00**	**2619.00**	**2619.00**
Bid Amount	$2,619.10	$4,262.00	$4,500.97	$2,710.00	$2,619.00	$2,619.00
SECTION TOTALS	**$48,599.00**	**$46,848.60**	**$49,491.35**	**$50,422.00**	**$48,598.90**	**$48,598.90**

Section 0007: SIGNING ITEMS - J5P0951B

1910 903-10.10 CONCRETE FOOTINGS, EMBEDDED						**17.10 CUYD**
Bid Price	**900.00**	**900.00**	**950.46**	**930.00**	**900.00**	**900.00**
Bid Amount	$15,390.00	$15,390.00	$16,252.87	$15,903.00	$15,390.00	$15,390.00
1920 903-12.10 STRUCTURAL STEEL POSTS						**4,610 LB**
Bid Price	**2.60**	**2.60**	**2.75**	**2.70**	**2.60**	**2.60**
Bid Amount	$11,986.00	$11,986.00	$12,677.50	$12,447.00	$11,986.00	$11,986.00

TABULATION OF BIDS

Call No: D01	Iron Mountain Trap Rock Company Low Bid	C. J. Moyna & Sons, Inc. 2nd Low	Bloomsdale Excavating Company, Inc. 3rd Low	Chester Bross Const. Co./CB Equip. Inc. 4th Low	Emery Sapp & Sons Inc. 5th Low	Kolb Grading, LLC 6th Low
1930 903-12.20 PIPE POSTS						**8,190 LB**
Bid Price	**2.20**	**2.20**	**2.32**	**2.25**	**2.20**	**2.20**
Bid Amount	$18,018.00	$18,018.00	$19,000.80	$18,427.50	$18,018.00	$18,018.00
1940 903-12.40 BREAKAWAY ASSEMBLY						**57 EA**
Bid Price	**80.00**	**80.00**	**84.49**	**82.90**	**80.00**	**80.00**
Bid Amount	$4,560.00	$4,560.00	$4,815.93	$4,725.30	$4,560.00	$4,560.00
1950 903-12.52 7 FT. CHANNEL POST DELINEATOR, DOUBLE STACKED WHITE						**35 EA**
Bid Price	**36.00**	**36.00**	**38.02**	**37.25**	**36.00**	**36.00**
Bid Amount	$1,260.00	$1,260.00	$1,330.70	$1,303.75	$1,260.00	$1,260.00
1960 903-12.53A 7 FT. CHANNEL POST DELINEATOR, DOUBLE STACKED YELLOW						**47 EA**
Bid Price	**36.00**	**36.00**	**38.02**	**37.25**	**36.00**	**36.00**
Bid Amount	$1,692.00	$1,692.00	$1,786.94	$1,750.75	$1,692.00	$1,692.00
1970 903-12.56 7 FT. CHANNEL POST DELINEATOR, WHITE						**108 EA**
Bid Price	**32.00**	**32.00**	**33.79**	**33.00**	**32.00**	**32.00**
Bid Amount	$3,456.00	$3,456.00	$3,649.32	$3,564.00	$3,456.00	$3,456.00
1980 903-12.57A 7 FT. CHANNEL POST DELINEATOR, YELLOW						**5 EA**
Bid Price	**32.00**	**32.00**	**33.79**	**33.00**	**32.00**	**32.00**
Bid Amount	$160.00	$160.00	$168.95	$165.00	$160.00	$160.00
1990 903-12.58 7 FT. CHANNEL POST DELINEATOR, WHITE/RED						**2 EA**
Bid Price	**36.00**	**36.00**	**38.02**	**37.25**	**36.00**	**36.00**
Bid Amount	$72.00	$72.00	$76.04	$74.50	$72.00	$72.00
2000 903-12.71 PERFORATED SQUARE STEEL TUBE POST ANCHOR						**657 LF**
Bid Price	**18.00**	**18.00**	**19.01**	**18.65**	**18.00**	**18.00**
Bid Amount	$11,826.00	$11,826.00	$12,489.57	$12,253.05	$11,826.00	$11,826.00
2010 903-50.04 TYPE SHR2L-1 SIGN						**1,992 SQFT**
Bid Price	**16.00**	**16.00**	**16.90**	**16.50**	**16.00**	**16.00**
Bid Amount	$31,872.00	$31,872.00	$33,664.80	$32,868.00	$31,872.00	$31,872.00
2020 903-50.09 36 IN. OR 900 MM STOP SIGN						**4 EA**
Bid Price	**150.00**	**150.00**	**158.41**	**155.50**	**150.00**	**150.00**
Bid Amount	$600.00	$600.00	$633.64	$622.00	$600.00	$600.00
2030 903-50.11 SIGN, TYPE STR2L-3						**573 SQFT**
Bid Price	**21.00**	**21.00**	**22.18**	**21.75**	**21.00**	**21.00**
Bid Amount	$12,033.00	$12,033.00	$12,709.14	$12,462.75	$12,033.00	$12,033.00
2040 903-50.15 TYPE IV OBJECT MARKER						**2 EA**
Bid Price	**150.00**	**150.00**	**158.41**	**155.00**	**150.00**	**150.00**
Bid Amount	$300.00	$300.00	$316.82	$310.00	$300.00	$300.00
2050 903-50.17 48 IN. STOP SIGN						**10 EA**
Bid Price	**185.00**	**185.00**	**195.37**	**191.50**	**185.00**	**185.00**
Bid Amount	$1,850.00	$1,850.00	$1,953.70	$1,915.00	$1,850.00	$1,850.00
2060 903-50.71 TYPE STR4L-1 SIGN						**15 SQFT**
Bid Price	**24.00**	**24.00**	**25.35**	**24.85**	**24.00**	**24.00**
Bid Amount	$360.00	$360.00	$380.25	$372.75	$360.00	$360.00

Call No: D01	Iron Mountain Trap Rock Company Low Bid	C. J. Moyna & Sons, Inc. 2nd Low	Bloomsdale Excavating Company, Inc. 3rd Low	Chester Bross Const. Co./CB Equip. Inc. 4th Low	Emery Sapp & Sons Inc. 5th Low	Kolb Grading, LLC 6th Low
2070 903-99.02	**MISC. 7 FT. CHANNEL POST DELINEATOR, DOUBLE ST ACKED RED/YELLOW**					**7 EA**
Bid Price	**36.00**	**36.00**	**38.02**	**37.25**	**36.00**	**36.00**
Bid Amount	$252.00	$252.00	$266.14	$260.75	$252.00	$252.00
2080 903-99.02	**MISC. BREAKAWAY ASSEMBLY**					**136 EA**
Bid Price	**110.00**	**110.00**	**116.17**	**114.00**	**110.00**	**110.00**
Bid Amount	$14,960.00	$14,960.00	$15,799.12	$15,504.00	$14,960.00	$14,960.00
2090 903-99.03	**MISC. 2.5 IN PERF STEEL SQUARE POST**					**2,904 LF**
Bid Price	**10.00**	**10.00**	**10.56**	**10.35**	**10.00**	**10.00**
Bid Amount	$29,040.00	$29,040.00	$30,666.24	$30,056.40	$29,040.00	$29,040.00
2100 903-99.07	**MISC. PSST CONCRETE FOOTINGS EMBEDDED**					**20 CUYD**
Bid Price	**975.00**	**975.00**	**1029.67**	**1010.00**	**975.00**	**975.00**
Bid Amount	$19,500.00	$19,500.00	$20,593.40	$20,200.00	$19,500.00	$19,500.00
SECTION TOTALS	**$179,187.00**	**$179,187.00**	**$189,231.87**	**$185,185.50**	**$179,187.00**	**$179,187.00**

Section 0008: BRIDGE NO. A7923 - J5P0951B

2110 206-33.00	**CLASS 4 EXCAVATION**					**3,210 CUYD**
Bid Price	**15.00**	**10.00**	**23.82**	**15.00**	**8.40**	**10.00**
Bid Amount	$48,150.00	$32,100.00	$76,462.20	$48,150.00	$26,964.00	$32,100.00
2120 703-40.40	**CLASS B-1 CONCRETE (CULVERTS-BRIDGE)**					**1,572.70 CUYD**
Bid Price	**285.00**	**260.00**	**274.58**	**330.00**	**298.00**	**260.00**
Bid Amount	$448,219.50	$408,902.00	$431,831.97	$518,991.00	$468,664.60	$408,902.00
2130 706-10.20	**REINFORCING STEEL (CULVERTS-BRIDGE)**					**193,360 LB**
Bid Price	**1.00**	**1.23**	**1.30**	**0.90**	**0.91**	**1.20**
Bid Amount	$193,360.00	$237,832.80	$251,368.00	$174,024.00	$175,957.60	$232,032.00
SECTION TOTALS	**$689,729.50**	**$678,834.80**	**$759,662.17**	**$741,165.00**	**$671,586.20**	**$673,034.00**

Section 0009: BRIDGE NO. A7924 - J5P0951B

2140 206-33.00	**CLASS 4 EXCAVATION**					**1,170 CUYD**
Bid Price	**16.00**	**10.00**	**23.51**	**15.00**	**9.00**	**10.00**
Bid Amount	$18,720.00	$11,700.00	$27,506.70	$17,550.00	$10,530.00	$11,700.00
2150 703-40.40	**CLASS B-1 CONCRETE (CULVERTS-BRIDGE)**					**1,060.60 CUYD**
Bid Price	**300.00**	**250.00**	**264.02**	**330.00**	**298.00**	**250.00**
Bid Amount	$318,180.00	$265,150.00	$280,019.61	$349,998.00	$316,058.80	$265,150.00
2160 706-10.20	**REINFORCING STEEL (CULVERTS-BRIDGE)**					**109,500 LB**
Bid Price	**1.00**	**1.23**	**1.30**	**0.90**	**0.93**	**1.20**
Bid Amount	$109,500.00	$134,685.00	$142,350.00	$98,550.00	$101,835.00	$131,400.00
SECTION TOTALS	**$446,400.00**	**$411,535.00**	**$449,876.31**	**$466,098.00**	**$428,423.80**	**$408,250.00**

TABULATION OF BIDS

Call No: D01	Iron Mountain Trap Rock Company Low Bid	C. J. Moyna & Sons, Inc. 2nd Low	Bloomsdale Excavating Company, Inc. 3rd Low	Chester Bross Const. Co./CB Equip. Inc. 4th Low	Emery Sapp & Sons Inc. 5th Low	Kolb Grading, LLC 6th Low
Section 0010: BRIDGE NO. A7957 - J5P0951B						
2170 206-10.00 CLASS 1 EXCAVATION						**45 CUYD**
Bid Price	**19.00**	**50.00**	**77.09**	**50.00**	**28.00**	**50.00**
Bid Amount	$855.00	$2,250.00	$3,469.05	$2,250.00	$1,260.00	$2,250.00
2180 206-55.00 TEMPORARY SHORING						**LUMP SUM**
Lump Sum	**$9,000.00**	**$14,000.00**	**$13,200.88**	**$14,000.00**	**$15,000.00**	**$14,000.00**
2190 503-10.10 BRIDGE APPROACH SLAB (BRIDGE)						**218 SQYD**
Bid Price	**240.00**	**265.00**	**258.74**	**265.00**	**215.00**	**265.00**
Bid Amount	$52,320.00	$57,770.00	$56,405.32	$57,770.00	$46,870.00	$57,770.00
2200 701-11.07 DRILLED SHAFTS (4 FT. 6 IN. DIA.)						**216 LF**
Bid Price	**465.00**	**475.00**	**566.05**	**475.00**	**429.00**	**475.00**
Bid Amount	$100,440.00	$102,600.00	$122,266.80	$102,600.00	$92,664.00	$102,600.00
2210 701-12.06 ROCK SOCKETS (4 FT 0 IN. DIA.)						**56 LF**
Bid Price	**700.00**	**795.00**	**1082.47**	**795.00**	**729.00**	**795.00**
Bid Amount	$39,200.00	$44,520.00	$60,618.32	$44,520.00	$40,824.00	$44,520.00
2220 701-13.00 SUPPLEMENTARY TELEVISION CAMERA INSPECTION						**4 EA**
Bid Price	**100.00**	**625.00**	**739.25**	**625.00**	**600.00**	**625.00**
Bid Amount	$400.00	$2,500.00	$2,957.00	$2,500.00	$2,400.00	$2,500.00
2230 701-14.00 FOUNDATION INSPECTION HOLES						**96 LF**
Bid Price	**260.00**	**80.00**	**87.65**	**80.00**	**90.00**	**80.00**
Bid Amount	$24,960.00	$7,680.00	$8,414.40	$7,680.00	$8,640.00	$7,680.00
2240 701-16.00 SONIC LOGGING TESTING						**4 EA**
Bid Price	**3200.00**	**1000.00**	**3759.61**	**1000.00**	**4200.00**	**1000.00**
Bid Amount	$12,800.00	$4,000.00	$15,038.44	$4,000.00	$16,800.00	$4,000.00
2250 702-10.12 STRUCTURAL STEEL PILES (12 IN.)						**1,112 LF**
Bid Price	**40.00**	**46.00**	**68.06**	**46.00**	**44.00**	**46.00**
Bid Amount	$44,480.00	$51,152.00	$75,682.72	$51,152.00	$48,928.00	$51,152.00
2260 702-60.00 PRE-BORE FOR PILING						**88 LF**
Bid Price	**105.00**	**65.00**	**75.72**	**65.00**	**58.00**	**65.00**
Bid Amount	$9,240.00	$5,720.00	$6,663.36	$5,720.00	$5,104.00	$5,720.00
2270 702-70.00 PILE POINT REINFORCEMENT						**8 EA**
Bid Price	**120.00**	**125.00**	**126.73**	**125.00**	**90.00**	**125.00**
Bid Amount	$960.00	$1,000.00	$1,013.84	$1,000.00	$720.00	$1,000.00
2280 703-20.03 CLASS B CONCRETE (SUBSTRUCTURE)						**192.80 CUYD**
Bid Price	**535.00**	**535.00**	**459.39**	**535.00**	**645.00**	**535.00**
Bid Amount	$103,148.00	$103,148.00	$88,570.39	$103,148.00	$124,356.00	$103,148.00
2290 703-42.15 SAFETY BARRIER CURB						**709 LF**
Bid Price	**68.00**	**68.00**	**58.45**	**68.00**	**52.00**	**68.00**
Bid Amount	$48,212.00	$48,212.00	$41,441.05	$48,212.00	$36,868.00	$48,212.00
2300 703-42.21 SLAB ON CONCRETE NU-GIRDER						**1,459 SQYD**
Bid Price	**235.00**	**230.00**	**241.84**	**230.00**	**237.00**	**230.00**
Bid Amount	$342,865.00	$335,570.00	$352,844.56	$335,570.00	$345,783.00	$335,570.00

TABULATION OF BIDS

Call No: D01	Iron Mountain Trap Rock Company Low Bid	C. J. Moyna & Sons, Inc. 2nd Low	Bloomsdale Excavating Company, Inc. 3rd Low	Chester Bross Const. Co./CB Equip. Inc. 4th Low	Emery Sapp & Sons Inc. 5th Low	Kolb Grading, LLC 6th Low
2310 705-60.23	**NU 53, PRESTRESSED CONCRETE NU-GIRDER**					**1,279 LF**
Bid Price	**207.00**	**245.00**	**270.35**	**245.00**	**206.00**	**245.00**
Bid Amount	$264,753.00	$313,355.00	$345,777.65	$313,355.00	$263,474.00	$313,355.00
2320 705-99.03	**MISC. NU 53, P/S CONC. NU-GDR. (TEST GDR.)**					**80 LF**
Bid Price	**195.00**	**215.00**	**283.03**	**215.00**	**212.00**	**215.00**
Bid Amount	$15,600.00	$17,200.00	$22,642.40	$17,200.00	$16,960.00	$17,200.00
2330 706-10.60	**REINFORCING STEEL (BRIDGES)**					**44,590 LB**
Bid Price	**1.35**	**1.10**	**1.21**	**1.10**	**1.00**	**1.10**
Bid Amount	$60,196.50	$49,049.00	$53,953.90	$49,049.00	$44,590.00	$49,049.00
2340 712-33.01	**STEEL INTERMEDIATE DIAPHRAGM FOR P/S CONCRETE GIRDERS**					**18 EA**
Bid Price	**600.00**	**900.00**	**205.93**	**900.00**	**500.00**	**900.00**
Bid Amount	$10,800.00	$16,200.00	$3,706.74	$16,200.00	$9,000.00	$16,200.00
2350 712-36.10	**SLAB DRAIN**					**29 EA**
Bid Price	**310.00**	**290.00**	**316.82**	**290.00**	**240.00**	**290.00**
Bid Amount	$8,990.00	$8,410.00	$9,187.78	$8,410.00	$6,960.00	$8,410.00
2360 715-10.01	**VERTICAL DRAIN AT END BENTS**					**2 EA**
Bid Price	**1700.00**	**1850.00**	**1584.11**	**1850.00**	**1450.00**	**1850.00**
Bid Amount	$3,400.00	$3,700.00	$3,168.22	$3,700.00	$2,900.00	$3,700.00
2370 716-10.00	**PLAIN NEOPRENE BEARING PAD**					**8 EA**
Bid Price	**175.00**	**260.00**	**205.93**	**260.00**	**195.00**	**260.00**
Bid Amount	$1,400.00	$2,080.00	$1,647.44	$2,080.00	$1,560.00	$2,080.00
2380 716-10.02	**LAMINATED NEOPRENE BEARING PAD**					**16 EA**
Bid Price	**295.00**	**400.00**	**316.82**	**400.00**	**295.00**	**400.00**
Bid Amount	$4,720.00	$6,400.00	$5,069.12	$6,400.00	$4,720.00	$6,400.00
2390 725-10.00	**CORRUGATED METAL PIPE PILE SPACERS**					**8 EA**
Bid Price	**1.00**	**0.10**	**2112.14**	**0.10**	**1.00**	**0.10**
Bid Amount	$8.00	$0.80	$16,897.12	$0.80	$8.00	$0.80
SECTION TOTALS	**$1,158,747.50**	**$1,196,516.80**	**$1,310,636.50**	**$1,196,516.80**	**$1,136,389.00**	**$1,196,516.80**

Section 0011: BRIDGE NO. A7960 - J5P0951B

2400 206-10.03	**CLASS 1 EXCAVATION IN ROCK**					**11 CUYD**
Bid Price	**365.00**	**700.00**	**205.93**	**45.00**	**270.00**	**45.00**
Bid Amount	$4,015.00	$7,700.00	$2,265.23	$495.00	$2,970.00	$495.00
2410 703-20.03	**CLASS B CONCRETE (SUBSTRUCTURE)**					**56.80 CUYD**
Bid Price	**425.00**	**650.00**	**524.87**	**425.00**	**395.00**	**425.00**
Bid Amount	$24,140.00	$36,920.00	$29,812.62	$24,140.00	$22,436.00	$24,140.00
2420 703-42.15	**SAFETY BARRIER CURB**					**289 LF**
Bid Price	**63.00**	**75.00**	**80.05**	**72.00**	**70.00**	**72.00**
Bid Amount	$18,207.00	$21,675.00	$23,134.45	$20,808.00	$20,230.00	$20,808.00
2430 703-42.18	**SLAB ON CONCRETE BULB-TEE GIRDER**					**464 SQYD**
Bid Price	**285.00**	**300.00**	**274.58**	**255.00**	**300.00**	**255.00**
Bid Amount	$132,240.00	$139,200.00	$127,405.12	$118,320.00	$139,200.00	$118,320.00

TABULATION OF BIDS

Call No: D01	Iron Mountain Trap Rock Company Low Bid	C. J. Moyna & Sons, Inc. 2nd Low	Bloomsdale Excavating Company, Inc. 3rd Low	Chester Bross Const. Co./CB Equip. Inc. 4th Low	Emery Sapp & Sons Inc. 5th Low	Kolb Grading, LLC 6th Low
2440 705-60.10	**TYPE 8 (63 IN.), PRESTRESSED CONCRETE BULB TEE**					**477 LF**
Bid Price	**170.00**	**225.00**	**250.29**	**205.00**	**182.00**	**205.00**
Bid Amount	$81,090.00	$107,325.00	$119,388.33	$97,785.00	$86,814.00	$97,785.00
2450 706-10.60	**REINFORCING STEEL (BRIDGES)**					**2,020 LB**
Bid Price	**1.45**	**1.25**	**1.21**	**1.35**	**1.00**	**1.35**
Bid Amount	$2,929.00	$2,525.00	$2,444.20	$2,727.00	$2,020.00	$2,727.00
2460 707-10.00	**CONDUIT SYSTEM ON STRUCTURE**					**LUMP SUM**
Lump Sum	**$2,233.00**	**$3,200.00**	**$3,907.46**	**$3,500.00**	**$3,200.00**	**$2,233.00**
2470 712-33.01	**STEEL INTERMEDIATE DIAPHRAGM FOR P/S CONCRETE GIRDERS**					**6 EA**
Bid Price	**600.00**	**950.00**	**1641.13**	**1275.00**	**740.00**	**1275.00**
Bid Amount	$3,600.00	$5,700.00	$9,846.78	$7,650.00	$4,440.00	$7,650.00
2480 715-10.01	**VERTICAL DRAIN AT END BENTS**					**2 EA**
Bid Price	**1700.00**	**1600.00**	**1584.11**	**1800.00**	**1300.00**	**1800.00**
Bid Amount	$3,400.00	$3,200.00	$3,168.22	$3,600.00	$2,600.00	$3,600.00
2490 716-10.03	**LAMINATED NEOPRENE BEARING PAD (TAPERED)**					**8 EA**
Bid Price	**260.00**	**235.00**	**316.82**	**350.00**	**275.00**	**350.00**
Bid Amount	$2,080.00	$1,880.00	$2,534.56	$2,800.00	$2,200.00	$2,800.00
SECTION TOTALS	**$273,934.00**	**$329,325.00**	**$323,906.97**	**$281,825.00**	**$286,110.00**	**$280,558.00**

Section 0012: BRIDGE NO. A7981 - J5P0951B

2500 206-33.00	**CLASS 4 EXCAVATION**					**1,730 CUYD**
Bid Price	**16.00**	**10.00**	**32.57**	**15.00**	**16.50**	**10.00**
Bid Amount	$27,680.00	$17,300.00	$56,346.10	$25,950.00	$28,545.00	$17,300.00
2510 206-34.00	**CLASS 4 EXCAVATION IN ROCK**					**62 CUYD**
Bid Price	**550.00**	**50.00**	**133.65**	**110.00**	**200.00**	**50.00**
Bid Amount	$34,100.00	$3,100.00	$8,286.30	$6,820.00	$12,400.00	$3,100.00
2520 703-40.40	**CLASS B-1 CONCRETE (CULVERTS-BRIDGE)**					**1,734.80 CUYD**
Bid Price	**395.00**	**260.00**	**274.58**	**345.00**	**350.00**	**260.00**
Bid Amount	$685,246.00	$451,048.00	$476,341.38	$598,506.00	$607,180.00	$451,048.00
2530 706-10.20	**REINFORCING STEEL (CULVERTS-BRIDGE)**					**255,010 LB**
Bid Price	**1.00**	**1.23**	**1.30**	**1.10**	**0.95**	**1.20**
Bid Amount	$255,010.00	$313,662.30	$331,513.00	$280,511.00	$242,259.50	$306,012.00
SECTION TOTALS	**$1,002,036.00**	**$785,110.30**	**$872,486.78**	**$911,787.00**	**$890,384.50**	**$777,460.00**

Contract Totals - 120824-D01

	$25,541,654.86	**$25,625,611.57**	**$25,628,509.83**	**$25,739,048.08**	**$26,624,512.64**	**$27,589,518.01**

CONTRACT ID: 120824-D01
LETTING DATE: 08/24/12

TABULATION OF BIDS

Call No: D01	Millstone Bangert, Inc. 7th	Lehman Construction, L.L.C. 8th	H. R. Quadri Contractors, LLC 9th	Kat Excavation, Inc. 10th	Illinois Valley Paving a division of Uni 11th	Clarkson Construction Company 12th

Project J5P0951B: Grading, drainage, alternate pavement and bridges

Section 0001: ROADWAY ITEMS - J5P0951B

0010	**104-10.00**	**TEMPORARY SURFACING**				**708 CUYD**
Bid Price	**37.00**	**25.00**	**30.00**	**16.00**	**57.31**	**64.00**
Bid Amount	$26,196.00	$17,700.00	$21,240.00	$11,328.00	$40,575.48	$45,312.00
0020	**201-30.00**	**CLEARING AND GRUBBING**				**62 ACRE**
Bid Price	**5710.00**	**4960.00**	**6000.00**	**5000.00**	**5665.00**	**6700.00**
Bid Amount	$354,020.00	$307,520.00	$372,000.00	$310,000.00	$351,230.00	$415,400.00
0030	**202-20.10**	**REMOVAL OF IMPROVEMENTS**				**LUMP SUM**
Lump Sum	**$138,400.00**	**$406,000.00**	**$153,950.00**	**$96,186.00**	**$177,101.97**	**$143,000.00**
0040	**202-40.38**	**REMOVAL OF TRANSITE (CATEGORY II NON-FRIABLE)**				**10,625 SQFT**
Bid Price	**2.75**	**2.75**	**0.50**	**2.81**	**2.83**	**3.00**
Bid Amount	$29,218.75	$29,218.75	$5,312.50	$29,856.25	$30,068.75	$31,875.00
0050	**202-40.40**	**REMOVAL OF MISCELLANEOUS ACM (FRIABLE)**				**600 SQFT**
Bid Price	**20.00**	**20.00**	**1.00**	**20.40**	**20.60**	**18.00**
Bid Amount	$12,000.00	$12,000.00	$600.00	$12,240.00	$12,360.00	$10,800.00
0060	**202-40.46**	**REMOVAL OF CAULKING/GLAZING COMPOUNDS (WINDOWS/DOORS) (CATEG ORY II NONFRIABLE)**				**430 LF**
Bid Price	**10.00**	**10.00**	**1.00**	**10.20**	**10.30**	**2.00**
Bid Amount	$4,300.00	$4,300.00	$430.00	$4,386.00	$4,429.00	$860.00
0070	**202-40.70**	**REMOVAL OF FLOOR SHEETING ACM ON WOOD (FRIABLE)**				**1,170 SQFT**
Bid Price	**5.00**	**5.00**	**1.00**	**5.10**	**5.15**	**5.00**
Bid Amount	$5,850.00	$5,850.00	$1,170.00	$5,967.00	$6,025.50	$5,850.00
0080	**202-40.72**	**REMOVAL OF FLOOR SHEETING ACM ON CONCRETE (FRIABLE)**				**30 SQFT**
Bid Price	**15.00**	**15.00**	**0.50**	**15.30**	**15.45**	**5.00**
Bid Amount	$450.00	$450.00	$15.00	$459.00	$463.50	$150.00
0090	**202-40.98**	**REMOVAL OF FLOOR TILE AND MASTIC ACM ON CONCRETE (CATEGORY I NON-FRIABLE)**				**3,400 SQFT**
Bid Price	**2.50**	**2.50**	**1.00**	**2.55**	**2.58**	**3.00**
Bid Amount	$8,500.00	$8,500.00	$3,400.00	$8,670.00	$8,772.00	$10,200.00
0100	**202-70.00**	**DISPOSAL AND PLUGGING OF WELLS**				**3 EA**
Bid Price	**4000.00**	**5000.00**	**1500.00**	**4200.00**	**2575.00**	**1120.00**
Bid Amount	$12,000.00	$15,000.00	$4,500.00	$12,600.00	$7,725.00	$3,360.00
0110	**202-99.50**	**DEMOLITION AND REMOVAL OF BUILDINGS 4 (J5P0951B)**				**LUMP SUM**
Lump Sum	**$3,000.00**	**$1,000.00**	**$2,000.00**	**$2,100.00**	**$1,876.54**	**$2,250.00**

TABULATION OF BIDS

Call No: D01	Millstone Bangert, Inc. 7th	Lehman Construction, L.L.C. 8th	H. R. Quadri Contractors, LLC 9th	Kat Excavation, Inc. 10th	Illinois Valley Paving a division of Uni 11th	Clarkson Construction Company 12th
0120 202-99.50	**DEMOLITION AND REMOVAL OF BUILDINGS 5 (J5P0951B)**					**LUMP SUM**
Lump Sum	**$20,000.00**	**$32,935.00**	**$10,000.00**	**$26,000.00**	**$27,063.88**	**$17,000.00**
0130 202-99.50	**DEMOLITION AND REMOVAL OF BUILDINGS 9 (J5P0951B)**					**LUMP SUM**
Lump Sum	**$10,000.00**	**$15,909.00**	**$5,000.00**	**$22,000.00**	**$12,333.31**	**$11,000.00**
0140 202-99.50	**DEMOLITION AND REMOVAL OF BUILDINGS 16 (J5P0951B)**					**LUMP SUM**
Lump Sum	**$12,500.00**	**$7,491.00**	**$5,000.00**	**$4,500.00**	**$11,126.52**	**$3,300.00**
0150 202-99.50	**DEMOLITION AND REMOVAL OF BUILDINGS 17 (J5P0951B)**					**LUMP SUM**
Lump Sum	**$4,000.00**	**$3,500.00**	**$1,000.00**	**$2,000.00**	**$1,876.54**	**$1,100.00**
0160 202-99.50	**DEMOLITION AND REMOVAL OF BUILDINGS 18 (J5P0951B)**					**LUMP SUM**
Lump Sum	**$6,500.00**	**$4,994.00**	**$5,000.00**	**$8,500.00**	**$12,333.31**	**$4,500.00**
0170 202-99.50	**DEMOLITION AND REMOVAL OF BUILDINGS 27 (J5P0951B)**					**LUMP SUM**
Lump Sum	**$3,000.00**	**$5,000.00**	**$5,000.00**	**$2,000.00**	**$1,876.54**	**$3,300.00**
0180 203-10.00	**CLASS A EXCAVATION**					**716,361 CUYD**
Bid Price	**2.60**	**2.30**	**3.65**	**2.90**	**3.68**	**2.79**
Bid Amount	$1,862,538.60	$1,647,630.30	$2,614,717.65	$2,077,446.90	$2,636,208.48	$1,998,647.19
0190 203-20.00	**CLASS C EXCAVATION**					**1,165,196 CUYD**
Bid Price	**6.35**	**7.15**	**6.50**	**6.44**	**7.30**	**8.70**
Bid Amount	$7,398,994.60	$8,331,151.40	$7,573,774.00	$7,503,862.24	$8,505,930.80	$10,137,205.20
0200 203-60.00	**COMPACTING EMBANKMENT**					**1,771,727 CUYD**
Bid Price	**0.25**	**0.05**	**0.50**	**0.85**	**0.32**	**0.01**
Bid Amount	$442,931.75	$88,586.35	$885,863.50	$1,505,967.95	$566,952.64	$17,717.27
0210 203-70.75	**COMPACTING IN CUT**					**292 STA**
Bid Price	**455.00**	**385.00**	**350.00**	**350.00**	**315.35**	**1000.00**
Bid Amount	$132,860.00	$112,420.00	$102,200.00	$102,200.00	$92,082.20	$292,000.00
0220 203-99.01	**MISC. LAGOON CLOSURE**					**LUMP SUM**
Lump Sum	**$6,570.00**	**$22,000.00**	**$100,000.00**	**$50,000.00**	**$30,944.70**	**$95,000.00**
0230 206-30.00	**CLASS 3 EXCAVATION**					**374 CUYD**
Bid Price	**40.50**	**18.00**	**10.00**	**12.00**	**53.91**	**28.00**
Bid Amount	$15,147.00	$6,732.00	$3,740.00	$4,488.00	$20,162.34	$10,472.00
0240 206-33.00	**CLASS 4 EXCAVATION**					**1,906 CUYD**
Bid Price	**16.00**	**20.00**	**22.00**	**20.40**	**17.51**	**22.00**
Bid Amount	$30,496.00	$38,120.00	$41,932.00	$38,882.40	$33,374.06	$41,932.00
0250 206-34.00	**CLASS 4 EXCAVATION IN ROCK**					**53 CUYD**
Bid Price	**200.00**	**100.00**	**325.00**	**280.50**	**17.51**	**325.00**
Bid Amount	$10,600.00	$5,300.00	$17,225.00	$14,866.50	$928.03	$17,225.00
0260 207-10.00	**LINEAR GRADING CLASS 1**					**17 STA**
Bid Price	**760.00**	**330.00**	**1000.00**	**230.00**	**562.70**	**1300.00**
Bid Amount	$12,920.00	$5,610.00	$17,000.00	$3,910.00	$9,565.90	$22,100.00

TABULATION OF BIDS

Call No: D01	Millstone Bangert, Inc. 7th	Lehman Construction, L.L.C. 8th	H. R. Quadri Contractors, LLC 9th	Kat Excavation, Inc. 10th	Illinois Valley Paving a division of Uni 11th	Clarkson Construction Company 12th
0270 208-10.00 INTERCEPTION DITCH						**101 100F**
Bid Price	**101.00**	**192.50**	**150.00**	**625.00**	**172.18**	**225.00**
Bid Amount	$10,201.00	$19,442.50	$15,150.00	$63,125.00	$17,390.18	$22,725.00
0280 214-20.00 FURNISHING ROCK FILL						**10,972 CUYD**
Bid Price	**0.01**	**2.31**	**0.10**	**3.00**	**18.40**	**17.00**
Bid Amount	$109.72	$25,345.32	$1,097.20	$32,916.00	$201,884.80	$186,524.00
0290 214-30.00 PLACING ROCK FILL						**10,972 CUYD**
Bid Price	**10.10**	**7.59**	**20.00**	**19.00**	**9.62**	**3.70**
Bid Amount	$110,817.20	$83,277.48	$219,440.00	$208,468.00	$105,550.64	$40,596.40
0300 215-10.00A SHAPING SLOPES, CLASS I						**72 100F**
Bid Price	**278.00**	**330.00**	**200.00**	**200.00**	**416.87**	**225.00**
Bid Amount	$20,016.00	$23,760.00	$14,400.00	$14,400.00	$30,014.64	$16,200.00
0310 303-99.05 MISC. ROCK BASE OPTIONAL ROCK BASE						**404,510 SQYD**
Bid Price	**1.25**	**0.99**	**3.00**	**1.10**	**3.62**	**2.35**
Bid Amount	$505,637.50	$400,464.90	$1,213,530.00	$444,961.00	$1,464,326.20	$950,598.50
0320 304-01.43 TYPE 1 AGGREGATE FOR BASE (4 IN. THICK)						**16,835 SQYD**
Bid Price	**7.25**	**6.50**	**4.50**	**2.32**	**6.65**	**5.70**
Bid Amount	$122,053.75	$109,427.50	$75,757.50	$39,057.20	$111,952.75	$95,959.50
0330 304-99.05 MISC. TYPE 1 AGGREGATE FOR BASE (2 IN. THICK)						**8,877.20 SQYD**
Bid Price	**7.15**	**4.75**	**3.00**	**0.75**	**3.11**	**4.25**
Bid Amount	$63,471.98	$42,166.70	$26,631.60	$6,657.90	$27,608.09	$37,728.10
0340 310-70.02 GRAVEL (A) OR CRUSHED STONE (B) OR CHAT (C)						**1,173 TONS**
Bid Price	**17.60**	**16.78**	**18.00**	**13.75**	**41.58**	**31.00**
Bid Amount	$20,644.80	$19,682.94	$21,114.00	$16,128.75	$48,773.34	$36,363.00
0350 401-01.51 TYPE A3 SHOULDER						**82,473 SQYD**
Bid Price	**15.00**	**18.83**	**16.90**	**13.09**	**20.06**	**18.00**
Bid Amount	$1,237,095.00	$1,552,966.59	$1,393,793.70	$1,079,571.57	$1,654,408.38	$1,484,514.00
0360 401-12.09 BITUMINOUS PAVEMENT MIXTURE PG64-22, (BP-1)						**320.10 TONS**
Bid Price	**76.50**	**75.87**	**75.00**	**77.39**	**78.15**	**75.87**
Bid Amount	$24,487.65	$24,285.99	$24,007.50	$24,772.54	$25,015.82	$24,285.99
0370 401-30.00 BITUMINOUS PAVEMENT MIXTURE PG64-22 (BASE)						**746.30 TONS**
Bid Price	**62.50**	**61.74**	**61.50**	**62.98**	**63.59**	**61.74**
Bid Amount	$46,643.75	$46,076.56	$45,897.45	$47,001.97	$47,457.22	$46,076.56
0380 401-99.05 MISC. OPTIONAL PAVEMENT (6 IN. THICK)						**24,881.70 SQYD**
Bid Price	**21.70**	**21.51**	**21.60**	**21.94**	**22.16**	**21.51**
Bid Amount	$539,932.89	$535,205.37	$537,444.72	$545,904.50	$551,378.47	$535,205.37
0390 401-99.05 MISC. OPTIONAL PAVEMENT (6.5 IN. OR 7 IN. THIC K)						**3,703.10 SQYD**
Bid Price	**24.80**	**24.51**	**24.00**	**25.00**	**25.25**	**24.51**
Bid Amount	$91,836.88	$90,762.98	$88,874.40	$92,577.50	$93,503.28	$90,762.98
0400 401-99.05 MISC. OPTIONAL PAVEMENT (7 IN. THICK)						**4,687.10 SQYD**
Bid Price	**24.70**	**24.48**	**24.35**	**24.97**	**25.21**	**24.48**
Bid Amount	$115,771.37	$114,740.21	$114,130.89	$117,036.89	$118,161.79	$114,740.21

TABULATION OF BIDS

Call No: D01	Millstone Bangert, Inc. 7th	Lehman Construction, L.L.C. 8th	H. R. Quadri Contractors, LLC 9th	Kat Excavation, Inc. 10th	Illinois Valley Paving a division of Uni 11th	Clarkson Construction Company 12th
0410 401-99.05	**MISC. OPTIONAL PAVEMENT (7.5 IN. THICK)**					**549.50 SQYD**
Bid Price	**34.75**	**34.42**	**34.50**	**35.11**	**35.45**	**34.42**
Bid Amount	$19,095.13	$18,913.79	$18,957.75	$19,292.95	$19,479.78	$18,913.79
0420 402-05.20	**BITUMINOUS PAVEMENT MIXTURE PG64-22 (SURFACE LEVELING)**					**278.40 TONS**
Bid Price	**82.00**	**81.08**	**81.20**	**82.70**	**83.51**	**81.08**
Bid Amount	$22,828.80	$22,572.67	$22,606.08	$23,023.68	$23,249.18	$22,572.67
0430 407-10.05	**TACK COAT**					**230 GAL**
Bid Price	**5.05**	**5.00**	**0.01**	**5.00**	**5.15**	**0.01**
Bid Amount	$1,161.50	$1,150.00	$2.30	$1,150.00	$1,184.50	$2.30
0440 504-10.00	**CONCRETE APPROACH PAVEMENT**					**219.30 SQYD**
Bid Price	**140.00**	**95.00**	**135.00**	**136.50**	**128.75**	**76.00**
Bid Amount	$30,702.00	$20,833.50	$29,605.50	$29,934.45	$28,234.88	$16,666.80
0450 604-40.11	**PIPE COLLAR, TYPE A**					**1 EA**
Bid Price	**3030.00**	**1650.00**	**1200.00**	**960.00**	**3692.21**	**3300.00**
Bid Amount	$3,030.00	$1,650.00	$1,200.00	$960.00	$3,692.21	$3,300.00
0460 604-40.12	**PIPE COLLAR, TYPE B**					**8 EA**
Bid Price	**1010.00**	**800.00**	**1.00**	**570.00**	**352.07**	**560.00**
Bid Amount	$8,080.00	$6,400.00	$8.00	$4,560.00	$2,816.56	$4,480.00
0470 606-10.10	**GUARDRAIL TYPE A**					**6,575 LF**
Bid Price	**16.20**	**16.00**	**16.00**	**17.34**	**16.48**	**17.00**
Bid Amount	$106,515.00	$105,200.00	$105,200.00	$114,010.50	$108,356.00	$111,775.00
0480 606-10.11A	**GUARDRAIL TYPE A, 7 FT. POST, 3 FT. - 1.5 IN SPACING**					**1,325 LF**
Bid Price	**28.75**	**28.50**	**28.50**	**26.52**	**29.36**	**26.00**
Bid Amount	$38,093.75	$37,762.50	$37,762.50	$35,139.00	$38,902.00	$34,450.00
0490 606-10.40	**GUARDRAIL TYPE D**					**13 LF**
Bid Price	**20.20**	**20.00**	**20.00**	**20.40**	**20.60**	**20.00**
Bid Amount	$262.60	$260.00	$260.00	$265.20	$267.80	$260.00
0500 606-23.00A	**TRANSITION SECTION, 6.5 FT. POSTS**					**5 EA**
Bid Price	**303.00**	**300.00**	**300.00**	**30.60**	**309.00**	**300.00**
Bid Amount	$1,515.00	$1,500.00	$1,500.00	$153.00	$1,545.00	$1,500.00
0510 606-24.00	**BRIDGE ANCHOR SECTION (THRIE BEAM)**					**5 EA**
Bid Price	**1820.00**	**1800.00**	**1800.00**	**1530.00**	**1854.00**	**1500.00**
Bid Amount	$9,100.00	$9,000.00	$9,000.00	$7,650.00	$9,270.00	$7,500.00
0520 606-30.15	**TYPE A CRASHWORTHY END TERMINAL**					**11 EA**
Bid Price	**1970.00**	**1950.00**	**1950.00**	**1938.00**	**2008.50**	**1900.00**
Bid Amount	$21,670.00	$21,450.00	$21,450.00	$21,318.00	$22,093.50	$20,900.00
0530 606-30.17	**TYPE C CRASHWORTHY END TERMINAL**					**1 EA**
Bid Price	**14650.00**	**14500.00**	**14500.00**	**13260.00**	**14935.00**	**13000.00**
Bid Amount	$14,650.00	$14,500.00	$14,500.00	$13,260.00	$14,935.00	$13,000.00
0540 606-66.10	**END ANCHOR**					**8 EA**
Bid Price	**960.00**	**950.00**	**950.00**	**739.50**	**978.50**	**725.00**
Bid Amount	$7,680.00	$7,600.00	$7,600.00	$5,916.00	$7,828.00	$5,800.00

TABULATION OF BIDS

Call No: D01	Millstone Bangert, Inc. 7th	Lehman Construction, L.L.C. 8th	H. R. Quadri Contractors, LLC 9th	Kat Excavation, Inc. 10th	Illinois Valley Paving a division of Uni 11th	Clarkson Construction Company 12th
0550 607-10.50	**CHAIN-LINK FENCE (RETAINING WALLS)**					**226 LF**
Bid Price	**19.70**	**19.50**	**19.50**	**53.39**	**20.09**	**52.34**
Bid Amount	$4,452.20	$4,407.00	$4,407.00	$12,066.14	$4,540.34	$11,828.84
0560 607-11.01	**MODIFIED CONCRETE GUTTER TYPE A**					**226 LF**
Bid Price	**58.50**	**32.00**	**30.00**	**65.00**	**61.80**	**56.00**
Bid Amount	$13,221.00	$7,232.00	$6,780.00	$14,690.00	$13,966.80	$12,656.00
0570 609-20.11	**INTEGRAL CURB (6 IN. HEIGHT AND UNDER) TYPE A**					**20 LF**
Bid Price	**37.25**	**75.00**	**15.00**	**22.50**	**52.43**	**21.00**
Bid Amount	$745.00	$1,500.00	$300.00	$450.00	$1,048.60	$420.00
0580 609-60.20	**FURNISHING TYPE 2 ROCK DITCH LINER**					**8,546 CUYD**
Bid Price	**0.01**	**2.48**	**1.00**	**3.00**	**18.39**	**25.00**
Bid Amount	$85.46	$21,194.08	$8,546.00	$25,638.00	$157,160.94	$213,650.00
0590 609-60.30A	**FURNISHING TYPE 3 ROCK DITCH LINER**					**7,069 CUYD**
Bid Price	**0.01**	**2.48**	**1.00**	**3.00**	**18.52**	**22.56800**
Bid Amount	$70.69	$17,531.12	$7,069.00	$21,207.00	$130,917.88	$159,533.19
0600 609-60.42	**PLACING TYPE 2 ROCK DITCH LINER**					**8,546 CUYD**
Bid Price	**30.25**	**6.60**	**45.00**	**19.25**	**24.29**	**15.00**
Bid Amount	$258,516.50	$56,403.60	$384,570.00	$164,510.50	$207,582.34	$128,190.00
0610 609-60.43	**PLACING TYPE 3 ROCK DITCH LINER**					**7,069 CUYD**
Bid Price	**30.25**	**8.80**	**30.00**	**19.25**	**18.74**	**14.00**
Bid Amount	$213,837.25	$62,207.20	$212,070.00	$136,078.25	$132,473.06	$98,966.00
0620 609-60.50	**BEDDING MATERIAL FOR ROCK DITCH LINER**					**2,570 CUYD**
Bid Price	**20.20**	**23.38**	**30.00**	**22.05**	**39.68**	**30.00**
Bid Amount	$51,914.00	$60,086.60	$77,100.00	$56,668.50	$101,977.60	$77,100.00
0630 609-70.00	**ROCK LINING**					**1,764 CUYD**
Bid Price	**30.25**	**10.45**	**30.00**	**24.00**	**69.31**	**33.00**
Bid Amount	$53,361.00	$18,433.80	$52,920.00	$42,336.00	$122,262.84	$58,212.00
0640 611-30.20	**FURNISHING TYPE 2 ROCK BLANKET**					**988 CUYD**
Bid Price	**0.01**	**2.48**	**0.10**	**31.50**	**18.57**	**17.00**
Bid Amount	$9.88	$2,450.24	$98.80	$31,122.00	$18,347.16	$16,796.00
0650 611-30.40	**PLACING TYPE 2 ROCK BLANKET**					**988 CUYD**
Bid Price	**30.25**	**6.60**	**30.00**	**15.99**	**27.28**	**25.00**
Bid Amount	$29,887.00	$6,520.80	$29,640.00	$15,798.12	$26,952.64	$24,700.00
0660 611-60.10A	**SLOPE PROTECTION**					**40 SQYD**
Bid Price	**58.50**	**150.00**	**50.00**	**100.00**	**180.25**	**56.00**
Bid Amount	$2,340.00	$6,000.00	$2,000.00	$4,000.00	$7,210.00	$2,240.00
0670 611-70.00A	**GABIONS**					**78 CUYD**
Bid Price	**130.00**	**130.00**	**200.00**	**132.60**	**133.90**	**130.00**
Bid Amount	$10,140.00	$10,140.00	$15,600.00	$10,342.80	$10,444.20	$10,140.00
0680 612-20.14	**IMPACT ATTENUATOR (14 SAND BARRELS)**					**6 EA**
Bid Price	**3890.00**	**2000.00**	**3500.00**	**2657.00**	**4705.99**	**6100.00**
Bid Amount	$23,340.00	$12,000.00	$21,000.00	$15,942.00	$28,235.94	$36,600.00

TABULATION OF BIDS

Call No: D01	Millstone Bangert, Inc. 7th	Lehman Construction, L.L.C. 8th	H. R. Quadri Contractors, LLC 9th	Kat Excavation, Inc. 10th	Illinois Valley Paving a division of Uni 11th	Clarkson Construction Company 12th
0690 612-20.20	**REPLACEMENT SAND BARREL**					**14 EA**
Bid Price	**590.00**	**50.00**	**10.00**	**207.06**	**329.13**	**280.00**
Bid Amount	$8,260.00	$700.00	$140.00	$2,898.84	$4,607.82	$3,920.00
0700 614-10.22	**GRATE AND BEARING PLATE (3 FT. X 3 FT. OR 914 MM X 914 MM)**					**10 EA**
Bid Price	**860.00**	**1200.00**	**700.00**	**885.00**	**697.27**	**1080.00**
Bid Amount	$8,600.00	$12,000.00	$7,000.00	$8,850.00	$6,972.70	$10,800.00
0710 614-10.24	**GRATE AND BEARING PLATE (5 FT. X 3 FT. OR 1524 MM X 914 MM)**					**9 EA**
Bid Price	**1720.00**	**1500.00**	**1000.00**	**1910.00**	**936.63**	**1680.00**
Bid Amount	$15,480.00	$13,500.00	$9,000.00	$17,190.00	$8,429.67	$15,120.00
0720 614-11.21	**CURVED VANE GRATE AND FRAME (4 FT X 2 FT OR 1200MM X 600MM)**					**9 EA**
Bid Price	**660.00**	**1800.00**	**1000.00**	**1981.00**	**868.48**	**795.00**
Bid Amount	$5,940.00	$16,200.00	$9,000.00	$17,829.00	$7,816.32	$7,155.00
0730 616-10.05	**CONSTRUCTION SIGNS**					**1,912 SQFT**
Bid Price	**8.00**	**8.00**	**8.75**	**8.67**	**8.24**	**8.00**
Bid Amount	$15,296.00	$15,296.00	$16,730.00	$16,577.04	$15,754.88	$15,296.00
0740 616-10.08	**ADVANCED WARNING RAIL SYSTEM**					**5 EA**
Bid Price	**50.00**	**50.00**	**60.00**	**56.10**	**51.50**	**50.00**
Bid Amount	$250.00	$250.00	$300.00	$280.50	$257.50	$250.00
0750 616-10.09	**FLAG ASSEMBLY**					**21 EA**
Bid Price	**20.00**	**20.00**	**30.00**	**25.50**	**20.60**	**20.00**
Bid Amount	$420.00	$420.00	$630.00	$535.50	$432.60	$420.00
0760 616-10.10	**RELOCATED SIGNS**					**32 SQFT**
Bid Price	**7.00**	**7.00**	**10.50**	**10.20**	**7.21**	**7.00**
Bid Amount	$224.00	$224.00	$336.00	$326.40	$230.72	$224.00
0770 616-10.25	**CHANNELIZER (TRIM LINE)**					**90 EA**
Bid Price	**30.00**	**30.00**	**25.00**	**18.90**	**30.90**	**30.00**
Bid Amount	$2,700.00	$2,700.00	$2,250.00	$1,701.00	$2,781.00	$2,700.00
0780 616-10.30	**TYPE III MOVEABLE BARRICADE**					**79 EA**
Bid Price	**175.00**	**175.00**	**125.00**	**96.90**	**180.25**	**175.00**
Bid Amount	$13,825.00	$13,825.00	$9,875.00	$7,655.10	$14,239.75	$13,825.00
0790 616-10.98	**CHANGEABLE MESSAGE SIGN, CONTRACTOR FURNISHED, CONTRACTOR RE TAINED**					**4 EA**
Bid Price	**3500.00**	**3500.00**	**4100.00**	**5100.00**	**3605.00**	**3500.00**
Bid Amount	$14,000.00	$14,000.00	$16,400.00	$20,400.00	$14,420.00	$14,000.00
0800 617-30.00	**CONCRETE TRAFFIC BARRIER, TYPE C**					**2,997 LF**
Bid Price	**51.00**	**50.00**	**60.00**	**64.13**	**40.41**	**58.00**
Bid Amount	$152,847.00	$149,850.00	$179,820.00	$192,197.61	$121,108.77	$173,826.00
0810 617-36.00D	**TEMPORARY TRAFFIC BARRIER, CONTRACTOR FURNISHED / RETAINED**					**1,882 LF**
Bid Price	**22.90**	**15.00**	**30.00**	**24.00**	**15.45**	**18.00**
Bid Amount	$43,097.80	$28,230.00	$56,460.00	$45,168.00	$29,076.90	$33,876.00

TABULATION OF BIDS

Call No: D01	Millstone Bangert, Inc. 7th	Lehman Construction, L.L.C. 8th	H. R. Quadri Contractors, LLC 9th	Kat Excavation, Inc. 10th	Illinois Valley Paving a division of Uni 11th	Clarkson Construction Company 12th
0820 618-10.00 MOBILIZATION						**LUMP SUM**
Lump Sum	**$1,756,172.00**	**$1,530,000.00**	**$2,204,623.07**	**$2,600,000.00**	**$1,021,377.71**	**$2,354,578.04**
0830 619-10.00 PAVEMENT EDGE TREATMENT						**7,104 LF**
Bid Price	**3.00**	**2.00**	**2.00**	**3.33**	**1.71**	**1.65**
Bid Amount	$21,312.00	$14,208.00	$14,208.00	$23,656.32	$12,147.84	$11,721.60
0840 620-51.20 TYPE 2 PREFORMED MARKING TAPE (GROOVED), 24 IN., WHITE						**204 LF**
Bid Price	**20.00**	**28.00**	**20.10**	**23.97**	**21.85**	**20.00**
Bid Amount	$4,080.00	$5,712.00	$4,100.40	$4,889.88	$4,457.40	$4,080.00
0850 620-51.30 TYPE 2 PREFORMED MARKING TAPE (GROOVED), LEFT/RIGHT ARROW						**26 EA**
Bid Price	**330.00**	**325.00**	**255.00**	**331.50**	**360.49**	**330.00**
Bid Amount	$8,580.00	$8,450.00	$6,630.00	$8,619.00	$9,372.74	$8,580.00
0860 620-51.40 TYPE 2 PREFORMED MARKING TAPE (GROOVED), 24 IN. WHITE, YIELD LINE TRIANGLES						**28 EA**
Bid Price	**35.00**	**50.00**	**35.50**	**51.00**	**38.23**	**35.00**
Bid Amount	$980.00	$1,400.00	$994.00	$1,428.00	$1,070.44	$980.00
0870 620-59.22 6 IN. WHITE WET REFLECTIVE HIGH BUILD ACRYLIC WATERBORNE PAV EMENT MARKING PAINT						**16,754 LF**
Bid Price	**0.40**	**0.40**	**0.39**	**0.45**	**0.44**	**0.40**
Bid Amount	$6,701.60	$6,701.60	$6,534.06	$7,539.30	$7,371.76	$6,701.60
0880 620-60.00B 4 IN. WHITE ACRYLIC WATERBORNE PAVEMENT MARKING PAINT						**15,967 LF**
Bid Price	**0.20**	**0.30**	**0.19**	**0.24**	**0.22**	**0.20**
Bid Amount	$3,193.40	$4,790.10	$3,033.73	$3,832.08	$3,512.74	$3,193.40
0890 620-60.01B 4 IN. YELLOW ACRYLIC WATERBORNE PAVEMENT MARKING PAINT						**26,819 LF**
Bid Price	**0.20**	**0.15**	**0.21**	**0.24**	**0.22**	**0.20**
Bid Amount	$5,363.80	$4,022.85	$5,631.99	$6,436.56	$5,900.18	$5,363.80
0900 620-61.06 ACRYLIC WATERBORNE PAVEMENT MARKING PAINT, 6 IN., WHITE						**74,485 LF**
Bid Price	**0.20**	**0.19**	**0.21**	**0.17**	**0.22**	**0.20**
Bid Amount	$14,897.00	$14,152.15	$15,641.85	$12,662.45	$16,386.70	$14,897.00
0910 620-61.08 ACRYLIC WATERBORNE PAVEMENT MARKING PAINT, 8 IN., WHITE						**214 LF**
Bid Price	**1.00**	**1.00**	**1.50**	**2.04**	**1.09**	**1.00**
Bid Amount	$214.00	$214.00	$321.00	$436.56	$233.26	$214.00
0920 620-61.19 ACRYLIC WATERBORNE PAVEMENT MARKING PAINT, 6 IN., YELLOW						**68,730 LF**
Bid Price	**0.20**	**0.19**	**0.21**	**0.17**	**0.22**	**0.20**
Bid Amount	$13,746.00	$13,058.70	$14,433.30	$11,684.10	$15,120.60	$13,746.00
0930 620-61.22 ACRYLIC WATERBORNE PAVEMENT MARKING PAINT, 12 IN., WHITE						**727 LF**
Bid Price	**0.40**	**1.50**	**0.39**	**1.17**	**0.44**	**0.40**
Bid Amount	$290.80	$1,090.50	$283.53	$850.59	$319.88	$290.80

TABULATION OF BIDS

Call No: D01	Millstone Bangert, Inc. 7th	Lehman Construction, L.L.C. 8th	H. R. Quadri Contractors, LLC 9th	Kat Excavation, Inc. 10th	Illinois Valley Paving a division of Uni 11th	Clarkson Construction Company 12th
0940 620-61.24	**ACRYLIC WATERBORNE PAVEMENT MARKING PAINT, 24 IN., WHITE**					**577 LF**
Bid Price	**2.00**	**3.00**	**1.90**	**3.77**	**2.18**	**2.00**
Bid Amount	$1,154.00	$1,731.00	$1,096.30	$2,175.29	$1,257.86	$1,154.00
0950 620-61.25	**ACRYLIC WATERBORNE PAVEMENT MARKING PAINT, 24 IN., YELLOW**					**264 LF**
Bid Price	**2.00**	**3.00**	**1.90**	**3.77**	**2.18**	**2.00**
Bid Amount	$528.00	$792.00	$501.60	$995.28	$575.52	$528.00
0960 620-70.01	**PAVEMENT MARKING REMOVAL**					**18,385 LF**
Bid Price	**0.50**	**0.70**	**0.52**	**0.56**	**0.55**	**0.50**
Bid Amount	$9,192.50	$12,869.50	$9,560.20	$10,295.60	$10,111.75	$9,192.50
0970 620-99.02	**MISC. TYPE 2 PERFORMED MARKING TAPE LANE REDUC TION ARROW (GROOVED)**					**2 EA**
Bid Price	**1590.00**	**675.00**	**1650.00**	**1683.00**	**1731.47**	**1585.00**
Bid Amount	$3,180.00	$1,350.00	$3,300.00	$3,366.00	$3,462.94	$3,170.00
0980 620-99.02	**MISC. PAVEMENT MARKING REMOVAL (LEFT TURN ARRO W)**					**3 EA**
Bid Price	**50.00**	**300.00**	**65.00**	**178.50**	**54.62**	**50.00**
Bid Amount	$150.00	$900.00	$195.00	$535.50	$163.86	$150.00
0990 622-40.10	**MODIFIED COLDMILLING (DEPTH TRANSITIONS)**					**229 SQYD**
Bid Price	**20.20**	**10.00**	**5.00**	**8.00**	**20.60**	**6.50**
Bid Amount	$4,625.80	$2,290.00	$1,145.00	$1,832.00	$4,717.40	$1,488.50
1000 624-01.03A	**PERMANENT EROSION CONTROL GEOTEXTILE**					**52,990 SQYD**
Bid Price	**1.85**	**1.65**	**2.00**	**2.47**	**1.62**	**2.63200**
Bid Amount	$98,031.50	$87,433.50	$105,980.00	$130,885.30	$85,843.80	$139,469.68
1010 624-01.04A	**SEPARATION GEOTEXTILE**					**1,059 SQYD**
Bid Price	**2.55**	**5.00**	**3.00**	**2.78**	**2.50**	**3.05**
Bid Amount	$2,700.45	$5,295.00	$3,177.00	$2,944.02	$2,647.50	$3,229.95
1020 624-99.05	**MISC. GEOSYNTHETIC REINFORCEMENT**					**3,639 SQYD**
Bid Price	**4.05**	**5.00**	**12.00**	**4.29**	**4.87**	**4.50**
Bid Amount	$14,737.95	$18,195.00	$43,668.00	$15,611.31	$17,721.93	$16,375.50
1030 627-40.00	**CONTRACTOR FURNISHED SURVEYING AND STAKING**					**LUMP SUM**
Lump Sum	**$170,000.00**	**$126,685.00**	**$182,000.00**	**$145,000.00**	**$194,670.00**	**$150,000.00**
1040 703-40.41	**CLASS B-1 CONCRETE (CULVERTS)**					**916.80 CUYD**
Bid Price	**422.00**	**525.00**	**430.00**	**433.50**	**386.25**	**420.00**
Bid Amount	$386,889.60	$481,320.00	$394,224.00	$397,432.80	$354,114.00	$385,056.00
1050 703-44.13	**MEDIAN BARRIER CURB TRANSITION (TYPE C)**					**10 LF**
Bid Price	**208.00**	**200.00**	**210.00**	**220.00**	**286.83**	**159.00**
Bid Amount	$2,080.00	$2,000.00	$2,100.00	$2,200.00	$2,868.30	$1,590.00
1060 706-10.30	**REINFORCING STEEL (CULVERTS)**					**151,540 LB**
Bid Price	**1.00**	**1.00**	**1.00**	**1.06**	**1.03**	**1.00**
Bid Amount	$151,540.00	$151,540.00	$151,540.00	$160,632.40	$156,086.20	$151,540.00
1070 720-10.00	**MECHANICALLY STABILIZED EARTH WALL SYSTEMS**					**2,563 SQFT**
Bid Price	**46.25**	**39.00**	**39.00**	**39.78**	**56.65**	**39.00**
Bid Amount	$118,538.75	$99,957.00	$99,957.00	$101,956.14	$145,193.95	$99,957.00

TABULATION OF BIDS

Call No: D01	Millstone Bangert, Inc. 7th	Lehman Construction, L.L.C. 8th	H. R. Quadri Contractors, LLC 9th	Kat Excavation, Inc. 10th	Illinois Valley Paving a division of Uni 11th	Clarkson Construction Company 12th
1080 725-03.15A 15 IN. PIPE GROUP B						**232 LF**
Bid Price	**46.50**	**55.00**	**25.00**	**29.00**	**25.45**	**45.00**
Bid Amount	$10,788.00	$12,760.00	$5,800.00	$6,728.00	$5,904.40	$10,440.00
1090 725-03.18A 18 IN. PIPE GROUP B						**489 LF**
Bid Price	**47.50**	**56.00**	**25.00**	**30.50**	**27.26**	**43.00**
Bid Amount	$23,227.50	$27,384.00	$12,225.00	$14,914.50	$13,330.14	$21,027.00
1100 725-03.24A 24 IN. PIPE GROUP B						**399 LF**
Bid Price	**56.50**	**58.00**	**32.00**	**32.50**	**30.05**	**49.00**
Bid Amount	$22,543.50	$23,142.00	$12,768.00	$12,967.50	$11,989.95	$19,551.00
1110 725-04.15 15 IN. PIPE GROUP C						**190 LF**
Bid Price	**40.50**	**65.00**	**24.00**	**26.00**	**24.21**	**37.00**
Bid Amount	$7,695.00	$12,350.00	$4,560.00	$4,940.00	$4,599.90	$7,030.00
1120 725-04.18 18 IN. PIPE GROUP C						**173 LF**
Bid Price	**44.50**	**68.00**	**26.00**	**30.00**	**27.79**	**41.00**
Bid Amount	$7,698.50	$11,764.00	$4,498.00	$5,190.00	$4,807.67	$7,093.00
1130 725-04.24 24 IN. PIPE GROUP C						**89 LF**
Bid Price	**60.50**	**72.00**	**30.00**	**36.00**	**31.21**	**46.00**
Bid Amount	$5,384.50	$6,408.00	$2,670.00	$3,204.00	$2,777.69	$4,094.00
1140 725-04.36 36 IN. PIPE GROUP C						**173 LF**
Bid Price	**65.50**	**75.00**	**40.00**	**44.00**	**45.63**	**62.00**
Bid Amount	$11,331.50	$12,975.00	$6,920.00	$7,612.00	$7,893.99	$10,726.00
1150 725-04.42 42 IN. PIPE GROUP C						**59 LF**
Bid Price	**76.00**	**95.00**	**50.00**	**54.00**	**57.97**	**84.00**
Bid Amount	$4,484.00	$5,605.00	$2,950.00	$3,186.00	$3,420.23	$4,956.00
1160 725-04.60 60 IN. PIPE GROUP C						**163 LF**
Bid Price	**101.00**	**112.50**	**90.00**	**73.00**	**75.43**	**179.00**
Bid Amount	$16,463.00	$18,337.50	$14,670.00	$11,899.00	$12,295.09	$29,177.00
1170 726-10.15 15 IN. PIPE GROUP A						**1,598 LF**
Bid Price	**40.50**	**40.25**	**35.00**	**36.00**	**31.83**	**42.00**
Bid Amount	$64,719.00	$64,319.50	$55,930.00	$57,528.00	$50,864.34	$67,116.00
1180 726-10.18 18 IN. PIPE GROUP A						**266 LF**
Bid Price	**50.50**	**48.00**	**40.00**	**41.00**	**44.88**	**49.00**
Bid Amount	$13,433.00	$12,768.00	$10,640.00	$10,906.00	$11,938.08	$13,034.00
1190 726-10.24 24 IN. PIPE GROUP A						**897 LF**
Bid Price	**51.50**	**59.00**	**45.00**	**50.00**	**47.99**	**51.00**
Bid Amount	$46,195.50	$52,923.00	$40,365.00	$44,850.00	$43,047.03	$45,747.00
1200 726-10.36 36 IN. PIPE GROUP A						**397 LF**
Bid Price	**131.00**	**65.00**	**65.00**	**107.00**	**89.45**	**74.00**
Bid Amount	$52,007.00	$25,805.00	$25,805.00	$42,479.00	$35,511.65	$29,378.00
1210 726-10.42 42 IN. PIPE GROUP A						**466 LF**
Bid Price	**141.00**	**85.00**	**85.00**	**113.00**	**94.68**	**93.00**
Bid Amount	$65,706.00	$39,610.00	$39,610.00	$52,658.00	$44,120.88	$43,338.00
1220 726-10.48 48 IN. PIPE GROUP A						**755 LF**
Bid Price	**119.00**	**95.00**	**100.00**	**122.00**	**104.91**	**118.00**
Bid Amount	$89,845.00	$71,725.00	$75,500.00	$92,110.00	$79,207.05	$89,090.00

TABULATION OF BIDS

Call No: D01	Millstone Bangert, Inc. 7th	Lehman Construction, L.L.C. 8th	H. R. Quadri Contractors, LLC 9th	Kat Excavation, Inc. 10th	Illinois Valley Paving a division of Uni 11th	Clarkson Construction Company 12th
1230 726-10.54 54 IN. PIPE GROUP A						**403 LF**
Bid Price	**182.00**	**110.00**	**135.00**	**322.00**	**143.29**	**152.00**
Bid Amount	$73,346.00	$44,330.00	$54,405.00	$129,766.00	$57,745.87	$61,256.00
1240 726-10.60 60 IN. PIPE GROUP A						**37 LF**
Bid Price	**182.00**	**195.00**	**145.00**	**214.00**	**154.40**	**148.00**
Bid Amount	$6,734.00	$7,215.00	$5,365.00	$7,918.00	$5,712.80	$5,476.00
1250 726-10.66 66 IN. PIPE GROUP A						**196 LF**
Bid Price	**202.00**	**190.00**	**180.00**	**260.00**	**179.26**	**214.00**
Bid Amount	$39,592.00	$37,240.00	$35,280.00	$50,960.00	$35,134.96	$41,944.00
1260 726-10.72 72 IN. PIPE GROUP A						**260 LF**
Bid Price	**222.00**	**265.00**	**220.00**	**270.00**	**202.29**	**332.00**
Bid Amount	$57,720.00	$68,900.00	$57,200.00	$70,200.00	$52,595.40	$86,320.00
1270 726-99.03 MISC. 48 IN RCP (SPECIAL DESIGN)						**614 LF**
Bid Price	**219.00**	**280.00**	**150.00**	**225.00**	**197.84**	**280.00**
Bid Amount	$134,466.00	$171,920.00	$92,100.00	$138,150.00	$121,473.76	$171,920.00
1280 726-99.03 MISC. 60 IN RCP (SPECIAL DESIGN)						**650 LF**
Bid Price	**293.00**	**300.00**	**200.00**	**341.00**	**248.50**	**504.00**
Bid Amount	$190,450.00	$195,000.00	$130,000.00	$221,650.00	$161,525.00	$327,600.00
1290 731-10.33 PRECAST CONCRETE DROP INLET 3 FT X 3 FT						**33 FT**
Bid Price	**303.00**	**650.00**	**400.00**	**567.00**	**391.47**	**594.00**
Bid Amount	$9,999.00	$21,450.00	$13,200.00	$18,711.00	$12,918.51	$19,602.00
1300 731-10.42 PRECAST CONCRETE DROP INLET 4 FT X 2 FT						**34 FT**
Bid Price	**570.00**	**700.00**	**450.00**	**550.00**	**388.08**	**594.00**
Bid Amount	$19,380.00	$23,800.00	$15,300.00	$18,700.00	$13,194.72	$20,196.00
1310 731-10.53 PRECAST CONCRETE DROP INLET 5 FT X 3 FT						**34 FT**
Bid Price	**404.00**	**775.00**	**475.00**	**631.00**	**455.45**	**728.00**
Bid Amount	$13,736.00	$26,350.00	$16,150.00	$21,454.00	$15,485.30	$24,752.00
1320 732-00.15A 15 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION						**6 EA**
Bid Price	**303.00**	**325.00**	**300.00**	**454.00**	**445.96**	**263.00**
Bid Amount	$1,818.00	$1,950.00	$1,800.00	$2,724.00	$2,675.76	$1,578.00
1330 732-00.18A 18 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION						**3 EA**
Bid Price	**354.00**	**400.00**	**325.00**	**481.00**	**472.68**	**263.00**
Bid Amount	$1,062.00	$1,200.00	$975.00	$1,443.00	$1,418.04	$789.00
1340 732-00.24A 24 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION						**1 EA**
Bid Price	**404.00**	**475.00**	**375.00**	**538.00**	**530.18**	**330.00**
Bid Amount	$404.00	$475.00	$375.00	$538.00	$530.18	$330.00
1350 732-06.15A 15 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION						**2 EA**
Bid Price	**510.00**	**350.00**	**500.00**	**759.00**	**531.43**	**358.00**
Bid Amount	$1,020.00	$700.00	$1,000.00	$1,518.00	$1,062.86	$716.00

TABULATION OF BIDS

Call No: D01	Millstone Bangert, Inc. 7th	Lehman Construction, L.L.C. 8th	H. R. Quadri Contractors, LLC 9th	Kat Excavation, Inc. 10th	Illinois Valley Paving a division of Uni 11th	Clarkson Construction Company 12th
1360 732-06.18A	**18 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION**					**2 EA**
Bid Price	**560.00**	**435.00**	**600.00**	**803.00**	**570.93**	**470.00**
Bid Amount	$1,120.00	$870.00	$1,200.00	$1,606.00	$1,141.86	$940.00
1370 732-06.24A	**24 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION**					**8 EA**
Bid Price	**660.00**	**625.00**	**750.00**	**1110.00**	**1038.79**	**521.00**
Bid Amount	$5,280.00	$5,000.00	$6,000.00	$8,880.00	$8,310.32	$4,168.00
1380 732-06.36A	**36 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION**					**2 EA**
Bid Price	**1110.00**	**800.00**	**1000.00**	**1340.00**	**1407.68**	**1040.00**
Bid Amount	$2,220.00	$1,600.00	$2,000.00	$2,680.00	$2,815.36	$2,080.00
1390 732-06.42A	**42 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION**					**4 EA**
Bid Price	**1520.00**	**1500.00**	**1500.00**	**1570.00**	**1599.57**	**1530.00**
Bid Amount	$6,080.00	$6,000.00	$6,000.00	$6,280.00	$6,398.28	$6,120.00
1400 732-06.48A	**48 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION**					**6 EA**
Bid Price	**1720.00**	**1850.00**	**1800.00**	**2010.00**	**1719.44**	**2050.00**
Bid Amount	$10,320.00	$11,100.00	$10,800.00	$12,060.00	$10,316.64	$12,300.00
1410 732-06.54A	**54 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION**					**4 EA**
Bid Price	**2020.00**	**2200.00**	**2000.00**	**2502.00**	**1772.09**	**2690.00**
Bid Amount	$8,080.00	$8,800.00	$8,000.00	$10,008.00	$7,088.36	$10,760.00
1420 732-06.60A	**60 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION**					**1 EA**
Bid Price	**2320.00**	**2800.00**	**2500.00**	**2776.00**	**1832.47**	**3630.00**
Bid Amount	$2,320.00	$2,800.00	$2,500.00	$2,776.00	$1,832.47	$3,630.00
1430 732-06.66A	**66 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION**					**2 EA**
Bid Price	**4040.00**	**3100.00**	**3500.00**	**3477.00**	**1055.25**	**3640.00**
Bid Amount	$8,080.00	$6,200.00	$7,000.00	$6,954.00	$2,110.50	$7,280.00
1440 732-06.72A	**72 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION**					**2 EA**
Bid Price	**5050.00**	**3850.00**	**5000.00**	**3477.00**	**1079.67**	**4350.00**
Bid Amount	$10,100.00	$7,700.00	$10,000.00	$6,954.00	$2,159.34	$8,700.00
1450 732-08.15A	**15 IN. OR ALLOWED SUBSTITUTE GROUP C FLARED END SECTION**					**4 EA**
Bid Price	**303.00**	**400.00**	**250.00**	**419.00**	**410.69**	**375.00**
Bid Amount	$1,212.00	$1,600.00	$1,000.00	$1,676.00	$1,642.76	$1,500.00
1460 732-08.36A	**36 IN. OR ALLOWED SUBSTITUTE GROUP C FLARED END SECTION**					**4 EA**
Bid Price	**610.00**	**1300.00**	**525.00**	**652.00**	**644.09**	**952.00**
Bid Amount	$2,440.00	$5,200.00	$2,100.00	$2,608.00	$2,576.36	$3,808.00

TABULATION OF BIDS

Call No: D01	Millstone Bangert, Inc. 7th	Lehman Construction, L.L.C. 8th	H. R. Quadri Contractors, LLC 9th	Kat Excavation, Inc. 10th	Illinois Valley Paving a division of Uni 11th	Clarkson Construction Company 12th
1470	**732-08.42A**	**42 IN. OR ALLOWED SUBSTITUTE GROUP C FLARED END SECTION**				**2 EA**
Bid Price	**910.00**	**1500.00**	**875.00**	**973.00**	**1176.87**	**1420.00**
Bid Amount	$1,820.00	$3,000.00	$1,750.00	$1,946.00	$2,353.74	$2,840.00
1480	**732-10.14A**	**18 IN. OR ALLOWED SUBSTITUTE SAFETY SLOPE END SECTION**				**4 EA**
Bid Price	**1010.00**	**1625.00**	**600.00**	**770.00**	**939.92**	**560.00**
Bid Amount	$4,040.00	$6,500.00	$2,400.00	$3,080.00	$3,759.68	$2,240.00
1490	**732-10.16A**	**24 IN. OR ALLOWED SUBSTITUTE SAFETY SLOPE END SECTION**				**10 EA**
Bid Price	**1210.00**	**1800.00**	**900.00**	**1005.00**	**1116.21**	**1010.00**
Bid Amount	$12,100.00	$18,000.00	$9,000.00	$10,050.00	$11,162.10	$10,100.00
1500	**732-99.02**	**MISC. 48 IN PRECAST CONC FES (SPECIAL DESIGN)**				**2 EA**
Bid Price	**1210.00**	**3500.00**	**3000.00**	**3653.00**	**1085.36**	**2030.00**
Bid Amount	$2,420.00	$7,000.00	$6,000.00	$7,306.00	$2,170.72	$4,060.00
1510	**732-99.02**	**MISC. 60 IN PRECAST CONC FES (SPECIAL DESIGN)**				**2 EA**
Bid Price	**2020.00**	**4500.00**	**4000.00**	**5188.00**	**1222.49**	**3420.00**
Bid Amount	$4,040.00	$9,000.00	$8,000.00	$10,376.00	$2,444.98	$6,840.00
1520	**805-10.00A**	**SEEDING - COOL SEASON MIXTURES**				**82.70 ACRE**
Bid Price	**1550.00**	**1550.00**	**1300.00**	**1581.00**	**1493.50**	**1550.00**
Bid Amount	$128,185.00	$128,185.00	$107,510.00	$130,748.70	$123,512.45	$128,185.00
1530	**805-20.00A**	**SEEDING - WARM SEASON MIXTURES**				**45.70 ACRE**
Bid Price	**1650.00**	**1650.00**	**1400.00**	**1683.00**	**1493.50**	**1650.00**
Bid Amount	$75,405.00	$75,405.00	$63,980.00	$76,913.10	$68,252.95	$75,405.00
1540	**806-10.10A**	**TYPE B BERM**				**12,367 LF**
Bid Price	**1.00**	**3.85**	**0.10**	**4.80**	**1.26**	**2.25**
Bid Amount	$12,367.00	$47,612.95	$1,236.70	$59,361.60	$15,582.42	$27,825.75
1550	**806-10.11**	**SLOPE DRAINS**				**1,985 LF**
Bid Price	**8.10**	**33.00**	**0.10**	**11.00**	**6.42**	**13.00**
Bid Amount	$16,078.50	$65,505.00	$198.50	$21,835.00	$12,743.70	$25,805.00
1560	**806-10.15**	**SEDIMENT BASIN**				**430 CUYD**
Bid Price	**15.20**	**15.00**	**9.00**	**29.00**	**41.27**	**9.00**
Bid Amount	$6,536.00	$6,450.00	$3,870.00	$12,470.00	$17,746.10	$3,870.00
1570	**806-10.16**	**SEDIMENT REMOVAL**				**1,601 CUYD**
Bid Price	**10.10**	**18.00**	**9.00**	**15.00**	**10.06**	**28.00**
Bid Amount	$16,170.10	$28,818.00	$14,409.00	$24,015.00	$16,106.06	$44,828.00
1580	**806-10.17**	**TEMPORARY SEEDING AND MULCHING**				**51.30 ACRE**
Bid Price	**750.00**	**750.00**	**350.00**	**765.00**	**772.50**	**750.00**
Bid Amount	$38,475.00	$38,475.00	$17,955.00	$39,244.50	$39,629.25	$38,475.00
1590	**806-10.19**	**SILT FENCE**				**40,693 LF**
Bid Price	**1.95**	**1.95**	**1.80**	**1.99**	**3.30**	**1.95**
Bid Amount	$79,351.35	$79,351.35	$73,247.40	$80,979.07	$134,286.90	$79,351.35

TABULATION OF BIDS

Call No: D01	Millstone Bangert, Inc. 7th	Lehman Construction, L.L.C. 8th	H. R. Quadri Contractors, LLC 9th	Kat Excavation, Inc. 10th	Illinois Valley Paving a division of Uni 11th	Clarkson Construction Company 12th
1600 806-10.22 TYPE II DITCH CHECK						**638 EA**
Bid Price	**110.00**	**110.00**	**130.00**	**113.00**	**154.50**	**110.00**
Bid Amount	$70,180.00	$70,180.00	$82,940.00	$72,094.00	$98,571.00	$70,180.00
1610 806-10.23 SEDIMENT TRAP						**3,280 CUYD**
Bid Price	**15.20**	**15.00**	**9.00**	**40.00**	**13.64**	**9.00**
Bid Amount	$49,856.00	$49,200.00	$29,520.00	$131,200.00	$44,739.20	$29,520.00
1620 806-10.25 INLET CHECK						**20 EA**
Bid Price	**125.00**	**125.00**	**150.00**	**128.00**	**178.37**	**125.00**
Bid Amount	$2,500.00	$2,500.00	$3,000.00	$2,560.00	$3,567.40	$2,500.00
1630 806-10.50 TYPE C BERM						**595 LF**
Bid Price	**20.20**	**35.00**	**30.00**	**30.50**	**73.77**	**11.00**
Bid Amount	$12,019.00	$20,825.00	$17,850.00	$18,147.50	$43,893.15	$6,545.00
1640 806-99.05 MISC. CONCRETE BLOCK MAT						**2,630 SQYD**
Bid Price	**49.50**	**49.50**	**50.00**	**50.50**	**43.78**	**49.50**
Bid Amount	$130,185.00	$130,185.00	$131,500.00	$132,815.00	$115,141.40	$130,185.00
1650 806-99.07 MISC FURNISHING ROCK FOR SEDIMENT TRAPS/BASIN S						**3,710 CUYD**
Bid Price	**30.00**	**30.00**	**10.00**	**30.60**	**15.50**	**30.00**
Bid Amount	$111,300.00	$111,300.00	$37,100.00	$113,526.00	$57,505.00	$111,300.00
SECTION TOTALS	**$19,319,362.85**	**$19,593,542.94**	**$21,824,039.17**	**$21,476,036.09**	**$22,321,363.93**	**$23,840,264.33**

Section 0002: ALT A - SUPERPAVE PAVEMENT - J5P0951B

1660 403-04.01 8 INCHES, ASPHALTIC CONCRETE PAVEMENT SP125C						**187,857.10 SQYD**
Bid Price						
Bid Amount						
1670 620-99.03 MISC. MISC. 7 IN. GROOVE FOR PAVEMENT MARKING (ASHPHALT)						**16,711 LF**
Bid Price						
Bid Amount						
1680 626-10.00A BITUMINOUS SHOULDER RUMBLE STRIP						**1,224.20 STA**
Bid Price						
Bid Amount						
1690 626-10.01 BITUMINOUS CENTERLINE RUMBLE STRIP						**7.70 STA**
Bid Price						
Bid Amount						
SECTION TOTALS	**$0.00**	**$0.00**	**$0.00**	**$0.00**	**$0.00**	**$0.00**

Section 0003: ALT B - PCCP PAVEMENT - J5P0951B

1700 502-13.08 CONCRETE PAVEMENT (8 IN. NON-REINFORCED, 15 FT. JOINTS)						**187,857.10 SQYD**
Bid Price	**24.75**	**31.00**	**25.05**	**26.25**	**24.58**	**23.00**
Bid Amount	$4,649,463.23	$5,823,570.10	$4,705,820.36	$4,931,248.88	$4,617,527.52	$4,320,713.30

Call No: D01	Millstone Bangert, Inc. 7th	Lehman Construction, L.L.C. 8th	H. R. Quadri Contractors, LLC 9th	Kat Excavation, Inc. 10th	Illinois Valley Paving a division of Uni 11th	Clarkson Construction Company 12th
1710 620-59.35	**9 IN. BLACK ACRYLIC WATERBORNE CONTRAST PAVEMENT MARKING PAI NT**					**16,711 LF**
Bid Price	**0.43**	**0.32**	**0.50**	**0.32**	**0.14**	**0.13**
Bid Amount	$7,185.73	$5,347.52	$8,355.50	$5,347.52	$2,339.54	$2,172.43
1720 620-99.03	**MISC. MISC. 10 IN. GROOVE FOR PAVEMENT MARKING (CONCRETE)**					**16,711 LF**
Bid Price	**0.50**	**0.58**	**0.50**	**0.64**	**0.55**	**0.50**
Bid Amount	$8,355.50	$9,692.38	$8,355.50	$10,695.04	$9,191.05	$8,355.50
1730 626-20.00A	**PORTLAND CEMENT CONCRETE SHOULDER RUMBLE STRIP**					**1,224.20 STA**
Bid Price	**23.40**	**32.00**	**25.50**	**25.50**	**23.32**	**23.45**
Bid Amount	$28,646.28	$39,174.40	$31,217.10	$31,217.10	$28,548.34	$28,707.49
1740 626-20.01	**PORTLAND CEMENT CONCRETE CENTERLINE RUMBLE STRIP**					**7.70 STA**
Bid Price	**35.00**	**172.00**	**175.00**	**25.50**	**53.80**	**35.00**
Bid Amount	$269.50	$1,324.40	$1,347.50	$196.35	$414.26	$269.50
SECTION TOTALS	**$4,693,920.24**	**$5,879,108.80**	**$4,755,095.96**	**$4,978,704.89**	**$4,658,020.71**	**$4,360,218.22**

Section 0004: ALT C - ASPHALT A2 SHOULDERS - J5P0951B

1750 401-01.50	**TYPE A2 SHOULDER**					**5,043.30 SQYD**
Bid Price		**21.05**	**21.25**	**21.47**		**26.00**
Bid Amount		$106,161.47	$107,170.13	$108,279.65		$131,125.80

Section 0005: ALT D - CONCRETE A2 SHOULDERS - J5P0951B

1760 502-13.40	**TYPE A2 SHOULDER**					**5,043.30 SQYD**
Bid Price	**23.60**				**23.19**	
Bid Amount	$119,021.88				$116,954.13	

Section 0006: LIGHTING ITEMS - J5P0951B

1770 901-10.62	**LIGHTING POLE, 45 FT. OR 13.5 M, TYPE AT DESIGN 2**					**3 EA**
Bid Price	**2040.00**	**2040.00**	**2050.00**	**2035.00**	**1996.14**	**1938.00**
Bid Amount	$6,120.00	$6,120.00	$6,150.00	$6,105.00	$5,988.42	$5,814.00
1780 901-11.15	**BRACKET ARM, 15 FT. OR 4.6 M**					**3 EA**
Bid Price	**520.00**	**515.00**	**525.00**	**588.00**	**576.80**	**560.00**
Bid Amount	$1,560.00	$1,545.00	$1,575.00	$1,764.00	$1,730.40	$1,680.00
1790 901-13.10	**LUMINAIRE, 250 WATT HIGH PRESSURE SODIUM**					**3 EA**
Bid Price	**287.00**	**287.00**	**290.00**	**315.00**	**309.00**	**300.00**
Bid Amount	$861.00	$861.00	$870.00	$945.00	$927.00	$900.00
1800 901-22.30	**BASE MOUNTED CONTROL STATION 240 VOLT - 4 CIRCUIT**					**1 EA**
Bid Price	**2710.00**	**2706.00**	**3000.00**	**5894.70**	**5782.42**	**5614.00**
Bid Amount	$2,710.00	$2,706.00	$3,000.00	$5,894.70	$5,782.42	$5,614.00

TABULATION OF BIDS

Call No: D01	Millstone Bangert, Inc. 7th	Lehman Construction, L.L.C. 8th	H. R. Quadri Contractors, LLC 9th	Kat Excavation, Inc. 10th	Illinois Valley Paving a division of Uni 11th	Clarkson Construction Company 12th
1810 901-30.02 CONDUIT, 2 IN. RIGID, IN TRENCH						**48 LF**
Bid Price	**11.30**	**11.30**	**11.50**	**8.40**	**8.24**	**8.00**
Bid Amount	$542.40	$542.40	$552.00	$403.20	$395.52	$384.00
1820 901-30.03 CONDUIT, 3 IN. RIGID, IN TRENCH						**62 LF**
Bid Price	**13.40**	**13.40**	**13.50**	**8.93**	**8.76**	**8.50**
Bid Amount	$830.80	$830.80	$837.00	$553.66	$543.12	$527.00
1830 901-40.03 CONDUIT, 3 IN. RIGID, PUSHED						**58 LF**
Bid Price	**32.00**	**31.90**	**32.00**	**22.05**	**21.63**	**21.00**
Bid Amount	$1,856.00	$1,850.20	$1,856.00	$1,278.90	$1,254.54	$1,218.00
1840 901-50.20 TRENCHING TYPE II						**2,560 LF**
Bid Price	**4.75**	**4.75**	**4.85**	**3.15**	**3.09**	**3.00**
Bid Amount	$12,160.00	$12,160.00	$12,416.00	$8,064.00	$7,910.40	$7,680.00
1850 901-61.10 PULL BOX, PREFORMED CLASS 1						**7 EA**
Bid Price	**710.00**	**708.00**	**720.00**	**976.50**	**957.90**	**930.00**
Bid Amount	$4,970.00	$4,956.00	$5,040.00	$6,835.50	$6,705.30	$6,510.00
1860 901-70.02 CABLE, 2 AWG 1 CONDUCTOR						**170 LF**
Bid Price	**2.85**	**2.85**	**2.90**	**2.40**	**2.35**	**2.28**
Bid Amount	$484.50	$484.50	$493.00	$408.00	$399.50	$387.60
1870 901-71.10 CABLE, 10 AWG 1 CONDUCTOR, POLE AND BRACKET						**360 LF**
Bid Price	**0.55**	**0.55**	**0.75**	**1.05**	**1.03**	**1.00**
Bid Amount	$198.00	$198.00	$270.00	$378.00	$370.80	$360.00
1880 901-74.07 CABLE-CONDUIT, 1 IN., 2 CONDUCTORS AND 1 BARE NEUTRAL, 8 AWG						**3,040 LF**
Bid Price	**3.40**	**3.40**	**3.50**	**2.94**	**2.88**	**2.80**
Bid Amount	$10,336.00	$10,336.00	$10,640.00	$8,937.60	$8,755.20	$8,512.00
1890 901-82.45 POLE FOUNDATION (45 FT. OR 13.5 M MOUNTING HEIGHT)						**3 EA**
Bid Price	**1130.00**	**1130.00**	**1100.00**	**1050.00**	**1030.00**	**1000.00**
Bid Amount	$3,390.00	$3,390.00	$3,300.00	$3,150.00	$3,090.00	$3,000.00
1900 901-86.12 POWER SUPPLY ASSEMBLY, TYPE 2, 240/120 VOLT SERVICE, LIGHTIN G ONLY						**1 EA**
Bid Price	**2620.00**	**2619.10**	**2625.00**	**4475.10**	**4389.86**	**4262.00**
Bid Amount	$2,620.00	$2,619.10	$2,625.00	$4,475.10	$4,389.86	$4,262.00
SECTION TOTALS	**$48,638.70**	**$48,599.00**	**$49,624.00**	**$49,192.66**	**$48,242.48**	**$46,848.60**

Section 0007: SIGNING ITEMS - J5P0951B

1910 903-10.10 CONCRETE FOOTINGS, EMBEDDED						**17.10 CUYD**
Bid Price	**910.00**	**900.00**	**900.00**	**741.52**	**927.00**	**727.00**
Bid Amount	$15,561.00	$15,390.00	$15,390.00	$12,679.99	$15,851.70	$12,431.70
1920 903-12.10 STRUCTURAL STEEL POSTS						**4,610 LB**
Bid Price	**2.65**	**2.60**	**2.60**	**2.48**	**2.68**	**2.47**
Bid Amount	$12,216.50	$11,986.00	$11,986.00	$11,432.80	$12,354.80	$11,386.70

TABULATION OF BIDS

Call No: D01	Millstone Bangert, Inc. 7th	Lehman Construction, L.L.C. 8th	H. R. Quadri Contractors, LLC 9th	Kat Excavation, Inc. 10th	Illinois Valley Paving a division of Uni 11th	Clarkson Construction Company 12th
1930 903-12.20 PIPE POSTS						**8,190 LB**
Bid Price	**2.20**	**2.20**	**2.20**	**2.26**	**2.27**	**2.21**
Bid Amount	$18,018.00	$18,018.00	$18,018.00	$18,509.40	$18,591.30	$18,099.90
1940 903-12.40 BREAKAWAY ASSEMBLY						**57 EA**
Bid Price	**81.00**	**80.00**	**80.00**	**2379.64**	**82.40**	**233.00**
Bid Amount	$4,617.00	$4,560.00	$4,560.00	$135,639.48	$4,696.80	$13,281.00
1950 903-12.52 7 FT. CHANNEL POST DELINEATOR, DOUBLE STACKED WHITE						**35 EA**
Bid Price	**36.25**	**36.00**	**36.00**	**45.13**	**37.08**	**44.00**
Bid Amount	$1,268.75	$1,260.00	$1,260.00	$1,579.55	$1,297.80	$1,540.00
1960 903-12.53A 7 FT. CHANNEL POST DELINEATOR, DOUBLE STACKED YELLOW						**47 EA**
Bid Price	**36.25**	**36.00**	**36.00**	**45.13**	**37.08**	**44.00**
Bid Amount	$1,703.75	$1,692.00	$1,692.00	$2,121.11	$1,742.76	$2,068.00
1970 903-12.56 7 FT. CHANNEL POST DELINEATOR, WHITE						**108 EA**
Bid Price	**32.25**	**32.00**	**32.00**	**39.27**	**32.96**	**39.00**
Bid Amount	$3,483.00	$3,456.00	$3,456.00	$4,241.16	$3,559.68	$4,212.00
1980 903-12.57A 7 FT. CHANNEL POST DELINEATOR, YELLOW						**5 EA**
Bid Price	**32.25**	**32.00**	**32.00**	**39.27**	**32.96**	**39.00**
Bid Amount	$161.25	$160.00	$160.00	$196.35	$164.80	$195.00
1990 903-12.58 7 FT. CHANNEL POST DELINEATOR, WHITE/RED						**2 EA**
Bid Price	**36.25**	**36.00**	**36.00**	**44.45**	**37.08**	**45.00**
Bid Amount	$72.50	$72.00	$72.00	$88.90	$74.16	$90.00
2000 903-12.71 PERFORATED SQUARE STEEL TUBE POST ANCHOR						**657 LF**
Bid Price	**18.20**	**18.00**	**18.00**	**23.17**	**18.54**	**23.00**
Bid Amount	$11,957.40	$11,826.00	$11,826.00	$15,222.69	$12,180.78	$15,111.00
2010 903-50.04 TYPE SHR2L-1 SIGN						**1,992 SQFT**
Bid Price	**16.20**	**16.00**	**16.00**	**19.85**	**16.48**	**19.46**
Bid Amount	$32,270.40	$31,872.00	$31,872.00	$39,541.20	$32,828.16	$38,764.32
2020 903-50.09 36 IN. OR 900 MM STOP SIGN						**4 EA**
Bid Price	**152.00**	**150.00**	**150.00**	**166.81**	**154.50**	**164.00**
Bid Amount	$608.00	$600.00	$600.00	$667.24	$618.00	$656.00
2030 903-50.11 SIGN, TYPE STR2L-3						**573 SQFT**
Bid Price	**21.20**	**21.00**	**21.00**	**17.65**	**21.63**	**17.30**
Bid Amount	$12,147.60	$12,033.00	$12,033.00	$10,113.45	$12,393.99	$9,912.90
2040 903-50.15 TYPE IV OBJECT MARKER						**2 EA**
Bid Price	**152.00**	**150.00**	**150.00**	**118.62**	**154.50**	**116.00**
Bid Amount	$304.00	$300.00	$300.00	$237.24	$309.00	$232.00
2050 903-50.17 48 IN. STOP SIGN						**10 EA**
Bid Price	**187.00**	**185.00**	**185.00**	**222.91**	**190.55**	**219.00**
Bid Amount	$1,870.00	$1,850.00	$1,850.00	$2,229.10	$1,905.50	$2,190.00
2060 903-50.71 TYPE STR4L-1 SIGN						**15 SQFT**
Bid Price	**24.20**	**24.00**	**24.00**	**28.19**	**24.72**	**28.00**
Bid Amount	$363.00	$360.00	$360.00	$422.85	$370.80	$420.00

Call No: D01	Millstone Bangert, Inc. 7th	Lehman Construction, L.L.C. 8th	H. R. Quadri Contractors, LLC 9th	Kat Excavation, Inc. 10th	Illinois Valley Paving a division of Uni 11th	Clarkson Construction Company 12th
2070 903-99.02	**MISC. 7 FT. CHANNEL POST DELINEATOR, DOUBLE ST ACKED RED/YELLOW**					**7 EA**
Bid Price	**36.25**	**36.00**	**36.00**	**44.45**	**37.08**	**44.00**
Bid Amount	$253.75	$252.00	$252.00	$311.15	$259.56	$308.00
2080 903-99.02	**MISC. BREAKAWAY ASSEMBLY**					**136 EA**
Bid Price	**111.00**	**110.00**	**110.00**	**146.75**	**113.30**	**144.00**
Bid Amount	$15,096.00	$14,960.00	$14,960.00	$19,958.00	$15,408.80	$19,584.00
2090 903-99.03	**MISC. 2.5 IN PERF STEEL SQUARE POST**					**2,904 LF**
Bid Price	**10.10**	**10.00**	**10.00**	**8.61**	**10.30**	**8.44**
Bid Amount	$29,330.40	$29,040.00	$29,040.00	$25,003.44	$29,911.20	$24,509.76
2100 903-99.07	**MISC. PSST CONCRETE FOOTINGS EMBEDDED**					**20 CUYD**
Bid Price	**980.00**	**975.00**	**975.00**	**1107.96**	**1004.25**	**1085.00**
Bid Amount	$19,600.00	$19,500.00	$19,500.00	$22,159.20	$20,085.00	$21,700.00
SECTION TOTALS	**$180,902.30**	**$179,187.00**	**$179,187.00**	**$322,354.30**	**$184,604.59**	**$196,692.28**

Section 0008: BRIDGE NO. A7923 - J5P0951B

2110 206-33.00	**CLASS 4 EXCAVATION**					**3,210 CUYD**
Bid Price	**25.50**	**15.00**	**25.00**	**16.83**	**9.30**	**12.00**
Bid Amount	$81,855.00	$48,150.00	$80,250.00	$54,024.30	$29,853.00	$38,520.00
2120 703-40.40	**CLASS B-1 CONCRETE (CULVERTS-BRIDGE)**					**1,572.70 CUYD**
Bid Price	**444.00**	**350.00**	**397.00**	**347.82**	**311.93**	**325.00**
Bid Amount	$698,278.80	$550,445.00	$624,361.90	$547,016.51	$490,572.31	$511,127.50
2130 706-10.20	**REINFORCING STEEL (CULVERTS-BRIDGE)**					**193,360 LB**
Bid Price	**0.97**	**1.00**	**1.00**	**0.98**	**1.15**	**0.95**
Bid Amount	$187,559.20	$193,360.00	$193,360.00	$189,492.80	$222,364.00	$183,692.00
SECTION TOTALS	**$967,693.00**	**$791,955.00**	**$897,971.90**	**$790,533.61**	**$742,789.31**	**$733,339.50**

Section 0009: BRIDGE NO. A7924 - J5P0951B

2140 206-33.00	**CLASS 4 EXCAVATION**					**1,170 CUYD**
Bid Price	**30.50**	**18.00**	**22.00**	**20.40**	**9.30**	**27.00**
Bid Amount	$35,685.00	$21,060.00	$25,740.00	$23,868.00	$10,881.00	$31,590.00
2150 703-40.40	**CLASS B-1 CONCRETE (CULVERTS-BRIDGE)**					**1,060.60 CUYD**
Bid Price	**432.00**	**355.00**	**300.00**	**312.12**	**391.32**	**325.00**
Bid Amount	$458,179.20	$376,513.00	$318,180.00	$331,034.47	$415,033.99	$344,695.00
2160 706-10.20	**REINFORCING STEEL (CULVERTS-BRIDGE)**					**109,500 LB**
Bid Price	**0.97**	**1.00**	**1.00**	**1.00**	**2.03**	**0.95**
Bid Amount	$106,215.00	$109,500.00	$109,500.00	$109,500.00	$222,285.00	$104,025.00
SECTION TOTALS	**$600,079.20**	**$507,073.00**	**$453,420.00**	**$464,402.47**	**$648,199.99**	**$480,310.00**

TABULATION OF BIDS

Call No: D01	Millstone Bangert, Inc. 7th	Lehman Construction, L.L.C. 8th	H. R. Quadri Contractors, LLC 9th	Kat Excavation, Inc. 10th	Illinois Valley Paving a division of Uni 11th	Clarkson Construction Company 12th
Section 0010: BRIDGE NO. A7957 - J5P0951B						
2170 206-10.00 CLASS 1 EXCAVATION						**45 CUYD**
Bid Price	**131.00**	**100.00**	**65.50**	**64.20**	**61.80**	**73.00**
Bid Amount	$5,895.00	$4,500.00	$2,947.50	$2,889.00	$2,781.00	$3,285.00
2180 206-55.00 TEMPORARY SHORING						**LUMP SUM**
Lump Sum	**$19,540.00**	**$85,000.00**	**$17,000.00**	**$15,225.00**	**$14,935.00**	**$12,500.00**
2190 503-10.10 BRIDGE APPROACH SLAB (BRIDGE)						**218 SQYD**
Bid Price	**263.00**	**225.00**	**200.00**	**220.50**	**216.30**	**228.00**
Bid Amount	$57,334.00	$49,050.00	$43,600.00	$48,069.00	$47,153.40	$49,704.00
2200 701-11.07 DRILLED SHAFTS (4 FT. 6 IN. DIA.)						**216 LF**
Bid Price	**284.00**	**600.00**	**460.00**	**577.50**	**566.50**	**536.00**
Bid Amount	$61,344.00	$129,600.00	$99,360.00	$124,740.00	$122,364.00	$115,776.00
2210 701-12.06 ROCK SOCKETS (4 FT 0 IN. DIA.)						**56 LF**
Bid Price	**1970.00**	**750.00**	**840.00**	**840.00**	**824.00**	**1025.00**
Bid Amount	$110,320.00	$42,000.00	$47,040.00	$47,040.00	$46,144.00	$57,400.00
2220 701-13.00 SUPPLEMENTARY TELEVISION CAMERA INSPECTION						**4 EA**
Bid Price	**840.00**	**950.00**	**500.00**	**257.25**	**252.35**	**700.00**
Bid Amount	$3,360.00	$3,800.00	$2,000.00	$1,029.00	$1,009.40	$2,800.00
2230 701-14.00 FOUNDATION INSPECTION HOLES						**96 LF**
Bid Price	**125.00**	**85.00**	**75.50**	**115.50**	**113.30**	**83.00**
Bid Amount	$12,000.00	$8,160.00	$7,248.00	$11,088.00	$10,876.80	$7,968.00
2240 701-16.00 SONIC LOGGING TESTING						**4 EA**
Bid Price	**2960.00**	**950.00**	**3000.00**	**4672.50**	**4583.50**	**3560.00**
Bid Amount	$11,840.00	$3,800.00	$12,000.00	$18,690.00	$18,334.00	$14,240.00
2250 702-10.12 STRUCTURAL STEEL PILES (12 IN.)						**1,112 LF**
Bid Price	**42.50**	**50.00**	**46.50**	**40.95**	**40.17**	**64.45**
Bid Amount	$47,260.00	$55,600.00	$51,708.00	$45,536.40	$44,669.04	$71,668.40
2260 702-60.00 PRE-BORE FOR PILING						**88 LF**
Bid Price	**40.00**	**65.00**	**74.00**	**105.00**	**103.00**	**71.70**
Bid Amount	$3,520.00	$5,720.00	$6,512.00	$9,240.00	$9,064.00	$6,309.60
2270 702-70.00 PILE POINT REINFORCEMENT						**8 EA**
Bid Price	**105.00**	**125.00**	**100.00**	**141.75**	**139.05**	**120.00**
Bid Amount	$840.00	$1,000.00	$800.00	$1,134.00	$1,112.40	$960.00
2280 703-20.03 CLASS B CONCRETE (SUBSTRUCTURE)						**192.80 CUYD**
Bid Price	**780.00**	**525.00**	**663.00**	**498.75**	**489.25**	**435.00**
Bid Amount	$150,384.00	$101,220.00	$127,826.40	$96,159.00	$94,327.40	$83,868.00
2290 703-42.15 SAFETY BARRIER CURB						**709 LF**
Bid Price	**89.50**	**65.00**	**46.00**	**73.50**	**72.10**	**55.35**
Bid Amount	$63,455.50	$46,085.00	$32,614.00	$52,111.50	$51,118.90	$39,243.15
2300 703-42.21 SLAB ON CONCRETE NU-GIRDER						**1,459 SQYD**
Bid Price	**280.00**	**205.00**	**243.00**	**367.50**	**360.50**	**229.00**
Bid Amount	$408,520.00	$299,095.00	$354,537.00	$536,182.50	$525,969.50	$334,111.00

TABULATION OF BIDS

Call No: D01	Millstone Bangert, Inc. 7th	Lehman Construction, L.L.C. 8th	H. R. Quadri Contractors, LLC 9th	Kat Excavation, Inc. 10th	Illinois Valley Paving a division of Uni 11th	Clarkson Construction Company 12th
2310 705-60.23	**NU 53, PRESTRESSED CONCRETE NU-GIRDER**					**1,279 LF**
Bid Price	**198.00**	**215.00**	**200.00**	**236.25**	**231.75**	**256.00**
Bid Amount	$253,242.00	$274,985.00	$255,800.00	$302,163.75	$296,408.25	$327,424.00
2320 705-99.03	**MISC. NU 53, P/S CONC. NU-GDR. (TEST GDR.)**					**80 LF**
Bid Price	**182.00**	**220.00**	**182.00**	**210.00**	**206.00**	**268.00**
Bid Amount	$14,560.00	$17,600.00	$14,560.00	$16,800.00	$16,480.00	$21,440.00
2330 706-10.60	**REINFORCING STEEL (BRIDGES)**					**44,590 LB**
Bid Price	**1.05**	**1.00**	**1.20**	**1.32**	**1.29**	**1.15**
Bid Amount	$46,819.50	$44,590.00	$53,508.00	$58,858.80	$57,521.10	$51,278.50
2340 712-33.01	**STEEL INTERMEDIATE DIAPHRAGM FOR P/S CONCRETE GIRDERS**					**18 EA**
Bid Price	**499.00**	**1250.00**	**480.00**	**750.75**	**736.45**	**1195.00**
Bid Amount	$8,982.00	$22,500.00	$8,640.00	$13,513.50	$13,256.10	$21,510.00
2350 712-36.10	**SLAB DRAIN**					**29 EA**
Bid Price	**301.00**	**255.00**	**285.00**	**330.75**	**324.45**	**300.00**
Bid Amount	$8,729.00	$7,395.00	$8,265.00	$9,591.75	$9,409.05	$8,700.00
2360 715-10.01	**VERTICAL DRAIN AT END BENTS**					**2 EA**
Bid Price	**3440.00**	**1800.00**	**905.00**	**1785.00**	**1751.00**	**1500.00**
Bid Amount	$6,880.00	$3,600.00	$1,810.00	$3,570.00	$3,502.00	$3,000.00
2370 716-10.00	**PLAIN NEOPRENE BEARING PAD**					**8 EA**
Bid Price	**206.00**	**200.00**	**315.00**	**141.75**	**139.05**	**195.00**
Bid Amount	$1,648.00	$1,600.00	$2,520.00	$1,134.00	$1,112.40	$1,560.00
2380 716-10.02	**LAMINATED NEOPRENE BEARING PAD**					**16 EA**
Bid Price	**303.00**	**342.00**	**330.00**	**210.00**	**206.00**	**300.00**
Bid Amount	$4,848.00	$5,472.00	$5,280.00	$3,360.00	$3,296.00	$4,800.00
2390 725-10.00	**CORRUGATED METAL PIPE PILE SPACERS**					**8 EA**
Bid Price	**0.01**	**500.00**	**1.00**	**404.25**	**396.55**	**2000.00**
Bid Amount	$0.08	$4,000.00	$8.00	$3,234.00	$3,172.40	$16,000.00
SECTION TOTALS	**$1,301,321.08**	**$1,216,372.00**	**$1,155,583.90**	**$1,421,359.20**	**$1,394,016.14**	**$1,255,545.65**

Section 0011: BRIDGE NO. A7960 - J5P0951B

2400 206-10.03	**CLASS 1 EXCAVATION IN ROCK**					**11 CUYD**
Bid Price	**600.00**	**225.00**	**300.00**	**735.00**	**721.00**	**195.00**
Bid Amount	$6,600.00	$2,475.00	$3,300.00	$8,085.00	$7,931.00	$2,145.00
2410 703-20.03	**CLASS B CONCRETE (SUBSTRUCTURE)**					**56.80 CUYD**
Bid Price	**530.00**	**650.00**	**570.00**	**682.50**	**669.50**	**497.00**
Bid Amount	$30,104.00	$36,920.00	$32,376.00	$38,766.00	$38,027.60	$28,229.60
2420 703-42.15	**SAFETY BARRIER CURB**					**289 LF**
Bid Price	**142.00**	**65.00**	**59.00**	**78.75**	**77.25**	**75.80**
Bid Amount	$41,038.00	$18,785.00	$17,051.00	$22,758.75	$22,325.25	$21,906.20
2430 703-42.18	**SLAB ON CONCRETE BULB-TEE GIRDER**					**464 SQYD**
Bid Price	**385.00**	**225.00**	**260.00**	**315.00**	**309.00**	**260.00**
Bid Amount	$178,640.00	$104,400.00	$120,640.00	$146,160.00	$143,376.00	$120,640.00

TABULATION OF BIDS

Call No: D01	Millstone Bangert, Inc. 7th	Lehman Construction, L.L.C. 8th	H. R. Quadri Contractors, LLC 9th	Kat Excavation, Inc. 10th	Illinois Valley Paving a division of Uni 11th	Clarkson Construction Company 12th
2440 705-60.10	**TYPE 8 (63 IN.), PRESTRESSED CONCRETE BULB TEE**					**477 LF**
Bid Price	**171.00**	**200.00**	**200.00**	**236.25**	**231.75**	**237.00**
Bid Amount	$81,567.00	$95,400.00	$95,400.00	$112,691.25	$110,544.75	$113,049.00
2450 706-10.60	**REINFORCING STEEL (BRIDGES)**					**2,020 LB**
Bid Price	**1.40**	**5.00**	**1.80**	**1.32**	**1.29**	**1.15**
Bid Amount	$2,828.00	$10,100.00	$3,636.00	$2,666.40	$2,605.80	$2,323.00
2460 707-10.00	**CONDUIT SYSTEM ON STRUCTURE**					**LUMP SUM**
Lump Sum	**$2,230.00**	**$2,233.00**	**$2,000.00**	**$3,675.00**	**$3,296.00**	**$3,200.00**
2470 712-33.01	**STEEL INTERMEDIATE DIAPHRAGM FOR P/S CONCRETE GIRDERS**					**6 EA**
Bid Price	**740.00**	**1500.00**	**710.00**	**997.50**	**978.50**	**1554.00**
Bid Amount	$4,440.00	$9,000.00	$4,260.00	$5,985.00	$5,871.00	$9,324.00
2480 715-10.01	**VERTICAL DRAIN AT END BENTS**					**2 EA**
Bid Price	**2640.00**	**1800.00**	**700.00**	**1680.00**	**1648.00**	**1500.00**
Bid Amount	$5,280.00	$3,600.00	$1,400.00	$3,360.00	$3,296.00	$3,000.00
2490 716-10.03	**LAMINATED NEOPRENE BEARING PAD (TAPERED)**					**8 EA**
Bid Price	**301.00**	**195.00**	**240.00**	**246.75**	**242.05**	**300.00**
Bid Amount	$2,408.00	$1,560.00	$1,920.00	$1,974.00	$1,936.40	$2,400.00
SECTION TOTALS	**$355,135.00**	**$284,473.00**	**$281,983.00**	**$346,121.40**	**$339,209.80**	**$306,216.80**

Section 0012: BRIDGE NO. A7981 - J5P0951B

2500 206-33.00	**CLASS 4 EXCAVATION**					**1,730 CUYD**
Bid Price	**28.75**	**18.00**	**25.00**	**21.93**	**9.30**	**21.00**
Bid Amount	$49,737.50	$31,140.00	$43,250.00	$37,938.90	$16,089.00	$36,330.00
2510 206-34.00	**CLASS 4 EXCAVATION IN ROCK**					**62 CUYD**
Bid Price	**262.00**	**200.00**	**550.00**	**612.00**	**70.04**	**56.00**
Bid Amount	$16,244.00	$12,400.00	$34,100.00	$37,944.00	$4,342.48	$3,472.00
2520 703-40.40	**CLASS B-1 CONCRETE (CULVERTS-BRIDGE)**					**1,734.80 CUYD**
Bid Price	**500.00**	**350.00**	**377.00**	**377.40**	**294.67**	**350.00**
Bid Amount	$867,400.00	$607,180.00	$654,019.60	$654,713.52	$511,193.52	$607,180.00
2530 706-10.20	**REINFORCING STEEL (CULVERTS-BRIDGE)**					**255,010 LB**
Bid Price	**1.00**	**0.95**	**1.00**	**0.97**	**1.07**	**0.95**
Bid Amount	$255,010.00	$242,259.50	$255,010.00	$247,359.70	$272,860.70	$242,259.50
SECTION TOTALS	**$1,188,391.50**	**$892,979.50**	**$986,379.60**	**$977,956.12**	**$804,485.70**	**$889,241.50**

Contract Totals - 120824-D01

	$28,774,465.75	**$29,499,451.71**	**$30,690,454.66**	**$30,934,940.39**	**$31,257,886.78**	**$32,239,802.68**

CERTIFIED BY DESIGN STATE DESIGN ENGINEER

8/24/2012

Missouri Department of Transportation

Vendor Ranking

Call Order: D02
Contract ID: 120824-D02
Counties: PULASKI
Letting Date: August 24, 2012 11:00 a.m.
District(s): Central
Contract Time: DT - 12/1/2012

Contract Description: J5M0255 - ROUTE I-44 - PULASKI COUNTY
Project(s):

Rank	Vendor ID/Name		Total Bid	Percent Of Low Bid
1	0011146	APAC-Missouri, Inc.	$76,664.70	100.00%
2	0011540	Lehman Construction, L.L.C.	$82,013.90	106.98%
3	0012356	Lamke Trenching & Excavating, Inc.	$91,129.17	118.87%
4	0010307	N. B. West Contracting Company	$117,638.81	153.45%
5	0010528	Chester Bross Const. Co./C.B. Equipment Inc.	$127,381.50	166.15%

CONTRACT ID: 120824-D02
LETTING DATE: 08/24/12

TABULATION OF BIDS

Call No: D02	APAC-Missouri, Inc. Low Bid	Lehman Construction, L.L.C. 2nd Low	Lamke Trenching & Excavating, Inc. 3rd Low	N. B. West Contracting Company 4th Low	Chester Bross Const. Co./CB Equip. Inc. 5th Low	

Project J5M0255: Pavement replacement with optional pavement

Section 0001: ROADWAY ITEMS - J5M0255

0010	**202-20.10**	**REMOVAL OF IMPROVEMENTS**				**LUMP SUM**
Lump Sum	**$5,000.00**	**$3,000.00**	**$6,832.40**	**$15,500.00**	**$12,000.00**	
0020	**203-50.00**	**UNCLASSIFIED EXCAVATION**				**78 CUYD**
Bid Price	**16.00**	**30.00**	**20.00**	**35.50**	**50.00**	
Bid Amount	$1,248.00	$2,340.00	$1,560.00	$2,769.00	$3,900.00	
0030	**211-99.05**	**MISC. GEOSYNTHETIC REINFORCEMENT GRID**				**233.30 SQYD**
Bid Price	**4.00**	**5.00**	**8.00**	**11.25**	**5.15**	
Bid Amount	$933.20	$1,166.50	$1,866.40	$2,624.63	$1,201.50	
0040	**303-06.00**	**FURNISHING ROCK BASE MATERIAL**				**233 SQYD**
Bid Price	**16.00**	**15.00**	**9.50**	**12.00**	**9.15**	
Bid Amount	$3,728.00	$3,495.00	$2,213.50	$2,796.00	$2,131.95	
0050	**303-99.05**	**MISC. ROCK BASE PLACING ROCK BASE (12 IN. THICK)**				**233.30 SQYD**
Bid Price	**8.00**	**8.00**	**7.90**	**16.75**	**11.00**	
Bid Amount	$1,866.40	$1,866.40	$1,843.07	$3,907.78	$2,566.30	
0060	**403-99.05**	**MISC. OPTIONAL PAVEMENT (13 IN. SP OR 10 IN. P CCP)**				**235.30 SQYD**
Bid Price	**92.00**	**85.00**	**128.00**	**82.15**	**96.00**	
Bid Amount	$21,647.60	$20,000.50	$30,118.40	$19,329.90	$22,588.80	
0070	**605-30.30A**	**PIPE AGGREGATE PAVEMENT EDGE DRAIN**				**150 LF**
Bid Price	**10.00**	**20.00**	**15.00**	**19.00**	**20.00**	
Bid Amount	$1,500.00	$3,000.00	$2,250.00	$2,850.00	$3,000.00	
0075	**605-40.20**	**OUTLET PIPES AND SPLASH PADS**				**1 EA**
Bid Price	**800.00**	**1550.00**	**1200.00**	**1350.00**	**509.00**	
Bid Amount	$800.00	$1,550.00	$1,200.00	$1,350.00	$509.00	
0080	**612-20.19**	**IMPACT ATTENUATOR (19 SAND BARRELS)**				**1 EA**
Bid Price	**850.00**	**850.00**	**4400.00**	**5000.00**	**3675.00**	
Bid Amount	$850.00	$850.00	$4,400.00	$5,000.00	$3,675.00	
0090	**612-20.20**	**REPLACEMENT SAND BARREL**				**8 EA**
Bid Price	**25.00**	**25.00**	**330.00**	**325.00**	**105.00**	
Bid Amount	$200.00	$200.00	$2,640.00	$2,600.00	$840.00	
0100	**616-10.05**	**CONSTRUCTION SIGNS**				**318 SQFT**
Bid Price	**7.50**	**7.50**	**8.80**	**7.50**	**9.15**	
Bid Amount	$2,385.00	$2,385.00	$2,798.40	$2,385.00	$2,909.70	
0110	**616-10.08**	**ADVANCED WARNING RAIL SYSTEM**				**2 EA**
Bid Price	**80.00**	**80.00**	**55.00**	**115.00**	**102.00**	
Bid Amount	$160.00	$160.00	$110.00	$230.00	$204.00	
0120	**616-10.09**	**FLAG ASSEMBLY**				**8 EA**
Bid Price	**20.00**	**20.00**	**16.50**	**18.00**	**15.25**	
Bid Amount	$160.00	$160.00	$132.00	$144.00	$122.00	

TABULATION OF BIDS

Call No: D02	APAC-Missouri, Inc. Low Bid	Lehman Construction, L.L.C. 2nd Low	Lamke Trenching & Excavating, Inc. 3rd Low	N. B. West Contracting Company 4th Low	Chester Bross Const. Co./CB Equip. Inc. 5th Low	
0130	**616-10.25**	**CHANNELIZER (TRIM LINE)**				**25 EA**
Bid Price	**5.00**	**5.00**	**11.00**	**21.00**	**15.25**	
Bid Amount	$125.00	$125.00	$275.00	$525.00	$381.25	
0140	**616-10.33**	**DIRECTIONAL INDICATOR BARRICADE**				**15 EA**
Bid Price	**15.00**	**15.00**	**16.50**	**29.00**	**76.50**	
Bid Amount	$225.00	$225.00	$247.50	$435.00	$1,147.50	
0150	**616-10.40**	**FLASHING ARROW PANEL**				**1 EA**
Bid Price	**50.00**	**50.00**	**220.00**	**500.00**	**765.00**	
Bid Amount	$50.00	$50.00	$220.00	$500.00	$765.00	
0160	**616-10.52**	**WARNING LIGHT, TYPE B**				**8 EA**
Bid Price	**15.00**	**15.00**	**49.50**	**45.00**	**100.00**	
Bid Amount	$120.00	$120.00	$396.00	$360.00	$800.00	
0170	**616-10.98**	**CHANGEABLE MESSAGE SIGN, CONTRACTOR FURNISHED, CONTRACTOR RE TAINED**				**1 EA**
Bid Price	**150.00**	**150.00**	**440.00**	**2200.00**	**2550.00**	
Bid Amount	$150.00	$150.00	$440.00	$2,200.00	$2,550.00	
0180	**616-20.10**	**WORK ZONE LIGHTING**				**LUMP SUM**
Lump Sum	**$1,000.00**	**$2,400.00**	**$1,500.00**	**$2,000.00**	**$5,750.00**	
0190	**616-99.02**	**MISC. SEQUENTIAL FLASHING WARNING LIGHTS**				**15 EA**
Bid Price	**15.00**	**15.00**	**137.50**	**75.00**	**144.00**	
Bid Amount	$225.00	$225.00	$2,062.50	$1,125.00	$2,160.00	
0200	**617-60.00B**	**TEMPORARY TRAFFIC BARRIER, COMMISSION FURNISHED / RETAINED**				**376 LF**
Bid Price	**20.00**	**14.00**	**26.00**	**22.25**	**21.00**	
Bid Amount	$7,520.00	$5,264.00	$9,776.00	$8,366.00	$7,896.00	
0210	**618-10.00**	**MOBILIZATION**				**LUMP SUM**
Lump Sum	**$14,000.00**	**$20,000.00**	**$8,100.00**	**$31,000.00**	**$35,700.00**	
0220	**620-60.00B**	**4 IN. WHITE ACRYLIC WATERBORNE PAVEMENT MARKING PAINT**				**1,970 LF**
Bid Price	**1.00**	**1.00**	**1.20**	**1.10**	**1.05**	
Bid Amount	$1,970.00	$1,970.00	$2,364.00	$2,167.00	$2,068.50	
0230	**620-70.01**	**PAVEMENT MARKING REMOVAL**				**1,970 LF**
Bid Price	**0.95**	**0.95**	**1.10**	**1.00**	**1.00**	
Bid Amount	$1,871.50	$1,871.50	$2,167.00	$1,970.00	$1,970.00	
0240	**620-99.03**	**MISC. 6 IN. WHITE WET REFLECTIVE EPOXY PAVEMEN T MARKING PAINT**				**190 LF**
Bid Price	**35.00**	**35.00**	**14.30**	**13.00**	**36.75**	
Bid Amount	$6,650.00	$6,650.00	$2,717.00	$2,470.00	$6,982.50	
0250	**622-99.03**	**MISC. GROOVING FOR PAVEMENT MARKING**				**40 LF**
Bid Price	**35.00**	**35.00**	**45.00**	**41.00**	**36.75**	
Bid Amount	$1,400.00	$1,400.00	$1,800.00	$1,640.00	$1,470.00	
0260	**806-10.16**	**SEDIMENT REMOVAL**				**6 CUYD**
Bid Price	**30.00**	**40.00**	**25.00**	**22.00**	**20.00**	
Bid Amount	$180.00	$240.00	$150.00	$132.00	$120.00	

TABULATION OF BIDS

Call No: D02	APAC-Missouri, Inc. Low Bid	Lehman Construction, L.L.C. 2nd Low	Lamke Trenching & Excavating, Inc. 3rd Low	N. B. West Contracting Company 4th Low	Chester Bross Const. Co./CB Equip. Inc. 5th Low	
0270 806-10.19 SILT FENCE						**150 LF**
Bid Price	**2.00**	**3.00**	**3.00**	**3.75**	**6.35**	
Bid Amount	$300.00	$450.00	$450.00	$562.50	$952.50	
0280 806-10.22 TYPE II DITCH CHECK						**4 EA**
Bid Price	**100.00**	**175.00**	**125.00**	**175.00**	**255.00**	
Bid Amount	$400.00	$700.00	$500.00	$700.00	$1,020.00	
SECTION TOTALS	**$76,664.70**	**$82,013.90**	**$91,129.17**	**$117,638.81**	**$127,381.50**	

Contract Totals - 120824-D02

$76,664.70	**$82,013.90**	**$91,129.17**	**$117,638.81**	**$127,381.50**	

CERTIFIED BY DESIGN STATE DESIGN ENGINEER

8/24/2012

Missouri Department of Transportation

Vendor Ranking

Call Order: D03
Contract ID: 120824-D03
Counties: COLE
Letting Date: August 24, 2012 11:00 a.m.
District(s): Central
Contract Time: DT - 11/15/2012

Contract Description: J5P0965,J5P0966,J5M0257 - ROUTE 50 - COLE COUNTY
Project(s): FAF-50-3(89), FAF-50-3(84)

Rank	Vendor ID/Name		Total Bid	Percent Of Low Bid
1	0011146	APAC-Missouri, Inc.	$1,055,099.53	100.00%
2	0010307	N. B. West Contracting Company	$1,099,500.00	104.21%
3	0010528	Chester Bross Const. Co./C.B. Equipment Inc.	$1,132,073.04	107.30%
4	0011270	Pace Construction Company, LLC	$1,170,000.00	110.89%

CONTRACT ID: 120824-D03
LETTING DATE: 08/24/12

TABULATION OF BIDS

Call No: D03	APAC-Missouri, Inc. Low Bid	N. B. West Contracting Company 2nd Low	Chester Bross Const. Co./CB Equip. Inc. 3rd Low	Pace Construction Company, LLC 4th Low		

Project J5P0965: Resurfacing the westbound lanes with Type C UBAWS

Section 0001: ROADWAY ITEMS - J5P0965

0005	**202-20.10**	**REMOVAL OF IMPROVEMENTS**					**LUMP SUM**
Lump Sum	**$550.00**	**$1,200.00**	**$577.50**	**$5,000.00**			
0010	**413-32.00**	**ULTRATHIN BONDED WEARING SURFACE, TYPE C**					**82,624 SQYD**
Bid Price	**4.12**	**4.05**	**4.19**	**4.30**			
Bid Amount	$340,410.88	$334,627.20	$346,194.56	$355,283.20			
0020	**606-10.10**	**GUARDRAIL TYPE A**					**550 LF**
Bid Price	**17.00**	**18.00**	**17.85**	**18.00**			
Bid Amount	$9,350.00	$9,900.00	$9,817.50	$9,900.00			
0030	**606-30.15**	**TYPE A CRASHWORTHY END TERMINAL**					**6 EA**
Bid Price	**1900.00**	**2000.00**	**2000.00**	**2000.00**			
Bid Amount	$11,400.00	$12,000.00	$12,000.00	$12,000.00			
0040	**612-30.00A**	**TRUCK OR TRAILER MOUNTED ATTENUATOR (TMA)**					**2 EA**
Bid Price	**623.36**	**1500.00**	**1000.00**	**1700.00**			
Bid Amount	$1,246.72	$3,000.00	$2,000.00	$3,400.00			
0050	**616-10.05**	**CONSTRUCTION SIGNS**					**477 SQFT**
Bid Price	**5.00**	**7.50**	**5.25**	**7.50**			
Bid Amount	$2,385.00	$3,577.50	$2,504.25	$3,577.50			
0060	**616-10.08**	**ADVANCED WARNING RAIL SYSTEM**					**3 EA**
Bid Price	**75.00**	**115.00**	**78.75**	**115.00**			
Bid Amount	$225.00	$345.00	$236.25	$345.00			
0070	**616-10.09**	**FLAG ASSEMBLY**					**14 EA**
Bid Price	**25.00**	**17.00**	**26.25**	**17.00**			
Bid Amount	$350.00	$238.00	$367.50	$238.00			
0080	**616-10.24**	**CHANNELIZER (TRIM LINE) WITH LIGHT**					**128 EA**
Bid Price	**18.00**	**31.00**	**19.00**	**31.00**			
Bid Amount	$2,304.00	$3,968.00	$2,432.00	$3,968.00			
0090	**616-10.25**	**CHANNELIZER (TRIM LINE)**					**70 EA**
Bid Price	**15.00**	**21.00**	**15.75**	**21.00**			
Bid Amount	$1,050.00	$1,470.00	$1,102.50	$1,470.00			
0100	**616-10.40**	**FLASHING ARROW PANEL**					**2 EA**
Bid Price	**350.00**	**200.00**	**367.50**	**200.00**			
Bid Amount	$700.00	$400.00	$735.00	$400.00			
0110	**616-10.52**	**WARNING LIGHT, TYPE B**					**14 EA**
Bid Price	**50.00**	**34.00**	**52.50**	**34.00**			
Bid Amount	$700.00	$476.00	$735.00	$476.00			
0120	**616-10.98**	**CHANGEABLE MESSAGE SIGN, CONTRACTOR FURNISHED, CONTRACTOR RE TAINED**					**2 EA**
Bid Price	**2000.00**	**1000.00**	**2100.00**	**1000.00**			
Bid Amount	$4,000.00	$2,000.00	$4,200.00	$2,000.00			

TABULATION OF BIDS

Call No: D03	APAC-Missouri, Inc. Low Bid	N. B. West Contracting Company 2nd Low	Chester Bross Const. Co./CB Equip. Inc. 3rd Low	Pace Construction Company, LLC 4th Low		
0130	**616-20.10**	**WORK ZONE LIGHTING**				**LUMP SUM**
Lump Sum	**$542.72**	**$2,500.00**	**$2,500.00**	**$500.00**		
0140	**616-99.02**	**MISC. SEQUENTIAL FLASHING WARNING LIGHTS**				**70 EA**
Bid Price	**75.00**	**25.00**	**78.75**	**25.00**		
Bid Amount	$5,250.00	$1,750.00	$5,512.50	$1,750.00		
0150	**618-10.00**	**MOBILIZATION**				**LUMP SUM**
Lump Sum	**$12,255.31**	**$25,000.00**	**$20,000.00**	**$25,000.00**		
0160	**620-59.22**	**6 IN. WHITE WET REFLECTIVE HIGH BUILD ACRYLIC WATERBORNE PAV EMENT MARKING PAINT**				**4,710 LF**
Bid Price	**0.35**	**0.75**	**0.37**	**0.75**		
Bid Amount	$1,648.50	$3,532.50	$1,742.70	$3,532.50		
0170	**620-61.06**	**ACRYLIC WATERBORNE PAVEMENT MARKING PAINT, 6 IN., WHITE**				**18,359 LF**
Bid Price	**0.15**	**0.16**	**0.16**	**0.16**		
Bid Amount	$2,753.85	$2,937.44	$2,937.44	$2,937.44		
0180	**620-61.19**	**ACRYLIC WATERBORNE PAVEMENT MARKING PAINT, 6 IN., YELLOW**				**18,200 LF**
Bid Price	**0.15**	**0.16**	**0.16**	**0.16**		
Bid Amount	$2,730.00	$2,912.00	$2,912.00	$2,912.00		
0190	**620-61.22**	**ACRYLIC WATERBORNE PAVEMENT MARKING PAINT, 12 IN., WHITE**				**1,650 LF**
Bid Price	**0.25**	**0.75**	**0.26**	**0.75**		
Bid Amount	$412.50	$1,237.50	$429.00	$1,237.50		
0200	**620-99.03**	**MISC. 7 IN. GROOVE FOR PAVEMENT MARKING (ASPHA LT)**				**4,640 LF**
Bid Price	**0.40**	**0.70**	**0.42**	**0.70**		
Bid Amount	$1,856.00	$3,248.00	$1,948.80	$3,248.00		
0210	**622-40.10**	**MODIFIED COLDMILLING (DEPTH TRANSITIONS)**				**1,167 SQYD**
Bid Price	**7.04**	**10.00**	**6.30**	**8.75**		
Bid Amount	$8,215.68	$11,670.00	$7,352.10	$10,211.25		
0220	**626-10.00A**	**BITUMINOUS SHOULDER RUMBLE STRIP**				**353.80 STA**
Bid Price	**6.75**	**19.00**	**12.40**	**16.75**		
Bid Amount	$2,388.15	$6,722.20	$4,387.12	$5,926.15		
SECTION TOTALS	**$412,724.31**	**$434,711.34**	**$432,623.72**	**$455,312.54**		

Project Totals - J5P0965

$412,724.31	**$434,711.34**	**$432,623.72**	**$455,312.54**		

Project J5P0966: Resurfacing the eastbound lanes with Type C UBAWS

TABULATION OF BIDS

Call No: D03	APAC-Missouri, Inc. Low Bid	N. B. West Contracting Company 2nd Low	Chester Bross Const. Co./CB Equip. Inc. 3rd Low	Pace Construction Company, LLC 4th Low		

Section 0002: ROADWAY ITEMS - J5P0966

0225	**202-20.10**	**REMOVAL OF IMPROVEMENTS**				**LUMP SUM**
Lump Sum	**$550.00**	**$600.00**	**$577.50**	**$3,373.55**		
0230	**413-32.00**	**ULTRATHIN BONDED WEARING SURFACE, TYPE C**				**134,671 SQYD**
Bid Price	**4.01**	**4.05**	**4.17**	**4.30**		
Bid Amount	$540,030.71	$545,417.55	$561,578.07	$579,085.30		
0240	**606-10.10**	**GUARDRAIL TYPE A**				**550 LF**
Bid Price	**17.00**	**18.00**	**17.85**	**18.00**		
Bid Amount	$9,350.00	$9,900.00	$9,817.50	$9,900.00		
0250	**606-30.15**	**TYPE A CRASHWORTHY END TERMINAL**				**2 EA**
Bid Price	**1900.00**	**2000.00**	**2000.00**	**2000.00**		
Bid Amount	$3,800.00	$4,000.00	$4,000.00	$4,000.00		
0260	**612-30.00A**	**TRUCK OR TRAILER MOUNTED ATTENUATOR (TMA)**				**2 EA**
Bid Price	**623.36**	**1500.00**	**1000.00**	**1700.00**		
Bid Amount	$1,246.72	$3,000.00	$2,000.00	$3,400.00		
0270	**616-10.05**	**CONSTRUCTION SIGNS**				**477 SQFT**
Bid Price	**5.00**	**7.50**	**5.25**	**7.50**		
Bid Amount	$2,385.00	$3,577.50	$2,504.25	$3,577.50		
0280	**616-10.08**	**ADVANCED WARNING RAIL SYSTEM**				**3 EA**
Bid Price	**75.00**	**115.00**	**78.75**	**115.00**		
Bid Amount	$225.00	$345.00	$236.25	$345.00		
0290	**616-10.09**	**FLAG ASSEMBLY**				**14 EA**
Bid Price	**25.00**	**17.00**	**26.25**	**17.00**		
Bid Amount	$350.00	$238.00	$367.50	$238.00		
0300	**616-10.24**	**CHANNELIZER (TRIM LINE) WITH LIGHT**				**128 EA**
Bid Price	**18.00**	**31.00**	**19.00**	**31.00**		
Bid Amount	$2,304.00	$3,968.00	$2,432.00	$3,968.00		
0310	**616-10.25**	**CHANNELIZER (TRIM LINE)**				**70 EA**
Bid Price	**15.00**	**21.00**	**15.75**	**21.00**		
Bid Amount	$1,050.00	$1,470.00	$1,102.50	$1,470.00		
0320	**616-10.40**	**FLASHING ARROW PANEL**				**2 EA**
Bid Price	**350.00**	**200.00**	**367.50**	**200.00**		
Bid Amount	$700.00	$400.00	$735.00	$400.00		
0330	**616-10.52**	**WARNING LIGHT, TYPE B**				**14 EA**
Bid Price	**50.00**	**34.00**	**52.50**	**34.00**		
Bid Amount	$700.00	$476.00	$735.00	$476.00		
0340	**616-10.98**	**CHANGEABLE MESSAGE SIGN, CONTRACTOR FURNISHED, CONTRACTOR RE TAINED**				**2 EA**
Bid Price	**2000.00**	**1000.00**	**2100.00**	**1000.00**		
Bid Amount	$4,000.00	$2,000.00	$4,200.00	$2,000.00		
0350	**616-20.10**	**WORK ZONE LIGHTING**				**LUMP SUM**
Lump Sum	**$542.72**	**$1,500.00**	**$2,500.00**	**$500.00**		

Call No: D03	APAC-Missouri, Inc. Low Bid	N. B. West Contracting Company 2nd Low	Chester Bross Const. Co./CB Equip. Inc. 3rd Low	Pace Construction Company, LLC 4th Low		
0360	**616-99.02**	**MISC. SEQUENTIAL FLASHING WARNING LIGHTS**				**70 EA**
Bid Price	**75.00**	**25.00**	**78.75**	**25.00**		
Bid Amount	$5,250.00	$1,750.00	$5,512.50	$1,750.00		
0370	**618-10.00**	**MOBILIZATION**				**LUMP SUM**
Lump Sum	**$15,898.30**	**$21,000.00**	**$45,000.00**	**$30,000.00**		
0380	**620-59.22**	**6 IN. WHITE WET REFLECTIVE HIGH BUILD ACRYLIC WATERBORNE PAV EMENT MARKING PAINT**				**7,842 LF**
Bid Price	**0.35**	**0.60**	**0.37**	**0.60**		
Bid Amount	$2,744.70	$4,705.20	$2,901.54	$4,705.20		
0390	**620-61.06**	**ACRYLIC WATERBORNE PAVEMENT MARKING PAINT, 6 IN., WHITE**				**30,070 LF**
Bid Price	**0.15**	**0.16**	**0.16**	**0.16**		
Bid Amount	$4,510.50	$4,811.20	$4,811.20	$4,811.20		
0400	**620-61.19**	**ACRYLIC WATERBORNE PAVEMENT MARKING PAINT, 6 IN., YELLOW**				**30,070 LF**
Bid Price	**0.15**	**0.16**	**0.16**	**0.16**		
Bid Amount	$4,510.50	$4,811.20	$4,811.20	$4,811.20		
0410	**620-61.22**	**ACRYLIC WATERBORNE PAVEMENT MARKING PAINT, 12 IN., WHITE**				**2,985 LF**
Bid Price	**0.20**	**0.60**	**0.21**	**0.60**		
Bid Amount	$597.00	$1,791.00	$626.85	$1,791.00		
0420	**620-99.03**	**MISC. 7 IN. GROOVE FOR PAVEMENT MARKING (ASPHA LT)**				**7,842 LF**
Bid Price	**0.40**	**0.69**	**0.42**	**0.69**		
Bid Amount	$3,136.80	$5,410.98	$3,293.64	$5,410.98		
0430	**622-40.10**	**MODIFIED COLDMILLING (DEPTH TRANSITIONS)**				**767 SQYD**
Bid Price	**8.87**	**10.00**	**8.00**	**8.75**		
Bid Amount	$6,803.29	$7,670.00	$6,136.00	$6,711.25		
0440	**626-10.00A**	**BITUMINOUS SHOULDER RUMBLE STRIP**				**577.30 STA**
Bid Price	**6.75**	**19.00**	**12.40**	**16.75**		
Bid Amount	$3,896.78	$10,968.70	$7,158.52	$9,669.78		
SECTION TOTALS	**$614,582.02**	**$639,810.33**	**$673,037.02**	**$682,393.96**		

Project Totals - J5P0966

$614,582.02	**$639,810.33**	**$673,037.02**	**$682,393.96**		

Project J5M0257: Resurfacing with Type C UBAWS

Section 0003: ROADWAY ITEMS - J5M0257

0450	**413-32.00**	**ULTRATHIN BONDED WEARING SURFACE, TYPE C**				**1,163 SQYD**
Bid Price	**10.34**	**4.05**	**9.35**	**12.50**		
Bid Amount	$12,025.42	$4,710.15	$10,874.05	$14,537.50		

TABULATION OF BIDS

Call No: D03	APAC-Missouri, Inc. Low Bid	N. B. West Contracting Company 2nd Low	Chester Bross Const. Co./CB Equip. Inc. 3rd Low	Pace Construction Company, LLC 4th Low		
0460	**612-30.00A**	**TRUCK OR TRAILER MOUNTED ATTENUATOR (TMA)**				**1 EA**
Bid Price	**831.13**	**500.00**	**500.00**	**1.00**		
Bid Amount	$831.13	$500.00	$500.00	$1.00		
0470	**616-10.05**	**CONSTRUCTION SIGNS**				**178 SQFT**
Bid Price	**5.00**	**14.00**	**5.25**	**14.00**		
Bid Amount	$890.00	$2,492.00	$934.50	$2,492.00		
0480	**616-10.09**	**FLAG ASSEMBLY**				**10 EA**
Bid Price	**25.00**	**24.00**	**26.25**	**24.00**		
Bid Amount	$250.00	$240.00	$262.50	$240.00		
0490	**616-10.24**	**CHANNELIZER (TRIM LINE) WITH LIGHT**				**17 EA**
Bid Price	**18.00**	**54.00**	**19.00**	**54.00**		
Bid Amount	$306.00	$918.00	$323.00	$918.00		
0500	**616-10.25**	**CHANNELIZER (TRIM LINE)**				**5 EA**
Bid Price	**15.00**	**45.00**	**15.75**	**45.00**		
Bid Amount	$75.00	$225.00	$78.75	$225.00		
0510	**616-10.40**	**FLASHING ARROW PANEL**				**1 EA**
Bid Price	**350.00**	**500.00**	**367.50**	**500.00**		
Bid Amount	$350.00	$500.00	$367.50	$500.00		
0520	**616-10.52**	**WARNING LIGHT, TYPE B**				**10 EA**
Bid Price	**50.00**	**49.00**	**52.50**	**49.00**		
Bid Amount	$500.00	$490.00	$525.00	$490.00		
0530	**616-20.10**	**WORK ZONE LIGHTING**				**LUMP SUM**
Lump Sum	**$542.72**	**$500.00**	**$1,000.00**	**$500.00**		
0540	**616-99.02**	**MISC. SEQUENTIAL FLASHING WARNING LIGHTS**				**5 EA**
Bid Price	**75.00**	**54.00**	**78.75**	**54.00**		
Bid Amount	$375.00	$270.00	$393.75	$270.00		
0550	**618-10.00**	**MOBILIZATION**				**LUMP SUM**
Lump Sum	**$4,937.65**	**$9,353.18**	**$6,000.00**	**$7,500.00**		
0560	**620-51.20**	**TYPE 2 PREFORMED MARKING TAPE (GROOVED), 24 IN., WHITE**				**24 LF**
Bid Price	**30.00**	**55.00**	**31.50**	**55.00**		
Bid Amount	$720.00	$1,320.00	$756.00	$1,320.00		
0570	**620-59.21**	**4 IN. YELLOW WET REFLECTIVE HIGH BUILD ACRYLIC WATERBORNE PA VEMENT MARKING PAINT**				**436 LF**
Bid Price	**5.00**	**4.00**	**5.25**	**4.00**		
Bid Amount	$2,180.00	$1,744.00	$2,289.00	$1,744.00		
0580	**620-99.03**	**MISC. 4 IN. WHITE WET REFLECTIVE HIGH BUILD AC RYLIC WATERBORNE PAVEMENT MARKING PAINT**				**109 LF**
Bid Price	**5.00**	**4.00**	**5.25**	**4.00**		
Bid Amount	$545.00	$436.00	$572.25	$436.00		
0590	**622-40.10**	**MODIFIED COLDMILLING (DEPTH TRANSITIONS)**				**128 SQYD**
Bid Price	**25.51**	**10.00**	**12.00**	**8.75**		
Bid Amount	$3,265.28	$1,280.00	$1,536.00	$1,120.00		
SECTION TOTALS	**$27,793.20**	**$24,978.33**	**$26,412.30**	**$32,293.50**		

TABULATION OF BIDS

Call No: D03	APAC-Missouri, Inc. Low Bid	N. B. West Contracting Company 2nd Low	Chester Bross Const. Co./CB Equip. Inc. 3rd Low	Pace Construction Company, LLC 4th Low		
Project Totals - J5M0257						
	$27,793.20	$24,978.33	$26,412.30	$32,293.50		
Contract Totals - 120824-D03						
	$1,055,099.53	$1,099,500.00	$1,132,073.04	$1,170,000.00		

CERTIFIED BY DESIGN STATE DESIGN ENGINEER

8/24/2012

Missouri Department of Transportation

Vendor Ranking

Call Order: F01 **Contract ID:** 120824-F01 **Counties:** JEFFERSON, ST LOUIS

Letting Date: August 24, 2012 11:00 a.m. **District(s):** St. Louis

Contract Time: DT - 12/1/2012

Contract Description: J6P2373F - ROUTE 30 - JEFFERSON, ST LOUIS COUNTIES **Project(s):**

Rank	Vendor ID/Name		Total Bid	Percent Of Low Bid
1	0010144	Collins & Hermann Inc.	$303,030.30	100.00%
2	0010558	D & S Fencing Company	$310,887.20	102.59%

CONTRACT ID: 120824-F01
LETTING DATE: 08/24/12

TABULATION OF BIDS

Call No: F01	Collins & Hermann Inc. Low Bid	D & S Fencing Company 2nd Low

Project J6P2373F: Install guardrail, tree trimming and signing

Section 0001: ROADWAY ITEMS - J6P2373F

0010	**201-30.00**	**CLEARING AND GRUBBING**				**2 ACRE**
Bid Price	**14015.69**	**20000.00**				
Bid Amount	$28,031.38	$40,000.00				
0020	**202-20.10**	**REMOVAL OF IMPROVEMENTS**				**LUMP SUM**
Lump Sum	**$24,388.76**	**$45,000.00**				
0030	**606-10.10**	**GUARDRAIL TYPE A**				**2,625 LF**
Bid Price	**17.31**	**21.00**				
Bid Amount	$45,438.75	$55,125.00				
0040	**606-10.54**	**GUARDRAIL TYPE E, 6 FT POST, 6 FT.-3 IN. SPACING**				**38 LF**
Bid Price	**41.42**	**36.00**				
Bid Amount	$1,573.96	$1,368.00				
0050	**606-23.00A**	**TRANSITION SECTION, 6.5 FT. POSTS**				**3 EA**
Bid Price	**2176.85**	**400.00**				
Bid Amount	$6,530.55	$1,200.00				
0060	**606-30.15**	**TYPE A CRASHWORTHY END TERMINAL**				**12 EA**
Bid Price	**4091.67**	**2000.00**				
Bid Amount	$49,100.04	$24,000.00				
0070	**606-66.10**	**END ANCHOR**				**5 EA**
Bid Price	**1236.57**	**1200.00**				
Bid Amount	$6,182.85	$6,000.00				
0080	**606-99.03**	**MISC. RAISE EXISTING GUARDRAIL**				**5,300 LF**
Bid Price	**4.03**	**5.00**				
Bid Amount	$21,359.00	$26,500.00				
0090	**606-99.03**	**MISC. RELOCATE GUARDRAIL**				**458 LF**
Bid Price	**15.44**	**10.00**				
Bid Amount	$7,071.52	$4,580.00				
0100	**616-10.05**	**CONSTRUCTION SIGNS**				**312 SQFT**
Bid Price	**7.07**	**7.00**				
Bid Amount	$2,205.84	$2,184.00				
0110	**616-10.08**	**ADVANCED WARNING RAIL SYSTEM**				**2 EA**
Bid Price	**50.51**	**50.00**				
Bid Amount	$101.02	$100.00				
0120	**616-10.09**	**FLAG ASSEMBLY**				**10 EA**
Bid Price	**20.20**	**20.00**				
Bid Amount	$202.00	$200.00				
0130	**616-10.25**	**CHANNELIZER (TRIM LINE)**				**40 EA**
Bid Price	**25.25**	**25.00**				
Bid Amount	$1,010.00	$1,000.00				

TABULATION OF BIDS

Call No: F01	Collins & Hermann Inc. Low Bid	D & S Fencing Company 2nd Low				
0140	**616-10.33**	**DIRECTIONAL INDICATOR BARRICADE**				**14 EA**
Bid Price	**35.35**	**35.00**				
Bid Amount	$494.90	$490.00				
0150	**616-10.40**	**FLASHING ARROW PANEL**				**1 EA**
Bid Price	**505.07**	**500.00**				
Bid Amount	$505.07	$500.00				
0160	**616-10.98**	**CHANGEABLE MESSAGE SIGN, CONTRACTOR FURNISHED, CONTRACTOR RE TAINED**				**2 EA**
Bid Price	**1010.14**	**1000.00**				
Bid Amount	$2,020.28	$2,000.00				
0170	**618-10.00**	**MOBILIZATION**				**LUMP SUM**
Lump Sum	**$46,125.23**	**$30,000.00**				
0180	**620-51.30**	**TYPE 2 PREFORMED MARKING TAPE (GROOVED), LEFT/RIGHT ARROW**				**15 EA**
Bid Price	**30.30**	**350.00**				
Bid Amount	$454.50	$5,250.00				
0190	**620-99.03**	**MISC. 6 IN WHITE WET REFLECTIVE EPOXY (DOTTED)**				**1,526 LF**
Bid Price	**2.02**	**3.25**				
Bid Amount	$3,082.52	$4,959.50				
0200	**622-99.03**	**MISC. 7 IN GROOVE FOR PAVEMENT MARKING**				**1,526 LF**
Bid Price	**2.53**	**3.25**				
Bid Amount	$3,860.78	$4,959.50				
0210	**627-40.00**	**CONTRACTOR FURNISHED SURVEYING AND STAKING**				**LUMP SUM**
Lump Sum	**$4,040.56**	**$500.00**				
0220	**805-10.00A**	**SEEDING - COOL SEASON MIXTURES**				**0.40 ACRE**
Bid Price	**4848.67**	**2850.00**				
Bid Amount	$1,939.47	$1,140.00				
0230	**805-20.00A**	**SEEDING - WARM SEASON MIXTURES**				**1.80 ACRE**
Bid Price	**2424.34**	**2850.00**				
Bid Amount	$4,363.81	$5,130.00				
0240	**806-10.16**	**SEDIMENT REMOVAL**				**73 CUYD**
Bid Price	**50.51**	**1.00**				
Bid Amount	$3,687.23	$73.00				
0250	**806-10.19**	**SILT FENCE**				**2,857 LF**
Bid Price	**2.22**	**2.60**				
Bid Amount	$6,342.54	$7,428.20				
0260	**806-10.22**	**TYPE II DITCH CHECK**				**44 EA**
Bid Price	**146.47**	**165.00**				
Bid Amount	$6,444.68	$7,260.00				
SECTION TOTALS	**$276,557.24**	**$276,947.20**				

TABULATION OF BIDS

Call No: F01	Collins & Hermann Inc. Low Bid	D & S Fencing Company 2nd Low				
0270	**903-10.10**	**CONCRETE FOOTINGS, EMBEDDED**				**5.20 CUYD**
Bid Price	**1259.75**	**1200.00**				
Bid Amount	$6,550.70	$6,240.00				
0280	**903-12.10**	**STRUCTURAL STEEL POSTS**				**560 LB**
Bid Price	**2.12**	**4.00**				
Bid Amount	$1,187.20	$2,240.00				
0290	**903-12.20**	**PIPE POSTS**				**4,740 LB**
Bid Price	**1.97**	**3.00**				
Bid Amount	$9,337.80	$14,220.00				
0300	**903-12.40**	**BREAKAWAY ASSEMBLY**				**38 EA**
Bid Price	**60.32**	**100.00**				
Bid Amount	$2,292.16	$3,800.00				
0310	**903-50.04**	**TYPE SHR2L-1 SIGN**				**372 SQFT**
Bid Price	**19.10**	**20.00**				
Bid Amount	$7,105.20	$7,440.00				
SECTION TOTALS	**$26,473.06**	**$33,940.00**				

Section 0002: HIGHWAY SIGNING ITEMS - J6P2373F

Contract Totals - 120824-F01

	$303,030.30	**$310,887.20**				

CERTIFIED BY DESIGN STATE DESIGN ENGINEER

8/24/2012

Missouri Department of Transportation

Vendor Ranking **Page:** 1

Call Order: F02 **Contract ID:** 120824-F02 **Counties:** JEFFERSON

Letting Date: August 24, 2012 11:00 a.m. **District(s):** St. Louis

Contract Time: DT - 6/28/2013

Contract Description: J6S2086 - ROUTE TT, AA - JEFFERSON COUNTY **Project(s):** FAS-S618(13)

Rank	Vendor ID/Name		Total Bid	Percent Of Low Bid
1	0010307	N. B. West Contracting Company	$412,539.62	100.00%
2	0012021	Plattin Creek Excavating, LLC	$469,256.37	113.75%
3	0020263	J. M. Marschuetz Construction Co.	$475,430.00	115.24%
4	0012278	Concrete Strategies LLC	$478,680.67	116.03%
5	0020367	Jokerst Paving & Contracting, Inc.	$483,468.34	117.19%
6	0011270	Pace Construction Company, LLC	$534,900.00	129.66%
7	0010300	Unnerstall Contracting Company, Ltd.	$558,274.60	135.33%
8	0011280	L. F. Krupp Construction, Inc. dba Krupp Construction	$567,385.42	137.53%
9	0010866	CE Contracting, Inc.	$688,197.90	166.82%

CONTRACT ID: 120824-F02
LETTING DATE: 08/24/12

TABULATION OF BIDS

Call No: F02	N. B. West Contracting Company Low Bid	Plattin Creek Excavating, LLC 2nd Low	J. M. Marschuetz Construction Co. 3rd Low	Concrete Strategies LLC 4th Low	Jokerst Paving & Contracting, Inc. 5th Low	Pace Construction Company, LLC 6th Low

Project J6S2086: Replace drainage structures

Section 0001: ROADWAY ITEMS - J6S2086

0010	**202-20.10**	**REMOVAL OF IMPROVEMENTS**				**LUMP SUM**
Lump Sum	**$36,000.00**	**$50,958.60**	**$41,610.00**	**$30,000.00**	**$55,500.00**	**$38,003.51**
0020	**207-20.00**	**LINEAR GRADING CLASS 2**				**15 STA**
Bid Price	**1000.00**	**750.00**	**1000.00**	**350.00**	**515.00**	**375.00**
Bid Amount	$15,000.00	$11,250.00	$15,000.00	$5,250.00	$7,725.00	$5,625.00
0030	**304-99.07**	**MISC. TYPE 1 AGGREGATE FOR BASE**				**4,471 CUYD**
Bid Price	**0.01**	**19.89**	**21.00**	**10.00**	**14.30**	**20.40**
Bid Amount	$44.71	$88,928.19	$93,891.00	$44,710.00	$63,935.30	$91,208.40
0040	**401-12.11**	**BITUMINOUS PAVEMENT MIXTURE PG64-22, (BP-2)**				**97.90 TONS**
Bid Price	**210.00**	**133.65**	**120.00**	**225.00**	**118.65**	**120.00**
Bid Amount	$20,559.00	$13,084.34	$11,748.00	$22,027.50	$11,615.84	$11,748.00
0050	**401-30.00**	**BITUMINOUS PAVEMENT MIXTURE PG64-22 (BASE)**				**528 TONS**
Bid Price	**95.00**	**124.30**	**110.00**	**145.00**	**111.15**	**108.00**
Bid Amount	$50,160.00	$65,630.40	$58,080.00	$76,560.00	$58,687.20	$57,024.00
0060	**407-10.05**	**TACK COAT**				**70 GAL**
Bid Price	**5.00**	**5.50**	**8.90**	**5.00**	**4.00**	**5.85**
Bid Amount	$350.00	$385.00	$623.00	$350.00	$280.00	$409.50
0070	**608-99.02**	**MISC. CONCRETE ENCASEMENT OF EXISTING WATER U TILITES**				**10 EA**
Bid Price	**2000.00**	**181.30**	**970.00**	**800.00**	**625.00**	**880.00**
Bid Amount	$20,000.00	$1,813.00	$9,700.00	$8,000.00	$6,250.00	$8,800.00
0080	**609-70.00**	**ROCK LINING**				**355 CUYD**
Bid Price	**68.00**	**50.33**	**50.00**	**50.00**	**50.00**	**77.75**
Bid Amount	$24,140.00	$17,867.15	$17,750.00	$17,750.00	$17,750.00	$27,601.25
0090	**616-10.05**	**CONSTRUCTION SIGNS**				**1,360 SQFT**
Bid Price	**1.00**	**7.70**	**7.75**	**7.50**	**7.00**	**7.00**
Bid Amount	$1,360.00	$10,472.00	$10,540.00	$10,200.00	$9,520.00	$9,520.00
0100	**616-10.09**	**FLAG ASSEMBLY**				**2 EA**
Bid Price	**10.00**	**22.00**	**22.00**	**21.00**	**20.00**	**20.00**
Bid Amount	$20.00	$44.00	$44.00	$42.00	$40.00	$40.00
0110	**616-10.25**	**CHANNELIZER (TRIM LINE)**				**25 EA**
Bid Price	**5.00**	**33.00**	**33.50**	**32.00**	**30.00**	**30.00**
Bid Amount	$125.00	$825.00	$837.50	$800.00	$750.00	$750.00
0120	**616-10.30**	**TYPE III MOVEABLE BARRICADE**				**6 EA**
Bid Price	**200.00**	**165.00**	**170.00**	**158.00**	**150.00**	**150.00**
Bid Amount	$1,200.00	$990.00	$1,020.00	$948.00	$900.00	$900.00
0130	**616-10.98**	**CHANGEABLE MESSAGE SIGN, CONTRACTOR FURNISHED, CONTRACTOR RE TAINED**				**6 EA**
Bid Price	**500.00**	**2200.00**	**2220.00**	**2150.00**	**2000.00**	**2000.00**
Bid Amount	$3,000.00	$13,200.00	$13,320.00	$12,900.00	$12,000.00	$12,000.00

TABULATION OF BIDS

Call No: F02	N. B. West Contracting Company Low Bid	Plattin Creek Excavating, LLC 2nd Low	J. M. Marschuetz Construction Co. 3rd Low	Concrete Strategies LLC 4th Low	Jokerst Paving & Contracting, Inc. 5th Low	Pace Construction Company, LLC 6th Low
0140	**618-10.00**	**MOBILIZATION**				**LUMP SUM**
Lump Sum	**$46,000.00**	**$21,971.20**	**$21,840.00**	**$27,000.00**	**$24,000.00**	**$28,000.00**
0150	**622-10.01**	**COLDMILLING BITUMINOUS PAVEMENT FOR REMOVAL OF SURFACING (3 IN. THICK OR LESS)**				**471 SQYD**
Bid Price	**12.00**	**8.47**	**8.90**	**11.00**	**17.00**	**7.70**
Bid Amount	$5,652.00	$3,989.37	$4,191.90	$5,181.00	$8,007.00	$3,626.70
0160	**627-40.00**	**CONTRACTOR FURNISHED SURVEYING AND STAKING**				**LUMP SUM**
Lump Sum	**$5,000.00**	**$3,784.00**	**$5,550.00**	**$2,700.00**	**$5,500.00**	**$2,240.00**
0170	**725-03.12A**	**12 IN. PIPE GROUP B**				**30 LF**
Bid Price	**38.00**	**43.93**	**50.00**	**80.00**	**54.00**	**93.50**
Bid Amount	$1,140.00	$1,317.90	$1,500.00	$2,400.00	$1,620.00	$2,805.00
0180	**725-03.18A**	**18 IN. PIPE GROUP B**				**238 LF**
Bid Price	**52.00**	**48.53**	**56.00**	**85.00**	**46.00**	**134.00**
Bid Amount	$12,376.00	$11,550.14	$13,328.00	$20,230.00	$10,948.00	$31,892.00
0190	**725-03.24A**	**24 IN. PIPE GROUP B**				**233 LF**
Bid Price	**61.00**	**52.43**	**60.00**	**90.00**	**67.00**	**119.00**
Bid Amount	$14,213.00	$12,216.19	$13,980.00	$20,970.00	$15,611.00	$27,727.00
0200	**725-03.30A**	**30 IN. PIPE GROUP B**				**186 LF**
Bid Price	**78.00**	**57.16**	**75.00**	**100.00**	**75.75**	**150.00**
Bid Amount	$14,508.00	$10,631.76	$13,950.00	$18,600.00	$14,089.50	$27,900.00
0210	**725-03.36A**	**36 IN. PIPE GROUP B**				**52 LF**
Bid Price	**92.00**	**62.02**	**73.00**	**115.00**	**87.00**	**202.00**
Bid Amount	$4,784.00	$3,225.04	$3,796.00	$5,980.00	$4,524.00	$10,504.00
0220	**725-03.48A**	**48 IN. PIPE GROUP B**				**115 LF**
Bid Price	**110.00**	**71.24**	**76.00**	**135.00**	**131.00**	**130.00**
Bid Amount	$12,650.00	$8,192.60	$8,740.00	$15,525.00	$15,065.00	$14,950.00
0230	**725-03.72A**	**72 IN. PIPE GROUP B**				**318 LF**
Bid Price	**148.00**	**108.99**	**91.00**	**175.00**	**144.00**	**197.00**
Bid Amount	$47,064.00	$34,658.82	$28,938.00	$55,650.00	$45,792.00	$62,646.00
0240	**732-00.12A**	**12 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION**				**2 EA**
Bid Price	**280.00**	**338.61**	**420.00**	**500.00**	**263.00**	**72.00**
Bid Amount	$560.00	$677.22	$840.00	$1,000.00	$526.00	$144.00
0250	**732-00.18A**	**18 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION**				**10 EA**
Bid Price	**440.00**	**388.16**	**470.00**	**525.00**	**360.00**	**118.25**
Bid Amount	$4,400.00	$3,881.60	$4,700.00	$5,250.00	$3,600.00	$1,182.50
0260	**732-00.24A**	**24 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION**				**10 EA**
Bid Price	**600.00**	**458.98**	**540.00**	**575.00**	**400.00**	**176.25**
Bid Amount	$6,000.00	$4,589.80	$5,400.00	$5,750.00	$4,000.00	$1,762.50
0270	**732-00.30A**	**30 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION**				**8 EA**
Bid Price	**850.00**	**614.28**	**530.00**	**725.00**	**680.00**	**321.25**
Bid Amount	$6,800.00	$4,914.24	$4,240.00	$5,800.00	$5,440.00	$2,570.00

TABULATION OF BIDS

Call No: F02	N. B. West Contracting Company Low Bid	Plattin Creek Excavating, LLC 2nd Low	J. M. Marschuetz Construction Co. 3rd Low	Concrete Strategies LLC 4th Low	Jokerst Paving & Contracting, Inc. 5th Low	Pace Construction Company, LLC 6th Low
0280 732-00.36A	**36 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION**					**2 EA**
Bid Price	**1200.00**	**824.48**	**1030.00**	**950.00**	**850.00**	**518.50**
Bid Amount	$2,400.00	$1,648.96	$2,060.00	$1,900.00	$1,700.00	$1,037.00
0290 732-00.48A	**48 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION**					**4 EA**
Bid Price	**2200.00**	**1599.41**	**1750.00**	**1450.00**	**1950.00**	**1138.00**
Bid Amount	$8,800.00	$6,397.64	$7,000.00	$5,800.00	$7,800.00	$4,552.00
0300 732-00.72A	**72 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION**					**12 EA**
Bid Price	**3600.00**	**2972.11**	**3400.00**	**2800.00**	**3700.00**	**2411.00**
Bid Amount	$43,200.00	$35,665.32	$40,800.00	$33,600.00	$44,400.00	$28,932.00
0310 805-10.00A	**SEEDING - COOL SEASON MIXTURES**					**1 ACRE**
Bid Price	**5000.00**	**2640.00**	**2660.00**	**2600.00**	**7500.00**	**2400.00**
Bid Amount	$5,000.00	$2,640.00	$2,660.00	$2,600.00	$7,500.00	$2,400.00
0320 806-10.16	**SEDIMENT REMOVAL**					**87 CUYD**
Bid Price	**0.01**	**22.00**	**28.00**	**0.01**	**30.00**	**28.72**
Bid Amount	$0.87	$1,914.00	$2,436.00	$0.87	$2,610.00	$2,498.64
0330 806-10.19	**SILT FENCE**					**3,253 LF**
Bid Price	**0.01**	**3.63**	**2.20**	**2.10**	**2.50**	**2.00**
Bid Amount	$32.53	$11,808.39	$7,156.60	$6,831.30	$8,132.50	$6,506.00
0340 806-10.22	**TYPE II DITCH CHECK**					**51 EA**
Bid Price	**0.01**	**159.50**	**160.00**	**125.00**	**150.00**	**145.00**
Bid Amount	$0.51	$8,134.50	$8,160.00	$6,375.00	$7,650.00	$7,395.00
SECTION TOTALS	**$412,539.62**	**$469,256.37**	**$475,430.00**	**$478,680.67**	**$483,468.34**	**$534,900.00**

Contract Totals - 120824-F02

	$412,539.62	**$469,256.37**	**$475,430.00**	**$478,680.67**	**$483,468.34**	**$534,900.00**

CONTRACT ID: 120824-F02
LETTING DATE: 08/24/12

TABULATION OF BIDS

Call No: F02	Unnerstall Contracting Company, Ltd. 7th	L. F. Krupp Construction, Inc. dba Krupp 8th	CE Contracting, Inc. 9th

Project J6S2086: Replace drainage structures

Section 0001: ROADWAY ITEMS - J6S2086

0010	**202-20.10**	**REMOVAL OF IMPROVEMENTS**					**LUMP SUM**
Lump Sum	**$26,600.00**	**$23,500.12**	**$50,000.00**				
0020	**207-20.00**	**LINEAR GRADING CLASS 2**					**15 STA**
Bid Price	**660.00**	**429.36**	**2500.00**				
Bid Amount	$9,900.00	$6,440.40	$37,500.00				
0030	**304-99.07**	**MISC. TYPE 1 AGGREGATE FOR BASE**					**4,471 CUYD**
Bid Price	**22.50**	**21.83**	**25.00**				
Bid Amount	$100,597.50	$97,601.93	$111,775.00				
0040	**401-12.11**	**BITUMINOUS PAVEMENT MIXTURE PG64-22, (BP-2)**					**97.90 TONS**
Bid Price	**159.00**	**98.18**	**150.00**				
Bid Amount	$15,566.10	$9,611.82	$14,685.00				
0050	**401-30.00**	**BITUMINOUS PAVEMENT MIXTURE PG64-22 (BASE)**					**528 TONS**
Bid Price	**159.00**	**78.34**	**150.00**				
Bid Amount	$83,952.00	$41,363.52	$79,200.00				
0060	**407-10.05**	**TACK COAT**					**70 GAL**
Bid Price	**12.00**	**11.05**	**12.00**				
Bid Amount	$840.00	$773.50	$840.00				
0070	**608-99.02**	**MISC. CONCRETE ENCASEMENT OF EXISTING WATER U TILITES**					**10 EA**
Bid Price	**350.00**	**4569.68**	**2000.00**				
Bid Amount	$3,500.00	$45,696.80	$20,000.00				
0080	**609-70.00**	**ROCK LINING**					**355 CUYD**
Bid Price	**64.00**	**52.17**	**50.00**				
Bid Amount	$22,720.00	$18,520.35	$17,750.00				
0090	**616-10.05**	**CONSTRUCTION SIGNS**					**1,360 SQFT**
Bid Price	**14.00**	**7.79**	**7.50**				
Bid Amount	$19,040.00	$10,594.40	$10,200.00				
0100	**616-10.09**	**FLAG ASSEMBLY**					**2 EA**
Bid Price	**40.00**	**22.25**	**30.00**				
Bid Amount	$80.00	$44.50	$60.00				
0110	**616-10.25**	**CHANNELIZER (TRIM LINE)**					**25 EA**
Bid Price	**40.00**	**33.38**	**17.50**				
Bid Amount	$1,000.00	$834.50	$437.50				
0120	**616-10.30**	**TYPE III MOVEABLE BARRICADE**					**6 EA**
Bid Price	**300.00**	**166.87**	**85.00**				
Bid Amount	$1,800.00	$1,001.22	$510.00				
0130	**616-10.98**	**CHANGEABLE MESSAGE SIGN, CONTRACTOR FURNISHED, CONTRACTOR RE TAINED**					**6 EA**
Bid Price	**3000.00**	**2224.93**	**3470.00**				
Bid Amount	$18,000.00	$13,349.58	$20,820.00				

TABULATION OF BIDS

Call No: F02	Unnerstall Contracting Company, Ltd. 7th	L. F. Krupp Construction, Inc. dba Krupp 8th	CE Contracting, Inc. 9th			
0140	**618-10.00**	**MOBILIZATION**				**LUMP SUM**
Lump Sum	**$20,000.00**	**$40,820.10**	**$64,375.00**			
0150	**622-10.01**	**COLDMILLING BITUMINOUS PAVEMENT FOR REMOVAL OF SURFACING (3 IN. THICK OR LESS)**				**471 SQYD**
Bid Price	**12.00**	**5.56**	**12.00**			
Bid Amount	$5,652.00	$2,618.76	$5,652.00			
0160	**627-40.00**	**CONTRACTOR FURNISHED SURVEYING AND STAKING**				**LUMP SUM**
Lump Sum	**$12,000.00**	**$2,135.93**	**$6,400.00**			
0170	**725-03.12A**	**12 IN. PIPE GROUP B**				**30 LF**
Bid Price	**75.00**	**69.39**	**115.00**			
Bid Amount	$2,250.00	$2,081.70	$3,450.00			
0180	**725-03.18A**	**18 IN. PIPE GROUP B**				**238 LF**
Bid Price	**78.00**	**66.48**	**120.00**			
Bid Amount	$18,564.00	$15,822.24	$28,560.00			
0190	**725-03.24A**	**24 IN. PIPE GROUP B**				**233 LF**
Bid Price	**82.00**	**74.08**	**130.00**			
Bid Amount	$19,106.00	$17,260.64	$30,290.00			
0200	**725-03.30A**	**30 IN. PIPE GROUP B**				**186 LF**
Bid Price	**86.00**	**83.87**	**135.00**			
Bid Amount	$15,996.00	$15,599.82	$25,110.00			
0210	**725-03.36A**	**36 IN. PIPE GROUP B**				**52 LF**
Bid Price	**90.00**	**90.20**	**140.00**			
Bid Amount	$4,680.00	$4,690.40	$7,280.00			
0220	**725-03.48A**	**48 IN. PIPE GROUP B**				**115 LF**
Bid Price	**99.00**	**88.47**	**150.00**			
Bid Amount	$11,385.00	$10,174.05	$17,250.00			
0230	**725-03.72A**	**72 IN. PIPE GROUP B**				**318 LF**
Bid Price	**123.00**	**159.14**	**175.00**			
Bid Amount	$39,114.00	$50,606.52	$55,650.00			
0240	**732-00.12A**	**12 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION**				**2 EA**
Bid Price	**290.00**	**222.11**	**100.00**			
Bid Amount	$580.00	$444.22	$200.00			
0250	**732-00.18A**	**18 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION**				**10 EA**
Bid Price	**350.00**	**272.22**	**150.00**			
Bid Amount	$3,500.00	$2,722.20	$1,500.00			
0260	**732-00.24A**	**24 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION**				**10 EA**
Bid Price	**420.00**	**335.03**	**240.00**			
Bid Amount	$4,200.00	$3,350.30	$2,400.00			
0270	**732-00.30A**	**30 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION**				**8 EA**
Bid Price	**610.00**	**492.10**	**430.00**			
Bid Amount	$4,880.00	$3,936.80	$3,440.00			

TABULATION OF BIDS

Call No: F02	Unnerstall Contracting Company, Ltd. 7th	L. F. Krupp Construction, Inc. dba Krupp 8th	CE Contracting, Inc. 9th			
0280	**732-00.36A**	**36 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION**				**2 EA**
Bid Price	**850.00**	**704.68**	**690.00**			
Bid Amount	$1,700.00	$1,409.36	$1,380.00			
0290	**732-00.48A**	**48 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION**				**4 EA**
Bid Price	**1680.00**	**1373.85**	**1520.00**			
Bid Amount	$6,720.00	$5,495.40	$6,080.00			
0300	**732-00.72A**	**72 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION**				**12 EA**
Bid Price	**3850.00**	**2748.66**	**3220.00**			
Bid Amount	$46,200.00	$32,983.92	$38,640.00			
0310	**805-10.00A**	**SEEDING - COOL SEASON MIXTURES**				**1 ACRE**
Bid Price	**12000.00**	**2669.91**	**3540.00**			
Bid Amount	$12,000.00	$2,669.91	$3,540.00			
0320	**806-10.16**	**SEDIMENT REMOVAL**				**87 CUYD**
Bid Price	**25.00**	**778.73**	**45.00**			
Bid Amount	$2,175.00	$67,749.51	$3,915.00			
0330	**806-10.19**	**SILT FENCE**				**3,253 LF**
Bid Price	**4.00**	**2.23**	**2.80**			
Bid Amount	$13,012.00	$7,254.19	$9,108.40			
0340	**806-10.22**	**TYPE II DITCH CHECK**				**51 EA**
Bid Price	**215.00**	**161.31**	**200.00**			
Bid Amount	$10,965.00	$8,226.81	$10,200.00			
SECTION TOTALS	**$558,274.60**	**$567,385.42**	**$688,197.90**			

Contract Totals - 120824-F02

	$558,274.60	**$567,385.42**	**$688,197.90**			

CERTIFIED BY DESIGN STATE DESIGN ENGINEER

8/24/2012

Missouri Department of Transportation

Vendor Ranking **Page:** 1

Call Order: F03 **Contract ID:** 120824-F03 **Counties:** FRANKLIN, ST CHARLES, ST LOUIS, ST LOUIS CITY

Letting Date: August 24, 2012 11:00 a.m. **District(s):** St. Louis

Contract Time: DT - 4/30/2013

Contract Description: J6P2406 - VARIOUS ROUTES - VARIOUS COUNTIES **Project(s):** FAS-9901(601)

Rank	Vendor ID/Name		Total Bid	Percent Of Low Bid
1	0010340	Gerstner Electric Inc.	$696,748.00	100.00%
2	0010349	T.G.B., Inc.	$714,692.00	102.58%
3	0026160	Reinhold Electric, Inc.	$838,770.00	120.38%
4	0010233	Meyer Electric Company, Inc.	$859,646.10	123.38%

TABULATION OF BIDS

Call No: F03	Gerstner Electric Inc. Low Bid	T.G.B., Inc. 2nd Low	Reinhold Electric, Inc. 3rd Low	Meyer Electric Company, Inc. 4th Low		

Project J6P2406: ITS installation

Section 0001: ROADWAY ITEMS - J6P2406

0010	**612-30.00A**	**TRUCK OR TRAILER MOUNTED ATTENUATOR (TMA)**				**1 EA**
Bid Price	**500.00**	**1000.00**	**1900.00**	**5310.00**		
Bid Amount	$500.00	$1,000.00	$1,900.00	$5,310.00		
0020	**616-10.05**	**CONSTRUCTION SIGNS**				**480 SQFT**
Bid Price	**5.00**	**5.00**	**8.00**	**9.45**		
Bid Amount	$2,400.00	$2,400.00	$3,840.00	$4,536.00		
0030	**616-10.08**	**ADVANCED WARNING RAIL SYSTEM**				**12 EA**
Bid Price	**7.00**	**45.00**	**55.00**	**179.00**		
Bid Amount	$84.00	$540.00	$660.00	$2,148.00		
0040	**616-10.09**	**FLAG ASSEMBLY**				**30 EA**
Bid Price	**1.00**	**15.00**	**25.00**	**23.60**		
Bid Amount	$30.00	$450.00	$750.00	$708.00		
0050	**616-10.25**	**CHANNELIZER (TRIM LINE)**				**75 EA**
Bid Price	**5.00**	**25.00**	**32.00**	**23.60**		
Bid Amount	$375.00	$1,875.00	$2,400.00	$1,770.00		
0060	**616-10.34**	**DIRECTIONAL INDICATOR BARRICADE WITH LIGHT**				**42 EA**
Bid Price	**7.00**	**40.00**	**45.00**	**37.75**		
Bid Amount	$294.00	$1,680.00	$1,890.00	$1,585.50		
0070	**616-10.40**	**FLASHING ARROW PANEL**				**6 EA**
Bid Price	**1.00**	**100.00**	**2050.00**	**1062.00**		
Bid Amount	$6.00	$600.00	$12,300.00	$6,372.00		
0080	**618-10.00**	**MOBILIZATION**				**LUMP SUM**
Lump Sum	**$79,548.46**	**$37,500.00**	**$36,000.00**	**$59,945.00**		
SECTION TOTALS	**$83,237.46**	**$46,045.00**	**$59,740.00**	**$82,374.50**		

Section 0002: TRAFFIC SIGNAL ITEMS - J6P2406

0090	**902-52.00**	**CONDUIT, 2 IN., TRENCH**				**14,285 LF**
Bid Price	**7.10**	**6.25**	**5.00**	**8.00**		
Bid Amount	$101,423.50	$89,281.25	$71,425.00	$114,280.00		
0100	**902-75.02**	**CONDUIT, 2 IN., EXTERNAL ON STRUCTURE**				**54 LF**
Bid Price	**28.00**	**35.00**	**75.00**	**28.40**		
Bid Amount	$1,512.00	$1,890.00	$4,050.00	$1,533.60		
0110	**902-88.11**	**PULL BOX, PREFORMED CLASS 2**				**2 EA**
Bid Price	**1042.00**	**1050.00**	**650.00**	**1350.00**		
Bid Amount	$2,084.00	$2,100.00	$1,300.00	$2,700.00		
0120	**902-99.01**	**MISC. WIRELESS ACCEPTANCE TESTING**				**LUMP SUM**
Lump Sum	**$1,625.00**	**$11,000.00**	**$8,100.00**	**$9,010.00**		

TABULATION OF BIDS

Call No: F03	Gerstner Electric Inc. Low Bid	T.G.B., Inc. 2nd Low	Reinhold Electric, Inc. 3rd Low	Meyer Electric Company, Inc. 4th Low		
0130	**902-99.01**	**MISC. RADIO LICENSING**				**LUMP SUM**
Lump Sum	**$220.00**	**$1,140.00**	**$1,190.00**	**$1,222.00**		
0140	**902-99.02**	**MISC. ITS PULL BOX, PREFORMED CLASS 2**				**18 EA**
Bid Price	**1425.00**	**1225.00**	**650.00**	**1350.00**		
Bid Amount	$25,650.00	$22,050.00	$11,700.00	$24,300.00		
0150	**902-99.02**	**MISC. ITS PULL BOX, PREFORMED CLASS 5**				**8 EA**
Bid Price	**1640.00**	**1375.00**	**1200.00**	**1750.00**		
Bid Amount	$13,120.00	$11,000.00	$9,600.00	$14,000.00		
0160	**902-99.02**	**MISC. MODOT BURIED CABLE DRIVEABLE DELINEATOR POST**				**37 EA**
Bid Price	**105.00**	**145.00**	**115.00**	**115.00**		
Bid Amount	$3,885.00	$5,365.00	$4,255.00	$4,255.00		
0170	**902-99.02**	**MISC. INSTALL COMMUNICATION EQUIPMENT**				**37 EA**
Bid Price	**377.00**	**275.00**	**375.00**	**370.50**		
Bid Amount	$13,949.00	$10,175.00	$13,875.00	$13,708.50		
0180	**902-99.02**	**MISC. FIBER OPTIC FUSION SPLICE, SINGLE MODE, FURNISH AND INSTALL**				**218 EA**
Bid Price	**70.00**	**48.00**	**40.00**	**44.15**		
Bid Amount	$15,260.00	$10,464.00	$8,720.00	$9,624.70		
0190	**902-99.02**	**MISC. FIBER OPTIC PIGTAIL, SINGLE MODE, FURNIS H AND INSTALL**				**114 EA**
Bid Price	**11.01**	**20.00**	**20.00**	**39.60**		
Bid Amount	$1,255.14	$2,280.00	$2,280.00	$4,514.40		
0200	**902-99.02**	**MISC. FIBER OPTIC JUMPER, SINGLE MODE, FURNISH AND INSTALL**				**100 EA**
Bid Price	**25.67**	**25.00**	**20.00**	**24.00**		
Bid Amount	$2,567.00	$2,500.00	$2,000.00	$2,400.00		
0210	**902-99.02**	**MISC. NETWORK CONNECTED SIGNAL MONITOR**				**34 EA**
Bid Price	**899.00**	**815.00**	**1050.00**	**1305.00**		
Bid Amount	$30,566.00	$27,710.00	$35,700.00	$44,370.00		
0220	**902-99.02**	**MISC. TRAFFIC SIGNAL CONTROLLER**				**22 EA**
Bid Price	**3495.00**	**3200.00**	**3270.00**	**4063.00**		
Bid Amount	$76,890.00	$70,400.00	$71,940.00	$89,386.00		
0230	**902-99.02**	**MISC. 4.9 GHZ ETHERNET BRIDGE RADIO WITH INTEG RATED ANTENNA**				**4 EA**
Bid Price	**3583.00**	**3000.00**	**5200.00**	**2624.00**		
Bid Amount	$14,332.00	$12,000.00	$20,800.00	$10,496.00		
0240	**902-99.02**	**MISC. REMOVAL AND REINSTALLATION OF THE EXISTI NG VIDEO CAMERA ASSEMBLY**				**141 EA**
Bid Price	**500.00**	**1050.00**	**2000.00**	**577.00**		
Bid Amount	$70,500.00	$148,050.00	$282,000.00	$81,357.00		
0250	**902-99.02**	**MISC. INSTALL VIDEO CARD AND MODIFY RACK**				**13 EA**
Bid Price	**3821.00**	**3000.00**	**125.00**	**5061.00**		
Bid Amount	$49,673.00	$39,000.00	$1,625.00	$65,793.00		

TABULATION OF BIDS

Call No: F03	Gerstner Electric Inc. Low Bid	T.G.B., Inc. 2nd Low	Reinhold Electric, Inc. 3rd Low	Meyer Electric Company, Inc. 4th Low		
0260	**902-99.02**	**MISC. MEDIA CONVERTER, FURNISH AND INSTALL**				**4 EA**
Bid Price	**1074.00**	**1100.00**	**940.00**	**1126.50**		
Bid Amount	$4,296.00	$4,400.00	$3,760.00	$4,506.00		
0270	**902-99.02**	**MISC. WALL MOUNT INTERCONNECT CENTER, FURNISH AND INSTALL**				**11 EA**
Bid Price	**545.00**	**775.00**	**905.00**	**1049.00**		
Bid Amount	$5,995.00	$8,525.00	$9,955.00	$11,539.00		
0280	**902-99.02**	**MISC. REPLACE VIDEO PROCESSOR**				**7 EA**
Bid Price	**8390.00**	**11135.00**	**11600.00**	**12206.00**		
Bid Amount	$58,730.00	$77,945.00	$81,200.00	$85,442.00		
0290	**902-99.02**	**MISC. REPLACE VIDEO LOOPING SWITCHER**				**60 EA**
Bid Price	**313.00**	**300.00**	**160.00**	**512.00**		
Bid Amount	$18,780.00	$18,000.00	$9,600.00	$30,720.00		
0300	**902-99.02**	**MISC. SIGNAL CABINET BASE WRAP AND CABINET SHI FT**				**1 EA**
Bid Price	**2400.00**	**3000.00**	**1600.00**	**1215.40**		
Bid Amount	$2,400.00	$3,000.00	$1,600.00	$1,215.40		
0310	**902-99.03**	**MISC. FIBER OPTIC CABLE, 24 STRAND, SINGLE MOD E**				**26,390 LF**
Bid Price	**1.48**	**1.45**	**1.50**	**1.70**		
Bid Amount	$39,057.20	$38,265.50	$39,585.00	$44,863.00		
0320	**902-99.03**	**MISC. CONDUIT, 2 IN. RIGID, PUSHED**				**8,097 LF**
Bid Price	**7.10**	**6.25**	**10.00**	**13.00**		
Bid Amount	$57,488.70	$50,606.25	$80,970.00	$105,261.00		
0330	**902-99.03**	**MISC. REPAIR CONDUIT**				**100 LF**
Bid Price	**22.52**	**15.00**	**18.00**	**7.75**		
Bid Amount	$2,252.00	$1,500.00	$1,800.00	$775.00		
SECTION TOTALS	**$613,510.54**	**$668,647.00**	**$779,030.00**	**$777,271.60**		

Contract Totals - 120824-F03

	$696,748.00	**$714,692.00**	**$838,770.00**	**$859,646.10**		

CERTIFIED BY DESIGN STATE DESIGN ENGINEER

8/24/2012

Missouri Department of Transportation

Vendor Ranking

Call Order: G01
Contract ID: 120824-G01
Counties: GREENE
Letting Date: August 24, 2012 11:00 a.m.
District(s): Southwest
Contract Time: DT - 9/1/2013

Contract Description: J8P3012 - ROUTE 13 - GREENE COUNTY
Project(s): FAF-13-2(70)

Rank	Vendor ID/Name		Total Bid	Percent Of Low Bid
1	0011123	Hartman and Company, Inc.	$2,571,600.00	100.00%
2	0011146	APAC-Missouri, Inc.	$2,635,398.00	102.48%
3	0010445	Emery Sapp & Sons Inc.	$2,674,590.19	104.00%
4	0011540	Lehman Construction, L.L.C.	$2,755,727.00	107.16%

CONTRACT ID: 120824-G01
LETTING DATE: 08/24/12

TABULATION OF BIDS

Call No: G01	Hartman and Company, Inc. Low Bid	APAC-Missouri, Inc. 2nd Low	Emery Sapp & Sons Inc. 3rd Low	Lehman Construction, L.L.C. 4th Low		

Project J8P3012: Grading, drainage, bridge, Opt. Pvmt. for new interchange

Section 0001: ROADWAY ITEMS - J8P3012

0010	**202-20.10**	**REMOVAL OF IMPROVEMENTS**				**LUMP SUM**
Lump Sum	**$50,699.28**	**$50,000.00**	**$75,000.00**	**$150,190.00**		
0020	**203-50.00**	**UNCLASSIFIED EXCAVATION**				**3,309 CUYD**
Bid Price	**9.20**	**13.25**	**4.90**	**10.20**		
Bid Amount	$30,442.80	$43,844.25	$16,214.10	$33,751.80		
0030	**203-55.00**	**EMBANKMENT IN PLACE**				**7,870 CUYD**
Bid Price	**9.30**	**14.35**	**7.90**	**4.95**		
Bid Amount	$73,191.00	$112,934.50	$62,173.00	$38,956.50		
0040	**206-30.00**	**CLASS 3 EXCAVATION**				**157 CUYD**
Bid Price	**16.50**	**20.00**	**18.00**	**20.00**		
Bid Amount	$2,590.50	$3,140.00	$2,826.00	$3,140.00		
0050	**304-05.04**	**TYPE 5 AGGREGATE FOR BASE (4 IN. THICK)**				**11,384 SQYD**
Bid Price	**4.90**	**5.25**	**5.30**	**6.10**		
Bid Amount	$55,781.60	$59,766.00	$60,335.20	$69,442.40		
0060	**401-01.50**	**TYPE A2 SHOULDER**				**1,171 SQYD**
Bid Price	**29.25**	**39.50**	**41.00**	**35.00**		
Bid Amount	$34,251.75	$46,254.50	$48,011.00	$40,985.00		
0070	**401-99.05**	**MISC. OPTIONAL PAVEMENT**				**9,311.30 SQYD**
Bid Price	**42.50**	**39.60**	**48.90**	**46.80**		
Bid Amount	$395,730.25	$368,727.48	$455,322.57	$435,768.84		
0080	**413-32.00**	**ULTRATHIN BONDED WEARING SURFACE, TYPE C**				**20,571 SQYD**
Bid Price	**7.55**	**6.75**	**6.75**	**6.75**		
Bid Amount	$155,311.05	$138,854.25	$138,854.25	$138,854.25		
0090	**504-10.00**	**CONCRETE APPROACH PAVEMENT**				**401.80 SQYD**
Bid Price	**121.15**	**130.00**	**92.00**	**38.00**		
Bid Amount	$48,678.07	$52,234.00	$36,965.60	$15,268.40		
0100	**604-40.11**	**PIPE COLLAR, TYPE A**				**2 EA**
Bid Price	**980.00**	**500.00**	**1250.00**	**550.00**		
Bid Amount	$1,960.00	$1,000.00	$2,500.00	$1,100.00		
0110	**606-22.02A**	**BRIDGE ANCHOR SECTION, 7.5 FT. POSTS (SAFETY BARRIER CURB) (ROADWAY AND REHABILITATION WORK ONLY)**				**4 EA**
Bid Price	**1800.00**	**1800.00**	**1800.00**	**1700.00**		
Bid Amount	$7,200.00	$7,200.00	$7,200.00	$6,800.00		
0120	**606-23.01A**	**TRANSITION SECTION, 7.5 FT. POSTS**				**4 EA**
Bid Price	**400.00**	**400.00**	**400.00**	**450.00**		
Bid Amount	$1,600.00	$1,600.00	$1,600.00	$1,800.00		
0130	**606-30.15**	**TYPE A CRASHWORTHY END TERMINAL**				**3 EA**
Bid Price	**2100.00**	**2100.00**	**2100.00**	**2000.00**		
Bid Amount	$6,300.00	$6,300.00	$6,300.00	$6,000.00		

TABULATION OF BIDS

Call No: G01	Hartman and Company, Inc. Low Bid	APAC-Missouri, Inc. 2nd Low	Emery Sapp & Sons Inc. 3rd Low	Lehman Construction, L.L.C. 4th Low		
0140	**606-66.10**	**END ANCHOR**				**3 EA**
Bid Price	**1200.00**	**1200.00**	**1200.00**	**800.00**		
Bid Amount	$3,600.00	$3,600.00	$3,600.00	$2,400.00		
0150	**606-99.03**	**MISC. GUARDRAIL TYPE A, 7 FT. POSTS, 6 FT. 3 I N. SPACING**				**925 LF**
Bid Price	**22.00**	**22.00**	**22.00**	**25.00**		
Bid Amount	$20,350.00	$20,350.00	$20,350.00	$23,125.00		
0160	**608-10.10**	**CONCRETE CURB RAMP**				**79.90 SQYD**
Bid Price	**54.60**	**85.00**	**85.00**	**122.00**		
Bid Amount	$4,362.54	$6,791.50	$6,791.50	$9,747.80		
0170	**608-10.12**	**TRUNCATED DOMES**				**134 SQFT**
Bid Price	**25.75**	**36.00**	**21.00**	**20.00**		
Bid Amount	$3,450.50	$4,824.00	$2,814.00	$2,680.00		
0180	**608-30.08**	**8 IN. CONCRETE MEDIAN STRIP**				**2,888.10 SQYD**
Bid Price	**47.40**	**45.00**	**50.00**	**70.00**		
Bid Amount	$136,895.94	$129,964.50	$144,405.00	$202,167.00		
0190	**608-60.04**	**CONCRETE SIDEWALK, 4 IN.**				**1,763.80 SQYD**
Bid Price	**34.00**	**30.00**	**27.00**	**35.00**		
Bid Amount	$59,969.20	$52,914.00	$47,622.60	$61,733.00		
0200	**609-10.41**	**CONCRETE GUTTER TYPE A**				**122 LF**
Bid Price	**24.65**	**35.00**	**61.00**	**21.50**		
Bid Amount	$3,007.30	$4,270.00	$7,442.00	$2,623.00		
0210	**609-10.52**	**CURB AND GUTTER TYPE B**				**2,219 LF**
Bid Price	**14.80**	**23.60**	**21.00**	**17.50**		
Bid Amount	$32,841.20	$52,368.40	$46,599.00	$38,832.50		
0220	**609-20.21**	**INTEGRAL CURB (OVER 6 IN. HEIGHT) TYPE A**				**312 LF**
Bid Price	**13.10**	**36.00**	**3.00**	**5.00**		
Bid Amount	$4,087.20	$11,232.00	$936.00	$1,560.00		
0230	**612-30.00A**	**TRUCK OR TRAILER MOUNTED ATTENUATOR (TMA)**				**2 EA**
Bid Price	**5000.00**	**1200.00**	**7500.00**	**3000.00**		
Bid Amount	$10,000.00	$2,400.00	$15,000.00	$6,000.00		
0240	**613-10.10**	**FURNISHING AND PLACING CONCRETE MATERIAL FOR FULL DEPTH PAVE MENT REPAIR**				**280 SQYD**
Bid Price	**134.00**	**120.00**	**66.00**	**70.00**		
Bid Amount	$37,520.00	$33,600.00	$18,480.00	$19,600.00		
0250	**613-10.12**	**SUBGRADE COMPACTION (6 IN. DEPTH) (PAVEMENT REPAIR)**				**28 SQYD**
Bid Price	**7.20**	**4.00**	**69.00**	**8.00**		
Bid Amount	$201.60	$112.00	$1,932.00	$224.00		
0260	**613-10.13**	**TYPE 1 OR 5 AGGREGATE FOR BASE (4 IN. THICK) (PAVEMENT REPA IR)**				**28 SQYD**
Bid Price	**7.20**	**2.50**	**54.00**	**243.00**		
Bid Amount	$201.60	$70.00	$1,512.00	$6,804.00		

TABULATION OF BIDS

Call No: G01	Hartman and Company, Inc. Low Bid	APAC-Missouri, Inc. 2nd Low	Emery Sapp & Sons Inc. 3rd Low	Lehman Construction, L.L.C. 4th Low		
0270	**613-10.14**	**FULL DEPTH PAVEMENT REPAIR SAW CUT (FOR PERIMETER AND INTER NAL SAW CUTS)**				**1,032 LF**
Bid Price	**4.15**	**2.50**	**4.30**	**5.00**		
Bid Amount	$4,282.80	$2,580.00	$4,437.60	$5,160.00		
0280	**613-10.15**	**DOWEL BAR (DRILLING, FURNISHING AND INSTALLATION) FOR FULL DEPTH PAVEMENT REPAIR**				**660 EA**
Bid Price	**9.25**	**3.50**	**10.00**	**16.90**		
Bid Amount	$6,105.00	$2,310.00	$6,600.00	$11,154.00		
0290	**613-20.14**	**CLASS A PARTIAL DEPTH PAVEMENT REPAIR SAW CUTS (FOR RESEALI NG JOINTS AND CRACKS)**				**208 LF**
Bid Price	**6.20**	**2.50**	**4.00**	**4.00**		
Bid Amount	$1,289.60	$520.00	$832.00	$832.00		
0300	**613-20.18**	**FURNISHING AND PLACING CONCRETE MATERIAL FOR CLASS A PARTIAL DEPTH PAVEMENT REPAIR**				**2.40 CUYD**
Bid Price	**1545.00**	**1100.00**	**1000.00**	**1101.00**		
Bid Amount	$3,708.00	$2,640.00	$2,400.00	$2,642.40		
0310	**613-20.19**	**REMOVAL FOR CLASS A PARTIAL DEPTH PAVEMENT REPAIR**				**20 SQYD**
Bid Price	**30.90**	**225.00**	**250.00**	**12.00**		
Bid Amount	$618.00	$4,500.00	$5,000.00	$240.00		
0320	**614-11.20**	**CURVED VANE GRATE AND FRAME (2 FT. X 2 FT. OR 600MM X 600MM)**				**20 EA**
Bid Price	**565.00**	**720.00**	**465.00**	**485.00**		
Bid Amount	$11,300.00	$14,400.00	$9,300.00	$9,700.00		
0330	**614-30.13**	**MANHOLE FRAME AND COVER, TYPE 3**				**5 EA**
Bid Price	**500.00**	**300.00**	**450.00**	**280.00**		
Bid Amount	$2,500.00	$1,500.00	$2,250.00	$1,400.00		
0340	**616-10.05**	**CONSTRUCTION SIGNS**				**1,414 SQFT**
Bid Price	**9.00**	**6.10**	**6.00**	**6.00**		
Bid Amount	$12,726.00	$8,625.40	$8,484.00	$8,484.00		
0350	**616-10.08**	**ADVANCED WARNING RAIL SYSTEM**				**7 EA**
Bid Price	**55.00**	**81.00**	**80.00**	**80.00**		
Bid Amount	$385.00	$567.00	$560.00	$560.00		
0360	**616-10.09**	**FLAG ASSEMBLY**				**23 EA**
Bid Price	**22.00**	**20.00**	**20.00**	**20.00**		
Bid Amount	$506.00	$460.00	$460.00	$460.00		
0370	**616-10.25**	**CHANNELIZER (TRIM LINE)**				**350 EA**
Bid Price	**22.00**	**15.00**	**15.00**	**15.00**		
Bid Amount	$7,700.00	$5,250.00	$5,250.00	$5,250.00		
0380	**616-10.30**	**TYPE III MOVEABLE BARRICADE**				**33 EA**
Bid Price	**85.00**	**132.00**	**130.00**	**130.00**		
Bid Amount	$2,805.00	$4,356.00	$4,290.00	$4,290.00		

TABULATION OF BIDS

Call No: G01	Hartman and Company, Inc. Low Bid	APAC-Missouri, Inc. 2nd Low	Emery Sapp & Sons Inc. 3rd Low	Lehman Construction, L.L.C. 4th Low		
0390	**616-10.40**	**FLASHING ARROW PANEL**				**2 EA**
Bid Price	**1000.00**	**1270.00**	**1855.00**	**1250.00**		
Bid Amount	$2,000.00	$2,540.00	$3,710.00	$2,500.00		
0400	**616-10.98**	**CHANGEABLE MESSAGE SIGN, CONTRACTOR FURNISHED, CONTRACTOR RE TAINED**				**4 EA**
Bid Price	**3200.00**	**4080.00**	**4600.00**	**4000.00**		
Bid Amount	$12,800.00	$16,320.00	$18,400.00	$16,000.00		
0410	**616-20.10**	**WORK ZONE LIGHTING**				**LUMP SUM**
Lump Sum	**$22,800.00**	**$5,000.00**	**$2,600.00**	**$8,000.00**		
0420	**617-31.00**	**CONCRETE TRAFFIC BARRIER, TYPE D**				**128 LF**
Bid Price	**52.70**	**52.00**	**80.00**	**80.00**		
Bid Amount	$6,745.60	$6,656.00	$10,240.00	$10,240.00		
0430	**618-10.00**	**MOBILIZATION**				**LUMP SUM**
Lump Sum	**$129,000.00**	**$141,600.59**	**$236,000.00**	**$248,590.99**		
0440	**619-10.00**	**PAVEMENT EDGE TREATMENT**				**6,735 LF**
Bid Price	**3.45**	**4.00**	**1.70**	**1.60**		
Bid Amount	$23,235.75	$26,940.00	$11,449.50	$10,776.00		
0450	**620-51.05**	**TYPE 2 PREFORMED MARKING TAPE (GROOVED), 6 IN., WHITE**				**617 LF**
Bid Price	**5.00**	**5.86**	**5.00**	**5.00**		
Bid Amount	$3,085.00	$3,615.62	$3,085.00	$3,085.00		
0460	**620-51.20**	**TYPE 2 PREFORMED MARKING TAPE (GROOVED), 24 IN., WHITE**				**532 LF**
Bid Price	**20.00**	**20.71**	**20.00**	**20.00**		
Bid Amount	$10,640.00	$11,017.72	$10,640.00	$10,640.00		
0470	**620-51.21**	**TYPE 2 PREFORMED MARKING TAPE (GROOVED), 24 IN., YELLOW**				**251 LF**
Bid Price	**20.00**	**20.71**	**20.00**	**20.00**		
Bid Amount	$5,020.00	$5,198.21	$5,020.00	$5,020.00		
0480	**620-51.30**	**TYPE 2 PREFORMED MARKING TAPE (GROOVED), LEFT/RIGHT ARROW**				**22 EA**
Bid Price	**327.00**	**331.31**	**327.00**	**327.00**		
Bid Amount	$7,194.00	$7,288.82	$7,194.00	$7,194.00		
0490	**620-51.31**	**TYPE 2 PREFORMED MARKING TAPE (GROOVED), STRAIGHT ARROW**				**24 EA**
Bid Price	**228.00**	**331.31**	**228.00**	**228.00**		
Bid Amount	$5,472.00	$7,951.44	$5,472.00	$5,472.00		
0500	**620-51.32**	**TYPE 2 PREFORMED MARKING TAPE (GROOVED), COMBINATION STRAIGH T-LEFT/RIGHT ARROW**				**4 EA**
Bid Price	**554.00**	**662.63**	**554.00**	**554.00**		
Bid Amount	$2,216.00	$2,650.52	$2,216.00	$2,216.00		
0510	**620-51.33**	**TYPE 2 PREFORMED MARKING TAPE (GROOVED), WORD (ONLY)**				**9 EA**
Bid Price	**500.00**	**475.76**	**500.00**	**500.00**		
Bid Amount	$4,500.00	$4,281.84	$4,500.00	$4,500.00		

TABULATION OF BIDS

Call No: G01	Hartman and Company, Inc. Low Bid	APAC-Missouri, Inc. 2nd Low	Emery Sapp & Sons Inc. 3rd Low	Lehman Construction, L.L.C. 4th Low		
0520	**620-51.37**	**TYPE 2 PREFORMED WHITE MIDBLOCK (GROOVED), 36 IN. OR 900 MM WIDE FOR 12 FT. OR 3.6 M LANE**				**7 EA**
Bid Price	**290.00**	**370.71**	**290.00**	**290.00**		
Bid Amount	$2,030.00	$2,594.97	$2,030.00	$2,030.00		
0530	**620-51.39A**	**TYPE 2 PREFORMED MARKING TAPE (GROOVED), 16 IN. WHITE, YIELD LINE TRIANGLES**				**30 EA**
Bid Price	**30.00**	**22.22**	**30.00**	**30.00**		
Bid Amount	$900.00	$666.60	$900.00	$900.00		
0540	**620-53.01B**	**PREFORMED REMOVABLE MARKING TAPE 4 IN., WHITE**				**996 LF**
Bid Price	**1.10**	**1.25**	**1.10**	**1.10**		
Bid Amount	$1,095.60	$1,245.00	$1,095.60	$1,095.60		
0550	**620-53.03B**	**PREFORMED REMOVABLE MARKING TAPE 4 IN., YELLOW**				**1,010 LF**
Bid Price	**1.10**	**1.25**	**1.10**	**1.10**		
Bid Amount	$1,111.00	$1,262.50	$1,111.00	$1,111.00		
0560	**620-53.15A**	**PREFORMED REMOVABLE MARKING TAPE 8 IN., WHITE**				**752 LF**
Bid Price	**2.20**	**2.25**	**2.20**	**2.20**		
Bid Amount	$1,654.40	$1,692.00	$1,654.40	$1,654.40		
0570	**620-53.20**	**PREFORMED REMOVABLE MARKING TAPE, 12 IN., WHITE**				**240 LF**
Bid Price	**3.30**	**5.75**	**3.30**	**3.30**		
Bid Amount	$792.00	$1,380.00	$792.00	$792.00		
0580	**620-59.02**	**6 IN. WHITE HIGH BUILD ACRYLIC WATERBORNE PAVEMENT MARKING P AINT**				**9,604 LF**
Bid Price	**0.18**	**0.30**	**0.18**	**0.18**		
Bid Amount	$1,728.72	$2,881.20	$1,728.72	$1,728.72		
0590	**620-59.03**	**6 IN. YELLOW HIGH BUILD ACRYLIC WATERBORNE PAVEMENT MARKING PAINT**				**5,585 LF**
Bid Price	**0.18**	**0.30**	**0.18**	**0.18**		
Bid Amount	$1,005.30	$1,675.50	$1,005.30	$1,005.30		
0600	**620-70.01**	**PAVEMENT MARKING REMOVAL**				**1,611 LF**
Bid Price	**0.40**	**3.03**	**0.40**	**0.40**		
Bid Amount	$644.40	$4,881.33	$644.40	$644.40		
0610	**620-99.03**	**MISC. 7 IN. GROOVE FOR PAVEMENT MARKING (ASPHA LT)**				**3,426 LF**
Bid Price	**0.40**	**0.61**	**0.40**	**0.40**		
Bid Amount	$1,370.40	$2,089.86	$1,370.40	$1,370.40		
0620	**620-99.03**	**MISC. 10 IN. GROOVE FOR PAVEMENT MARKING (CONC RETE)**				**1,962 LF**
Bid Price	**0.50**	**1.01**	**0.50**	**0.50**		
Bid Amount	$981.00	$1,981.62	$981.00	$981.00		

TABULATION OF BIDS

Call No: G01	Hartman and Company, Inc. Low Bid	APAC-Missouri, Inc. 2nd Low	Emery Sapp & Sons Inc. 3rd Low	Lehman Construction, L.L.C. 4th Low		
0630	**620-99.03**	**MISC. VARIABLE WIDTH STRIPING, WHITE**				**2,698 LF**
Bid Price	**2.00**	**1.01**	**2.00**	**2.00**		
Bid Amount	$5,396.00	$2,724.98	$5,396.00	$5,396.00		
0640	**620-99.03**	**MISC. VARIABLE WIDTH STRIPING, YELLOW**				**2,717 LF**
Bid Price	**2.00**	**1.01**	**2.00**	**2.00**		
Bid Amount	$5,434.00	$2,744.17	$5,434.00	$5,434.00		
0650	**622-40.10**	**MODIFIED COLDMILLING (DEPTH TRANSITIONS)**				**1,946 SQYD**
Bid Price	**5.05**	**10.85**	**10.85**	**5.00**		
Bid Amount	$9,827.30	$21,114.10	$21,114.10	$9,730.00		
0660	**627-40.00**	**CONTRACTOR FURNISHED SURVEYING AND STAKING**				**LUMP SUM**
Lump Sum	**$21,255.00**	**$41,255.00**	**$17,300.00**	**$21,255.00**		
0670	**711-03.00**	**CONCRETE AND MASONRY PROTECTION SYSTEM**				**LUMP SUM**
Lump Sum	**$2,715.00**	**$2,784.62**	**$2,715.00**	**$2,715.00**		
0680	**711-04.00**	**SACRIFICIAL GRAFFITI PROTECTION SYSTEM**				**LUMP SUM**
Lump Sum	**$2,715.00**	**$2,784.62**	**$2,715.00**	**$2,715.00**		
0690	**725-03.15A**	**15 IN. PIPE GROUP B**				**480 LF**
Bid Price	**31.75**	**30.00**	**27.00**	**27.00**		
Bid Amount	$15,240.00	$14,400.00	$12,960.00	$12,960.00		
0700	**726-10.15**	**15 IN. PIPE GROUP A**				**738 LF**
Bid Price	**35.65**	**35.00**	**27.00**	**27.00**		
Bid Amount	$26,309.70	$25,830.00	$19,926.00	$19,926.00		
0710	**726-10.30**	**30 IN. PIPE GROUP A**				**64 LF**
Bid Price	**82.65**	**60.00**	**58.00**	**57.70**		
Bid Amount	$5,289.60	$3,840.00	$3,712.00	$3,692.80		
0720	**731-10.22**	**PRECAST CONCRETE DROP INLET 2 FT X 2 FT**				**59 FT**
Bid Price	**315.00**	**300.00**	**385.00**	**305.00**		
Bid Amount	$18,585.00	$17,700.00	$22,715.00	$17,995.00		
0730	**731-10.30**	**PRECAST CONCRETE DROP INLET 3 FT X 2 FT-6 IN.**				**23 FT**
Bid Price	**250.00**	**350.00**	**310.00**	**271.00**		
Bid Amount	$5,750.00	$8,050.00	$7,130.00	$6,233.00		
0740	**732-00.15A**	**15 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION**				**12 EA**
Bid Price	**215.00**	**250.00**	**220.00**	**125.00**		
Bid Amount	$2,580.00	$3,000.00	$2,640.00	$1,500.00		
0750	**732-06.30A**	**30 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION**				**2 EA**
Bid Price	**995.00**	**800.00**	**910.00**	**550.00**		
Bid Amount	$1,990.00	$1,600.00	$1,820.00	$1,100.00		
0760	**805-10.00A**	**SEEDING - COOL SEASON MIXTURES**				**1.90 ACRE**
Bid Price	**1500.00**	**1515.15**	**1500.00**	**1500.00**		
Bid Amount	$2,850.00	$2,878.79	$2,850.00	$2,850.00		
0770	**806-10.16**	**SEDIMENT REMOVAL**				**55 CUYD**
Bid Price	**22.45**	**20.00**	**30.00**	**40.00**		
Bid Amount	$1,234.75	$1,100.00	$1,650.00	$2,200.00		

Call No: G01	Hartman and Company, Inc. Low Bid	APAC-Missouri, Inc. 2nd Low	Emery Sapp & Sons Inc. 3rd Low	Lehman Construction, L.L.C. 4th Low		
0780	**806-10.17**	**TEMPORARY SEEDING AND MULCHING**				**0.50 ACRE**
Bid Price	**1000.00**	**1010.10**	**1000.00**	**1000.00**		
Bid Amount	$500.00	$505.05	$500.00	$500.00		
0790	**806-10.19**	**SILT FENCE**				**2,626 LF**
Bid Price	**2.00**	**2.00**	**2.00**	**2.00**		
Bid Amount	$5,252.00	$5,252.00	$5,252.00	$5,252.00		
0800	**806-10.22**	**TYPE II DITCH CHECK**				**29 EA**
Bid Price	**175.00**	**176.00**	**175.00**	**175.00**		
Bid Amount	$5,075.00	$5,104.00	$5,075.00	$5,075.00		
0810	**806-10.25**	**INLET CHECK**				**25 EA**
Bid Price	**100.00**	**100.00**	**100.00**	**100.00**		
Bid Amount	$2,500.00	$2,500.00	$2,500.00	$2,500.00		
0820	**806-41.22**	**TYPE 3 EROSION CONTROL BLANKET**				**7,273 SQYD**
Bid Price	**1.50**	**1.52**	**1.50**	**1.50**		
Bid Amount	$10,909.50	$11,054.96	$10,909.50	$10,909.50		
0830	**806-41.30**	**TYPE 3 TURF REINFORCEMENT MAT**				**1,050 SQYD**
Bid Price	**4.50**	**4.55**	**4.50**	**4.50**		
Bid Amount	$4,725.00	$4,777.50	$4,725.00	$4,725.00		
SECTION TOTALS	**$1,638,302.80**	**$1,706,470.91**	**$1,773,527.34**	**$1,861,936.00**		

Section 0002: LIGHTING ITEMS - J8P3012

0840	**901-10.60**	**LIGHTING POLE, 45 FT. OR 13.5 M, TYPE AT DESIGN 1**				**4 EA**
Bid Price	**1760.00**	**2250.00**	**2250.00**	**2250.00**		
Bid Amount	$7,040.00	$9,000.00	$9,000.00	$9,000.00		
0850	**901-11.15**	**BRACKET ARM, 15 FT. OR 4.6 M**				**17 EA**
Bid Price	**635.00**	**525.00**	**525.00**	**525.00**		
Bid Amount	$10,795.00	$8,925.00	$8,925.00	$8,925.00		
0860	**901-13.20**	**LUMINAIRE, 400 WATT HIGH PRESSURE SODIUM**				**17 EA**
Bid Price	**425.00**	**275.00**	**275.00**	**275.00**		
Bid Amount	$7,225.00	$4,675.00	$4,675.00	$4,675.00		
0870	**901-22.30**	**BASE MOUNTED CONTROL STATION 240 VOLT - 4 CIRCUIT**				**1 EA**
Bid Price	**6000.00**	**4959.00**	**4959.00**	**4959.00**		
Bid Amount	$6,000.00	$4,959.00	$4,959.00	$4,959.00		
0880	**901-30.04**	**CONDUIT, 4 IN. RIGID, IN TRENCH**				**199 LF**
Bid Price	**13.00**	**13.00**	**13.00**	**13.00**		
Bid Amount	$2,587.00	$2,587.00	$2,587.00	$2,587.00		
0890	**901-40.04**	**CONDUIT, 4 IN. RIGID, PUSHED**				**915 LF**
Bid Price	**17.50**	**18.00**	**18.00**	**18.00**		
Bid Amount	$16,012.50	$16,470.00	$16,470.00	$16,470.00		
0900	**901-50.10**	**TRENCHING TYPE I**				**4,563 LF**
Bid Price	**4.75**	**4.25**	**4.25**	**4.25**		
Bid Amount	$21,674.25	$19,392.75	$19,392.75	$19,392.75		

TABULATION OF BIDS

Call No: G01	Hartman and Company, Inc. Low Bid	APAC-Missouri, Inc. 2nd Low	Emery Sapp & Sons Inc. 3rd Low	Lehman Construction, L.L.C. 4th Low		
0910	**901-61.10**	**PULL BOX, PREFORMED CLASS 1**				**17 EA**
Bid Price	**765.00**	**610.00**	**610.00**	**610.00**		
Bid Amount	$13,005.00	$10,370.00	$10,370.00	$10,370.00		
0920	**901-70.02**	**CABLE, 2 AWG 1 CONDUCTOR**				**410 LF**
Bid Price	**3.65**	**2.15**	**2.15**	**2.15**		
Bid Amount	$1,496.50	$881.50	$881.50	$881.50		
0930	**901-71.10**	**CABLE, 10 AWG 1 CONDUCTOR, POLE AND BRACKET**				**1,910 LF**
Bid Price	**0.80**	**0.90**	**0.90**	**0.90**		
Bid Amount	$1,528.00	$1,719.00	$1,719.00	$1,719.00		
0940	**901-74.04**	**CABLE-CONDUIT, 1 IN., 2 CONDUCTORS AND 1 BARE NEUTRAL, 6 AWG**				**4,700 LF**
Bid Price	**3.45**	**3.00**	**3.00**	**3.00**		
Bid Amount	$16,215.00	$14,100.00	$14,100.00	$14,100.00		
0950	**901-74.07**	**CABLE-CONDUIT, 1 IN., 2 CONDUCTORS AND 1 BARE NEUTRAL, 8 AWG**				**2,490 LF**
Bid Price	**3.30**	**2.50**	**2.50**	**2.50**		
Bid Amount	$8,217.00	$6,225.00	$6,225.00	$6,225.00		
0960	**901-82.45**	**POLE FOUNDATION (45 FT. OR 13.5 M MOUNTING HEIGHT)**				**4 EA**
Bid Price	**1140.00**	**1175.00**	**1175.00**	**1175.00**		
Bid Amount	$4,560.00	$4,700.00	$4,700.00	$4,700.00		
0970	**901-99.01**	**MISC. PEDESTRIAN WALKWAY LIGHTING**				**LUMP SUM**
Lump Sum	**$55,640.00**	**$53,820.00**	**$53,820.00**	**$53,820.00**		
0980	**901-99.02**	**MISC. POLE FOUNDATION (40 FT MOUNTING HEIGHT)**				**13 EA**
Bid Price	**1210.00**	**1175.00**	**1175.00**	**1175.00**		
Bid Amount	$15,730.00	$15,275.00	$15,275.00	$15,275.00		
0990	**901-99.02**	**MISC. LIGHTING POLE, 40 FT**				**13 EA**
Bid Price	**1365.00**	**1750.00**	**1750.00**	**1750.00**		
Bid Amount	$17,745.00	$22,750.00	$22,750.00	$22,750.00		
1000	**901-99.02**	**MISC. INSTALL LIGHTING FOUNDATION (WW40S-*)**				**6 EA**
Bid Price	**840.00**	**805.00**	**805.00**	**805.00**		
Bid Amount	$5,040.00	$4,830.00	$4,830.00	$4,830.00		
1010	**901-99.02**	**MISC. INSTALL LIGHTING FOUNDATION (WW25S-*)**				**1 EA**
Bid Price	**840.00**	**745.00**	**745.00**	**745.00**		
Bid Amount	$840.00	$745.00	$745.00	$745.00		
1020	**901-99.02**	**MISC. INSTALL SECONDARY PEDESTAL (SP-2C)**				**2 EA**
Bid Price	**575.00**	**310.00**	**310.00**	**310.00**		
Bid Amount	$1,150.00	$620.00	$620.00	$620.00		
1030	**901-99.03**	**MISC. INSTALL 1-2 IN PVC CONDUIT IN TRENCH**				**937 LF**
Bid Price	**8.90**	**8.15**	**8.15**	**8.15**		
Bid Amount	$8,339.30	$7,636.55	$7,636.55	$7,636.55		
1040	**901-99.03**	**MISC. INSTALL 1-2 IN GALV CONDUIT IN TRENCH**				**94 LF**
Bid Price	**17.20**	**18.85**	**18.85**	**18.85**		
Bid Amount	$1,616.80	$1,771.90	$1,771.90	$1,771.90		

Call No: G01	Hartman and Company, Inc. Low Bid	APAC-Missouri, Inc. 2nd Low	Emery Sapp & Sons Inc. 3rd Low	Lehman Construction, L.L.C. 4th Low		

Section 0003: SIGNAL ITEMS - J8P3012

1050	**902-02.13**	**SIGNAL HEAD, TYPE 3S**				**6 EA**
Bid Price	**910.00**	**770.00**	**770.00**	**770.00**		
Bid Amount	$5,460.00	$4,620.00	$4,620.00	$4,620.00		
1060	**902-05.13**	**SIGNAL HEAD, TYPE 3B**				**10 EA**
Bid Price	**945.00**	**930.00**	**930.00**	**930.00**		
Bid Amount	$9,450.00	$9,300.00	$9,300.00	$9,300.00		
1070	**902-08.11**	**SIGNAL HEAD, TYPE 1S, PEDESTRIAN**				**10 EA**
Bid Price	**750.00**	**555.00**	**555.00**	**555.00**		
Bid Amount	$7,500.00	$5,550.00	$5,550.00	$5,550.00		
1080	**902-27.08**	**POST, SIGNAL 8 FT. OR 2.4 M**				**3 EA**
Bid Price	**975.00**	**925.00**	**925.00**	**925.00**		
Bid Amount	$2,925.00	$2,775.00	$2,775.00	$2,775.00		
1090	**902-27.15**	**POST, SIGNAL 15 FT. OR 4.6 M**				**4 EA**
Bid Price	**1030.00**	**1105.00**	**1105.00**	**1105.00**		
Bid Amount	$4,120.00	$4,420.00	$4,420.00	$4,420.00		
1100	**902-32.40**	**POST, TYPE C, 40 FT. ARM OR 12.2 M ARM**				**1 EA**
Bid Price	**6865.00**	**6560.00**	**6560.00**	**6560.00**		
Bid Amount	$6,865.00	$6,560.00	$6,560.00	$6,560.00		
1110	**902-41.70**	**CONTROLLER ASSEMBLY HOUSING, TYPE 170**				**1 EA**
Bid Price	**17650.00**	**15750.00**	**15750.00**	**15750.00**		
Bid Amount	$17,650.00	$15,750.00	$15,750.00	$15,750.00		
1120	**902-49.20**	**DETECTOR, PUSHBUTTON**				**10 EA**
Bid Price	**270.00**	**225.00**	**225.00**	**225.00**		
Bid Amount	$2,700.00	$2,250.00	$2,250.00	$2,250.00		
1130	**902-50.20**	**CONDUIT, 1 IN., LOOP DETECTOR**				**60 LF**
Bid Price	**6.70**	**6.50**	**6.50**	**6.50**		
Bid Amount	$402.00	$390.00	$390.00	$390.00		
1140	**902-52.00**	**CONDUIT, 2 IN., TRENCH**				**1,089 LF**
Bid Price	**8.10**	**8.15**	**8.15**	**8.15**		
Bid Amount	$8,820.90	$8,875.35	$8,875.35	$8,875.35		
1150	**902-53.00**	**CONDUIT, 3 IN., TRENCH**				**481 LF**
Bid Price	**10.00**	**10.70**	**10.70**	**10.70**		
Bid Amount	$4,810.00	$5,146.70	$5,146.70	$5,146.70		
1160	**902-54.00**	**CONDUIT, 4 IN., TRENCH**				**357 LF**
Bid Price	**10.85**	**11.25**	**11.25**	**11.25**		
Bid Amount	$3,873.45	$4,016.25	$4,016.25	$4,016.25		
1170	**902-73.00**	**CONDUIT, 3 IN., PUSHED**				**980 LF**
Bid Price	**15.35**	**18.00**	**18.00**	**18.00**		
Bid Amount	$15,043.00	$17,640.00	$17,640.00	$17,640.00		
1180	**902-75.06**	**CONDUIT, 4 IN., EXTERNAL ON STRUCTURE**				**225 LF**
Bid Price	**24.00**	**15.50**	**15.50**	**15.50**		
Bid Amount	$5,400.00	$3,487.50	$3,487.50	$3,487.50		

TABULATION OF BIDS

Call No: G01	Hartman and Company, Inc. Low Bid	APAC-Missouri, Inc. 2nd Low	Emery Sapp & Sons Inc. 3rd Low	Lehman Construction, L.L.C. 4th Low		
1190	**902-82.06**	**CABLE, 6 AWG 1 CONDUCTOR, POWER**				**2,050 LF**
Bid Price	**1.45**	**1.25**	**1.25**	**1.25**		
Bid Amount	$2,972.50	$2,562.50	$2,562.50	$2,562.50		
1200	**902-82.08**	**CABLE, 8 AWG 1 CONDUCTOR, POWER**				**740 LF**
Bid Price	**1.25**	**1.00**	**1.00**	**1.00**		
Bid Amount	$925.00	$740.00	$740.00	$740.00		
1210	**902-83.08**	**CABLE, 16 AWG 2 CONDUCTOR**				**3,770 LF**
Bid Price	**0.90**	**0.90**	**0.90**	**0.90**		
Bid Amount	$3,393.00	$3,393.00	$3,393.00	$3,393.00		
1220	**902-83.10**	**CABLE, 16 AWG 5 CONDUCTOR**				**3,780 LF**
Bid Price	**1.10**	**1.05**	**1.05**	**1.05**		
Bid Amount	$4,158.00	$3,969.00	$3,969.00	$3,969.00		
1230	**902-83.11**	**CABLE, 16 AWG 7 CONDUCTOR**				**5,240 LF**
Bid Price	**1.30**	**1.25**	**1.25**	**1.25**		
Bid Amount	$6,812.00	$6,550.00	$6,550.00	$6,550.00		
1240	**902-86.20**	**POWER SUPPLY ASSEMBLY, TYPE 2**				**1 EA**
Bid Price	**4735.00**	**3715.00**	**3715.00**	**3715.00**		
Bid Amount	$4,735.00	$3,715.00	$3,715.00	$3,715.00		
1250	**902-88.11**	**PULL BOX, PREFORMED CLASS 2**				**21 EA**
Bid Price	**905.00**	**850.00**	**850.00**	**850.00**		
Bid Amount	$19,005.00	$17,850.00	$17,850.00	$17,850.00		
1260	**902-88.16**	**PULL BOX, PREFORMED CLASS 5**				**2 EA**
Bid Price	**1230.00**	**1020.00**	**1020.00**	**1020.00**		
Bid Amount	$2,460.00	$2,040.00	$2,040.00	$2,040.00		
1270	**902-91.00**	**BASE, CONCRETE**				**21.90 CUYD**
Bid Price	**885.00**	**890.00**	**890.00**	**890.00**		
Bid Amount	$19,381.50	$19,491.00	$19,491.00	$19,491.00		
1280	**902-94.01**	**TEMPORARY TRAFFIC SIGNALS AND LIGHTING**				**LUMP SUM**
Lump Sum	**$10,000.00**	**$20,035.00**	**$20,035.00**	**$20,035.00**		
1290	**902-99.01**	**MISC. OPTIONAL TRAFFIC SIGNAL DETECTORS**				**LUMP SUM**
Lump Sum	**$9,075.00**	**$8,950.00**	**$8,950.00**	**$8,950.00**		
1300	**902-99.01**	**MISC. RELOCATE EXISTING CCTV POLE AND EQUIPMEN T**				**LUMP SUM**
Lump Sum	**$4,875.00**	**$6,590.00**	**$6,590.00**	**$6,590.00**		
1310	**902-99.01**	**MISC. FIBER OPTIC INSTALLATION**				**LUMP SUM**
Lump Sum	**$6,550.00**	**$4,470.00**	**$4,470.00**	**$4,470.00**		
1320	**902-99.02**	**MISC. POST, TYPE C, 44 FT ARM**				**1 EA**
Bid Price	**7365.00**	**7425.00**	**7425.00**	**7425.00**		
Bid Amount	$7,365.00	$7,425.00	$7,425.00	$7,425.00		
1330	**902-99.02**	**MISC. POST, TYPE C, 29 FT ARM**				**1 EA**
Bid Price	**5000.00**	**3715.00**	**3715.00**	**3715.00**		
Bid Amount	$5,000.00	$3,715.00	$3,715.00	$3,715.00		
1340	**902-99.02**	**MISC. POST, TYPE C, 42 FT ARM**				**1 EA**
Bid Price	**7570.00**	**7045.00**	**7045.00**	**7045.00**		
Bid Amount	$7,570.00	$7,045.00	$7,045.00	$7,045.00		

Call No: G01	Hartman and Company, Inc. Low Bid	APAC-Missouri, Inc. 2nd Low	Emery Sapp & Sons Inc. 3rd Low	Lehman Construction, L.L.C. 4th Low		
1350	**902-99.02**	**MISC. POST, TYPE C, 12 FT ARM**				**1 EA**
Bid Price	**3775.00**	**3585.00**	**3585.00**	**3585.00**		
Bid Amount	$3,775.00	$3,585.00	$3,585.00	$3,585.00		
1360	**902-99.02**	**MISC. RELOCATE EXISTING FOS CABINET**				**1 EA**
Bid Price	**2785.00**	**1005.00**	**1005.00**	**1005.00**		
Bid Amount	$2,785.00	$1,005.00	$1,005.00	$1,005.00		
SECTION TOTALS	**$215,856.35**	**$213,911.30**	**$213,911.30**	**$213,911.30**		

Section 0004: SIGNING ITEMS - J8P3012

1370	**703-20.03**	**CLASS B CONCRETE (SUBSTRUCTURE)**				**34.80 CUYD**
Bid Price	**0.01**	**0.01**	**0.01**	**500.00**		
Bid Amount	$0.35	$0.35	$0.35	$17,400.00		
1380	**903-10.10**	**CONCRETE FOOTINGS, EMBEDDED**				**8.30 CUYD**
Bid Price	**1200.00**	**1200.00**	**1200.00**	**1117.48**		
Bid Amount	$9,960.00	$9,960.00	$9,960.00	$9,275.08		
1390	**903-12.10**	**STRUCTURAL STEEL POSTS**				**1,630 LB**
Bid Price	**2.60**	**2.60**	**2.60**	**2.41**		
Bid Amount	$4,238.00	$4,238.00	$4,238.00	$3,928.30		
1400	**903-12.20**	**PIPE POSTS**				**3,040 LB**
Bid Price	**2.40**	**2.40**	**2.40**	**2.36**		
Bid Amount	$7,296.00	$7,296.00	$7,296.00	$7,174.40		
1410	**903-12.40**	**BREAKAWAY ASSEMBLY**				**25 EA**
Bid Price	**90.00**	**90.00**	**90.00**	**224.07**		
Bid Amount	$2,250.00	$2,250.00	$2,250.00	$5,601.75		
1420	**903-12.56**	**7 FT. CHANNEL POST DELINEATOR, WHITE**				**2 EA**
Bid Price	**36.00**	**36.00**	**36.00**	**37.75**		
Bid Amount	$72.00	$72.00	$72.00	$75.50		
1430	**903-12.58**	**7 FT. CHANNEL POST DELINEATOR, WHITE/RED**				**2 EA**
Bid Price	**42.00**	**42.00**	**42.00**	**42.83**		
Bid Amount	$84.00	$84.00	$84.00	$85.66		
1440	**903-12.70A**	**PERFORATED SQUARE STEEL TUBE POST, 2 IN., 12 GA.**				**123 LF**
Bid Price	**12.00**	**12.00**	**12.00**	**14.39**		
Bid Amount	$1,476.00	$1,476.00	$1,476.00	$1,769.97		
1450	**903-12.71**	**PERFORATED SQUARE STEEL TUBE POST ANCHOR**				**36 LF**
Bid Price	**30.00**	**30.00**	**30.00**	**24.80**		
Bid Amount	$1,080.00	$1,080.00	$1,080.00	$892.80		
1460	**903-50.04**	**TYPE SHR2L-1 SIGN**				**406 SQFT**
Bid Price	**18.00**	**18.00**	**18.00**	**22.71**		
Bid Amount	$7,308.00	$7,308.00	$7,308.00	$9,220.26		
1470	**903-50.11**	**SIGN, TYPE STR2L-3**				**864 SQFT**
Bid Price	**20.00**	**20.00**	**20.00**	**18.67**		
Bid Amount	$17,280.00	$17,280.00	$17,280.00	$16,130.88		

Call No: G01	Hartman and Company, Inc. Low Bid	APAC-Missouri, Inc. 2nd Low	Emery Sapp & Sons Inc. 3rd Low	Lehman Construction, L.L.C. 4th Low		
1480	**903-50.68**	**SIGNAL SIGN, TYPE SHR2L-1**				**91 SQFT**
Bid Price	**38.00**	**38.00**	**38.00**	**39.86**		
Bid Amount	$3,458.00	$3,458.00	$3,458.00	$3,627.26		
1490	**903-60.36**	**TUBULAR SUPPORT, TYPE C-2315-20**				**2 EA**
Bid Price	**16500.00**	**16500.00**	**16500.00**	**18408.18**		
Bid Amount	$33,000.00	$33,000.00	$33,000.00	$36,816.36		
1500	**903-99.02**	**MISC. SIGN RELOCATION**				**7 EA**
Bid Price	**200.00**	**200.00**	**200.00**	**118.03**		
Bid Amount	$1,400.00	$1,400.00	$1,400.00	$826.21		
1510	**903-99.02**	**MISC. TUBULAR STEEL SUPPORT, TYPE S-2310, 51 F T 6 IN**				**1 EA**
Bid Price	**35000.00**	**35000.00**	**35000.00**	**34296.35**		
Bid Amount	$35,000.00	$35,000.00	$35,000.00	$34,296.35		
1520	**903-99.02**	**MISC. TYPE B OVERHEAD SIGN TRUSS 105 FT**				**1 EA**
Bid Price	**61000.00**	**61000.00**	**61000.00**	**63863.87**		
Bid Amount	$61,000.00	$61,000.00	$61,000.00	$63,863.87		
1530	**903-99.03**	**MISC. PERFORATED SQUARE STEEL TUBE POST, 2.5 I N**				**61 LF**
Bid Price	**14.00**	**14.00**	**14.00**	**14.79**		
Bid Amount	$854.00	$854.00	$854.00	$902.19		
1540	**903-99.03**	**MISC. PERFORATED SQUARE STEEL TUBE POST ANCHOR , 3 IN**				**18 LF**
Bid Price	**30.00**	**30.00**	**30.00**	**27.37**		
Bid Amount	$540.00	$540.00	$540.00	$492.66		
SECTION TOTALS	**$186,296.35**	**$186,296.35**	**$186,296.35**	**$212,379.50**		

Section 0005: BR. NO. A41851 - J8P3012

1550	**216-50.00**	**REMOVAL OF EXISTING EXPANSION JOINT SEAL OR SEALANT**				**171 LF**
Bid Price	**27.75**	**45.00**	**15.00**	**17.50**		
Bid Amount	$4,745.25	$7,695.00	$2,565.00	$2,992.50		
1560	**216-99.04**	**MISC. REMOVAL OF RAISED MEDIAN BARRIER**				**509 SQFT**
Bid Price	**16.60**	**26.00**	**16.00**	**2.50**		
Bid Amount	$8,449.40	$13,234.00	$8,144.00	$1,272.50		
1570	**503-10.10**	**BRIDGE APPROACH SLAB (BRIDGE)**				**478 SQYD**
Bid Price	**235.00**	**228.00**	**220.00**	**173.50**		
Bid Amount	$112,330.00	$108,984.00	$105,160.00	$82,933.00		
1580	**703-42.19A**	**BARRIER CURB (TYPE D)**				**625 LF**
Bid Price	**74.00**	**73.00**	**43.50**	**84.50**		
Bid Amount	$46,250.00	$45,625.00	$27,187.50	$52,812.50		
1590	**704-01.01**	**SUBSTRUCTURE REPAIR (FORMED)**				**100 SQFT**
Bid Price	**63.50**	**150.00**	**135.00**	**55.00**		
Bid Amount	$6,350.00	$15,000.00	$13,500.00	$5,500.00		

TABULATION OF BIDS

Call No: G01	Hartman and Company, Inc. Low Bid	APAC-Missouri, Inc. 2nd Low	Emery Sapp & Sons Inc. 3rd Low	Lehman Construction, L.L.C. 4th Low		
1600	**704-01.02**	**SUBSTRUCTURE REPAIR (UNFORMED)**				**100 SQFT**
Bid Price	**100.00**	**100.00**	**127.00**	**55.00**		
Bid Amount	$10,000.00	$10,000.00	$12,700.00	$5,500.00		
1610	**704-01.04**	**REPAIRING CONCRETE DECK (HALF-SOLING)**				**50 SQFT**
Bid Price	**232.90**	**135.00**	**100.00**	**68.00**		
Bid Amount	$11,645.00	$6,750.00	$5,000.00	$3,400.00		
1620	**707-10.00**	**CONDUIT SYSTEM ON STRUCTURE**				**LUMP SUM**
Lump Sum	**$4,480.00**	**$1,730.00**	**$1,730.00**	**$1,730.00**		
1630	**711-02.00**	**PROTECTIVE COATING - CONCRETE BENTS AND PIERS (EPOXY)**				**LUMP SUM**
Lump Sum	**$3,000.00**	**$3,076.92**	**$3,000.00**	**$3,000.00**		
1640	**712-52.00**	**SURFACE PREPARATION FOR RECOATING STRUCTURAL STEEL**				**1,200 SQFT**
Bid Price	**22.00**	**22.56**	**22.00**	**22.00**		
Bid Amount	$26,400.00	$27,072.00	$26,400.00	$26,400.00		
1650	**712-52.01**	**SURFACE PREPARATION FOR OVERCOATING STRUCTURAL STEEL**				**25,900 SQFT**
Bid Price	**0.75**	**0.77**	**0.75**	**0.75**		
Bid Amount	$19,425.00	$19,943.00	$19,425.00	$19,425.00		
1660	**712-52.10**	**FIELD APPLICATION OF INORGANIC ZINC PRIMER**				**1,200 SQFT**
Bid Price	**2.00**	**2.05**	**2.00**	**2.00**		
Bid Amount	$2,400.00	$2,460.00	$2,400.00	$2,400.00		
1670	**712-53.65A**	**INTERMEDIATE FIELD COAT (SYSTEM G)**				**1,200 SQFT**
Bid Price	**2.00**	**2.05**	**2.00**	**2.00**		
Bid Amount	$2,400.00	$2,460.00	$2,400.00	$2,400.00		
1680	**712-53.70A**	**FINISH FIELD COAT (SYSTEM G)**				**1,200 SQFT**
Bid Price	**2.00**	**2.05**	**2.00**	**2.00**		
Bid Amount	$2,400.00	$2,460.00	$2,400.00	$2,400.00		
1690	**712-59.00**	**CALCIUM SULFONATE RUST PENETRATING SEALER**				**LUMP SUM**
Lump Sum	**$5,180.00**	**$5,312.82**	**$5,180.00**	**$5,180.00**		
1700	**712-99.04**	**MISC. APPLICATION OF CALCIUM SULFONATE TOPCOAT**				**25,900 SQFT**
Bid Price	**1.25**	**1.28**	**1.25**	**1.25**		
Bid Amount	$32,375.00	$33,152.00	$32,375.00	$32,375.00		
1710	**717-99.03**	**MISC. PREFORMED SILICONE OR EPDM EXP. JT. SEAL**				**171 LF**
Bid Price	**63.50**	**72.00**	**116.00**	**37.00**		
Bid Amount	$10,858.50	$12,312.00	$19,836.00	$6,327.00		
SECTION TOTALS	**$308,688.15**	**$317,266.74**	**$289,402.50**	**$256,047.50**		

Contract Totals - 120824-G01

	$2,571,600.00	**$2,635,398.00**	**$2,674,590.19**	**$2,755,727.00**		

CERTIFIED BY DESIGN STATE DESIGN ENGINEER

8/24/2012

Missouri Department of Transportation

Vendor Ranking

Call Order: H01
Contract ID: 120824-H01
Counties: BOLLINGER
Letting Date: August 24, 2012 11:00 a.m.
District(s): Southeast
Contract Time: DT - 10/1/2013

Contract Description: J9S2254 - ROUTE 51 - BOLLINGER COUNTY
Project(s): FAF-51-2(25)

Rank	Vendor ID/Name		Total Bid	Percent Of Low Bid
1	0012577	Magruder Paving LLC	$3,253,384.90	100.00%
2	0011270	Pace Construction Company, LLC	$3,456,000.00	106.23%
3	0010528	Chester Bross Const. Co./C.B. Equipment Inc.	$3,688,772.86	113.38%
4	0011146	APAC-Missouri, Inc.	$4,010,195.27	123.26%
5	0010371	Apex Paving Co.	$4,014,281.87	123.39%

CONTRACT ID: 120824-H01
LETTING DATE: 08/24/12

TABULATION OF BIDS

Call No: H01	Magruder Paving LLC Low Bid	Pace Construction Company, LLC 2nd Low	Chester Bross Const. Co./CB Equip. Inc. 3rd Low	APAC-Missouri, Inc. 4th Low	Apex Paving Co. 5th Low	

Project J9S2254: Resurfacing and add shoulders

Section 0001: ROADWAY ITEMS - J9S2254

0010	**104-10.00**	**TEMPORARY SURFACING**				**400 CUYD**
Bid Price	**10.00**	**35.00**	**36.75**	**35.00**	**35.00**	
Bid Amount	$4,000.00	$14,000.00	$14,700.00	$14,000.00	$14,000.00	
0020	**202-20.10**	**REMOVAL OF IMPROVEMENTS**				**LUMP SUM**
Lump Sum	**$15,000.00**	**$46,977.13**	**$47,250.00**	**$45,500.00**	**$40,000.00**	
0030	**207-10.00**	**LINEAR GRADING CLASS 1**				**0.60 STA**
Bid Price	**2000.00**	**2000.00**	**2100.00**	**2000.00**	**2000.00**	
Bid Amount	$1,200.00	$1,200.00	$1,260.00	$1,200.00	$1,200.00	
0040	**215-20.00A**	**SHAPING SLOPES, CLASS II**				**1,878 100F**
Bid Price	**321.00**	**440.00**	**495.00**	**440.00**	**470.00**	
Bid Amount	$602,838.00	$826,320.00	$929,610.00	$826,320.00	$882,660.00	
0050	**310-50.02**	**GRAVEL (A) OR CRUSHED STONE (B)**				**170 TONS**
Bid Price	**25.00**	**20.00**	**21.00**	**20.00**	**20.00**	
Bid Amount	$4,250.00	$3,400.00	$3,570.00	$3,400.00	$3,400.00	
0060	**401-12.11**	**BITUMINOUS PAVEMENT MIXTURE PG64-22, (BP-2)**				**17,432.60 TONS**
Bid Price	**55.25**	**50.50**	**52.10**	**62.12**	**55.30**	
Bid Amount	$963,151.15	$880,346.30	$908,238.46	$1,082,913.11	$964,022.78	
0070	**401-30.00**	**BITUMINOUS PAVEMENT MIXTURE PG64-22 (BASE)**				**16.50 TONS**
Bid Price	**150.00**	**56.50**	**75.05**	**199.38**	**325.00**	
Bid Amount	$2,475.00	$932.25	$1,238.33	$3,289.77	$5,362.50	
0080	**401-99.05**	**MISC. OPTIONAL SHOULDERS**				**62,180.80 SQYD**
Bid Price	**15.35**	**15.30**	**15.24**	**20.01**	**19.70**	
Bid Amount	$954,475.28	$951,366.24	$947,635.39	$1,244,237.81	$1,224,961.76	
0090	**407-10.05**	**TACK COAT**				**13,120 GAL**
Bid Price	**0.01**	**0.01**	**1.00**	**2.55**	**0.05**	
Bid Amount	$131.20	$131.20	$13,120.00	$33,456.00	$656.00	
0100	**604-40.11**	**PIPE COLLAR, TYPE A**				**14 EA**
Bid Price	**950.00**	**400.00**	**420.00**	**400.00**	**415.00**	
Bid Amount	$13,300.00	$5,600.00	$5,880.00	$5,600.00	$5,810.00	
0110	**604-40.13**	**PIPE COLLAR, TYPE C**				**16 EA**
Bid Price	**1175.00**	**400.00**	**420.00**	**400.00**	**415.00**	
Bid Amount	$18,800.00	$6,400.00	$6,720.00	$6,400.00	$6,640.00	
0120	**606-22.00A**	**BRIDGE ANCHOR SECTION, 6.5 FT. POSTS (SAFETY BARRIER CURB) (ROADWAY AND REHABILITATION WORK ONLY)**				**3 EA**
Bid Price	**2400.00**	**2400.00**	**2520.00**	**2400.00**	**2500.00**	
Bid Amount	$7,200.00	$7,200.00	$7,560.00	$7,200.00	$7,500.00	
0130	**606-23.00A**	**TRANSITION SECTION, 6.5 FT. POSTS**				**3 EA**
Bid Price	**400.00**	**400.00**	**420.00**	**400.00**	**415.00**	
Bid Amount	$1,200.00	$1,200.00	$1,260.00	$1,200.00	$1,245.00	

TABULATION OF BIDS

Call No: H01	Magruder Paving LLC Low Bid	Pace Construction Company, LLC 2nd Low	Chester Bross Const. Co./CB Equip. Inc. 3rd Low	APAC-Missouri, Inc. 4th Low	Apex Paving Co. 5th Low	
0140	**606-30.15**	**TYPE A CRASHWORTHY END TERMINAL**				**3 EA**
Bid Price	**2100.00**	**2100.00**	**2205.00**	**2100.00**	**2200.00**	
Bid Amount	$6,300.00	$6,300.00	$6,615.00	$6,300.00	$6,600.00	
0150	**609-70.00**	**ROCK LINING**				**150 CUYD**
Bid Price	**60.00**	**50.00**	**52.50**	**50.00**	**50.00**	
Bid Amount	$9,000.00	$7,500.00	$7,875.00	$7,500.00	$7,500.00	
0160	**612-20.12**	**IMPACT ATTENUATOR (12 SAND BARRELS)**				**2 EA**
Bid Price	**2400.00**	**2400.00**	**2520.00**	**2400.00**	**2400.00**	
Bid Amount	$4,800.00	$4,800.00	$5,040.00	$4,800.00	$4,800.00	
0170	**612-20.20**	**REPLACEMENT SAND BARREL**				**10 EA**
Bid Price	**100.00**	**100.00**	**105.00**	**100.00**	**100.00**	
Bid Amount	$1,000.00	$1,000.00	$1,050.00	$1,000.00	$1,000.00	
0180	**612-30.00A**	**TRUCK OR TRAILER MOUNTED ATTENUATOR (TMA)**				**2 EA**
Bid Price	**1900.00**	**750.00**	**2475.30**	**500.00**	**7500.00**	
Bid Amount	$3,800.00	$1,500.00	$4,950.60	$1,000.00	$15,000.00	
0190	**616-10.05**	**CONSTRUCTION SIGNS**				**1,432 SQFT**
Bid Price	**8.00**	**8.50**	**9.00**	**8.50**	**4.00**	
Bid Amount	$11,456.00	$12,172.00	$12,888.00	$12,172.00	$5,728.00	
0200	**616-10.09**	**FLAG ASSEMBLY**				**38 EA**
Bid Price	**20.00**	**18.00**	**19.00**	**18.00**	**12.50**	
Bid Amount	$760.00	$684.00	$722.00	$684.00	$475.00	
0210	**616-10.25**	**CHANNELIZER (TRIM LINE)**				**60 EA**
Bid Price	**30.00**	**18.00**	**19.00**	**18.00**	**10.00**	
Bid Amount	$1,800.00	$1,080.00	$1,140.00	$1,080.00	$600.00	
0220	**616-10.47**	**TYPE III OBJECT MARKER**				**20 EA**
Bid Price	**30.00**	**150.00**	**47.25**	**150.00**	**150.00**	
Bid Amount	$600.00	$3,000.00	$945.00	$3,000.00	$3,000.00	
0230	**616-10.98**	**CHANGEABLE MESSAGE SIGN, CONTRACTOR FURNISHED, CONTRACTOR RE TAINED**				**2 EA**
Bid Price	**3500.00**	**3200.00**	**3360.00**	**3200.00**	**9500.00**	
Bid Amount	$7,000.00	$6,400.00	$6,720.00	$6,400.00	$19,000.00	
0240	**616-20.00**	**WORK ZONE TRAFFIC SIGNALS**				**1 EA**
Bid Price	**10000.00**	**6000.00**	**10000.00**	**5800.00**	**9500.00**	
Bid Amount	$10,000.00	$6,000.00	$10,000.00	$5,800.00	$9,500.00	
0250	**617-36.00D**	**TEMPORARY TRAFFIC BARRIER, CONTRACTOR FURNISHED / RETAINED**				**343 LF**
Bid Price	**25.00**	**25.00**	**26.25**	**25.00**	**25.00**	
Bid Amount	$8,575.00	$8,575.00	$9,003.75	$8,575.00	$8,575.00	
0260	**617-50.10A**	**RELOCATING TEMPORARY TRAFFIC BARRIER**				**343 LF**
Bid Price	**10.00**	**10.00**	**10.50**	**10.00**	**10.00**	
Bid Amount	$3,430.00	$3,430.00	$3,601.50	$3,430.00	$3,430.00	
0270	**618-10.00**	**MOBILIZATION**				**LUMP SUM**
Lump Sum	**$185,000.00**	**$172,000.00**	**$272,000.00**	**$232,750.00**	**$215,000.00**	

TABULATION OF BIDS

Call No: H01	Magruder Paving LLC Low Bid	Pace Construction Company, LLC 2nd Low	Chester Bross Const. Co./CB Equip. Inc. 3rd Low	APAC-Missouri, Inc. 4th Low	Apex Paving Co. 5th Low	
0280	**620-53.01B**	**PREFORMED REMOVABLE MARKING TAPE 4 IN., WHITE**				**886 LF**
Bid Price	**1.25**	**1.90**	**2.00**	**1.90**	**1.90**	
Bid Amount	$1,107.50	$1,683.40	$1,772.00	$1,683.40	$1,683.40	
0290	**620-53.09**	**PREFORMED REMOVABLE MARKING TAPE, 24 IN., WHITE**				**21 LF**
Bid Price	**7.50**	**25.00**	**26.25**	**25.00**	**25.00**	
Bid Amount	$157.50	$525.00	$551.25	$525.00	$525.00	
0300	**620-61.06**	**ACRYLIC WATERBORNE PAVEMENT MARKING PAINT, 6 IN., WHITE**				**187,810 LF**
Bid Price	**0.17**	**0.13**	**0.14**	**0.13**	**0.13**	
Bid Amount	$31,927.70	$24,415.30	$26,293.40	$24,415.30	$24,415.30	
0310	**620-61.19**	**ACRYLIC WATERBORNE PAVEMENT MARKING PAINT, 6 IN., YELLOW**				**176,171 LF**
Bid Price	**0.17**	**0.13**	**0.14**	**0.13**	**0.13**	
Bid Amount	$29,949.07	$22,902.23	$24,663.94	$22,902.23	$22,902.23	
0320	**620-70.01**	**PAVEMENT MARKING REMOVAL**				**943 LF**
Bid Price	**0.50**	**1.95**	**2.05**	**1.95**	**1.95**	
Bid Amount	$471.50	$1,838.85	$1,933.15	$1,838.85	$1,838.85	
0330	**621-46.00A**	**FLOWABLE BACKFILL**				**3 CUYD**
Bid Price	**250.00**	**150.00**	**157.50**	**150.00**	**155.00**	
Bid Amount	$750.00	$450.00	$472.50	$450.00	$465.00	
0340	**622-10.01**	**COLDMILLING BITUMINOUS PAVEMENT FOR REMOVAL OF SURFACING (3 IN. THICK OR LESS)**				**173 SQYD**
Bid Price	**9.00**	**9.50**	**16.30**	**25.00**	**20.00**	
Bid Amount	$1,557.00	$1,643.50	$2,819.90	$4,325.00	$3,460.00	
0350	**622-40.10**	**MODIFIED COLDMILLING (DEPTH TRANSITIONS)**				**817 SQYD**
Bid Price	**9.00**	**9.50**	**16.30**	**11.20**	**20.00**	
Bid Amount	$7,353.00	$7,761.50	$13,317.10	$9,150.40	$16,340.00	
0360	**626-10.01**	**BITUMINOUS CENTERLINE RUMBLE STRIP**				**866.80 STA**
Bid Price	**15.00**	**15.75**	**9.63**	**6.00**	**25.25**	
Bid Amount	$13,002.00	$13,652.10	$8,347.28	$5,200.80	$21,886.70	
0370	**626-99.09**	**MISC. OPTIOINAL SHOULDER RUMBLE STRIP**				**1,725.10 STA**
Bid Price	**15.00**	**15.00**	**9.63**	**6.00**	**18.50**	
Bid Amount	$25,876.50	$25,876.50	$16,612.71	$10,350.60	$31,914.35	
0380	**627-40.00**	**CONTRACTOR FURNISHED SURVEYING AND STAKING**				**LUMP SUM**
Lump Sum	**$32,600.00**	**$40,000.00**	**$31,800.00**	**$25,000.00**	**$37,500.00**	
0390	**703-40.41**	**CLASS B-1 CONCRETE (CULVERTS)**				**28.50 CUYD**
Bid Price	**1000.00**	**1105.00**	**1050.00**	**1000.00**	**1900.00**	
Bid Amount	$28,500.00	$31,492.50	$29,925.00	$28,500.00	$54,150.00	
0400	**706-10.30**	**REINFORCING STEEL (CULVERTS)**				**5,630 LB**
Bid Price	**2.00**	**2.85**	**2.10**	**2.00**	**1.60**	
Bid Amount	$11,260.00	$16,045.50	$11,823.00	$11,260.00	$9,008.00	

TABULATION OF BIDS

Call No: H01	Magruder Paving LLC Low Bid	Pace Construction Company, LLC 2nd Low	Chester Bross Const. Co./CB Equip. Inc. 3rd Low	APAC-Missouri, Inc. 4th Low	Apex Paving Co. 5th Low	
0410	**725-03.24A**	**24 IN. PIPE GROUP B**				**63 LF**
Bid Price	**60.00**	**50.00**	**52.50**	**50.00**	**51.00**	
Bid Amount	$3,780.00	$3,150.00	$3,307.50	$3,150.00	$3,213.00	
0420	**725-03.48A**	**48 IN. PIPE GROUP B**				**8 LF**
Bid Price	**90.00**	**100.00**	**105.00**	**100.00**	**105.00**	
Bid Amount	$720.00	$800.00	$840.00	$800.00	$840.00	
0430	**725-04.15**	**15 IN. PIPE GROUP C**				**632 LF**
Bid Price	**43.50**	**33.00**	**34.65**	**33.00**	**34.00**	
Bid Amount	$27,492.00	$20,856.00	$21,898.80	$20,856.00	$21,488.00	
0440	**725-04.18**	**18 IN. PIPE GROUP C**				**632 LF**
Bid Price	**51.00**	**33.00**	**34.65**	**33.00**	**34.00**	
Bid Amount	$32,232.00	$20,856.00	$21,898.80	$20,856.00	$21,488.00	
0450	**725-04.60**	**60 IN. PIPE GROUP C**				**45 LF**
Bid Price	**140.00**	**100.00**	**105.00**	**100.00**	**105.00**	
Bid Amount	$6,300.00	$4,500.00	$4,725.00	$4,500.00	$4,725.00	
0460	**732-00.24A**	**24 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION**				**2 EA**
Bid Price	**400.00**	**700.00**	**735.00**	**700.00**	**735.00**	
Bid Amount	$800.00	$1,400.00	$1,470.00	$1,400.00	$1,470.00	
0470	**732-00.48A**	**48 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION**				**1 EA**
Bid Price	**1800.00**	**2000.00**	**2100.00**	**2000.00**	**2100.00**	
Bid Amount	$1,800.00	$2,000.00	$2,100.00	$2,000.00	$2,100.00	
0480	**735-00.01**	**PIPE LINER FOR EXISTING CULVERT**				**372 LF**
Bid Price	**110.00**	**200.00**	**210.00**	**200.00**	**210.00**	
Bid Amount	$40,920.00	$74,400.00	$78,120.00	$74,400.00	$78,120.00	
0490	**805-10.00A**	**SEEDING - COOL SEASON MIXTURES**				**51.70 ACRE**
Bid Price	**775.00**	**1775.00**	**1575.00**	**1500.00**	**1850.00**	
Bid Amount	$40,067.50	$91,767.50	$81,427.50	$77,550.00	$95,645.00	
0500	**806-10.16**	**SEDIMENT REMOVAL**				**185 CUYD**
Bid Price	**15.00**	**10.00**	**10.50**	**10.00**	**10.50**	
Bid Amount	$2,775.00	$1,850.00	$1,942.50	$1,850.00	$1,942.50	
0510	**806-10.17**	**TEMPORARY SEEDING AND MULCHING**				**10.30 ACRE**
Bid Price	**700.00**	**700.00**	**945.00**	**900.00**	**735.00**	
Bid Amount	$7,210.00	$7,210.00	$9,733.50	$9,270.00	$7,570.50	
0520	**806-10.19**	**SILT FENCE**				**3,080 LF**
Bid Price	**2.00**	**2.00**	**2.00**	**1.80**	**3.25**	
Bid Amount	$6,160.00	$6,160.00	$6,160.00	$5,544.00	$10,010.00	
0530	**806-10.22**	**TYPE II DITCH CHECK**				**154 EA**
Bid Price	**80.00**	**80.00**	**157.50**	**150.00**	**125.00**	
Bid Amount	$12,320.00	$12,320.00	$24,255.00	$23,100.00	$19,250.00	
SECTION TOTALS	**$3,208,629.90**	**$3,415,070.00**	**$3,658,802.86**	**$3,960,085.27**	**$3,951,616.87**	

TABULATION OF BIDS

Call No: H01	Magruder Paving LLC Low Bid	Pace Construction Company, LLC 2nd Low	Chester Bross Const. Co./CB Equip. Inc. 3rd Low	APAC-Missouri, Inc. 4th Low	Apex Paving Co. 5th Low	

Section 0002: BR. NO. G03141 - J9S2254

0540	**216-40.00**	**CURB REMOVAL**				**85 LF**
Bid Price	**200.00**	**155.00**	**10.00**	**263.00**	**400.00**	
Bid Amount	$17,000.00	$13,175.00	$850.00	$22,355.00	$34,000.00	
0550	**712-23.00**	**BRIDGE RAIL (TWO TUBE STRUCTURAL STEEL)**				**91 LF**
Bid Price	**305.00**	**305.00**	**320.00**	**305.00**	**315.00**	
Bid Amount	$27,755.00	$27,755.00	$29,120.00	$27,755.00	$28,665.00	
SECTION TOTALS	**$44,755.00**	**$40,930.00**	**$29,970.00**	**$50,110.00**	**$62,665.00**	

Contract Totals - 120824-H01

	$3,253,384.90	**$3,456,000.00**	**$3,688,772.86**	**$4,010,195.27**	**$4,014,281.87**

CERTIFIED BY DESIGN STATE DESIGN ENGINEER

8/24/2012

Missouri Department of Transportation

Vendor Ranking **Page:** 1

Call Order: H02 **Contract ID:** 120824-H02 **Counties:** CAPE GIRARDEAU

Letting Date: August 24, 2012 11:00 a.m. **District(s):** Southeast

Contract Time: DT - 6/30/2013

Contract Description: J0P2277 - ROUTES K & 74 - CAPE GIRARDEAU COUNTY **Project(s):** FAF-74-1(19)

Rank	Vendor ID/Name		Total Bid	Percent Of Low Bid
1	0010703	RL Persons Construction Inc.	$1,091,591.95	100.00%
2	0011122	Fronabarger Concreters, Inc.	$1,140,664.10	104.50%
3	0010575	Nip Kelley Equipment Company, Inc.	$1,202,597.45	110.17%
4	0011806	Joe's Bridge & Grading, Inc.	$1,325,429.96	121.42%
5	0010528	Chester Bross Const. Co./C.B. Equipment Inc.	$1,443,440.95	132.23%
6	0012499	Strait-Line Construction USA Inc.	$1,756,108.10	160.88%

CONTRACT ID: 120824-H02
LETTING DATE: 08/24/12

TABULATION OF BIDS

Call No: H02	RL Persons Construction Inc. Low Bid	Fronabarger Concreters, Inc. 2nd Low	Nip Kelley Equipment Company, Inc. 3rd Low	Joe's Bridge & Grading, Inc. 4th Low	Chester Bross Const. Co./CB Equip. Inc. 5th Low	Strait-Line Construction USA Inc. 6th Low

Project J0P2277: Bicycle/pedestrian improvements

Section 0001: ROADWAY ITEMS - J0P2277

0010	**202-20.10**	**REMOVAL OF IMPROVEMENTS**				**LUMP SUM**
Lump Sum	**$35,000.00**	**$38,000.00**	**$55,811.00**	**$100,000.00**	**$26,000.00**	**$39,500.00**
0020	**203-10.00**	**CLASS A EXCAVATION**				**7,570 CUYD**
Bid Price	**9.00**	**11.00**	**7.94**	**12.00**	**22.35**	**18.75**
Bid Amount	$68,130.00	$83,270.00	$60,105.80	$90,840.00	$169,189.50	$141,937.50
0030	**203-60.00**	**COMPACTING EMBANKMENT**				**5,359 CUYD**
Bid Price	**1.50**	**4.00**	**0.70**	**3.00**	**3.35**	**2.50**
Bid Amount	$8,038.50	$21,436.00	$3,751.30	$16,077.00	$17,952.65	$13,397.50
0040	**207-10.00**	**LINEAR GRADING CLASS 1**				**13 STA**
Bid Price	**900.00**	**1100.00**	**1612.00**	**650.00**	**750.00**	**1355.00**
Bid Amount	$11,700.00	$14,300.00	$20,956.00	$8,450.00	$9,750.00	$17,615.00
0050	**304-01.43**	**TYPE 1 AGGREGATE FOR BASE (4 IN. THICK)**				**6,135 SQYD**
Bid Price	**5.00**	**4.50**	**5.60**	**7.00**	**8.25**	**7.85**
Bid Amount	$30,675.00	$27,607.50	$34,356.00	$42,945.00	$50,613.75	$48,159.75
0060	**310-50.02**	**GRAVEL (A) OR CRUSHED STONE (B)**				**24 TONS**
Bid Price	**30.00**	**25.00**	**24.61**	**7.00**	**28.50**	**29.50**
Bid Amount	$720.00	$600.00	$590.64	$168.00	$684.00	$708.00
0070	**604-40.11**	**PIPE COLLAR, TYPE A**				**2 EA**
Bid Price	**1100.00**	**750.00**	**581.21**	**3000.00**	**2350.00**	**500.00**
Bid Amount	$2,200.00	$1,500.00	$1,162.42	$6,000.00	$4,700.00	$1,000.00
0080	**608-10.10**	**CONCRETE CURB RAMP**				**181.60 SQYD**
Bid Price	**97.00**	**65.00**	**96.23**	**48.00**	**141.00**	**105.00**
Bid Amount	$17,615.20	$11,804.00	$17,475.37	$8,716.80	$25,605.60	$19,068.00
0090	**608-10.12**	**TRUNCATED DOMES**				**1,533 SQFT**
Bid Price	**24.00**	**25.00**	**25.15**	**38.00**	**33.00**	**23.95**
Bid Amount	$36,792.00	$38,325.00	$38,554.95	$58,254.00	$50,589.00	$36,715.35
0100	**608-50.07**	**PAVED APPROACH, 7 IN.**				**50.20 SQYD**
Bid Price	**133.00**	**45.00**	**60.72**	**50.00**	**93.00**	**65.50**
Bid Amount	$6,676.60	$2,259.00	$3,048.14	$2,510.00	$4,668.60	$3,288.10
0110	**608-60.04**	**CONCRETE SIDEWALK, 4 IN.**				**5,938.20 SQYD**
Bid Price	**31.00**	**32.00**	**36.84**	**45.00**	**38.75**	**32.50**
Bid Amount	$184,084.20	$190,022.40	$218,763.29	$267,219.00	$230,105.25	$192,991.50
0120	**608-99.02**	**MISC. BOLLARDS**				**1 EA**
Bid Price	**700.00**	**1250.00**	**1380.00**	**2000.00**	**1140.00**	**450.00**
Bid Amount	$700.00	$1,250.00	$1,380.00	$2,000.00	$1,140.00	$450.00
0130	**608-99.02**	**MISC. WELDED STEEL OR ALUMINUM POWDER COATED B ENCH**				**1 EA**
Bid Price	**2000.00**	**1650.00**	**1575.00**	**3000.00**	**1850.00**	**2675.00**
Bid Amount	$2,000.00	$1,650.00	$1,575.00	$3,000.00	$1,850.00	$2,675.00

TABULATION OF BIDS

Call No: H02	RL Persons Construction Inc.	Fronabarger Concreters, Inc.	Nip Kelley Equipment Company, Inc.	Joe's Bridge & Grading, Inc.	Chester Bross Const. Co./CB Equip. Inc.	Strait-Line Construction USA Inc.
	Low Bid	2nd Low	3rd Low	4th Low	5th Low	6th Low
0140 609-10.10	**CONCRETE CURB (6 IN. HEIGHT AND UNDER) TYPE S**					**85 LF**
Bid Price	**35.00**	**25.00**	**23.14**	**30.00**	**44.50**	**37.85**
Bid Amount	$2,975.00	$2,125.00	$1,966.90	$2,550.00	$3,782.50	$3,217.25
0150 609-10.11	**CONCRETE CURB (OVER 6 IN. HEIGHT) TYPE S**					**403 LF**
Bid Price	**25.00**	**23.00**	**24.40**	**30.00**	**44.50**	**37.85**
Bid Amount	$10,075.00	$9,269.00	$9,833.20	$12,090.00	$17,933.50	$15,253.55
0160 609-99.03	**MISC. 6 IN TYPE B MODIFIED CURB AND GUTTER**					**322 LF**
Bid Price	**33.00**	**28.00**	**25.28**	**32.00**	**60.00**	**26.75**
Bid Amount	$10,626.00	$9,016.00	$8,140.16	$10,304.00	$19,320.00	$8,613.50
0170 614-11.20	**CURVED VANE GRATE AND FRAME (2 FT. X 2 FT. OR 600MM X 600MM)**					**3 EA**
Bid Price	**500.00**	**430.00**	**252.38**	**900.00**	**425.00**	**1500.00**
Bid Amount	$1,500.00	$1,290.00	$757.14	$2,700.00	$1,275.00	$4,500.00
0180 614-11.21	**CURVED VANE GRATE AND FRAME (4 FT X 2 FT OR 1200MM X 600MM)**					**13 EA**
Bid Price	**800.00**	**710.00**	**252.38**	**1000.00**	**740.00**	**2000.00**
Bid Amount	$10,400.00	$9,230.00	$3,280.94	$13,000.00	$9,620.00	$26,000.00
0190 614-99.02	**MISC. CURVED VANE GRATE AND FRAME (3FT X 2FT)**					**1 EA**
Bid Price	**830.00**	**1450.00**	**3550.00**	**1200.00**	**740.00**	**1850.00**
Bid Amount	$830.00	$1,450.00	$3,550.00	$1,200.00	$740.00	$1,850.00
0200 616-10.05	**CONSTRUCTION SIGNS**					**512 SQFT**
Bid Price	**15.00**	**6.50**	**8.77**	**7.00**	**8.40**	**7.50**
Bid Amount	$7,680.00	$3,328.00	$4,490.24	$3,584.00	$4,300.80	$3,840.00
0210 616-10.08	**ADVANCED WARNING RAIL SYSTEM**					**4 EA**
Bid Price	**120.00**	**100.00**	**112.22**	**120.00**	**52.50**	**125.00**
Bid Amount	$480.00	$400.00	$448.88	$480.00	$210.00	$500.00
0220 616-10.09	**FLAG ASSEMBLY**					**15 EA**
Bid Price	**25.00**	**20.00**	**30.00**	**21.00**	**21.00**	**25.00**
Bid Amount	$375.00	$300.00	$450.00	$315.00	$315.00	$375.00
0230 616-10.25	**CHANNELIZER (TRIM LINE)**					**100 EA**
Bid Price	**40.00**	**20.00**	**22.50**	**21.00**	**31.50**	**25.00**
Bid Amount	$4,000.00	$2,000.00	$2,250.00	$2,100.00	$3,150.00	$2,500.00
0240 616-10.40	**FLASHING ARROW PANEL**					**2 EA**
Bid Price	**2400.00**	**1600.00**	**1796.00**	**1650.00**	**2100.00**	**1750.00**
Bid Amount	$4,800.00	$3,200.00	$3,592.00	$3,300.00	$4,200.00	$3,500.00
0250 618-10.00	**MOBILIZATION**					**LUMP SUM**
Lump Sum	**$35,000.00**	**$56,000.00**	**$79,950.00**	**$57,500.00**	**$112,000.00**	**$52,550.00**
0260 620-51.05	**TYPE 2 PREFORMED MARKING TAPE (GROOVED), 6 IN., WHITE**					**4,903 LF**
Bid Price	**5.00**	**4.85**	**5.72**	**5.00**	**5.10**	**7.10**
Bid Amount	$24,515.00	$23,779.55	$28,045.16	$24,515.00	$25,005.30	$34,811.30

TABULATION OF BIDS

Call No: H02	RL Persons Construction Inc. Low Bid	Fronabarger Concreters, Inc. 2nd Low	Nip Kelley Equipment Company, Inc. 3rd Low	Joe's Bridge & Grading, Inc. 4th Low	Chester Bross Const. Co./CB Equip. Inc. 5th Low	Strait-Line Construction USA Inc. 6th Low
0270 620-51.20 TYPE 2 PREFORMED MARKING TAPE (GROOVED), 24 IN., WHITE						**444 LF**
Bid Price	**21.00**	**19.50**	**24.70**	**20.00**	**20.50**	**25.00**
Bid Amount	$9,324.00	$8,658.00	$10,966.80	$8,880.00	$9,102.00	$11,100.00
0280 620-51.31 TYPE 2 PREFORMED MARKING TAPE (GROOVED), STRAIGHT ARROW						**25 EA**
Bid Price	**250.00**	**230.00**	**366.00**	**235.00**	**241.50**	**245.00**
Bid Amount	$6,250.00	$5,750.00	$9,150.00	$5,875.00	$6,037.50	$6,125.00
0290 620-70.01 PAVEMENT MARKING REMOVAL						**946 LF**
Bid Price	**0.55**	**0.50**	**2.81**	**0.51**	**0.55**	**4.95**
Bid Amount	$520.30	$473.00	$2,658.26	$482.46	$520.30	$4,682.70
0300 620-99.02 MISC. TYPE 2 PREFORMED BIKE SYMBOL (GROOVED)						**38 EA**
Bid Price	**375.00**	**350.00**	**522.00**	**360.00**	**367.50**	**455.00**
Bid Amount	$14,250.00	$13,300.00	$19,836.00	$13,680.00	$13,965.00	$17,290.00
0310 704-99.01 MISC. BIKE/PED BRIDGE						**LUMP SUM**
Lump Sum	**$149,000.00**	**$122,000.00**	**$185,732.00**	**$185,000.00**	**$158,000.00**	**$128,541.45**
0320 725-03.24A 24 IN. PIPE GROUP B						**16 LF**
Bid Price	**53.00**	**80.00**	**79.88**	**36.00**	**58.50**	**56.00**
Bid Amount	$848.00	$1,280.00	$1,278.08	$576.00	$936.00	$896.00
0330 725-04.18 18 IN. PIPE GROUP C						**85 LF**
Bid Price	**43.00**	**65.00**	**42.36**	**30.00**	**49.00**	**45.00**
Bid Amount	$3,655.00	$5,525.00	$3,600.60	$2,550.00	$4,165.00	$3,825.00
0340 726-10.24 24 IN. PIPE GROUP A						**13 LF**
Bid Price	**67.00**	**95.00**	**65.09**	**48.00**	**73.00**	**70.00**
Bid Amount	$871.00	$1,235.00	$846.17	$624.00	$949.00	$910.00
0350 726-10.30 30 IN. PIPE GROUP A						**25 LF**
Bid Price	**60.00**	**85.00**	**79.21**	**58.00**	**78.00**	**78.90**
Bid Amount	$1,500.00	$2,125.00	$1,980.25	$1,450.00	$1,950.00	$1,972.50
0360 726-10.48 48 IN. PIPE GROUP A						**45 LF**
Bid Price	**115.00**	**125.00**	**109.32**	**110.00**	**156.00**	**140.00**
Bid Amount	$5,175.00	$5,625.00	$4,919.40	$4,950.00	$7,020.00	$6,300.00
0370 731-10.33 PRECAST CONCRETE DROP INLET 3 FT X 3 FT						**1 FT**
Bid Price	**700.00**	**750.00**	**582.68**	**5500.00**	**1340.00**	**850.00**
Bid Amount	$700.00	$750.00	$582.68	$5,500.00	$1,340.00	$850.00
0380 731-10.53 PRECAST CONCRETE DROP INLET 5 FT X 3 FT						**7 FT**
Bid Price	**700.00**	**450.00**	**224.54**	**6000.00**	**828.00**	**940.00**
Bid Amount	$4,900.00	$3,150.00	$1,571.78	$42,000.00	$5,796.00	$6,580.00
0390 732-00.24A 24 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION						**2 EA**
Bid Price	**900.00**	**540.00**	**308.56**	**400.00**	**412.00**	**1857.25**
Bid Amount	$1,800.00	$1,080.00	$617.12	$800.00	$824.00	$3,714.50
0400 732-06.24A 24 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION						**1 EA**
Bid Price	**900.00**	**540.00**	**967.25**	**400.00**	**871.00**	**650.00**
Bid Amount	$900.00	$540.00	$967.25	$400.00	$871.00	$650.00

TABULATION OF BIDS

Call No: H02	RL Persons Construction Inc. Low Bid	Fronabarger Concreters, Inc. 2nd Low	Nip Kelley Equipment Company, Inc. 3rd Low	Joe's Bridge & Grading, Inc. 4th Low	Chester Bross Const. Co./CB Equip. Inc. 5th Low	Strait-Line Construction USA Inc. 6th Low
0410 732-06.30A	**30 IN. OR ALLOWED SUBSTITUTE GROUP A FLARED END SECTION**					**1 EA**
Bid Price	**1100.00**	**700.00**	**1088.45**	**700.00**	**951.00**	**1800.00**
Bid Amount	$1,100.00	$700.00	$1,088.45	$700.00	$951.00	$1,800.00
0420 803-10.00A	**TURF TYPE TALL FESCUE SODDING**					**920 SQYD**
Bid Price	**8.00**	**5.00**	**11.51**	**6.75**	**6.80**	**7.50**
Bid Amount	$7,360.00	$4,600.00	$10,589.20	$6,210.00	$6,256.00	$6,900.00
0430 805-10.00A	**SEEDING - COOL SEASON MIXTURES**					**3.10 ACRE**
Bid Price	**2500.00**	**2100.00**	**2637.22**	**2400.00**	**2465.00**	**2500.00**
Bid Amount	$7,750.00	$6,510.00	$8,175.38	$7,440.00	$7,641.50	$7,750.00
0440 806-10.17	**TEMPORARY SEEDING AND MULCHING**					**0.70 ACRE**
Bid Price	**1300.00**	**1000.00**	**3206.35**	**1225.00**	**1260.00**	**1400.00**
Bid Amount	$910.00	$700.00	$2,244.45	$857.50	$882.00	$980.00
0450 806-10.19	**SILT FENCE**					**1,056 LF**
Bid Price	**3.00**	**2.50**	**2.58**	**2.35**	**2.40**	**2.60**
Bid Amount	$3,168.00	$2,640.00	$2,724.48	$2,481.60	$2,534.40	$2,745.60
0460 806-10.22	**TYPE II DITCH CHECK**					**64 EA**
Bid Price	**200.00**	**180.00**	**168.50**	**153.00**	**157.50**	**200.00**
Bid Amount	$12,800.00	$11,520.00	$10,784.00	$9,792.00	$10,080.00	$12,800.00
0470 806-41.22	**TYPE 3 EROSION CONTROL BLANKET**					**3,121 SQYD**
Bid Price	**2.15**	**1.75**	**2.19**	**2.00**	**2.05**	**2.50**
Bid Amount	$6,710.15	$5,461.75	$6,834.99	$6,242.00	$6,398.05	$7,802.50
SECTION TOTALS	**$757,078.95**	**$757,034.20**	**$891,431.87**	**$1,046,308.36**	**$1,040,919.20**	**$909,231.55**

Section 0002: SIGNAL ITEMS - J0P2277

0480 902-08.11	**SIGNAL HEAD, TYPE 1S, PEDESTRIAN**					**50 EA**
Bid Price	**600.00**	**666.50**	**576.82**	**514.00**	**682.50**	**710.00**
Bid Amount	$30,000.00	$33,325.00	$28,841.00	$25,700.00	$34,125.00	$35,500.00
0490 902-27.08	**POST, SIGNAL 8 FT. OR 2.4 M**					**50 EA**
Bid Price	**700.00**	**670.25**	**757.50**	**675.00**	**682.50**	**710.00**
Bid Amount	$35,000.00	$33,512.50	$37,875.00	$33,750.00	$34,125.00	$35,500.00
0500 902-52.00	**CONDUIT, 2 IN., TRENCH**					**6,025 LF**
Bid Price	**8.00**	**8.00**	**7.86**	**7.00**	**8.40**	**8.80**
Bid Amount	$48,200.00	$48,200.00	$47,356.50	$42,175.00	$50,610.00	$53,020.00
0510 902-53.00	**CONDUIT, 3 IN., TRENCH**					**490 LF**
Bid Price	**6.00**	**10.00**	**6.49**	**5.78**	**10.50**	**11.00**
Bid Amount	$2,940.00	$4,900.00	$3,180.10	$2,832.20	$5,145.00	$5,390.00
0520 902-72.00	**CONDUIT, 2 IN., PUSHED**					**1,558 LF**
Bid Price	**9.00**	**12.00**	**8.75**	**7.80**	**12.60**	**13.20**
Bid Amount	$14,022.00	$18,696.00	$13,632.50	$12,152.40	$19,630.80	$20,565.60
0530 902-82.06	**CABLE, 6 AWG 1 CONDUCTOR, POWER**					**2,480 LF**
Bid Price	**1.25**	**1.10**	**1.09**	**0.97**	**1.15**	**1.35**
Bid Amount	$3,100.00	$2,728.00	$2,703.20	$2,405.60	$2,852.00	$3,348.00

TABULATION OF BIDS

Call No: H02	RL Persons Construction Inc. Low Bid	Fronabarger Concreters, Inc. 2nd Low	Nip Kelley Equipment Company, Inc. 3rd Low	Joe's Bridge & Grading, Inc. 4th Low	Chester Bross Const. Co./CB Equip. Inc. 5th Low	Strait-Line Construction USA Inc. 6th Low
0540 902-83.11 CABLE, 16 AWG 7 CONDUCTOR						**9,560 LF**
Bid Price	**2.00**	**3.00**	**1.63**	**1.45**	**3.15**	**3.30**
Bid Amount	$19,120.00	$28,680.00	$15,582.80	$13,862.00	$30,114.00	$31,548.00
0550 902-86.20 POWER SUPPLY ASSEMBLY, TYPE 2						**1 EA**
Bid Price	**4000.00**	**4500.00**	**3050.65**	**2718.40**	**4725.00**	**4950.00**
Bid Amount	$4,000.00	$4,500.00	$3,050.65	$2,718.40	$4,725.00	$4,950.00
0560 902-88.11 PULL BOX, PREFORMED CLASS 2						**8 EA**
Bid Price	**1100.00**	**750.00**	**1167.11**	**1040.00**	**787.50**	**825.00**
Bid Amount	$8,800.00	$6,000.00	$9,336.88	$8,320.00	$6,300.00	$6,600.00
0570 902-91.00 BASE, CONCRETE						**22 CUYD**
Bid Price	**2400.00**	**1959.00**	**1613.76**	**1438.00**	**2057.00**	**2154.90**
Bid Amount	$52,800.00	$43,098.00	$35,502.72	$31,636.00	$45,254.00	$47,407.80
0580 902-99.02 MISC. UNDERGROUND SPLICE ENCLOSURE						**1 EA**
Bid Price	**1300.00**	**1050.00**	**1415.12**	**1261.00**	**1102.50**	**1180.00**
Bid Amount	$1,300.00	$1,050.00	$1,415.12	$1,261.00	$1,102.50	$1,180.00
0590 902-99.02 MISC. FIBER OPTIC SPLICE						**204 EA**
Bid Price	**80.00**	**82.00**	**87.53**	**78.00**	**86.10**	**90.00**
Bid Amount	$16,320.00	$16,728.00	$17,856.12	$15,912.00	$17,564.40	$18,360.00
0600 902-99.02 MISC. FIBER OPTIC PIGTAIL						**156 EA**
Bid Price	**31.00**	**25.00**	**33.67**	**30.00**	**26.25**	**2750.00**
Bid Amount	$4,836.00	$3,900.00	$5,252.52	$4,680.00	$4,095.00	$429,000.00
0610 902-99.02 MISC. INSTALL VIDEO DETECTION						**14 EA**
Bid Price	**3000.00**	**4825.00**	**2950.32**	**2629.00**	**5066.25**	**5307.50**
Bid Amount	$42,000.00	$67,550.00	$41,304.48	$36,806.00	$70,927.50	$74,305.00
0620 902-99.02 MISC. PRESSURE ACTIVATED PEDESTRIAN PUCH BUTTO N ASSEMBLY						**50 EA**
Bid Price	**175.00**	**260.00**	**172.82**	**154.00**	**273.00**	**286.00**
Bid Amount	$8,750.00	$13,000.00	$8,641.00	$7,700.00	$13,650.00	$14,300.00
0630 902-99.02 MISC. PULL BOX ADJUSTMENT						**16 EA**
Bid Price	**500.00**	**1200.00**	**513.98**	**458.00**	**1260.00**	**1320.00**
Bid Amount	$8,000.00	$19,200.00	$8,223.68	$7,328.00	$20,160.00	$21,120.00
0640 902-99.02 MISC. WALL MOUNTED INTERCONNECT CENTER						**6 EA**
Bid Price	**500.00**	**925.00**	**448.89**	**400.00**	**971.25**	**1017.50**
Bid Amount	$3,000.00	$5,550.00	$2,693.34	$2,400.00	$5,827.50	$6,105.00
0650 902-99.03 MISC. INSTALLATION/MODIFICATION OF EXISTING FI BER CABLE						**3,135 LF**
Bid Price	**2.00**	**3.00**	**1.91**	**1.70**	**3.15**	**3.35**
Bid Amount	$6,270.00	$9,405.00	$5,987.85	$5,329.50	$9,875.25	$10,502.25
SECTION TOTALS	**$308,458.00**	**$360,022.50**	**$288,435.46**	**$256,968.10**	**$376,082.95**	**$818,701.65**

TABULATION OF BIDS

Call No: H02	RL Persons Construction Inc. Low Bid	Fronabarger Concreters, Inc. 2nd Low	Nip Kelley Equipment Company, Inc. 3rd Low	Joe's Bridge & Grading, Inc. 4th Low	Chester Bross Const. Co./CB Equip. Inc. 5th Low	Strait-Line Construction USA Inc. 6th Low
Section 0003: SIGNING ITEMS - J0P2277						
0660 903-12.70A PERFORATED SQUARE STEEL TUBE POST, 2 IN., 12 GA.						**290 LF**
Bid Price	**17.00**	**10.50**	**15.49**	**16.32**	**16.80**	**19.00**
Bid Amount	$4,930.00	$3,045.00	$4,492.10	$4,732.80	$4,872.00	$5,510.00
0670 903-12.71 PERFORATED SQUARE STEEL TUBE POST ANCHOR						**88 LF**
Bid Price	**32.00**	**30.00**	**22.04**	**30.60**	**31.50**	**34.00**
Bid Amount	$2,816.00	$2,640.00	$1,939.52	$2,692.80	$2,772.00	$2,992.00
0680 903-50.04 TYPE SHR2L-1 SIGN						**134 SQFT**
Bid Price	**26.00**	**24.00**	**25.60**	**24.50**	**25.20**	**26.00**
Bid Amount	$3,484.00	$3,216.00	$3,430.40	$3,283.00	$3,376.80	$3,484.00
SECTION TOTALS	**$11,230.00**	**$8,901.00**	**$9,862.02**	**$10,708.60**	**$11,020.80**	**$11,986.00**
Section 0004: ITS ITEMS - J0P2277						
0690 910-83.54 FIBER OPTIC CABLE, 48-STRAND, SINGLE MODE						**5,930 LF**
Bid Price	**2.50**	**2.48**	**2.17**	**1.93**	**2.60**	**2.73**
Bid Amount	$14,825.00	$14,706.40	$12,868.10	$11,444.90	$15,418.00	$16,188.90
Contract Totals - 120824-H02						
	$1,091,591.95	**$1,140,664.10**	**$1,202,597.45**	**$1,325,429.96**	**$1,443,440.95**	**$1,756,108.10**